Contract D2C-08						Addendum -02
DELHI METRO RAIL CORPORATION LTD.						
Contract D2C-08: Civil works including earth filling and construction of depot buildings, workshop, inspection shed, plumbing, drainage, external development, architectural finishes, road works, design and construction of PEB works in Sanoth Depot of Rithala-Kundli corridor of Delhi Metro Phase-IV.						
S.No.	**Part/Section**	**Document Name**	**Page No.**	**Clause No./Item No.**	**Addendum/Corrigendum**	**Remarks**
1		Invitation for Bids	2	6,7 & 8	Change in deadline of Bid submission, date of opening of Technical bids etc.	Replace Page 2 with 2R
2	Part-1, Section- I	BDS	4 & 7	ITB 19.2, 22.1 & 25.1	Change in deadline of Submission of Bid Security in "Original", deadline of Bid submission & date of opening of Technical Bids.	Replace Page 4R & 7R with 4R1 & 7R1 respectively
3	Part-1, Section-III	Evaluation & Qualification Criteria	13	2.4.2 (b)	Clause 2.4.2 (b), Specific Experience	Replace Page 13 with 13R
4	Part-1, Section-IV	Bidding Forms	5	ABSTRACT OF SCHEDULE - A, B & C	TOTAL AMOUNT (in Rs.) (Rates in schedule A, B & C are inclusive of all taxes and duties)	Replace Page 5 with 5R
5	Part-2, Section -VI	Employer's Requirements : Functional	19	2.2.2 B	Scope of works for PEB Works	Replace Page 19 with 19R
6	Part-2, Section -VI	Employer's Requirements : Functional	35	9	Environmental Considerations	Replace Page 35 with 35R
7	Part-2, Section -VI	Employer's Requirements : Construction	54	3	Use of the site	Replace Page 54 with 54R
8	Part-2, Section -VI	Employer's Requirements : Construction	72-73	14	Provision and disposal of Earthworks material	Replace Page 72-73 with 72R-73R
9	Part-2, Section -VI	Employer's Requirements : Appendix	232	Appendix -10	Approved Manufacturer's List	Replace Page 232 with 232R
10	Part-2	Outline Design Specifications (ODS)			Inadvertently written as Dec 2025 (Rev 2) in summary of Addendum-1 , to be read as **July 2021 (Rev-2)**	
11	Part-2	Part-B: Technical Specifications			List of Empanelled Manufacturers-Suppliers of Major Civil Items (as on 17.04.2026)	List of Empanelled Manufacturers-Suppliers of Major Civil Items (as on 27.03.2026)(10 pages) is replaced by latest list as on 17.04.2026) (07 pages)
12	Part-2	Part-B: Technical Specifications			List of Empanelled Manufacturers-Suppliers of Major Architectural Items (as on 17.04.2026)	List of Empanelled Manufacturers-Suppliers of Major Architectural tems (as on 01.12.2025)(11 pages) is replaced by latest list as on 17.04.2026) (10 pages)
13	Part -3	Conditions of Contract on Safety & Health and Environment, May 2025	170	Part-3, SHE May 2025	Clause 52.7.3.9	Replace Page 170
14	Replies to pre-bid queries (03 pages)					

Office of Sr. General Manager/Contracts
Delhi Metro Rail Corporation Limited
5th floor, A-Wing, Metro Bhawan
Fire Brigade Lane, Barakhamba Road
New Delhi - 110 001, India

6. Bids must be submitted online on the e-tendering website ***https://eprocure.gov.in/eprocure/app*** from ~~**06.05.2026**~~ ***21.05.2026*** (0900 hrs) to ~~**13.05.2026**~~ ***28.05.2026*** (1500 hrs) and must be accompanied by a Bid Security of **17.10 Million.**
7. Bids will be opened on the e-tendering website ***https://eprocure.gov.in/eprocure/app*** at 1500 hrs on ~~**14.05.2026**~~ ***29.05.2026***.
8. Key Details for Contract D2C-08 are as follows:

- Completion period of the Work: **30 months**.
- Sale of Bidding documents: From **13.04.2026** to ~~**13.05.2026**~~ ***28.05.2026***
- Pre-bid Meeting: at 1100 hrs **22.04.2026** as per BDS 7.4
- Deadline for Bid submission: 1500 hrs on ~~**13.05.2026**~~ ***28.05.2026*** as per BDS 22.1
- Technical Bid Opening date: 1500 hrs on ~~**14.05.2026**~~ ***29.05.2026*** as per BDS 25.1

Notes for Bidders:

1. The intending Bidders must be registered on e-tendering portal ***https://eprocure.gov.in/eprocure/app***. Those who are not registered on the e-tendering portal shall be required to get registered beforehand. After registration, the bidder will get user id and password. On login, bidder can participate in bidding process and can witness various activities of the process.

2. The authorized signatory of intending bidder, as per Power of Attorney, must have valid Class-III digital signature. Bidding Documents can only be downloaded or uploaded using Class-III digital signature. However, the bidder shall upload their bid on ***https://eprocure.gov.in/eprocure/app*** using Class-III digital signature of the authorized signatory only.

3. Bid submissions shall be done online on ***https://eprocure.gov.in/eprocure/app*** after uploading the scanned documents towards cost of Bidding Documents (scanned copy of Demand Draft / Pay Order / Bank Draft or of transaction of payment in case of RTGS/ NEFT/ IMPS), scanned copy of Bid Security and other documents as stated in the Bidding Documents. Instructions for on-line bid submission are furnished hereinafter.

4. Submission of bids shall be closed on e-tendering website at the date and time of submission prescribed in IFB (or extended deadline, if any, as per ITB 22.2) after which no bid shall be accepted.

   It shall be the responsibility of the bidder to ensure that his bid is submitted online on e-tendering website ***https://eprocure.gov.in/eprocure/app*** before the deadline of submission. Delhi Metro Rail Corporation Limited will not be responsible for non-receipt of Bidding Documents due to any delay and/or loss etc.

	(b) Form UTK-2: Undertaking for compliance to Employer's Requirement & Specification by Bidder. **(c) Form TB-DEV:** Proforma for Statement of Minor Deviations/Non material Nonconformity. **(d) Documentary evidence for payment** towards cost of the Bidding Documents.
ITB 11.3 (c)	The Bidder shall submit with its Price Bid the following additional documents: a) Form PB-DEV: Proforma for Cost of each of Minor Deviations/ Nonmaterial Nonconformity.
ITB 13.1	Alternative times for completion will not be permitted.
ITB 13.2	Alternative Bids will not be permitted.
ITB 14.5	**Deleted and add following:** The rates of the accepted Price Bid as per ITB 38.1 shall be applicable till the completion of the Work and will be varied only to the extent of permissible price variation under Clause 13.8 of Particular Conditions. However, this adjustment shall be to the extent that full compensation for any rise or fall in costs to the Contractor if not covered by the Price variation formula, the rates in the accepted Price Bid shall be deemed to include amounts to cover the contingency of such rise or fall in costs.
ITB 15.1	The prices shall be quoted by the bidder in the price schedules separately in INR only as described below: **For Schedule – A, B & C** The percentage above/below or at par the basic amount given in INR shall be quoted by the Bidder in the Price Schedule -A, B & C.
ITB 16.2	"At this time the Employer does not intend to execute certain specific parts of the Works by subcontractors (i.e.: nominated Subcontractors) selected in advance."
ITB 18.1	The Bid validity period shall be **120** days.
ITB 18.3(a)	Not applicable.
ITB 19.1	The amount and currency of the Bid Security shall be **INR 17.10 Million**
ITB 19.2	For submission of Bid Security in "Original", the Employer's address is: Office of Sr. General Manager/Contracts Delhi Metro Rail Corporation Limited 5th floor, A-Wing, Metro Bhawan Fire Brigade Lane, Barakhamba Road New Delhi-110001, India. The deadline for submission of Bid Security in "Original" is: Date: ~~**11.05.2026**~~ ~~**13.05.2026**~~ ***28.05.2026*** Time: **1500hrs**

	Convention 1961. 4) In case any accompanying printed document is in language other than the English, it shall be accompanied by an accurate translation in English by the authorized translator along with sign and stamp of translator. The translated documents shall be duly notarized by the notary public of country of origin and should be either stamped by Embassy/ High Commission of India in that Country or Apostilled if the bidder is from a country which has signed the Hague Legislation Convention 1961.
D. Submission and Opening of Bids	
ITB 21.1	Bidders shall submit their Technical Bid and Price Bid on e-tendering website ***https://eprocure.gov.in/eprocure/app***.
ITB 21.2	Not Applicable.
ITB 21.3	Not Applicable.
ITB 21.4	Not Applicable.
ITB 21.5	Not Applicable.
ITB 21.6	Not Applicable.
ITB 22.1	Bidders shall submit their Technical Bid and Price Bid on e-tendering website ***https://eprocure.gov.in/eprocure/app***. The deadline for Bid submission is: Date:~~**11.05.202613.05.2026**~~ ***28.05.2026*** Time: **1500hrs**
ITB 24.1	Not Applicable.
ITB 24.2	Not Applicable.
ITB 24.3	Not Applicable.
ITB 25.1	The Technical Bid shall be opened on e-tendering website ***https://eprocure.gov.in/eprocure/app*** The date and time for Opening of Technical Bids is: Date: ~~**12.05.2026 14.05.2026**~~ ***29.05.2026*** Time: **1500hrs**
ITB 25.2	Not Applicable.
ITB 25.3	Not Applicable.
ITB 25.4	Not Applicable.
ITB 25.5	Not Applicable.
ITB 25.7	At the end of the evaluation of Technical Bids, the Employer will notify the Bidders, on e-tendering website

2.4.2 (b)		(b) For the above or other contracts completed and under implementation as prime contractor[(i)] (single entity or JV member) or subcontractor[(vi)] between 1st January 2016 and Bid submission deadline, ~~a~~ minimum experience in the following key activity successfully completed[(iii)] **i. Key Activity:<u>The bidder should have experience of "Pre-engineered steel structures including roof sheeting"</u>** The **<u>total</u>** cost of "**~~pre-fabricated~~ <u>Pre-engineered</u>** steel structures including roof sheeting" should be of value of INR **107.2 Million** or more in the above work(s) **~~put together~~.** ii. In case the bidder does not have required work experience of "**~~pre-fabricated~~ <u>Pre-engineered</u>** steel structures including roof sheeting" of value equal to or more than **INR 107.2 Million** in the above works, then bidder **~~has~~ <u>is required</u>** to submit one separate additional work of "**~~pre-fabricated~~ <u>Pre-engineered</u>** steel structures including roof sheeting" of value of INR **107.2 Million** or more in a single work. iii. Further, in case the bidder does not have required work experience of "Pre-engineered steel structure with roof sheeting" of value of INR **107.2 Million** or more in the qualifying works under 2.4.2 (a) or in a separate single work **<u>as stated in 2.4.2 (b) above</u>** and intends to engage a sub-contractor for this work, **~~the~~ <u>such</u>** sub-contractor must have executed work of "Pre-engineered steel structure with roof sheeting" of value of INR **107.2 Million** or more in a single work. **Bidder shall submit an undertaking in this regard along with their technical bid.**	Must meet requirement.	Must meet requirement [(v)]	N/A	N/A	Form ELI-3, Form EXP-2(b) with attachments.

Contract D2C-08: Civil works including earth filling and construction of depot buildings, workshop, Inspection shed, plumbing, drainage, external development, architectural finishes, road works, design and construction of PEB works at Sanoth Depot of Rithala-Kundli Corridor of Delhi Metro Phase - IV.

ABSTRACT OF SCHEDULE - A, B & C

SUB HEAD NO.	DESCRIPTION OF SUB HEADS		TOTAL AMOUNT (in Rs.) (Rates in schedule A, B & C are inclusive of all taxes and duties)
A	SCHEDULE - A : CIVIL & PLUMBING WORKS	DSR 2023 ITEMS	₹ 1,09,98,46,855
B	SCHEDULE - B : CIVIL & PLUMBING WORKS	NDSR ITEMS	₹ 34,16,01,238
C	SCHEDULE - C : PEB WORKS	NDSR ITEMS	₹ 26,81,46,908
	GRAND TOTAL		₹ 1,70,95,95,001

Overall load of PEB structures shall be calculated and provided by the contractor to the ~~**DDC**~~ **Detailed Design Consultant of Employer** for foundation design.

A. **Design and execution of Pre-Engineered buildings including portals, purlins, sheeting, gutters, down take pipes etc for the PEB at Sanoth Depot.**

All the fabrication works involve welding of structural steel plates. Only Automatic submerged arc welding is permitted. It is also planned that all the site connections of fabricated members will be done by using HSFG (HIGH STRENGTH FRICTION GRIP) bolts. Hence Contractor has to make the holes for the site bolted connection while fabricating the members. All the HSFG bolts and its compatible nuts and washers will be also supplied by the contractor. All the plates used for fabrication has to be sand blasted and coated with primer and internal and external painting coats as specified in Technical Specifications. The fabricated members are required to be loaded and transported to site for assembly and erection etc. by the Contractor.

B. **Design and construction of Pre-Engineered Buildings for Workshop & Inspection sheds etc. including sheeting, gutters, provision for EOT Cranes, OHE drop arm, termination support & louvers.** ~~**Tenderers will arrange design of steel roof with all its connections and related components. Design will be evaluated at the time of technical package evaluation.**~~ Design criteria and material specifications for structural steel members shall be as per Outline Design Specification (Revision-2, July 2021), Outline Construction Specifications for Civil Works (Revision - 4, June 2025). ~~**Tenderers**~~ The contractor is required to submit ~~**with technical bid**~~ the following details:

i. General arrangement drawing of all buildings showing all structural elements including bracings, sag rods, holding down bolts etc.
ii. Sizes of all major members including purlins, portals, gutters, down take pipes etc.
iii. List of codes of standards in addition to those mentioned in specifications.
iv. Basic design calculations establishing sizes of structural members.

C. Fabrication & supply of steel roof of depot buildings as per Technical Specifications will include the following but not limited:

i. Preparation of complete detailed fabrication drawings based on the design drawings, required for all the permanent structures.
ii. Submission of revised design with calculations and detailed fabrication drawings, in case any substitution of the designed sections is required.
iii. Procurement of all raw steel materials for fabrication, taking into account wastage margin, including storage and upkeep of the materials.

DMRC being a socially and environmentally responsible organisation promotes the practice of utilising recycled waste products. Special attention of the tenderers is drawn towards clause 52.7.3 of Conditions of Contract on Safety, Health & Environment – Construction and Demolition Waste.

Also. Department of urban development, GNCTD vide its letter no. F.No. 7(84)/AD/LB/2016/5782-5805 dated 06.07.2016 has ordered the following measures for compliance of all Municipal/Local and Government bodies in Delhi subject to strict quality control.

i) A minimum of 2% of C&D recycled products shall be used for building works.
ii) At least 10% of C&D products shall be used for Road works.
iii) At least 10% of C&D products shall be used for Finishing works.

In addition, Engineer-In Charge may issue directions for use of C&D waste recycled products as and when necessary.

BIS 383:2016 shall also be read in conjunction with DMRC's of Conditions of Contract on Safety, Health & Environment which permits the use of manufactured aggregate namely recycled aggregate (RA) and recycled concrete aggregate (RCA) in lean concrete, PCC and RCC. DPCC's direction dated 14.01.2020 states that the agencies shall expedite and maximize the utilization of C&D waste recycled product. Further, the payment to contractor shall be stopped by DMRC if the materials are not being used by the contractor. ***The contractor shall dispose off their construction & demolition waste only at an authorized/approved C&D recycling facility. For such disposal, no processing fee will be reimbursed to the contractor. No separate payment shall be made for transportation of C&D waste, regardless of lead distance.***

A compliance report containing details of C&D waste recycled products being used by the contractor in the project shall be submitted along with the Monthly Environment report to DMRC.

10. URBAN PLANNING FUNCTIONAL REQUIREMENTS

1) Requests for temporary power supplies for the construction of the works must be submitted by the contractor to the concerned authorities. Alternatively separate power supplies may be arranged by the Contractor independent of concerned electricity distribution/transmission authority subject to compliance with all necessary statutes.

2) In addition, a number of agencies are involved in the reinstatement works, permanent road accesses, temporary road accesses, refuse collection accesses, street lighting, traffic management and fire hydrant positions. The Contractor is responsible for obtaining the approvals for these other works.

contracts under the Employer.

(ii) Rock crushing plant shall not be used on the Site.

(iii) The location and size of each stockpile of materials, including excavated materials, within the Site shall be as permitted by the Engineer. Stockpiles shall be maintained at all times in a stable condition. ~~**Due to unavailability of space in the existing depot, stockpile of materials, including excavated materials within the site shall not be permitted by the Engineer.**~~

(iv) Entry to and exit from the Site shall be controlled and shall be only available at the locations for which the Engineer has given his consent.

ACCESS TO THE SITE

(v) The Contractor shall make its own arrangements, subject to the consent of the Engineer, for any further access required to the Site.

(vi) In addition, the Contractor shall ensure that access to every portion of the Site is continually available to the Employer and Engineer.

(vii) Following the handover of the Railway Envelope, (as defined in the Employer's Requirements- General), to the Employer, the Employer will control the Railway Envelope and will be responsible for all matters relating to security and safety therein. Access to the Railway Envelope by the Contractor shall be in accordance with any procedures, requirements and conditions defined in Employer's Requirements – (if applicable).

(viii) The Employer shall grant the Contractor right of access to, and / or possession of, the Site progressively for the completion of Works. Such right and possession may not be exclusive to the Contractor. The Contractor will draw/modify the schedule for completion of Works according to progressive possession/right of such sites.

(ix) The Employer will not provide any machinery or materials under the Contract.

ACCESS TO OUTSIDE THE SITE

(x) The Contractor shall be responsible for ensuring that any access or egress through the Site boundaries are controlled such that no disturbance to nearby residents or damage to public or private property occur as a result of the use of such access or egress by its employees and sub-contractors.

SURVEY OF THE SITE

(xi) A survey shall be carried out of the Site to establish its precise boundaries and the existing ground levels within it. This survey shall include a drone cum photographic survey sufficient to provide a full record of the state of the Site before commencing the work with particular attention paid to those areas where reinstatement will be carried out later on. The survey shall be carried out before the site clearance wherever possible and in any case prior to the commencement of work in any Works Area. The survey shall be carried out

to the Engineer during inspection

14. MATERIALS

(i) Materials and goods for inclusion in the Permanent Works shall be new unless the Engineer has consented otherwise. Preference shall be given to local materials where available**. Approved Manufacturers/Suppliers of few important items have been given in Appendix 10 of Employer's Requirements.** These materials shall be procured only for these manufacturers/Suppliers.

(ii) Certificates of tests by manufacturers which are to be submitted to the Engineer shall be current and shall relate to the batch of material delivered to the Site. Certified true copies of certificates may be submitted if the original certificates could not be obtained from the manufacturer.

(iii) Parts of materials which are to be assembled on the Site shall be marked to identify the different parts.

(iv) Materials which are specified by means of trade or proprietary names may be substituted by materials from a different manufacturer which has received the consent of the Engineer provided that the materials are of the same or better quality and comply with the specified requirements.

(v) Samples of materials submitted to the Engineer for information or consent shall be kept on the Site and shall not be returned to the Contractor or used in the Permanent Works unless permitted by the Engineer. The samples shall be used as a mean of comparison which the Engineer shall use to determine the quality of the materials subsequently delivered. Materials delivered to the Site for use in the Permanent Works shall be of the same or better quality as the samples which have received consent.

PROVISION AND DISPOSAL OF EARTHWORKS MATERIAL

(vi) The Contractor shall be responsible for the provision of all classes of earthworks material required for the Works, whether sourced from the excavations within the Contract or obtained from any other sources, which are located outside the Site, for which the Engineer has given the consent.

(vii) For fill or dumping sites, the Contractor shall prepare a land plan with details of surface drainage requirements, final formation levels, spreading and compaction of the fill during dumping acceptable to the Engineer. The Contractor shall also provide security for such sites. The dumping sites to be used by the Contractor shall be designated site or as directed by the Engineer.

(viii) ~~**All excavated material, excluding waste material, Polymer fluid and Polymer contaminated material shall be disposed of at the appointed site only. This material shall be placed and compacted in accordance with the Construction Specification for Earth Works or as otherwise directed by the Engineer's Representative. The disposal of waste material, Polymer fluid and material contaminated with Polymer shall be the full responsibility of the Contractor and these materials shall be disposed of by the Contractor at an approved location. The dumping sites provided by the Employer shall not be used for disposal of waste material, Polymer fluid or material contaminated with**~~

~~**Polymer.**~~

All excavated material, excluding waste material, Polymer fluid and Polymer contaminated material up to a distance of 40kms from the worksite shall be disposed at the appointed dumping site in Delhi or National Capital Region (NCR)—primarily located at Mundka or as otherwise directed by the Engineer. This material shall be placed and compacted in accordance with the Construction Specification for Earth Works or as otherwise directed by the Engineer's Representative. The disposal of waste material, Polymer fluid and material contaminated with Polymer shall be the full responsibility of the Contractor and these materials shall be disposed of by the Contractor at an approved location. The dumping sites provided by the Employer shall not be used for disposal of waste material, Polymer fluid or material contaminated with Polymer.

All excavated material comprising rock, moorum, or mixed soil-rock-moorum shall be considered the property of DMRC and shall be disposed of by the Contractor in accordance with the Engineer's instructions, which may include segregation, stockpiling, or reuse.

(ix) Rock deposited as fill material at the dumpsites shall be capable of compaction with single pieces no larger than 300 mm.

15. PROVISIONS FOR DESIGNATED CONTRACTORS

Interface responsibilities mentioned in Appendix – 2D, shall be followed by the Civil Contractor.

16. RESTORATION OF AREAS DISTURBED BY CONSTRUCTION.

Unless otherwise directed by the Engineer, any areas disturbed by the construction activity, either inside or outside the Project Right of Way, shall be reinstated as follows:

All areas affected by the construction work shall be reinstated to their original condition, with new materials, including but not necessarily limited to, sidewalks, parking lots, access roads, roads, adjacent roads properties, footpath, kerbstone, boundary wall, grill, fencing, grill, bore well, bus shelter, horticulture and landscaping. Grass cover shall be provided for any bare earth surface areas, along with proper provisions for surface drainage.

17. LANDSCAPING

Landscaping design must be submitted to the relevant authorities and match the remaining areas. In addition, the Contractor shall carry out the design and construction of landscaping for all works areas and will submit his proposals to the relevant authorities for approval before commencement of landscaping works.

EMPLOYER'S REQUIREMENTS

APPENDIX 10

APPROVED MANUFACTURERS/ SUPPLIERS LIST

~~**The list of approved manufacturers/suppliers list is issued separately with tender documents**~~**.**

The List of approved manufacturers / suppliers (as on date) for civil works, architectural finishing works and major electrical items is issued with the tender documents. However, the list of empanelled manufacturers/suppliers keeps getting updated from time to time; the latest list available on the DMRC website may be followed.

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Civil Items (as on 17.04.2026)

All materials and products shall conform to the Outline Construction Specification (OCS) of DMRC, BIS codes, and other relevant codes, etc., and shall be of make as approved by DMRC.

In addition to above, following may be noted:

1) Once the manufacturer / supplier supplies the product for any project, all the tests required in OCS are to be performed to ensure the quality of product at work site as per the approval of engineer-in-charge.
2) In case the manufacturer / supplier does not have a valid document / certificate at the time of usage at site, then the product shall not be allowed for usage at site.

Category No.	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
C1	Cement	*Category deleted – Approval of manufacturer / supplier for all contracts shall be processed by the field unit concerned.*	-
C2	Reinforcement Bars	*Category deleted – Approval of manufacturer / supplier for all contracts shall be processed by the field unit concerned.*	-
C3	Epoxy Grout	• Fosroc • Asian Paints • Sunanda • Sika • Fairmate • Kunal Conchem • Hindcon Chemicals • STP Limited • Apple Chemie	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C4(a)	Expansion Joints for Viaduct	• Prequalified Manufacturers as per RDSO's latest approved list • DECG International	 09.10.2030
C4(b)	Expansion Joints for Buildings	• VR Engineers • MAURER-Sanfield • DECG International	27.09.2026 27.09.2026 27.09.2026
C5	Admixtures	*Category deleted – Approval of manufacturer / supplier for all contracts shall be processed by the field unit concerned.*	-
C6(a)	Low strain Pile Integrity Testing, UPV Test, Rebound Hammer Test	• CEG Test House • Aadco Testing • Cengrs • DVG Lab • ADS Labtech • Raicon Labs Pvt. Ltd. • Innovato Solution • Independent Consultants & Technocrates Pvt. Ltd. • QA Testing Lab Note: Testing shall be permitted only for those tests for which the testing agency holds a valid NABL accreditation certificate.	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030 09.10.2030 09.10.2030 09.10.2030

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Civil Items (as on 17.04.2026)

Category No.	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
C6(b)	Cross-hole Testing of Piles	• CEG Test House • Aadco Testing • Cengrs • ADS Labtech • Independent Consultants & Technocrates Pvt. Ltd. • QA Testing Lab Note: Testing shall be permitted only for those tests for which the testing agency holds a valid NABL accreditation certificate.	27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030 09.10.2030
C7	Anchor Fasteners (for Structural works)	• Trutek • Pioneer nuts and bolts • Fosroc • Hilti • Styrene Packings • Fischer • Wuerth	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C8	Structural Steel (Fabrication)	*Category deleted – Approval of manufacturer / supplier for all contracts shall be processed by the field unit concerned.*	-
C9	Pre-stressing Strand (LRPC)	• Tata SSL Ltd. • Usha Martin • DP Wires • Miki Steel • Kataria Group • Bajrang Wire and Infra Ltd. • Neotrex Steel	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C10(a)	Pot/PTFE Bearings	• Deevin Systems • VSIL • MAURER-Sanfield • Dynamic Prestress • Kanta Rubber • CECO • RKC Infra Projects • Steel Auto Industries • DECG International	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030
C10(b)	Elastomeric Bearings	• Deevin Systems • VSIL • Kanta Rubber • Polymer Products • DECG International • CECO • RKC Infra Projects • Steel Auto Industries	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C10(c)	Spherical Bearings	• MAURER-Sanfield • Mageba	27.09.2026 27.09.2026

OS Saini 17/04
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Civil Items (as on 17.04.2026)

Category No.	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
C11	Horizontal Tie Bars / Shear Bars	• Dextra	27.09.2026
C12	High-Density Polyethylene (HDPE) Sheathing (for Prestressing works)	• Dynamic Prestress • JK Prestressing • Fosroc • Tirupati Plastomatics	27.09.2026 27.09.2026 27.09.2026 27.09.2026
C13	Formwork Release Agent	• Eastern Petroleum • Yahska Polymers • Kunal Conchem • Ado Additives • STP Limited • Fairmate • Hindcon Chemicals • Apple Chemie	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C14	Prestressing System	• Dynamic Prestress • Tensa India • JK Prestressing • Usha Martin	27.09.2026 27.09.2026 27.09.2026 27.09.2026
C15	Reinforcement Couplers (cold forged parallel threaded type)	• Tata Steel • MAURER-Sanfield • Dextra India • Leviat India • Rebar Couplers India Pvt. Ltd. • Vadol Corporation • Vruddhi Engineering Works Ltd. • SNTP Technologies	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030 09.10.2030 16.10.2030
C16	Hollow Sections, Tubes	• Surya Roshni • Dadu Pipes • APL Apollo Tubes • Tata Steel • Goodluck India Ltd. • Mahalakshmi Profiles Pvt. Ltd.	27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030 09.10.2030
C17	Drainage Pipes (> 150 mm dia.)	• Texmo Pipes • Tirupati Plastomatics	27.09.2026 27.09.2026
C18	Non-Shrink Grout	• DURABUILD • Yahska Polymers • Fosroc • Asian Paints • Sika India • Kunal Conchem • Fairmate • STP Limited • Chryso India • Mapei • MYK Arment • Hindcon Chemicals • Apple Chemie	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Civil Items (as on 17.04.2026)

Category No.	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
C19	Epoxy Bonding Agent (for Construction Joint)	• Asian Paints • STP Limted • Fairmate • Chryso India	27.09.2026 27.09.2026 27.09.2026 27.09.2026
C20	Polysulphide Sealant (for Structural works)	• Asian Paints • Sika • Kunal Conchem • IWL India • Hindcon Chemicals • STP Limited • Fairmate • Chryso India • Apple Chemie	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C21	Steel Structural Fasteners	• Panchsheel Fasteners • Pioneer Nuts and Bolts • Kirti Fasteners • Haryana Fasteners • Imperial Bolts and Fasteners • Karamtara	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C22	Corrosion Protection Paints	• Berger Paints • Fosroc • Advance Paints • Grauer & Weil India • Sunanda • Asian Paints • Ameetuff Technical Paints	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C23	Microsilica / Ultra-Fine Ground Granulated Blast Furnace Slag (UGGBS) (conforming to IS 16715:2018)	• Ultrafine Minerals and Admixtures • Counto Microfine Products • Rockfit • CAC • Kunal Conchem • Hindcon Chemicals • Pinnacle • Normet India • Technokem • Mapei • Sunlight Conschem Corporation	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030
C24	Fire Resistant Paint	• Advance Paints • Asian Paints • Ameetuff Technical Paints	27.09.2026 27.09.2026 27.09.2026
C25	Integral Crystalline Waterproofing	*Category deleted – Approval of manufacturer / supplier for all contracts shall be processed by the field unit concerned.*	-
C26	Water Stopper / Bar	• Asian Paints • HITECH Rubber • Penetron • Kantaflex • Puraflex Industries	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Civil Items (as on 17.04.2026)

Category No.	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
C27	Liquid Polymer Membrane Waterproofing	• Pidilite • Berger Paints • TECHNONICOL • Fosroc • Asian Paints • ECMAS • Sika • Kunal Conchem • Sunanda • Fairmate • Hindcon Chemicals • STP Limited • Chryso India • Mapei • MYK Arment • Tiki Tar Danosa	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026
C28	Curing Compound	*Category deleted – Approval of manufacturer / supplier for all contracts shall be processed by the field unit concerned.*	-
C29	Polycarbonate Sheets	*Category deleted and moved under Item A12 of the 'List of Empanelled Manufacturers / Suppliers of Major Architecture Items'. Applicants desiring empanelment need to submit application for the Architecture item.*	-
C30	Fly Ash / Ground Granulated Blast Furnace Slag (GGBS) (conforming to IS 16714:2018)	• Ashtech India • Jaycee Buildcorp • Bisla Industries • Shree Ashtech	27.09.2026 27.09.2026 27.09.2026 09.10.2030
C31	Pre-Coated Profiled Metal Sheeting	• Aditya Profiles • Tata Bluescope Steel • APL Apollo Building Products Pvt. Ltd.	27.09.2026 27.09.2026 09.10.2030
C32	Sodium Silicate (for grouting purposes during TBM operations)	• Kunal Conchem • National Glass Works • Kiran Global Geocements Ltd. • Sri Varahi Chemicals • Asian Laboratories • Deepak Chemicals • Shubham Mineral Co.	27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030 09.10.2030 09.10.2030
C33	AAC Block	• Magicrete • JK Lakshmi • OFB Tech	27.09.2026 27.09.2026 27.09.2026
C34	Tunnel Segment EPDM	• Daeryong India • FIP • Datwyler	27.09.2026 27.09.2026 27.09.2026
C35	Rock Bolts / Swellex Bolts	• Sandvik Mining	27.09.2026

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Civil Items (as on 17.04.2026)

Category No.	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
C36	Glass Fiber Reinforced Polymer (GFRP) Bars (conforming to IS 18255:2023, IS 18256:2023, and IRC:137-2022)	• Sandvik Mining • Arc Insulations • Dextra	27.09.2026 27.09.2026 27.09.2026
C37	Material Testing	*Category deleted – Approval of manufacturer / supplier for all contracts shall be processed by the field unit concerned.*	-
C38	Rainwater Harvesting	• Water Field Technology	27.09.2026
C39	Geotechnical Investigation	• Scientific Infra • CEG Test House • Shree Balaji Test House • Emmtech • CENGRS • G. Soil & Rock Probe • Sarathy Geotech • SECON • Techpro India • Independent Consultants & Technocrates Pvt. Ltd. • Innovato Solution • QA Testing Lab	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030 09.10.2030
C40	Premix Prestress Cable Grouts	• Fosroc • Ultratech	27.09.2026 27.09.2026
C41	Ultrasonic Logging Tubes	• MAURER-Sanfield • Dextra	27.09.2026 27.09.2026
C42	Welding Electrodes	• Alpha Arc Electrode • Varun Electrodes • Weld Alloy Products • D&H Secheron • Spectra Super Alloys Ltd.	27.09.2026 27.09.2026 27.09.2026 27.09.2026 09.10.2030
C43	Ultrafine Fly Ash	• Ashtech India • Ultrafine Mineral and Admixtures	27.09.2026 27.09.2026
C44	Drilling Polymer	• Sugam Infra • Innova • Manoj Kumar Kharakia Co. • Laviosa • Neel Kanth Chemicals • Trishul • Relemac India • ECO Drilling • Goldy Minerals • Vidhya Enterprises • Drilltech Fluid and Chemicals	27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026 27.09.2026

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Civil Items (as on 17.04.2026)

Category No.	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
C45	Anti-Carbonation Coating of RCC Structures	• Asian Paints	27.09.2026
		• Godavari Paints	27.09.2026
		• Fairmate India	27.09.2026
		• Sunanda	27.09.2026
		• Fosroc	27.09.2026
		• STP Limited	27.09.2026
		• Ameetuff Technical Paints	27.09.2026

17/04/2026

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Note: In case the manufacturer / supplier does not have required valid documents / certificates at the time of usage at site, then the product shall not be allowed for usage at site.

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A1	Flooring	Vitrified Tiles (Plain, Designer and Tactile)	• H&R Johnson	02.10.2030
			• Kajaria	02.10.2030
			• Oasis (Marbomax Group)	02.10.2030
			• Orient Bell Ceramics	02.10.2030
			• Pavit Ceramics	02.10.2030
			• Pelican Ceramics	02.10.2030
			• Qutone Tiles	02.10.2030
			• RAK Ceramics	02.10.2030
			• Restile Ceramics	02.10.2030
			• Royale Touch and Silk Touch Vitrified	02.10.2030
			• Simpolo	02.10.2030
			• Varmora Granito	02.10.2030
			• Vitero	02.10.2030
			• Sunshine Tiles Co. Pvt. Ltd. (Sunhearrt Ceramik)	02.10.2030
			• Karara Ceramics Pvt. Ltd.	02.10.2030
			• Hindware	02.10.2030
			• Somany Ceramics Pvt. Ltd.	02.10.2030
			• Ambani Vitrified Pvt. Ltd.	26.10.2030
			• Mozart Vitrified Pvt. Ltd.	26.10.2030
			• Nitco Tiles Ltd.	26.10.2030
		Ceramic / Porcelain Tiles	• H&R Johnson	02.10.2030
			• Kajaria	02.10.2030
			• Oasis (Marbomax Group)	02.10.2030
			• Orient Bell Ceramics	02.10.2030
			• Qutone Tiles	02.10.2030
			• Simpolo	02.10.2030
			• Varmora Granito	02.10.2030
			• Somany Ceramics Pvt. Ltd.	02.10.2030
			• Hindware	02.10.2030
			• Karara Ceramics Pvt. Ltd.	02.10.2030
			• Sunshine Tiles Co. Pvt. Ltd. (Sunhearrt Ceramik)	02.10.2030
		Raised Floor	• Hewetson / Kingspan Access Floors	02.10.2030
			• United Access Floors / United Insulation	02.10.2030
			• AET Flexiblespace India Pvt. Ltd. (FLEXIFLOOR)	26.10.2030
			• Universal Building Products Pvt. Ltd. (UNIFLOOR)	26.10.2030
		Polyurethane / Epoxy Coated Flooring	• Cipy Polyurethanes	02.10.2030
			• Flowcrete	02.10.2030
			• Pidilite	02.10.2030
			• Shalimar Paints	02.10.2030
			(contd...)	

17/04
OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A1	Flooring	Polyurethane / Epoxy Coated Flooring	• Sika	02.10.2030
			• Hygie Profile (India) Pvt. Ltd.	02.10.2030
			• Berger Paints India Ltd.	02.10.2030
			• STP Ltd.	02.10.2030
			• Ulfcar Chemicals Pvt. Ltd. (DenCoat)	26.10.2030
			• RachTR Chemicals Pvt. Ltd.	26.10.2030
			• JSW Paints Ltd.	26.10.2030
			• Growel (Grauer & Weil)	26.10.2030
		Concrete Pavers, Kerbs and Chequered Tiles, Paving Tiles, Grass Paver, Plantable Blocks, Hollow Blocks, Retaining Blocks, Slope Stone	• Chelsea Concrete	02.10.2030
			• Dalal Tiles	02.10.2030
			• Pave Espania	02.10.2030
			• Sarita Pre Fab	02.10.2030
			• Perfect Tiles	02.10.2030
			• JRC Brickworks Pvt. Ltd.	02.10.2030
			• KJS Concrete	02.10.2030
			• Parmeshwari Enterprises	26.10.2030
		Ceramic or Glass Mosaic Tiles / Handmade Tile Mosaic Tiles	• Bisazza	02.10.2030
			• GND Tiles	02.10.2030
			• Italica Mosaic	02.10.2030
			• Kenzai Ceramic	02.10.2030
			• Mridul Enterprises	02.10.2030
			• Mosaico People Corporation	02.10.2030
			• Raja Tiles	02.10.2030
			• Ayush Inter Décor	02.10.2030
A2	Finishing	Pre-mix Cement Plaster	• Birla-Aerocon	02.10.2030
			• Ultratech Cement Ltd.	02.10.2030
			• Ambuja Cements	02.10.2030
			• ACC	02.10.2030
			• Trimurti	02.10.2030
			• Pidilite	24.11.2030
		Emulsion Paints	• Acro Paints	02.10.2030
			• AkzoNobel	02.10.2030
			• Asian Paints	02.10.2030
			• Berger Paints	02.10.2030
			• BSC Paints	02.10.2030
			• Godavari Paints	02.10.2030
			• Jenson & Nicholson	02.10.2030
			• Kamdhenu Paints	02.10.2030
			• Nerolac Paints	02.10.2030
			• IMAGICO India Pvt. Ltd. (previously OIKOS India Pvt. Ltd.)	02.10.2030
			• Shalimar Paints	02.10.2030
			• Sherwin-Williams Paints	02.10.2030
			• Luxture Surface Coatings Pvt. Ltd.	02.10.2030
			• JSW Paints Ltd.	26.10.2030
			• Growel (Grauer & Weil)	26.10.2030
			• JK Maxx Paints Ltd.	24.11.2030

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A2	Finishing	Synthetic Enamels	• Acro Paints	02.10.2030
			• AkzoNobel	02.10.2030
			• Asian Paints	02.10.2030
			• Berger Paints	02.10.2030
			• Jenson & Nicholson	02.10.2030
			• Kamdhenu Paints	02.10.2030
			• Nerolac Paints	02.10.2030
			• Shalimar Paints	02.10.2030
			• Sherwin-Williams Paints	02.10.2030
			• Maharani Innovative Paints Pvt. Ltd.	02.10.2030
			• JSW Paints Ltd.	26.10.2030
			• Growel (Grauer & Weil)	24.11.2030
		Polyurethane Paints / Epoxy Paints	• AkzoNobel	02.10.2030
			• Asian Paints	02.10.2030
			• Jenson & Nicholson	02.10.2030
			• MRF Paints	02.10.2030
			• Nerolac Paints	02.10.2030
			• Shalimar Paints	02.10.2030
			• Sherwin-Williams Paints	02.10.2030
			• Berger Paints India Pvt. Ltd.	02.10.2030
			• Ameetuff Technical Paints	02.10.2030
			• JSW Paints Ltd.	26.10.2030
			• Growel (Grauer & Weil)	24.11.2030
		Bonding Coat / Primer (for Paint)	• Pidilite	02.10.2030
			• Dr. Fixit	02.10.2030
			• Ameetuff Technical Paints	02.10.2030
			• Fosroc	02.10.2030
			• Ultratech Cement Ltd.	26.10.2030
			• Growel (Grauer & Weil)	24.11.2030
			• Premium Coatings and Chemical Pvt. Ltd.	24.11.2030
		Texture Paint	• AkzoNobel	02.10.2030
			• BSC Paints	02.10.2030
			• Berger Paints India Pvt. Ltd.	02.10.2030
			• Luxture Surface Coating Pvt. Ltd.	02.10.2030
			• Ultratech Cement Ltd.	26.10.2030
			• JK Maxx Paints Ltd.	24.11.2030
		Wall Care Putty	• Birla (Aditya Birla Group)	02.10.2030
			• EBIPL: Evershine	02.10.2030
			• Gyproc Wall Putty (Saint-Gobain)	02.10.2030
			• HIL Ltd. (Aerocon)	02.10.2030
			• JK White	02.10.2030
			• Shalimar Paints	02.10.2030
			• Berger Paints India Pvt. Ltd.	02.10.2030
			• Ferrous Crete India Pvt. Ltd.	02.10.2030

(contd...)

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A2	Finishing	Wall Care Putty	• Luxture Surface Coating Pvt. Ltd. • Trimurti Wall Care Products Pvt. Ltd. • Ultratech Cement Ltd. • JSW Paints Ltd. • Growel (Grauer & Weil)	02.10.2030 26.10.2030 26.10.2030 26.10.2030 24.11.2030
		Glass (Float / Toughened)	• Asahi Float (AIS) • Glaverbel • Modiguard • Saint-Gobain • Art N Glass Group Company • Şişecam Glass India Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Fire Rated Glass	• FG Glass • Pilkington Glass • Saint-Gobain • Asahi India Glass Ltd. (AIS)	02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Structural Glazing Fabricators	• Permasteelisa India Pvt. Ltd. • Alufit India Pvt. Ltd. • Shapoorji Pallonji Fab Pvt. Ltd. • Innovators Façade Systems Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030
A3	Cladding	GRC Products (GRC Screen, Panels, etc.)	• Dalal Tiles • Terra firma GRC & Concrete Industries • UniStone Products (India) Pvt. Ltd. • Ayush Inter Décor • Everest Composites Pvt. Ltd. • Mahesh Prefab Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030
		High Pressure Laminate	• Fundermax • Greenlam • Merino • Century Plyboards • Virgo Laminates Ltd. • Samrat Plywood Ltd. • Stylam Industries • Stonelam Surface LLP	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Acrylic Solid Surface	• DuPont Corian • LX Hausys HIMACS (previously LG Hausys HIMACS)	02.10.2030 02.10.2030
A4	False Ceiling	Calcium Silicate Board	• Aerolite • Ramco Hilux • Promat	02.10.2030 02.10.2030 02.10.2030
		Metal Ceilings	• Knauf Ceiling Solutions (previously Armstrong World Industries) • Dexune • durlum *(contd...)*	02.10.2030 02.10.2030 02.10.2030

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A4	False Ceiling	Metal Ceilings	• Hunter Douglas • Canon Fasteners • SCJ Mascot LLP (Metacil) • JC Industries • Royal Kraft (Manraj Ceiling Products) • Harsons & Associates (Harsons Green)	02.10.2030 02.10.2030 26.10.2030 26.10.2030 26.10.2030 26.10.2030
A5	Adhesive, Fillers, and Sealants	Adhesive for Tiles	• Araldite • EBIPL: Evershine • Kerakoll • Laticrete • Pidilite • Alstone Industries Pvt. Ltd. • Ultratech Cement Ltd. • Berger Paints India Ltd. • Ferrous Crete India Pvt. Ltd. • Trimurti Wall Care Products Pvt. Ltd. • RachTR Chemicals Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030 26.10.2030
		Tiles Joint Filler, Tile Grouts	• Ardex Endura (previously Bal Adhesives and Grouts) • EBIPL: Evershine • GE Bayer Silicones • Laticrete • MC-Bauchemie (India) • Roff Constructions Chemicals • Ultratech Cement Ltd. • Berger Paints India Ltd. • Kerakoll • Alstone Industries Pvt. Ltd. • Ferrous Crete India Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Polysulphide Sealants (for Stone / Vitrified Tiles)	• 3M • BASF • CICO • Fosroc • McCoy Soudal • Pidilite • Sika • STP Ltd. • MYK Arment • Berger Paints India Ltd. • Ferrous Crete India Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Silicon Sealants	• 3M • Dow Corning • GE Bayer Silicones • McCoy Soudal • Sika • Alstone Industries Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030

17/04
OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A5	Adhesive, Fillers, and Sealants	Silicon Water Repellent Solution	• Choksey Chemicals • MC-Bauchemie • GE Bayer Silicones • STP Ltd. • Wacker Metroark	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
A6	Joinery Woodwork Products	Plywood	• Duroply Sarda Plywood • Century Ply • Greenply Plywood • Swastik Plyboard Ltd. (Swati Ply) • Merino • Archidply • Visaka Plywood • Vidya Ply & Board • Greenpanel Industries Ltd. • Samrat Plywood Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030
		Blockboard	• Century Ply • Duroply Sarda Plywood • Greenply Plywood • Merino • Vidya Ply & Board • Greenpanel Industries Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Laminates	• Archidply • Formica Corporation • Greenlam • Merino • Royal Touche Laminates • Stylam Industries • Samrat Plywood Ltd. • Virgo Laminates Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Dry Partition System	• Aerocon (HIL Ltd.) • Metecno • V-Board (Visaka Industries Ltd.)	02.10.2030 02.10.2030 02.10.2030
		Toilet Cubicles and Compact Laminated Doors	• Fundermax • Greenlam • Merino • Stylam Industries • Century Panels Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 24.11.2030
		Pressed Steel Doors Frame	• AGEW Steel Manufacturers Pvt. Ltd. • Sen-Harvic Windows Pvt. Ltd. • SKS Steel Industries	02.10.2030 02.10.2030 24.11.2030
		PVC / WPC / UPVC Doors and Window / Frame	• Fenesta • Venster • Wintrack • Rajshri Plastiwood • AVSL Industries Ltd. *(contd...)*	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A6	Joinery Woodwork Products	PVC / WPC / UPVC Doors and Window / Frame	• Alstone Industries Pvt. Ltd. • PWDS Extrusions Pvt. Ltd. (Prominance) • SCL (Shani Corporation Ltd.) • Encraft India Pvt. Ltd.	02.10.2030 24.11.2030 24.11.2030 24.11.2030
A7	Fire Rated Doors	Fire Door (Tested as per BIS / BS Standard)	• Bhawani Fire Protection Systems Ltd. • Iclean Hollow Metal System Pvt. Ltd. • Navair International Ltd. • Sehgal & Sehgal • Shakti Hormann • Signum Fire Protections Pvt. Ltd. • SKS Steel Industries • Sukriti Doors and Hardware Pvt. Ltd. • Trio India • JC Fire Door Corporation • Basic Doors • Kross Innovations Pvt. Ltd. • Pacific Fire Controls Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030 26.10.2030 26.10.2030 26.10.2030 24.11.2030 24.11.2030 24.11.2030
		Fire Door (Tested as per NFPA Standard)	• GMP Technicals • Shakti Hormann	02.10.2030 02.10.2030
A8	Plumbing	Sanitaryware	• Cera • Hindware • Parryware • Roca • H&R Johnson (India) • Euronics Industries Pvt. Ltd. • Somany Sanitaryware Pvt. Ltd. • Simpolo Vitrified Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030 26.10.2030 24.11.2030 24.11.2030
		Sanitary and Bath Fittings	• Hindware • Jaquar • Kohler • Mayur Öcich • H&R Johnson (India) • Euronics Industries Pvt. Ltd. • Aqua Systems Pvt. Ltd. (JAL- Jupiter Aqualines)	02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030 26.10.2030 26.10.2030
A9	Hardware	Frameless Glass Partition Fixtures	• Dorma • Dorset-Kaba • Dline • Häfele • Hardwyn • Kich	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Spider Fitting / Patch Fittings	• Dline • Kich • Ozone	02.10.2030 02.10.2030 02.10.2030

17/04

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A9	Hardware	Anchor Fasteners (for Finishing works)	• Anchorite Fixing Technology (AFT) • Axel India (Trixel) • Bosch Fischer • Boun Group • Hilti India Pvt. Ltd. • Hitachi-Mungo • Canon Fasteners	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Stone Cladding Clamps	• Anchorite Fixing Technology (AFT) • Axel India (Trixel) • Bosch Fischer • Boun Group • Hilti India Pvt. Ltd. • Canon Fasteners	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Door Hardware / Architectural Profiles	• Dorma • Dorset-Kaba • Dline • Häfele • Hardwyn • Hettich • Ozone	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
A10	Pipes and Fitting (≤ 150 mm dia.)	Ductile Iron Pipes	• Electrosteel Castings Ltd. • Jindal	02.10.2030 02.10.2030
		Cast Iron Pipes, SS Pipes, and Fittings (IS 1536)	• HEPCO • NECO • Singhal Iron & Foundry (SKFCI)	02.10.2030 02.10.2030 02.10.2030
		GI and MS Pipes (IS 1239 Part-I & II, IS 3589)	• Jindal • Prakash Pipes • Surya Roshni Ltd. • T.T. Swastik • Nezone Tubes Ltd. • Indus Tubes Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030
		GI Fittings - Malleable (IS 1879 Part I to X)	• DRP • K.S. • Unik • Zoloto	02.10.2030 02.10.2030 02.10.2030 02.10.2030
		UPVC Pipes and Fittings (IS 4985 : 1981)	• Finolex • Jindal Plast India • Prakash Pipes • Polypack • Prince Pipes & Fittings Ltd. • Rex • Supreme • Surya Roshni Ltd. *(contd...)*	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A10	Pipes and Fitting (≤ 150 mm dia.)	UPVC Pipes and Fittings (IS 4985 : 1981)	• HIL Ltd. (Birla-Aerocon) • Fusion Industries Ltd. (Fusion Pipes) • AKG Extrusions Pvt. Ltd. (AKG Group) • Rajhans Rigid PVC Pipes Industries	02.10.2030 26.10.2030 26.10.2030 24.11.2030
		CPVC Pipes and Fittings (IS 15778 : 2007)	• Ajay • Ashirvad • Astral • Finolex • Surya Roshni • HIL Ltd. (Birla-Aerocon) • Fusion Industries Ltd. (Fusion Pipes) • AKG Extrusions Pvt. Ltd. (AKG Group) • Prince Pipes & Fittings Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030 26.10.2030 24.11.2030
		Stoneware Pipes and Gully Traps (IS 651)	• Lal Chand Anand & Sons • Perfect	02.10.2030 02.10.2030
		RCC Pipes (IS 458)	• Daya Concrete • Jain Spun • Pragati	02.10.2030 02.10.2030 02.10.2030
		Copper Pipes and Fittings	• Mehta Tubes • Mexflow • Rajco	02.10.2030 02.10.2030 02.10.2030
		High-Density Polyethylene (HDPE) Pipes and Fittings	• Duraline • Geberit • Reliance • TSL Tirupati • Prince Pipes & Fittings Ltd. • Chamunda Plastics Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 24.11.2030 24.11.2030 24.11.2030
		Polypropylene Random Copolymer (PPR) Pipes and Fittings	• Prince Pipes & Fittings Ltd. • Supreme • Uro-Allwin • Kanha Plastics Pvt. Ltd. (KPT)	02.10.2030 02.10.2030 02.10.2030 02.10.2030
A11	Water-proofing / Repellents Compound	Modified Bituminous Membrane Roof Waterproofing	• Asian Paints • BASF • EBIPL: Evershine • Flowcrete • Fosroc • Kemco • Sika • STP Ltd. • MYK Arment • Berger Paints India Ltd. • Ultratech Cement Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030

OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड
DELHI METRO RAIL CORPORATION LTD.

List of Empanelled Manufacturers / Suppliers of Major Architecture Items (as on 17.04.2026)

Category No.	Category	Material / Item / Product	Manufacturer's / Supplier's Name	Valid Till
A12	Metal and Roofing	Aluminium Section	• Bharat Aluminium Company United / Vedanta BALCO • Bhoruka • Hindalco • Jindal Aluminium Ltd. • Maan Aluminium Ltd. • Technorail • MM Metacraft Pvt. Ltd.	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030
		MS Hollow Section Pipes	• APL Apollo • Hi-Tech Pipes • Jindal • Surya Roshni • Nezone Tubes	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		MS Tubes / Sections	• APL Apollo • ISPAT • Jindal • Rana Steel • Swastik Pipes • Tata Structura	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030
		Prefabricated SS Works / SS Works	• Dline • Jindal Stainless (JSL) • Kich • Ozone • Koncept Steel Pvt. Ltd. • Technorail • Sialkot Shop	02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 02.10.2030 26.10.2030
		Metal Roofs System	• Kalzip • Supertech (India) Pvt. Ltd. • Tata BlueScope (Metal Coated and Pre-Painted Sheets ZINCALUME COLORBOND)	02.10.2030 02.10.2030 02.10.2030
		Polycarbonate Sheets	• Danpalon • Lexan (SABIC Innovative Plastics from GE)	02.10.2030 02.10.2030
		Tensile Fabric	• Ferrari • Mehler • SRF Ltd.	02.10.2030 02.10.2030 24.11.2030

17/04/2026
OS Saini
General Manager / Planning
Delhi Metro Rail Corporation Ltd.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi-110001

52.7.3 Construction and Demolition Waste

52.7.3.1 Construction and Demolition waste" means the waste comprising of building materials, debris and rubble resulting from construction, re-modelling, repair and demolition of any civil structure.

52.7.3.2 Construction & Demolition (C&D) waste shall be stored at a designated area.

52.7.3.3 The C&D waste shall be disposed off in a manner in compliance with the procedure given in the Construction & Demolition Waste Management Rules, 2016.

52.7.3.4 The contractor shall be responsible for collection, segregation and storage of construction and demolition waste, as directed or notified by the concerned local authority in consonance with the Construction & Demolition Waste Management Rules, 2016.

52.7.3.5 The contractor shall ensure that other waste does not get mixed with this waste and is stored and disposed separately.

52.7.3.6 The contractor shall dispose C&D waste only at authorized processing facilities and ensure that there is no littering or deposition of construction and demolition waste so as to prevent obstruction to the traffic or the public or drains.

52.7.3.7 Disposal of C&D waste along the riverbed, natural drainage and wet land is strictly prohibited and the contractor shall be fined for non-compliance of this requirement in addition to the penalty imposed by the NGT from time to time.

52.7.3.8 The requirement of concrete/RCC/PCC waste disposal, generated from the entire contract shall be either when 15 Tonnes of C&D waste has been generated or such C&D waste has been stored for 15 days (irrespective of quantity), of the two whichever is earlier.

52.7.3.9 The contractor shall dispose off their construction & demolition waste only at an authorized /approved C&D recycling facility. For such disposal, no processing fee will be reimbursed to the contractor.

52.7.3.10 A proper arrangement in record keeping has to be maintained to ensure disposal of C&D waste to C&D waste recycling plant. For this purpose, it is required that contractor shall generate triplicate copies/slips of dispatch when sending C&D waste from site to C&D recycling facility. One copy be retained at site, one copy for C&D waste processing authority and one received copy from C&D waste processing authority to be kept along with the initial copy. The slip shall contain name of contractor, serial number, date, vehicle number and quantity of waste among other things. The actual quantity of C&D waste shall be that which is mentioned by weighing bridge slip generated by the C&D waste recycling facility. Contractor shall submit the record of C&D waste disposal to recycling facility, in his Monthly Environment Report.

EXECUTIVE DIRECTOR / ENVIRONMENT DMRC

EXECUTIVE DIRECTOR/SAFETY DMRC

Contract D2C-08: Civil works including earth filling and construction of depot buildings, workshop, Inspection shed, plumbing, drainage, external development, architectural finishes, road works, design and construction of PEB works in Sanoth Depot of Rithala-Kundli Corridor of Delhi Metro Phase - IV.

S.No	Section	Clause No.	Description of Clause	Clarifications Sought/ Queries	DMRC's Reply
REPLY TO PRE BID QUERIES (Bidder A)					
1	Part-1, Section - IV (Bidding Forms)	Price Schedules	Abstract -A (DSR 2023 items), Sub-Head 20	In Schedule-A, Sub Head no. 20 pertaining to "Any other DSR Items excluding above", the item mentioned this sub head is Miscellaneous DSR 2023 Items which are not covered in the above BOQ which amounts to Rs. 1,45,95,000.00 as a Lump sum amount. To quote judiciously for this item, the bidder needs to know the exact scope of work covered under this sub head/item so that exact cost analysis can be achieved.	The works to be executed under this sub-head are of an unforeseen nature and shall be carried out in accordance with the prevailing site conditions. The exact scope and nature of the works under this head cannot be determined at this stage.
REPLY TO PRE BID QUERIES (Bidder B)					
2	Part-3, Section - VIII (Particular Conditions)	Sub Clause 13.8	Adjustments for Changes in Cost	Kindly clarify the price escalation formula for materials, particularly with respect to structural steel. Please confirm whether the payment for structural steel will be made as per CPWD norms.	Refer to Particular Conditions Sub-Clause 13.8. No change in tender conditions.
3	Part-1, Section - IV (Bidding Forms)	Price Schedules	Abstract - C (NDSR items for PEB Works)	With reference to BOQ Items 1.1 to 1.5 under Schedule 'C', we request to Clarify the estimated quantity per square meter considered for Estimate.	The tenderer shall evaluate the architectural drawings and calculate the quantity per square meter. No change in tender conditions.
4	Part-2, Section - VI Employer's Requirements (Functional)	Clause 2.2.2	Scope of works for PEB Works	Kindly confirm whether submission of DDC profile and tentative design is mandatory for participation in this tender. We request you to kindly provide the above clarifications to enable us to proceed with the tender submission.	Submission of DDC profile for design of PEB buildings/structures is not required at the bidding stage. Tentative design is not required at the bidding stage.
REPLY TO PRE BID QUERIES (Bidder C)					
5	Part -1 , Section -III (Evaluation and Qualification Criteria)	Clause 2.4.2 (a) & (b)	Specific Experience	The similar work for this tender shall be – "Construction of Depot/Workshop/RCC Framed Structure/Industrial shed, including pre-engineered steel structure with roof sheeting." We understand that RCC Framed structure does not require pre-engineered steel structure with roof sheeting. Kindly clarify and confirm. Further, we kindly request you to consider granting an extension of the Bid submission due date till 31.05.2026 to enable bidders to respond appropriately.	RCC framed structure or any other structure may or may not have pre-engineered steel structure with roof sheeting. Clause 2.4.2 (a) specific experience of Part -1 , Section -III, Evaluation and Qualification Criteria shall be read in conjunction with Clause 2.4.2 (b). Refer addendum -02.
REPLY TO PRE BID QUERIES (Bidder D)					
6	Part-1, Section - IV (Bidding Forms)	Price Schedules	Abstract of Schedule - A,B &C	Kindly clarify if the rates in the schedule A, B & C are inclusive of GST.	Rates mentioned in Schedule A, B & C are inclusive of GST. Refer addendum -02.

S.No	Section	Clause No.	Description of Clause	Clarifications Sought/ Queries	DMRC's Reply
7	Part-2, Section - VI Employer's Requirements (Functional)	Clause 2.2.1	Scope of works for PEB Works	Please give an outline for submission of PEB Design for different structure in the tender proposal. Also share the autocad drawings of structures provided in Addendum-1 so that the designer can give an accurate idea of dimensions of the different structures.	Design of PEB structures shall be developed by the tenderer based on Tender Drawings and Outline Design Specifications provided with the Bid documents. AutoCAD drawings have been shared on email through which query was raised.
8	Part-2, Section - VI Employer's Requirements (Functional)	Clause 2.2.2	Scope of works for PEB Works	Kindly specify the criteria of the designer which can give the design of PEB in tender proposal.	Refer page no 19R of addendum – 02. Criteria of designer to be engaged by the contractor for design of PEB works is mentioned in Employer's Requirements: Functional.
9	Part-1, Section - IV (Bidding Forms)	Price Schedules	Schedule -A (DSR 2023 items), Subhead -11	Kindly mention the depth of piling in all the structures. Also, the NGL level is shown below the cutoff level of piles. Is our understanding correct that earth filing, compaction will be done before the piling is executed?	Depth of piling shall vary as per detailed design. Exact pile length shall be provided after detailed design. Load of PEB Structure shall be calculated by the contractor and provided to the detailed design consultant of Employer for foundation design. After the final design of foundation, depth of pile shall be provided. (Refer Cluse 2.2.2, Page 19R of Employer's Requirements : Functional) Sequence of Earth filling and piling shall be decided as per site conditions. Piling shall be done as per approved method statement.
10	Part-2, Section - VI Employer's Requirements (Functional) & Appendices	Clause 2.11 (b) & Appendix -2A	Contractor's Site Accommodation & Work Areas	The plant layout boundary wall all along the depot. Is the boundary wall constructed, and will the bidder gets space for labour camp, stock yard & batching plant inside the depot?	Boundary wall construction is not a part of this tender. No space for labour camp inside the depot shall be provided by the Employer. For stacking & casting yard, kindly refer to appendix -2A of Employer's Requirements.
11	Part-3, Section - VIII (Particular Conditions)	Sub Clause 14.2	Advance Payment	The repayment of mobilization advance is given @16.67% per annum in contact data part-A whereas in part-B it is written that mobilization advance will be paid interest free against BG. Please clarify.	The 16.67% rate is the ammortization rate i.e. % amount of each interim payment through which advance payment shall be adjusted, and not the rate of interest on advance. For reference, Sub Clause 14.2 of the Particular Conditions (PC) may be referred. The Amortization Rate is defined under Clause 14.2(b) of the General Conditions (GC).

S.No	Section	Clause No.	Description of Clause	Clarifications Sought/ Queries	DMRC's Reply
12	Part-3, Section - VIII (Particular Conditions)	Sub Clause 4.2	Performance Security	The BG % mentioned is 10%. Can you clarify the time for which the BG will have to be made? Is there is a provision of giving 2 BG's of 5% and later return of 1 BG after execution of 50% work?	Validity of Performance Security shall be as per Sub -Clause 4.2 of Particular Conditions (Part -3, Section - VIII). No changes in tender conditions.
REPLY TO PRE BID QUERIES (Bidder E)					
13	Part-1 , Section -1	IFB, ITB 19.2, 22.1 & 251.1	Bid submission start, end and opening of technical bid opening date	The project involves the design of Pre-Engineered Building (PEB) structures, which requires comprehensive engineering design and detailed structural detailing to ensure optimal performance and efficiency. Additionally, the preparation of a responsive and technically sound bid necessitates extensive engineering efforts, including detailed design analysis, preparation of Bill of Quantities (BOQ), and a thorough review of the tender documents. Furthermore, it involves close coordination with specialized agencies, to ensure complete integration and compliance with project requirements. We therefore request you to kindly extend the bid due date by 4 weeks (i.e., till 10.06.2026).	Refer addendum -02.