



OUTLINE CONSTRUCTION SPECIFICATIONS FOR CIVIL WORKS

(REVISION-4)

(JUNE 2025)

**DELHI METRO RAIL CORPORATION LTD.
Metro Bhawan, Fire Brigade Lane,
Barakhamba Road, New Delhi – 110 001**

Table of Contents

DESCRIPTION	PAGE NO.
S.01 GENERAL	2
S.02 EARTHWORK	33
S.03 CONCRETE: PLAIN & REINFORCED	42
S.04 FORM WORK	74
S.05 REINFORCEMENT	86
S.06 PRESTRESSED CONCRETE	93
S.07 STRUCTURAL STEEL WORKS	111
S.08 FOUNDATIONS	145
S.09 MISCELLANEOUS	176
S.10 SPECIFICATIONS FOR PRECAST CONST.	222
S.11 ROOF SHEETING&PRE ENGINEERED STRUCTURES	249
S.12 WATER PROOFING	303
S.13 DIAPHRAGM WALLING	320
S.14 TUNNELING	327
S.15 ROAD WORK	374
S.16 BUILDING WORK	402

SECTION – S.01

GENERAL

1.1 GENERAL:

- 1.1.1** These Specifications contained herein shall be read in conjunction with other tender documents.
- 1.1.2** The Work shall be carried out in accordance with the "Good for Construction" drawings and designs as would be issued to the Contractor by the Engineer duly signed and stamped by him. The Contractor shall not take cognizance of any drawings, designs, specifications, etc. not bearing Engineer's signature and stamp. Similarly, the Contractor shall not take cognizance of instructions given by any other Authority except the instructions given by the Engineer in writing.
- 1.1.3** The work shall be executed and measured as per metric units given in the Schedule of Quantities, drawings etc. (FPS units where indicated are for guidance only).
- 1.1.4** Absence of terms such as providing, supplying, laying, installing, fixing etc. in the descriptions does not even remotely suggest that the Contractor is absolved of such providing, supplying etc. unless an explicit stipulation is made in this contract. The Engineer shall bear no costs of materials, labour, equipment, duties, taxes, royalties etc.
- 1.1.5** The specifications may have been divided into different sections / sub-heads for convenience only. They do not restrict any cross-references. The Contractor shall take into account inter-relations between various parts of works/trades. No claim shall be entertained on the basis of compartmental interpretations.
- 1.1.6** The classification of various items of works for purposes of measurements and payments shall be as per bills of quantities (BOQ). Except where distinguished by BOQ, the rates apply to all heights, leads, depths, sizes, shapes and locations. They also cater for all cuts and wastes. No floor wise separation shall be made for the rates. Likewise, all heights of centring, shuttering, staging, formwork and scaffolding, launching trusses and other launching methods are covered by the rates including multi stage propping for heights greater than one floor as per drawings.
- 1.1.7 Reference to the Standard Codes of Practice:**

1. The contractor shall make available at site all relevant Codes of practice as applicable.

Legends	Definition
ASCE	American Society of Civil Engineers
ASME	American Society of Mechanical Engineers
AASHTO	American Association of State Highway and Transportation Officials
ASTM	American Section of the International Association for Testing and Materials
BS	British Standard

ISO	International Organization for Standardization
EN	European Standard
CPWD	Central Public Works Department
DIN	Deutsches Institut für Normung.V.
IRC	Indian Road Congress
IRS	Indian Railway Standards
IS	Indian Standards
JIS	Japanese Industrial Standard
MORTH	Ministry of Road Transport and Highways
RDSO	Research Designs and Standards Organisation

2. Other Publications.

American Petroleum Industry (API) Standard 1104	
Indian Standard Hand Book on steel sections Part-I	
Indian Railway Manual on Design and Construction of well and pile foundations	
UIC/772-R	The International Union of Railways Publication
CIRIA Report 80	A review of instruments for gas and dust monitoring underground
CIRIA Report 81	Tunnel Water proofing
CIRIA Report 44	model code of practice for work in compressed air
CIRIA Report C660	Early age thermal crack control in concrete
CIRIA Report 91	Early age thermal crack control in concrete
Swedish standard 05 59 00	
PCI STD-112-84	
CRRI and IOC, New Delhi Bituminous Road Construction Hand Book	

1.1.8 Alternative or additional codes and standards proposed by the contractor shall be internationally recognized codes and shall be equivalent to or better than, Indian Standards issued by the Bureau of Indian Standards or any other Indian professional body or organization, subject to being, in the opinion of the Employer's Representative, suitable for incorporation or reference into the specifications

1.1.9 Contractor to Provide:

The Contractor shall provide and maintain at site throughout the period of works the following at his own cost and without extra charge, Except for the items specified in the Bill of Quantities the cost

being held to be included in the Contract Rates:

- a) General works such as setting out, site clearance before setting out and on completion of works. All weather approach roads to the site office should also be constructed and maintained in good condition.
- b) All labour, materials, plant, equipment and temporary works, Overhead charges as well as general liabilities, obligations, insurance and risks arising out of GCC, required to complete and maintain the works to the satisfaction of the Engineer.
- c) Adequate lighting for night work, and also whenever and wherever required by the Engineer.
- d) Temporary fences, barricades, guards, lights and protective work necessary for protection of workmen, supervisors, engineers, General public and any other persons permitted access to the site. Contractor shall provide proper signages as directed.

All fences, barricade shall be painted with colour shades as specified by the Engineer. The barricading should be of adequate height to ensure visual obstruction of work from public view.

- e) All equipment, instruments, labour and materials required by the Engineer for checking alignment, levels, slopes and evenness of surfaces measurements and quality etc.
- f) Design mixes and testing them as per relevant clauses of specifications giving proportion of ingredients, sources of aggregates and binder along with accompanying trial mixes. Test results to be submitted to the Engineer for his approval before adoption on works.
- g) Cost of Preparation and compliance with provision of a quality assurance control program.
- h) Cost of safe guarding the environment.
- i) A testing laboratory as specified by the Engineer equipped with the following minimum apparatus, materials and competent trained staff required for carrying out tests, as specified in the relevant sections of the specifications: -
 - i. 1 Set of standard sieves for testing grading of sand with mechanical sieve shaker.
 - ii. Sieves with openings respectively of 4.75mm, 10mm, 20mm, 25mm, 30mm for testing and grading of aggregates.
 - iii. Weighing Balance of capacity up to 10 Kg. reading up to 5 gm.
 - iv. Electric Thermostat controlled oven and pans for drying of sand and aggregates.
 - v. Glass measuring flasks of 1/2, 1 liter&2 liter capacity.
 - vi. Flask for determining moisture content of sand.
 - vii. Slump cone with rod and Vee Bee Apparatus, flow table to measure slump or DIN Specifications.
 - viii. Apparatus to measure permeability of concrete as per Appendix 1700/II of MOST Specifications.

- ix. Minimum 24 Nos. steel moulds for 150mm x 150mm x 150mm concrete test cubes. It may be necessary to provide more steel cube moulds depending upon concreting program.
- x. 25mm dia vibrator for compaction of concrete in test cubes and also vibrating table.
- xi. Concrete cube testing machine of 200 tonnes capacity with 3 dial gauges electrically operated.
- xii. Work benches, shelves, desks, sinks and any other furniture and lighting as required by the Engineer.
- xiii. Abrasion Flakiness & Impact testing Equipment for testing coarse aggregate.
- xiv. Silt Testing Equipment.
- xv. Any other equipment specified by Engineer.

1.1.10 Quality Assurance & Quality Control:

- a) The work shall conform to high standards of design and workmanship, shall be structurally sound and aesthetically pleasing. The Contractor shall conform to the Quality standards prescribed, which shall form the backbone for the Quality Assurance and Quality Control system.
- b) At the site, the Contractor shall arrange the materials, their stacking/storage in appropriate manner to ensure the quality. The Contractor shall provide all the necessary equipment and qualified manpower to test the quality of materials, assemblies etc., as directed by the Engineer. The tests shall be conducted at specified intervals and the results of tests properly documented. In addition the Contractor shall keep appropriate tools and equipment for checking alignments, levels, slopes and evenness of the surfaces.
- c) The Engineer shall be free to carry out such tests as may be decided by him at his sole discretion, from time to time, in addition to those specified in this document. The Contractor may provide the samples and labour for collecting the samples. Nothing extra shall be payable to the Contractor for samples or for the collection of the samples.
 - i. The test shall be conducted at the Site laboratory that may be established by the Contractor or at any other Standard Laboratory selected by the Engineer.
 - ii. The Contractor shall transport the samples to the laboratory for which nothing extra shall be payable. In the event of the Contractor failing to arrange transportation of the samples in proper time the Engineer shall have them transported and recover two times the actual cost from the Contractor's bills.
 - iii. All testing shall be performed in the presence of Engineer. Testing may be witnessed by the Contractor or his authorized representative if permitted by the Test House. Whether witnessed by the Contractor or not, the test results shall be binding on the Contractor.
- d) The Engineer shall have the right at all times to inspect all operations including the sources of materials, procurement, layout and storage of materials, all equipment including the concrete batching and mixing equipment, and the quality control system. Such an inspection shall be

arranged and the Engineer's approval obtained prior to starting of the particular item of work. This shall however, not relieve the Contractor of his responsibilities. All materials which do not conform to these specifications shall be rejected and shall be removed from the site immediately. The Engineer shall have the powers to cause the Contractors to purchase and use materials from any particular source, as Mayin the Engineer's opinion be necessary for the proper execution of work.

1.1.11 Dimensions:

- a) Figured dimensions on drawings shall only be followed and drawings to a large scale shall take precedence over those to a smaller scale. Special dimensions or directions in the specifications shall supersede all others. All dimensions shall be checked on site prior to execution.
- b) The dimensions where stated do not allow for waste, laps, joints, etc. but the Contractor shall provide at his own cost sufficient labour and materials to cover such waste, laps, joints, etc.
- c) The levels, measurements and other information concerning the existing site as shown on the drawings are believed to be correct, but the Contractor should verify them for himself and also examine the nature of the ground as no claim or allowance whatsoever will be entertained on account of any errors or omissions in the levels or the description of the ground levels or strata turning out different from what was expected or shown on the drawings.

1.1.12 Setting out of Works:

The Contractor shall set out the Works indicated in the Conditions of Contract. The Contractor shall provide suitable stones with flat tops and build the same in concrete for temporary bench marks. All the pegs for setting out the Works and fixing the levels required for the execution thereof shall, if desired by the Engineer, likewise be built in masonry at such places and in such a manner as the Engineer may direct. The Contractor shall carefully protect and preserve all bench marks and other marks used in setting out the works. The contractor will make overall layout of complete work and get it checked from engineer. The cost of all operations of setting out including construction of bench marks is deemed to be included in the quoted rates as per Bill of Quantities.

(a) All the survey work except levelling work shall be carried out using total stations with one second accuracy. The levelling work shall be carried out using Auto level.

(b) The triangulations point given by concerned organization before start of work shall be maintained during execution and handed over back to concerned organization after completion of work.

1.1.13 Materials:

a) Source of Materials:

It shall be the responsibility of the contractor to procure all the materials required for construction and completion of the contract. The contractor shall indicate in writing the source of materials well in advance to the Engineer, after the award of the work and before commencing the work. If the material from any source is found to be unacceptable at any time, it shall be rejected by the Engineer and the contractor shall forthwith remove the material immediately from the site as directed by the Engineer.

b) Quality:

All materials used in the works shall be of the best quality of their respective kinds as specified herein, obtained from sources and suppliers approved by the Engineer and shall comply strictly with the tests prescribed hereafter, or where tests are not laid down in the specifications, with the requirements of the latest issues of the relevant Indian/International Standards.

c) Sampling and Testing:

All materials used in the works shall be subjected to inspection and test in addition to test certificates. Samples of all materials proposed to be employed in the permanent works shall be submitted to the Engineer at least 45 days in advance for approval before they are brought to the site.

Samples provided to the Engineer for their retention are to be labeled in boxes suitable for storage. Materials or workmanship not corresponding in character and quality with approved samples will be rejected by the Engineer.

Samples required for approval and testing must be supplied sufficiently in advance if required quality and number to allow for testing and approval, due allowance being made for the fact that if the first samples are rejected further samples may be required. Delay to the works arising from the late submission of samples will not be acceptable as a reason for delay in completion of the works.

Materials shall be tested before leaving the manufacturer's premises, quarry or resource, wherever possible. Materials shall also be tested on the site and they may be rejected if not found suitable or in accordance with the specification, notwithstanding the results of the tests at the manufacturer's works or elsewhere or test certificates or any approval given earlier.

The contractor will bear all expenses for sampling and testing, whether at the manufacturer's premises at source, at site or at any testing laboratory or institution as directed by the Engineer. No extra payment shall be made on this account.

d) Dispatch of materials:

Materials shall not be dispatched from the manufacturer's works to the site without written authority from the Engineer.

e) Test certificates:

All manufacturer's certificates of test, proof sheets, etc. showing that the materials have been tested in accordance with the requirement of this specification and of the appropriate Indian Standard are to be supplied free of charge on request to the Engineer.

f) Rejection:

Any materials that have not been found to conform to the specifications will be rejected forthwith and shall be removed from the site by the Contractor at his own cost within two weeks or as instructed by the Engineer.

- g) The Engineer shall have power to cause the Contractors to purchase and use such materials from any particular source, as may in his opinion be necessary for the proper execution of the work.

1.1.14 Storing of Materials at site:

All materials used in the works shall be stored on racks, supports, in bins, under cover etc as appropriate to prevent deterioration or damage from any cause whatsoever to the entire satisfaction of the Engineer.

The storage of materials shall be in accordance with IS 4082 "Recommendation on stacking and storage of construction materials on site" and as per IS 7969 "Safety code for handling and storage of building materials".

The materials shall be stored in a proper manner at places at site approved by the Engineer. Should the place where material is stored by the Contractor be required by the Employer for any other purpose, the Contractor shall forthwith remove the material from that place at his own cost and clear the place for the use of the Employer.

1.1.15 Water:

- a) Water from approved source:

Potable water only shall be used for the works. Contractor shall have his own source or arrangements of water duly approved by Engineer. The water shall be free from any deleterious matter in solution or in suspension and be obtained from an approved source. The quality of water shall conform to IS 456.

- b) Storage:

The Contractor shall make his own arrangements for storing water, if necessary, in drums or tanks or cisterns, to the approval of the Engineer. Care shall be exercised to see that water is not contaminated in any way (Periodic cleaning of storage tank shall be done).

- c) Testing:

Before starting any concreting/construction work and wherever the source of water changes, the water shall be tested for its chemical and other impurities to ascertain its suitability for use in concrete/construction for approval of the Engineer. A Reverse Osmosis (RO) plant of appropriate capacity shall be installed and only RO treated water shall be used in all the works including curing. RO water shall also be tested for pH, TDS, Chlorides and Sulphates on daily basis. No water shall be used until tested and found satisfactory. Cost of all such Tests shall be borne by the contractor.

1.1.16 Workmanship:

- a) All works shall be true to level, plumb and square and the corners, edges and arises in all cases shall be unbroken and neat.
- b) Any work not to the satisfaction of the Engineer or his representative will be rejected and the same

shall be rectified, or removed and replaced with work of the required standard of workmanship at no extra cost.

1.1.17 Load Testing on Completed Structures

1.1.17.1 During the period of construction or within the defect liability period the Engineer may at his discretion order the load testing of any completed structure or any part thereof if he has reasonable doubts about the adequacy of the strength of such structure for any of the following reasons:

- i. Results of compressive strength on concrete test cubes falling below the specified strength.
- ii. Premature removal of formwork.
- iii. Inadequate curing of concrete.
- iv. Over loading during the construction of the structure or part thereof.
- v. Carrying out concreting of any portion without prior approval of the Engineer.
- vi. Honey combed or damaged concrete which in the opinion of the Engineer is particularly weak and will affect the stability of the structure to carry the design load, more so in important or critical areas of the structure.
- vii. Any other circumstances attributable to alleged negligence of the contractor which in the opinion of the Engineer may result in the structure or any part thereof being of less than the expected strength.

1.1.17.2 All the loading tests shall be carried out by the contractor strictly in accordance with the instructions of the Engineer, as per IRS: CBC and IRC: SP-51, as indicated in the Bill of Quantities and as indicated here under. Such tests shall be carried out only after expiry of minimum 28 days or such longer period as directed by the Engineer.

1.1.17.3 The structure shall be subjected to the load as approved for SLS condition in the design. This load shall be maintained for a period of 24 hours before removal. During the test, struts strong enough to take the whole load shall be placed in position leaving a gap under the members as directed. The deflection due to the superimposed load shall be recorded by sufficient number of approved deflectometers capable of reading up to 1/500 of a cm and located suitably under the structure as directed by the Engineer.

In case the recovery of the structure is not as per codal provisions, the structure shall be considered to have failed to pass the test and shall be deemed to be unacceptable.

1.1.17.4 In such cases the portion of the work concerned shall be taken down or cut out and reconstructed to comply with the specifications. Other remedial measures may be taken to make the structure secure at the discretion of the Engineer. However, such remedial measures shall be carried out to the complete satisfaction of the Engineer.

- 1.1.17.5** All costs involved in carrying out the tests (except integrity test for piles) and other incidental expense thereto shall be borne by the contractor regardless of the result of the tests. The contractor shall take down or cut out and reconstruct the defective work or shall make the remedial measures instructed at his own cost.

If the load testing is instructed on any ground other than mentioned in (i) to (vii) of 1.1.17.1, then the cost of the same shall be reimbursed if the result of the test are found to be satisfactory.

- 1.1.17.6** In addition to the above load tests, non-destructive test methods such as core test and ultrasonic pulse velocity test shall be carried out by the contractor at his own expense if so desired by the Engineer. Such tests shall be carried out by an agency approved by the Engineer and shall be done using only recommended testing equipment. The acceptance criteria for these tests shall be as per provisions in the relevant Indian/International standards and as approved by the Engineer.

1.2 STRUCTURAL WORK:

- 1.2.1** Unless specified, only controlled concrete with design mix and weigh batching is to be used for the work.
- 1.2.2** Minimum cement content specified in CPWD specification is purely from durability point of view. Larger content of cement shall have to be provided if demanded by mix design.
- 1.2.3** Provision of cement slurry to create bond between plain / reinforced concrete surface and subsequent applied finishes shall not be paid extra.
- 1.2.4** Mix design using smaller aggregates of 10mm down shall also be done in advance for the use in the junction having congested reinforcement.
- 1.2.5** Procedure of mixing the admixtures shall be strictly as per the manufacturer's recommendations if not otherwise directed by the Engineer.
- 1.2.6** All the water tanks and other liquid retaining concrete structures shall undergo hydro-testing.
- 1.2.7** Special benches shall be provided at site for stacking reinforcement bars of different sizes.
- 1.2.8** Formwork for beams of RCC areas shall be designed in such a way that the formwork of the adjacent slabs can be removed without disturbing the props / supports of the beams.
- 1.2.9** Wherever there are tension / suspended concrete members which are suspended from upper-level structural members, the shuttering / scaffolding of such members at lower level shall have to be kept in place till the time the upper level supporting members gain minimum required strength. Cost of such larger duration of keeping in place the shuttering/scaffolding shall be deemed to be included in the price quoted for respective structural members.
- 1.2.10** Formwork is required for full height at all locations. Special precaution for such tall formwork shall be taken to ensure its safety. Extra costs for such formwork shall be deemed to have been included in the price quoted against relevant items.
- 1.2.11** In the mobilization period, the contractor shall carry out expeditiously and without delay the following works:
- i. Material testing and mix designs of concrete as contemplated in the specifications.
 - ii. Setting up of full-fledged site laboratory as per the requirements of these specifications.
 - iii. Any other pre-requisite items required for final execution.
 - iv. Site office for the use of the Engineer staff.
 - v. Casting yard with full facilities.

1.2.12 Casting yard to have following minimum facilities:

- i. Casting beds as required.
- ii. All handling facilities for precast elements.
- iii. Curing arrangements as required.
- iv. Stacking arrangements for precast elements.
- v. Storing of materials.
- vi. Proper drainage and approach roads.

1.3 SUPPLY OF PROGRESS PHOTOGRAPHS AND ALBUMS (DIGITAL):

The work covers the supply of digital photographs to serve as a permanent record of various stages/facets of work needed for an authentic documentation as approved by the Engineer.

The photographs shall be of acceptable quality and they shall be taken by a professionally competent photographer with camera having the facility to record the date of the photographs taken in the soft copy. Each photograph in the album shall be suitably captioned and dated.

The photographs and materials shall form a part of the records of concerned organization and same cannot be supplied to anybody else or published without the written permission of concerned organization.

1.4 SUPPLY OF VIDEO CDS:

The work consists of taking video films of important activities of the works as directed by the Engineer during the currency of the Project and editing them to a video film of playing time not less than 60 minutes. It shall contain narration of the activities in English by a competent narrator. The edition of the film and script of the narration shall be approved by the Engineer.

Robotic Inspection

Remotely Operated vehicle's (ROV's) data collection technology provides safe and relatively accurate inspection and monitoring of structures. Camera, sensors, lights and other devices are commonly included on the platform of the robot to increase its usability and accuracy while inspection. It can even be set up to be operated by remote control.

There are numerous applications of ROV's such as drones for inspection and monitoring of structures. Infrared technologies can also be added to these devices. ROV shall also be used monitoring of physical progress of works.

The record of progress (photographs and videos) shall be submitted to the engineer on monthly basis or as directed by engineer.

1.5 SURVEY WORK:

The said work involves at the very start of work taking-over of reference point from the Engineer, establishment of control points, triangulation points, bench marks, grid layout for all the piers and other structures maintaining horizontal and vertical control within the permissible limits, incorporating changes (if any), submission of full data in the tabulation form and survey drawings including setting and layout of various works during the progress of work and matching of the

station area track alignment with the alignment of the approaches at station ends and incorporating the changes (if any).

1.6 **BARRICADING**

The work covers barricading for the work done along the median and areas affecting road traffic. Barricading for the other areas like casting yard, batching plant, storage and other working area shall be done at own cost by the contractor. The detailed scope of work is as follows:

- i. Supplying, providing and installing the barricade of the design and type as shown in the Tender Drawings furnished as per the approved plan firmly to the ground and maintaining it during the progress of work. If barricading cleaning and prompt replacement of damaged barricading not maintained, the Engineer may impose suitable penalty.
- ii. Dismantling of barricading and other temporary installations from the site and cleaning the site as per direction of Engineer upon completion and acceptance of work.
- iii. Providing earthing of Barricades.
- iv. Providing Lighting on the periphery of Barricades for Direction illumination.
- v. Arrangement of CCTV for dust control
- vi. Providing adequate road safety devices. A tentative list given hereunder identifies minimum items, which may be required. However, actual numbers required will be as per approved plan by the Engineer and clearance from the traffic department, Delhi. The contractor shall not be paid extra for any addition to this list if required during the execution of works.
- vii. The barricade shall be painted/ covered with construction fabric as required and directed by The Engineer

Construction Fabric Panel

Property	Specification
Material	HDPE woven mesh / HDPE laminated fabric
GSM	150–200 GSM (Grams per Square Meter)
Color	Green (Shade approval to be taken from DMRC)
UV Stabilization	Yes
Flame Retardant	DIN 4102-B1 or NFPA 701 compliant
Finish	Matte, anti-glare
Recyclability	Fabric shall be fully recyclable
Lifespan	3–5 years outdoor (with UV protection)

Tentative Road Safety Devices


Sr. No.	Brief Description
1.	Supply of Red portable heavy duty traffic cones of 750 mm height with white reflective tape bands on min. 100 mm width all around
2.	Hazard warning light flasher with rechargeable. Maintenance free battery & Charging system

3. Safety light island post with 11 nos. parallel reflector
4. Red reflective arrow fitted on enamelled mild steel board of 360 x 220 mm size
5. Traffic Triangular Tripod made of fluorescent cloth fitted on steel frame
6. Retro-reflective tape (I) 50 mm width
7. Fluorescent Jackets with reflective tape all around
8. Yellow reflective cat eyes of size 115 x 11 x 22 mm made of ABS material having 19 glass beads on each side.
9. Metal Tubular Delineator of 610 mm height with reflective tapes
10. Retro-reflective arrows diversion board 450 x 900 mm with crystal clear protective transparent coat to avoid damage on 14 gauge Mild Steel sheet with and without pole
11. Retro-reflective "Men at work" triangular board of size 900 mm with crystal protective transparent coat to avoid damage on 14 gauge Mild steel board with and without poles
12. Retro-reflective board for "Go Slow Work in progress" of size 1200 x 750 mm with crystal clear protective transparent coat to avoid damages to the Mild Steel sheets with and without pole.
13. Retro-reflective advance direction sign cum Diversion Boards of size 1200 x 900 mm with crystal clear protective transparent coat to avoid damage to the 14-gauge Mild Steel sheet with and without pole.
14. Retro-reflective speed limit circular sign Boards of 600 mm Diameter with crystal clear protective transparent coat to avoid damage to the 14-gauge sheet (without pole).
15. "SORRY FOR INCONVENIENCE" Retro-reflective Boards of size 900 x 300 mm size with crystal clear protective transparent coat to avoid damage to the 14 gauge Mild Steel Sheet (without pole).
16. HAZARD MARKERS (Yellow & Black) must be put all over the construction sites. This Retro-reflective board is of size 300 x 900 mm with crystal clear protective transport coat to avoid damage and the 14 gauge Mild Steel Sheet with or without pole.
17. "CAUTION" tape which is normally yellow tape of special Polythene Material having 75 mm width "CAUTION" is written all over with Black colour in rolls of 300 meter.
18. Heavy Duty Glass Reinforced Plastic Temporary Barricade

Providing Heavy Duty Glass Reinforced Plastic Temporary Barricade of 2.0m m high, 1.5m length with base width of 430 mm as a provision to accept water ballasting of 101 liters approx.. and arrangement for traffic diversion such as traffic signals during construction at site, for day and night as per requirement. The raw material shall be UV stabilized Linear Low Density Polyethylene and should meet the requirements stipulated in standard IS:10146-1982, IS:10141-1982 and should also comply to FDA:CFR Title 21.177.1520. Olefin Polymers, with specific FRP Grade 300-104 reinforced during moulding process to the permissible extent for improved impact strength, Qualification Criteria: For qualifying the sample, few tests shall be performed at Government Lab OR NABL Accredited Lab on site safety Fence sample, failure or Deviation in test results of sample shall be

disqualified. The tests and qualifying results are as under, (a) tensile strength at yield by ASTM D 638=20.93 Mpa, (b) Elongation at break ASTM D 638= 121.66 Mpa (c) Flexural Modulus ASTM D 790 = 633.76 Mpa (d) Izad Impact Strength (Notched) ASTM D 256= 4.41 Kg/Sqm (e) Izad Impact strength(Un-Notched) ASTM D 256 = 67.04Kg/Sqm (f) Drop Impact Strength 25 Kg Load from 1m, 2m & 5m height the weight of empty single Rotomoulded Plastic Barricade Without to fix two brackets at both end in corner for anchoring purpose each rear bracket is constructed through rod of Dia 60 mm with curvature welded with MS strip of 3mm thick, 50mm width and 90mm length at its top and base, effective bracket shall be 410mm approx.. the anchoring hole in each Bracket shall be 18mm dia. For routine the MS bolt of 16mm thickness and 15mm length with sharp pointed edge at one end. The upper part of each bracket shall have a slot size of 30mm x 10mm for connecting it with barricade model through bolts. Similarly front bracket for site safety fence is 3mm thick, 50mm width, effective height after single bend is 230 mm and anchoring in each bracket shall be dia 18mm unique safety feature for firm gripping to prevent from displacement and falling when inter connected even without water filling. There shall be 7 no's premoulded inserts on site safety Fence for following application: 2no's for safety latches interconnectivity, 2 no's for fixing rear brackets for anchoring. One no. at front side for fixing the front bracket for higher stability, and 2 nos on Extension top for holding light bracket/Rod for cloth holding. The plastic barricades has a strong vertical rib of 1740 mm length at the rear centre & 72 No's of kiss offs spread on entire rear surface, the water container (bottom)

Site Safety Fence (2.00 mtrs(H)) (Efficient Substitution to sheet Metal Barricade), Empty Weight : 1700 Kg/Rgm Full : 70.00 Kg/Rgm approx..(After Water/Sand Filling)



Measurement

The barricading including all the required safety devices as listed above shall be measured as per relevant item in BOQ (Payment of the item shall be made on monthly basis over contract period including extended period, if any. No extra payment shall be made for the extended period, if any. Payment shall be deducted for the period during which the barricading and arrangements for traffic diversion are not satisfactory to the Engineer. The payment and deduction (if any) for the item shall be on pro-rata basis). No extra payment will be made for any lateral shifted barricading required for satisfactory execution of work.

1.7

TRANSPLANTATION OF TREES

The item shall be carried out as per the approved plan by the Engineer after the identification of the trees to be transplanted. The actual number of trees shall be finalized after the necessary clearances by the concerned departments. The item is complete and including all expenditures for carrying out all operations i.e. excavation, watering, feeding of chemicals, back filling, lifting of trees by crane and transporting to the designated site where it is to be transplanted and all necessary care to be taken for the specified initial period till the tree gets settled at new site and up to the full satisfaction of the Engineer.

Measurements

The item shall be measured in numbers according to size of the tree as specified in the item and the full payment shall be released only when the item is executed fully as per the Scope of Work detailed out in the approved plan for transplantation of trees.

The rate shall include all required operations during the transplantation and specified duration afterwards, clearances from the concerned authorities.

1.8 FINISHING WORK:

1.8.1 The Contractor shall incorporate seismic considerations of anchoring and isolation in the design and detailing of the finishes as directed by the Engineer. The element to be anchored shall have its motion suitably restrained whilst at the same time it shall be suitably isolated so as not to be affected by the deformations/ vibrations of the building during Construction.

1.8.2 Sub-Contractor:

Works as listed below and those dealing with proprietary materials/ products may be carried out by the Contractor through the Sub-Contractors as may be approved by the Engineer in writing. The Sub-Contractors must be firms of repute and long standing, having adequate experience and complete facilities to carry out all items of work required for completion as per Specifications and expected quality to the satisfaction of the Engineer. The Sub-Contractor must also have personnel experienced in preparing shop drawings. All such works shall be carried out under the direct supervision of the manufacturers of the proprietary materials/ products or their trained and accredited licensee.

- i. Waterproofing
- ii. Caulking & Sealants
- iii. Seismic Joints
- iv. Expansion joints
- v. Application of Silicone water repellent solution where specified.
- vi. Bearings

1.8.3 Guarantees and Building Maintenance for Finishes:

The Contractor shall guarantee and undertake to maintain and rectify the various components of the Civil Works for their successful performance for the periods as specified below. The Contractor shall indemnify the Engineer for a similar period against any damage to property and injury to persons on account of any defective work or maintenance carried out by the Contractor. The format and text of the Guarantee and the Indemnity Bond shall be as followed in CPWD or as approved by the Engineer.

- i. Waterproofing for underground structures (which include raft, retaining walls, underground sump and expansion/separation joints in retaining walls) and roofs shall warranty for minimum 10 years against any leakage/seepage. The waterproofing shall include all allied

works on the roof such as concrete screed and the China Mosaic roof finish/ stone cladding on the parapet between which the waterproofing treatment shall be sandwiched.

- ii. Waterproofing for the other areas such as toilets, kitchens, chhajjas etc. shall also be guaranteed for 10 years. The waterproofing shall include all allied works on the slab etc. such as concrete/ mortar screeding, if any, floor finish between which the waterproofing treatment shall be sandwiched.

Contractor shall submit Performance Bank Guarantee for water proofing works (for 10% of the cost of water proofing item only) which shall be valid for the entire guarantee period.

1.8.4 Responsibility for Shop drawings, Samples and Mock-ups:

Approval of shop drawings, samples and mock-ups for the various components shall not absolve the Contractor of his responsibility of completing the work to the specifications, standards, tests for performance and guarantees given in these documents and to a quality of finish as desired by the Engineer.

1.8.5 Cleaning:

Surfaces on which finishes are to be provided shall be cleaned with water jets or oil free compressed air or power tools with wire brushes and detergents all as approved by the Engineer.

1.8.6 Expansion bolts/ fasteners:

- a) Unless specified otherwise all expansion bolts/ fasteners shall be fabricated from austenitic stainless steel sheet, strip or plate conforming to ASTM A 240 Gr 304 or bar to ASTM A 479Gr 304 or higher grade of approved make and design. The material of the bolt shall not cause any bimetallic corrosion with the reinforcing bars of the RCC/ brickwork or with any other fixings or doors or windows or skylights etc.
 - i. For steel backings the fasteners shall be prevented from contact with other metals, which would lead to bimetallic corrosion.
 - ii. For brick masonry backing the sleeves of the expansion bolts shall be fixed in wedge shaped pockets having an area of 75mm x 75mm at the surface and 100mm x 100mm at the inner surface and shall be 125mm deep. The wedge could also be as a truncated cone of 75mm dia/ 100mm dia. The dimensions shall be reviewed by the Engineer during execution of the work. The wedge shall be filled with PCC 1:1:2 (1 Cement, 1 Sand and 2 Coarse Aggregate) mixed with non-Shrink Compound in the proportion as recommended by the manufacturer.
 - iii. The holes drilled for the expansion fasteners shall be cleaned of all ground material, dust, etc. before inserting the expansion sleeves.
 - iv. All expansion bolts fixed into soffits shall be bonded to the backing with epoxy/ polyester resin of approved make.
 - v. All expansion bolt fixings shall be tightened in accordance with the recommended torque figures by the manufacturer. Where such values are not available the Contractor shall test

at least 6 samples to determine the safe torque values. All bolts shall be tightened using torque spanner/ wrenches. All bolts shall be checked 24 hours (minimum) after installation and retightened if necessary.

- 1.8.7** No walls, terraces shall be cut for making any opening after water proofing has been done without written approval of the Engineer. Cutting of waterproofing when authorized by the Engineer in writing shall be done very carefully so that no other portion of the waterproofing is damaged. On completion of the work at such places, the water proofing membrane shall be made good and ensured that the opening / cutting is made fully water proof as per specifications and details of water proofing approved by the Engineer at no extra cost. No structural member shall be cut or chased without the written permission of the Engineer.
- 1.8.8** Provision of grooves in plaster, drip courses etc., if directed, at junction of walls-ceilings, columns-walls, frames-plaster and such other generally typical locations shall not be paid extra, including grooves in concrete, masonry, stonework.

1.9 Applicable Codes, Standards & Publications for Structural & Architectural Work :

The more important Codes, Standards and Publications to Contract are listed here under:
Any other code/publication, if found necessary by the engineer, may be referred to for such works.
The latest revision along with all corrections slip & amendments shall only be followed

A	General
IS: 875	Code of practice for design loads (other than earthquake) for buildings and structures
IS: 1200 (Part 4)	Methods of measurement of building and Civil engineering works-Stone masonry
IS: 1237	Specification for cement concrete flooring tiles
IS: 1322	Bitumen felts for water proofing and damp-proofing
IS: 1893	Criteria for earthquake resistant design of structures
IS: 2185 (Part 1)	Concrete masonry units: Hollow and solid concrete Blocks
IS: 2185 (Part 2)	Concrete masonry units: Hollow and solid light weight concrete blocks
IS: 2185 (Part 3)	Concrete masonry units: Autoclaved cellular aerated concrete blocks
IS: 2572	Code of Practice for construction of hollow concrete block Masonry
IS: 3414	Code of practice for design and installation of joints in Buildings
IS: 3462	Specification for unbacked flexible PVC flooring

IS: 5318	Code of practice for laying of flexible PVC sheet and tile Flooring
IS: 6408 (Parts 1,2)	Recommendations for modular co-ordination in building industry – tolerances
IS: 8183	Bonded mineral wool
IS:10958	General check list of functions of joints in building
IS:11817	Classification of joints in buildings for accommodation of dimensional deviations during construction
IS:11818	Method of test for laboratory determination of air permeability of joints in buildings
IS:12440	Precast concrete stone masonry blocks
CPWD	Specifications with up-to-date correction slips
BS:476 (Part 7)	Method for classification of the surface spread of flame of Products
BS:476 (Part 20)	Method of determination of the fire resistance of elements of construction (general principles)
BS:476 (Part 22)	Methods for determination of the fire resistance of non- load bearing elements of construction
BS: 1245	Specification for metal door frames (steel)
BS: 3261	Specification for unbacked flexible PVC flooring
BS:3261:Part 1	Homogeneous flooring
BS:5215	Specification for one-part gun grade polysulphide-based Sealants
BS:5606	Guide to accuracy in building
BS:5725 (Part 1)	Specification for panic bolts and panic latches mechanically operated by a horizontal push-bar
BS:6093	Code of practice for the design of joints and jointing in building construction
BS:8200	Code of practice for the design of non-load bearing external vertical enclosure of building

ASTM C 332	Specification for light weight aggregate for insulating Concrete
ASTM C 635	Specification for the manufacture, performance and testing of metal suspension systems for acoustical tile and lay-in panel ceilings
SP 7	National Building Code of India
SP 23 (S&T)	Hand Book on Concrete Mixes
B	Bitumen
IS:702	Industrial Bitumen
IS:3384	Specification for bitumen primer for use in waterproofing and damp-proofing
C	Building Construction Practices
IS: 1838 Parts I and II.	Specifications for preformed fillers for expansion joint in concrete pavements and structures.
IS: 1946	Code of Practice for use of fixing devices in walls, ceilings, and floors of solid construction.
IS: 3414	Code of Practice for design and installation of joints in buildings.
IS: 6509	Code of Practice for installation of joints in concrete pavements.
IS: 11134	Code of Practice for setting out of buildings.
IS: 11433	Parts I and II. Specifications for one part Gun grade polysulphide based joint sealant
IS: 12200	Code of Practice for provision of water stops at transverse contraction joints in masonry and concrete dams

D	Cement
IS: 269	33 grade ordinary Portland cement
IS: 455	Portland Slag Cement
IS: 650	Specification for standard sand for testing cement.
IS: 1489 (Part 1)	Portland pozzolana cement: Fly ash based
IS: 1489 (Part 2)	Portland pozzolana cement: Calcined clay based
IS: 3535	Method of Sampling Hydraulic Cements
IS: 4031	(Parts 1 to 13) Methods of physical tests for hydraulic cement.
IS: 4032	Method of chemical analysis of hydraulic cement.
IS: 6925	Methods of test for determination of water soluble chlorides in concrete admixtures.
IS: 8042	White Portland Cement
IS:269	Specification for Ordinary Portland Cement
IS: 12330	Specification for sulphate resistant Portland cement.
IRS: T 40	Indian Railways standard specifications for special grade cement for use in concrete sleepers
E	Concrete
IS:456	Code of practice for plain and reinforced concrete.
IS:457	Code of practice for general construction of plain and reinforced concrete for dams and other massive structures.
IS:460 (Part I to III)	Specification for Test Sieves
IS 516 (Part 1 to Part 8)	Methods of Test for Hardened Concrete
IS 1199: Part 1 to 7	Methods of Sampling, Testing and Analysis for fresh concrete.
IS:1200	Method of measurement of building and civil engineering

IS:1343	Code of practice for prestressed concrete
IS:1607	Method of Test Sieving
IS:2386	Parts I-VIII. Methods of tests for aggregates for concrete.
IS:2430	Methods of Sampling of Aggregates of Concrete
IS:2438	Specification for roller pan mixer
IS:2514	Specification for concrete vibrating tables
IS:2571	Code of practice for laying in-situ cement concrete Flooring
IS:2645	Specifications for integral cement water proofing Compounds
IS:2722	Specifications for portable swing batchers for concrete (double bucket type)
IS:2770	Methods of testing bond in reinforced concrete part I pull out test
IS:3025	Methods of sampling and test (physical and chemical) for water & waste water
IS:3370	Code of practice for concrete structures for storage of Liquids
IS:3935.	Code of practice for composite construction
IS:4326	Code of practice for earthquake resistant construction of Building
IS:6925.	Methods of test for determination of water soluble chlorides in concrete Admixtures
IS:7242	Specifications for concrete spreaders
IS:7251	Specifications for concrete finishers
IS:7861	Parts I & II. Code of practice for extreme weather concreting.
IS:7969	Safety code for handling and storage of building materials
IS:8989	Safety code for erection of concrete framed structures

IS:8142	Methods of test for determining setting time of concrete by penetration resistance
IS:9103	Specifications for admixtures for concrete
IS:9013	Method of making, curing and determining compressive strengths of accelerated cured concrete test specimens
IS:9284	Method of test for abrasion resistance of concrete
IS:10262	Recommended guidelines for concrete mix design.
IS:4926	Code of Practice ready mixed concrete needs to be included in list
MORTH	Specifications for Road and Bridge Works, Ministry of Road Transport and Highways (Roads Wing)
SP 34	Handbook on Concrete Reinforcement and Detailing
IRS	Concrete Bridge Code
IRC 112	Code of Practice for Concrete Road Bridges
IRC 83 (Part 4)	Standard Specifications and code of practice for road bridges Section IX Bearings (Spherical & Cylindrical)
ASTM -C -94	Ready Mix Concrete
F	Construction Plant and Machinery.
IS:1791	Specification for batch type concrete mixers.
IS:2505	General requirements for concrete vibrators: Immersion type.
IS:2506	General requirements for screed board concrete vibrators.
IS:3366	Specification for pan vibrators.
IS:3558	Code of Practice for use of immersion vibrators for consolidating concrete.
IS:4656	Specifications for form vibrators for concrete.
IS:4925	Specification for concrete batching and mixing plant.

IS:11993 Code of Practice for use of screed board concrete vibrators.

G

Formwork

IS:4990 Specifications for plywood for concrete shuttering work.

IRC:87 Guidelines for the design and erection of false work for road bridges.

IS:806 Code of practice for use of steel tubes in general building construction.

IS:1161 Specification of steel tubes for structural purposes.

IS:1239 Specification for mild steel tubes, tubular and other wrought steel fittings.

H

Gypsum and Gypsum Board

IS:2095 Gypsum plaster boards

IS:2542 (Part 1/Sec to 12) Methods of test for gypsum plaster, concrete and products: plaster and concrete

IS:2542 (Part 2/Sec 1 to 8) Methods of test for gypsum plaster, concrete and products: Gypsum products

IS:2547 (Part 1) Gypsum building plaster: Excluding premixed lightweight plaster

IS:2547 (Part 2)	Gypsum building plaster: Premixed lightweight plaster
I	Handling and Storage
IS:4082	Recommendation of Stacking and Storage of construction materials
IS:8348	Code of practice for stacking and packing of stone slabs for transportation
IS:8759	Code of practice for maintenance and preservation of stones in building
J	Instruments For Testing Cement and Concrete
IS:5513	Specification for vicat apparatus.
IS:5514	Specification for apparatus used in Le-Chaterlier test.
IS:5515	Specification for compaction factor apparatus.
IS:7320	Specification for concrete slump test apparatus.
IS:7325	Specification for apparatus to determine constituents of fresh concrete.
IS:10080	Specification for vibration machine.
IS:10086	Specification for moulds for use in tests of cement and concrete.
IS:10510	Specification for vee-bee consistometer.
K	Joint Fillers
IS:1838 (Part 1)	Preformed fillers for expansion joint in concrete pavements and structures (non extruding and resilient type): Bitumen impregnated fibre
L	Paints and Coatings
IS:102	Ready mixed paint, brushing, red lead, non-setting, priming
IS:109	Ready mixed paint, brushing, priming, plaster, to Indian Standard Colour No. 361 and 631 white and off white.
IS:218	Creosote and anthracene oil for use as wood preservatives
IS:347	Varnish, shellac, for general purpose.
IS:348	French Polish
IS:2074	Ready mixed paint, air drying, red oxide-zinc chrome,

	priming
IS:4833	Methods of field testing of preservatives in wood
IS:10013 (Parts 1 to 3)	Water soluble type wood preservatives:
IS:10013 (Parts 1 to 3)	(Part-1) Acid-copper-chrome preservative
IS:10013 (Parts 1 to 3)	(Part-2) Copper-chrome-arsenic wood preservative
IS:10013 (Parts 1 to 3)	(Part-3) Copper-chrome-boron wood preservative
BS:6496	Specification for powder organic coatings for application and stoving to aluminium alloy extrusions, sheet and preformed sections for external architectural purposes, and for the finish on aluminium alloy extrusions, sheet and preformed sections coated with powder organic coatings
BS:EN:10152	Specification for electrolytically zinc coated cold rolled steel flat products. Technical delivery conditions
ASTM A 164-71	Specification for electrodeposited coatings of zinc on steel
M	Pigment for Cement
BS:1014	Specification for pigments for Portland cement and Portland cement products
N	Reinforcement & Structural Steel
IS:206	Code of Practice for use of Steel Tubes in General Building Construction
IS:210	Grey Iron Castings
IS:280	Mild steel wire for general engineering purposes
IS:432	Part I. Mild steel and medium tensile steel bars. Part II Hard drawn steel wire.
IS:451	Technical Supply conditions for Wood Screws
IS:806	Code of practice for use of steel tubes in general building construction
IS:815	Classification coding of covered electrodes for metal arc welding of structural steels
IS:1239	Specification for mild steel tubes, tubulars and other wrought steel fittings
IS 1343	Code of Practice for Prestressed Concrete
IS:1363	Black hexagon bolts, nuts and lock nuts and black hexagon screws.
IS:1365	Slotted countersunk screws.
IS:1566	(Part I) Specifications for hard-drawn steel wire fabric for

	concrete reinforcement.
IS:1786	Specification for high strength deformed steel bars and wires for concrete reinforcement.
IS:2502	Code of Practice for bending and fixing of bars for concrete reinforcement.
IS:2629	Recommended practice for hot-dip galvanising of iron and steel.
IS:2751	Code of Practice for welding of mild steel plain and deformed bars for reinforced concrete construction.
IS 4000	Code of practice for high strength bolts in steel structures
IS:4759	Hot-dip zinc coating on structural steel and other allied products.
IS:5525	Recommendations for detailing of reinforcement in reinforced concrete works
IS:9417	Recommendations for welding cold-worked steel bars for reinforced concrete construction.
IS:14268	Uncoated stress relieved low relaxation steel class 2 for Prestressed concrete
IS:226	Structural steel (Standard Quality)
IS:800	Code of practice for use of structural steel in general building construction.
IS:813	Scheme of symbols for welding.
IS:814	Covered electrodes for metal arc welding of structural steel. (Part I & Part II)
IS:816	Code of practice for use of metal arc welding for general construction in mild steel.
IS:822	Code of practice for inspection of welds.
IS:961	Structural steel (High Tensile)
IS:1024	Code of practice for use of welding in bridges and structures subject to dynamic loading.
IS:1030	Carbon steel casting for General Engineering Purposes
IS:1120	Coach Screws
IS:1367	Technical Supply Conditions for Threaded Fasteners
IS:1161	Steel tubes for structural purposes.

IS:1182	Recommended practice for radiographic examination of fusion welded butt joints in steel plates.
IS:1915	Code of Practice for Steel Bridges
IS:2016	Plain Washers
IS:2062	Structural steel (Fusion welding quality)
IS:3063	Single Coil Rectangular Section Sprint Washers for Nuts, Bolts and Screws
IS:3443	Crane Rail Sections
IS:3757	Specification for high tensile friction grip bolts.
IS:5624	Specification for foundation bolts.
IS:3600	Code of practice for testing of fusion welded (Part I) joints and weld metal in steel.
IS:4923	Hollow steel sections for structural use.
IS:6227	Code of practice for use of metal arc welding in tubular structure.
IS:801	Code of practice for use of cold formed light gauge steel structural members in general building construction.
IS:811	Specifications for cold formed light gauge structural steel sections.
IS:8500	Structural steel Micro alloyed (Medium and high strength qualities)
IS:8910	General requirements of supply of weldable structural steel
IS:9595	Recommendations for metal arc welding of carbon & carbon-manganese steels.
IS 16172	Reinforced Couplers for Mechanical Splices of Bars in Concrete

O**Sand**

IS:383	Coarse and Fine Aggregate for concrete.

P**Scaffolding**

IS:2750	Specification for steel scaffoldings
IS:3696 (Part 1)	Safety Code of scaffolds and ladders: Scaffolds
IS:3696 (Part 2)	Safety Code of scaffolds and ladders: Ladders
IS:4014 (Part 1)	Code of practice for steel tubular scaffolding: Definition and materials
IS:4014 (Part 2)	Code of practice for steel tubular scaffolding: Safety regulations for scaffolding
IRC:87	Guidelines for the design and erection of falsework for Road bridge

Q	Sealants
IS:10959	Glossary of terms for sealants for building purposes
IS:11433 (Part 1)	One part grade polysulphide base joint sealant: General requirements
IS:11433 (Part 2)	One part grade polysulphide base joint sealant: Methods of test
IS:13055	Methods of sampling and test for anaerobic adhesives and sealants
BS:5889	Specification for one part gun grade silicone-based sealants.
R	Wood
IS:303	Plywood for General Purposes
IS:848	Synthetic resin adhesives for plywood (phenolic and aminoplastic)
IS:1141	Seasoning of Timber – Code of Practice
IS:1328	Veneered decorative plywood
IS:1659	Block Boards
IS:2046	Decorative thermosetting synthetic resin bonded laminated sheets
IS:2202 (Part 1)	Wooden flush door shutters (solid core type): Plywood face panels
IS:2202 (Part 2)	Wooden flush door shutters (solid core (type): Particle face panels and hardboard face panels
S	Bearing
IRC:83Part-II	Standard specifications and code of practice for road bridges Elastomeric Bearings
IRC:83 Part-III EN 1337gh	Standard specifications and code of practice for road bridges Pot Bearings
T	PILING
IS :2911 (All Parts)	Bored Cast in-situ Concrete Piles
IRC:78	Standard specifications and code of practice for road bridges Foundation and Substructure
U	All Indian Railway & RDSO Standards, any other code or publication as approved by engineer

V	Metal
IS:276	Austenitic manganese steel castings
IS:733	Wrought aluminium and aluminium alloy bars, rods and sections for general engineering purpose.
IS:737	Specifications for wrought aluminium and aluminium alloy sheet and strip for general engineering purpose.
IS:3614 (Part 1)	Specification for fire check doors: Plate metal covered and rolling type
IS:3614 (Part 2)	Specification for metallic and non-metallic fire check doors: Resistance test and performance criteria
IS:7196	Specification for Hold Fast
ASME Sect 2 Part A	Ferrous Material Specifications
ASTM B 221	Specification for aluminum-alloy extruded bars, rods, wires, shapes, and tubes
BS: 4873	Specification for Aluminum alloy windows
BS: 7352	Specification for strength and durability performance of metal hinges for side hanging applications and dimensional requirements for template drilled hinges
BS EN:10143	Specification for continuously hot-dip metal coated steel sheet and strip. Tolerances on dimensions and shape
W	Glazing
BS:952 (Part 1)	Glass for glazing: classification
BS:952 (Part 2)	Glass for glazing: Terminology for work on glass
BS:4315 (Part 2)	Methods of Test for Resistance to Air and water penetration: Permeable walling constructions (water penetration)
BS:5368 (Part 1)	Method of testing Windows: Air permeability test
BS:5368 (Part 2)	Method of testing Windows: Water tightness test under static pressure
BS:5368 (Part 3)	Method of testing Windows: Wind resistance tests
BS:5368 (Part 4)	Method of testing Windows: Form of test report
BS:5713	Specification for Hermetically sealed flat double glazing units
BS:6262	Code of practice for glazing for buildings
BS:6262 (Part 4)	Glazing for buildings: Code of practice for safety, Human impact

BS: 6375 (Parts 1)	Performance of windows: Classification for weather tightness (including guidance on selection and Specification)
BS:6375 (Parts 2)	Performance of windows: Specification for operation and strength characteristics
DIN:1249 (Part 12)	Glass for use in building construction; toughened glass; dimensions, working and requirements
JIS:R 3203	Float and Polished Plate Glasses
ASTM E 283	Test method for determining the rate of air leakage through exterior windows, curtain walls, and doors under specified pressure differences across the specimen
ASTM E 330	Test method for structural performance of exterior windows, curtain walls, and doors by uniform static air pressure difference
ASTM E 331	Test method for water penetration of exterior windows, curtain walls, and doors by uniform static air pressure difference

X**Stone and Facings/ Linings**

IS:1121-(Parts 1 to 4)	Methods of test for determination of strength properties of natural building stones
IS:1121-(Parts 1 to 4)	(Part-1 Compressive strength)
IS:1121-(Parts 1 to 4)	(Part-2 Transverse strength)
IS:1121-(Parts 1 to 4)	(Part-3 Tensile strength)
IS:1121-(Parts 1 to 4)	(Part-4 Shear strength)
IS:1122	Method of test for determination of true specific gravity of natural building stones.
IS:1123	Method of identification of natural building stones.
IS:1124	Method of test for determination of water absorption, apparent specific gravity and porosity of natural building Stones.
IS:1125	Method of test for determination of weathering of natural building stones.
IS:1126	Method of test for determination of durability of natural building stones.
IS:1127	Recommendations for dimensions and workmanship of natural building stones for masonry work.
IS:1128	Specification for Limestone (Slabs and Tiles)

IS:1129	Recommendation for dressing of natural building stones.
IS:1130	Specification for marble (blocks, slabs and tiles).
IS:1597 (Part 2)	Code of practice for construction of stone masonry: Ashlar masonry
IS:1706	Method for determination of resistance to wear by abrasion of natural building stones
IS:1805	Glossary of terms relating to stones, quarrying and Dressing
IS:3620	Specification for laterite stone block for masonry
IS:3622	Specification for Sandstone (slab & tiles)
IS:4101 (Part 1)	Code of practice for external facing and veneers: stone Facing
IS:4101 (Part 2)	Code of practice for external facing and veneers: Cement concrete facing
IS:4101 (Part 3)	Code of practice for external facing and veneers: Wall tiling and mosaics
IS:4121	Method of test for determination of water transmission rate by capillary action through natural building stones
IS:4122	Method of test for surface softening of natural building stones by exposure to acidic atmospheres
IS:4348	Method of test for determination of permeability of natural building stones
IS:5218	Method of test for toughness of natural building stones
IS:8381	Recommended practice for quarrying stones for construction purposes
IS:14223 (Part 1)	Polished building stones: Granite
BS: 8298	Code of practice for design and installation of natural stone cladding and lining

SECTION – S.02

EARTH WORK

2.1 EXCAVATION

2.1.1 Site Clearance

The Contractor shall clear the Site as required by demolishing and removing vegetation, debris, trees along with their roots, buildings etc. and the like to approved locations either on or off the site as agreed by the Employer's Representative.

Stumps and major roots shall be grubbed up and disposed of off the site or burnt as directed. The Contractor shall take precautions to prevent the spread of fire to adjacent areas.

2.1.2 Top Soil Stripping

Top soil shall be removed by the contractor as required, deposited in separate heaps at locations approved by the Engineer.

2.1.3 Removal of Unsuitable Material

The Contractor shall remove unsuitable material as ordered or agreed by the Employer's Representative and shall dispose of it on or off the site as directed in the required manner. Boulders, stones and other materials of value or usable again on the works shall be neatly stacked and graded as directed by Employer's Representative.

2.1.4 Excavation – General- (soil and rock)

- a) Excavation shall be carried out to the lines, levels and profiles shown on the Drawings. The work shall be carried out by the Contractor in such a way as to avoid soil erosion, ground water pollution, accidents in habitation or frequented places, disturbance to the surrounding ground or structures, accident to workmen and any other untoward incident. Particular care shall be taken to maintain stability when excavating in close proximity to existing works. Fencing, caution signages with red lights and other safety measures shall be employed to avoid accidents. Where necessary, signal men shall be employed to guide the movement of people, vehicles and equipment.
- b) The work shall be carried out in a careful manner to ensure that the exposed surfaces are as sound as the nature of the material permits and that no point shall protrude inside the lines shown on the Drawings except as otherwise specified or agreed by the Employer's Representative. In soft soil excavation which is to remain open permanently, exposed faces shall be formed accurately to the required slopes and profiles and properly protected by turving or pitching as required by Employer's Representative.
- c) The Contractor shall dispose of all material arising from excavations either off the site or to approved trips on the site, as required. Any valuable material/minerals found during excavation shall be the property of the Employer or follow as per applicable law.

- d) The Contractor shall be responsible for keeping all excavations free from water from whatever cause arising and shall provide such pumping capacity and other measures as may be necessary for this purpose.
- e) The Contractor shall properly support the sides of excavations and shall be responsible for their safety. In case of any slips or blows in the excavation, the same shall be cleared by the Contractor at his own cost.
- f) The Contractor shall notify the Employer's Representative without delay of any permeable strata, joints, faults, fissures or unusual ground conditions encountered during excavation.
- g) The contractor shall ensure that no air pollution takes place during excavation, storage and transportation of earth by providing suitable measures like cover etc.
- h) The Contractor shall provide to the Employer's Representative full details of the proposed rock excavation methods for his approval. Excavation should be carried out by such manual/mechanical means or methods, so as to eliminate noise and dust up to the prescribed limits and without using any blasting and/ or any expansive chemicals. Similarly, the Contractor shall submit his plans for methods for monitoring vibration adjacent to residential area.
- i) The Contractor shall carry out rock stabilization measures with minimum delay after the excavation of each round. In order to facilitate this, the Contractor shall request that the Employer's Representative always accompanies him when inspecting the existing structures and excavated rock surfaces revealed after excavation operations.

2.1.5 Excavation beyond True Lines and Levels

If from any cause whatsoever excavations are carried out beyond their true line and level other than as per existing approved drawings then the Contractor shall make good at his own cost to the required line and level with the appropriate grade of filling to be contained in the true excavation, or with concrete or other approved material in such a manner as the Employer's Representative shall require.

2.1.6 Approval of Excavation

When excavations have been taken out accurately to the profiles or dimensions required for the work, the Contractor shall inform the Employer's Representative so that he may carry out an inspection. If Dead man is used, it should be offered for inspection to the Employer's representative.

If, after his inspection the Employer's Representative requires additional excavation to be carried out, the Contractor shall do so to such new profiles or dimensions as the Employer's Representative may direct.

2.1.7 Excavations for Structures

- a) Open excavation to lay a foundation for a structure shall be carried out to the lines and dimensions necessary to permit the proper construction of the structure.
- b) Where a structure is to be founded on soft ground, the excavation shall be taken down until the required suitable soil formation is exposed and prepared to the satisfaction of the Employer's Representative.
- c) If required, before any concrete for a foundation is placed, the bottom of the excavation shall be re-compacted to achieve a dense smooth and level surface both longitudinally and transversely or stepped. Subject to the satisfaction of the Employer's Representative, sand layers not exceeding 150 mm thick shall be placed and compacted to minimum 95% of the maximum dry density over the same.
- d) In the event of excavation having been made deeper than that shown on the drawings or as ordered by the Employer's Representative, the extra depth shall be made up with concrete of the foundation grade at the cost of the contractor. Ordinary filling shall not be used for the purpose to bring the base of foundation to required level.
- e) Surfaces of excavations or filling which are to receive reinforced concrete work shall, where indicated, be prepared with a blinding layer of concrete as shown on the Drawings or in such other manner as will provide a suitable surface at the correct lines and levels to the satisfaction of the Employer's Representative.

2.1.8 Trench Excavation

- a) Trench excavation shall be performed by the use of suitable hand tools or mechanical equipment, in such manner as to minimize disturbance of the sides and bottom of the excavation.
- b) Trenches for pipes shall be excavated to a sufficient depth and width to enable the pipe and the specified joint, bedding, haunching and surrounding to be accommodated.

2.1.9 Trenches

- a) The Contractor shall carry out excavation in a safe manner such that the sides of the trench are adequately supported and stable till the completion of work.
- b) The Contractor shall leave a clear adequate space between the edge of the excavation and the inner toes of the spoil banks.
- c) Trenches shall be excavated to the lines and levels shown on the Drawings.
- d) Trenches shall not be excavated too far in advance of pipe laying and shall be sufficiently wide to allow proper and efficient jointing to be carried out in clean and dry conditions. Due allowance shall be made for bedding and surrounds where these are specified.
- e) The bottoms of all trenches shall be trimmed to grade and level and compacted before any bedding is placed or pipes are laid.
- f) The widths of trenches crossing roads or at other locations as directed shall be as narrow

as is practicably possible. The maximum width measured between undisturbed soil in the trench sides shall not exceed the outside diameter of the pipe being laid plus 550 mm for pipes up to and including 800 mm in diameter and plus 750 mm for pipes over 800 mm in diameter. The depth of excavation shall be such as to provide adequate cover / cushion to the pipe.

- g) Trenches for pipes carrying water under pressure shall, except where otherwise described in the Contract, be excavated to a sufficient depth to ensure a minimum cover of 900mm to the top of the pipes.

2.1.10 Road Crossings

The Contractor shall close sheet and adequately support all trenches across existing roads. Great care shall be taken by the Contractor to ensure that existing roads and services are not damaged by road crossing operations. The trenches on roads shall be back filled and roads repaired on utmost priority taking all safety precautions.

2.1.11 Channels

- a) Channels shall be excavated by methods which do not endanger the stability of the side slopes.
- b) Existing channels, which are to be reshaped, cleared and trimmed, shall be cleared of all weeds and growth and the beds graded to the required levels. The sides of channels shall be trimmed to the required safe limits of slope and width.
- c) Side banks of channels shall be trimmed to a neat appearance and even surfaces.
- d) Any channels, streams, drains or pipes taking water to or from cultivated land shall be diverted so as to maintain their flow before being moved or broken into. All diversions and their subsequent reinstatement shall be carried out to the satisfaction of the Employer's Representative.
- e) The Contractor shall control the rates of filling and draw-down of water in channels so as not to endanger the stability of earthworks.

2.1.12 Approval of Excavations prior to Backfilling

The Contractor shall obtain approval of excavations prior to placing pavement layers, fill or concrete. The Contractor shall maintain open excavations in an approved condition, and shall rectify the effects of deterioration due to weather.

2.2 FILL

2.2.1 Fill - General

Prior to commencement of filling, the Contractor shall submit in writing to the Employer's Representative for 'Notice of No Objection' his proposals for carrying out the work such that the optimum use may be made of excavated material. The proposals shall include details of the compaction plant and methods for adjusting the moisture content of the

material. Filling shall not commence until the 'Notice of No Objection' proposals and the material intended to be used are put up for review by the Employer's Representative and finally his observations are carried out.

2.2.2 Fill Material

Fill material, other than for roadworks, shall be evenly graded granular material. Material with more than 20% passing a 75 micron sieve or more than 10% in excess of 75 mm size is unlikely to be suitable for use. Clods or hard lumps of earth over 75 mm in greatest dimension shall be broken up before compacting the material in embankment.

Following types of material are considered unsuitable and shall not be used for fill or embankment:

- a) Materials brought from swamps, marshes or bogs;
- b) Peat, loam, fine silt, log, stump or organic or perishable materials;
- c) Material susceptible to spontaneous combustion;
- d) Clay having liquid limit exceeding 50 and plasticity index exceeding 25;
- e) Materials containing salts prone to inducing leaching in the embankment.

The Contractor shall carry out the following initial tests on the proposed material

- 1) Wet sieve analysis
- 2) Dry density/moisture content relationship

Thereafter, one set of tests shall be carried out for each 2000 cum of fill, supplied to Site or as required by Employer's Representative.

Fill material shall be obtained only from the approved source.

2.2.3 Backfill - General

Except around structures, excavations shall be backfilled with approved material and compacted in layers not exceeding 150 mm compacted thickness to achieve a density of at least 95% of the maximum dry density.

2.2.4 Backfill to Structures

The Contractor shall not backfill around structures until the structural elements have attained adequate strength and the consent of the Employer's Representative to proceed for type of fill material has been obtained. Unless otherwise directed, the backfill material shall be sand, thoroughly compacted in layers not exceeding 200 mm deep to achieve a density of at least 95% of the maximum dry density.

2.2.5 Preparation of Base/ Foundation for Embankment

- (a) Prior to placing any embankment upon any area all clearing and grubbing operations shall have been completed in accordance with Clauses 2.1.1 to 2.1.3 and got approved by the Engineer's Representative for starting of filling operations. Where the height of

embankment is 1 meter or less all sod, grass and vegetable matter shall be removed from the ground surface and the top 15 centimetres shall be processed as necessary and compacted to 95% of the maximum dry density.

- (b) Where embankments are to be constructed on slopes, the existing slopes shall be loosened by scarifying or ploughing to a depth of not less than 10 centimetres, to ensure a good bond between the embankment and the embankment foundation, or where this is impracticable, steps in vertical and horizontal face shall be cut in the existing slope and the embankment built up in successive layers. Material which has been loosened shall be recompacted simultaneously with the first level of embankment material placed.
- (c) Where an embankment is to be placed against sloping ground, having slopes steeper than 4 horizontal to 1 vertical, continuous horizontal benches, each at least 300 mm wide, shall be cut in to the old slope for ensuring adequate bond with fresh embankment being added.
- (d) Where existing embankments are to be widened or included in new embankment, the slopes of the exiting embankment shall be ploughed or scarified to a depth of not less than 10 centimetre or, where this is impracticable, steps in horizontal and vertical faces shall be cut in existing slopes and the embankment built up in successive layers to the level of the old road, before its height is increased.

Unless otherwise shown on the Drawings, where existing unpaved roads are to be covered with less than 30 centimetre of fill, excluding pavement, the top of the old road bed shall be scarified and recompacted with the next layer of the new embankment. The total depth of the scarified and added material shall not exceed the permissible depth of layer.

- (e) Embankments in swamps or water shall be constructed by sand embankment. The Contractor shall excavate or displace swamp ground and backfill with suitable material. Backfill will be in accordance with the same provisions as for embankment.
- (f) Fill material shall not be placed against any abutment or wing wall unless permission has been granted by the Employer's Representative.

2.2.6 Placing Embankment

Embankment shall be placed in accordance with the following requirements:

- (a) General:

Except as otherwise required all embankments shall be constructed in layers approximately parallel to the finished grade of the track/ road bed. During construction of embankment, a smooth grade having an adequate crown or superelevation shall be maintained to provide drainage. Embankments shall be constructed to the required grade, and completed embankments shall correspond to the shape of the typical sections as shown on the Drawings.

During construction of embankment, it should be ensured that any work, which is to be done during the course of laying the fill material shall not be left out.

(b) Earth Embankment:

Earth embankments shall be defined as those principally of material other than rock, and shall be constructed of approved material brought from designated or other approved sources.

Except as specified for embankment in swamps, earth embankments shall be constructed in successive layers, for the full width of the cross section and in such lengths as are suited to the compaction and watering methods used.

(c) Placing over swamp ground:

Embankment in or over swamps or in water shall be placed by dumping sand in a uniformly distributed layer of a thickness not greater than that necessary to support the equipment while placing subsequent layers, after which the remainder of the embankment should be constructed in layers and compacted as specified.

(d) Preparation of subgrade:

The surface of the finished subgrade shall be neat and workmanlike and shall have the required form, super elevation, levels, grades, and cross section. The surface shall be constructed to sufficient accuracy to permit the construction of subsequent layers of material to the thickness, surface tolerance, and compaction specified.

2.2.7 Compaction of Embankments

(a) When necessary each layer, before being compacted, shall be processed as required to bring the moisture content sufficiently close to optimum to make possible its compaction to the required density. The material shall be worked as to have uniform moisture content through the entire layer.

(b) Each layer of material shall be compacted uniformly by use of adequate and appropriate compaction equipment. The compaction shall be done in a longitudinal direction along the embankment and shall generally begin at the outer edges and progress towards the centre in such a manner that each section receives equal compactive effort.

Hauling equipment shall be operated over the full width of each layer in so far as practicable. There should be a minimum overlap of 150 mm between each run of the rollers.

(c) Embankment or backfill compaction shall be carried out in one of the following two ways:-

Either the top 15 centimetres of the finished embankment shall be compacted to a dry density equal to at least 95% of the maximum dry density. Other embankment layers more

than 15 centimetres below finished surface or the underside of the lowest layer of base sub-base and shoulder shall be compacted to a dry density equal to at least 95% of the maximum dry density.

OR the embankment shall be compacted to a dry density equal to at least 95% of the maximum dry density. In the case of embankment exceeding 70 cm in height, layers more than 50 cm below finished surface or the underside of the lowest layer of base sub-base and shoulder shall be compacted to a dry density equal to at least 95% of the maximum dry density. The method to be adopted shall be directed by Employer's Representative.

2.2.8 Inverted Filter

An inverted filter consisting of stone boulders and coarse aggregates to accepted grading shall be constructed behind the earth retaining structures up to the height as shown in the drawings.

It shall be constructed simultaneously with the filling work. Care shall be taken during laying of filter media that it does not cause damage to structural members or application of excessive pressure against the structure.

2.3 TESTS

2.3.1 Testing of Fill – General

Classification tests as per relevant Standards to which the Engineer's Representative has given his consent shall be carried out to ensure that true comparisons can be made between in-situ densities, laboratory compaction densities and field trial densities i.e. that variations in properties of materials being used in the tests are not affecting the results.

Tests shall be carried out on fill to determine the degree of compaction achieved, at the rate of one test for either each 1,200 cum or each layer whichever is more frequent. Compacted layers shall not be covered without approval.

The density of individual compacted layers shall be determined by a method acceptable to the Engineer's Representative.

The in-situ dry density of fill shall average 95% of the maximum reached in trials. No single result shall be less than 92% and no more than 25% of the results on any one layer shall fall between 92% and 95%. The average shall be computed from the total number of tests on any one layer where the extent of the layer is defined by the Contractor in submitting same for inspection.

2.3.2 Materials for Top Layer of Fill

In addition to the general requirements for fill material, the material in the top layer shall not exceed the following test values:

Plasticity Index : 6

Liquid Limit : 35

Total fine shall not exceed 15%,

Uniformity Coefficient (Cu) shall not be less than 4.

The laboratory California Bearing Ratio (CBR) value, at 95% of the maximum dry density achieved after soaking for 96 hours, shall not be less than 30%.

2.3.3 Testing of Top Layer

Tests shall be carried out on the top layer of fill as follows:

Test	Frequency of test (not less than one test per...)
A. Laboratory tests to monitor the consistency of the approved material during construction:	
Maximum dry density	1500 sqm
Optimum moisture content	1500 sqm
Grading	1500 sqm
Plasticity index	1500 sqm
Linear shrinkage	1500 sqm
CBR Value	3500 sqm
B. In situ tests to confirm that the required degree of compaction is being achieved during construction:	
Dry density	500 sqm
CBR Value	2500 sqm

Tests shall be carried out as required by the accepted test procedures.

SECTION – S.03

CONCRETE: PLAIN & REINFORCED

These specifications shall be read in conjunction with the latest edition CPWD specifications with up to date correction slips, MORTH latest revision Specifications and other relevant specifications described in the Section 1.1 of these Specifications.

3.1 **MATERIALS**

Before bringing to the site, all materials for concrete shall be approved by the Engineer. All approved samples shall be deposited in the office of the Engineer before placing orders for the materials with suppliers. The materials brought on to the works shall conform in every respect to their approved samples.

Fresh samples shall be got approved and deposited with Engineer whenever type or source of any material changes. The contractor shall check fresh consignment of materials as it is brought on to the works to ensure that they conform to the specifications and/or approved samples.

The Engineer shall have the option to have any of the materials tested to find whether they are in accordance with specifications at the contractor's expense. All bills vouchers and test certificates which in the opinion of the Engineer are necessary to convince him as to the quality of materials or their suitability shall be produced for his inspection when required.

If fly ash is used in concrete, the contractor shall demonstrate the quality control procedure including source of fly ash, its properties, handling as per the relevant IS & International codes etc. and shall use only after “no objection” to the same has been obtained from the Engineer.

Any materials which have not been found to conform to the specifications and not approved by the Engineer shall be rejected forthwith and shall be removed from the site by the contractor at his own cost within the time stipulated by the Engineer. The Engineer shall have the powers to cause the contractors to purchase and use materials from any particular source, as may in his opinion be necessary for the proper execution of work without any extra cost.

Contractor shall also ensure that all constituents of exposed concrete shall be taken from same sources including cement to achieve a uniform colour and texture.

3.1.1 **Cement**

3.1.1.1 The cement used shall be of the following types:

- a) 53 grade Ordinary Portland Cement conforming to IS: 269 (Insoluble residue shall not exceed 4% by mass of cement).
- b) Portland Slag Cement (PSC) conforming to IS: 455. Magnesia shall not exceed 8% by mass of cement
- c) IRST-40 Indian Railway standard specifications for special grade cement for use in concrete sleepers
- d) 43 grade Ordinary Portland Cement conforming to IS: 269 (Insoluble residue shall not exceed 4% by mass of cement)

- 3.1.1.2** Whenever possible all cements of each type shall be obtained from one constant source throughout the contract, cement of different types shall not be mixed together. Different brands of cement, or the same brand of cement from different sources, shall not be used without prior approval of the Engineer.
- 3.1.1.3** Cement shall be delivered to the site in original sealed bags which shall be labelled with the weight, name of manufacturer, brand and type and year/week of manufacturing. Cement may also be delivered to site in bulker Cement received in torn bags shall not be used. Cement shall be used in the order in which it is received. Cement in bags in storage for more than 3 months shall be re-tested for compressive strength and setting times (initial and final) before use and may be rejected if it fails to conform to any of the requirements. A sample taken once for every 1000 bags or part thereof shall be tested. The sampling from bulker shall be increased as decided by the Engineer. Contractor may obtain cement in bulk through bags or bulker and store it in suitable silos of adequate capacity. Each type of cement shall be stored in a separate silo and it shall be ensured, that cements of different quality are not mixed up.
- 3.1.1.4** All cement shall be fresh when delivered and at ambient atmospheric temperature.
- 3.1.1.5** In fair faced elements, the cement used in the concrete for any complete element shall be from a single consignment. All cement for exposed concrete shall be from the same approved source and uniform in colour.
- 3.1.1.6** With each and every delivery of cement the contractor shall provide manufacturers certificate that the cement conforms to the relevant Indian standard. The contractor shall provide complete facilities at site for carrying out the following test:
- Setting time by vicat's apparatus as per IS:5513 and IS:4031.
 - Compressive strength on cement as per IS: 4031, IS:650, IS:10080.
- 3.1.1.7** Total chloride content in cement shall in no case exceed 0.05 percent by mass of cement. Also, total sulphur content calculated as sulphuric anhydride (SO_3), shall in no case exceed 2.5 percent and 3.0 percent when tri-calcium aluminate per cent by mass is upto 5 or greater than 5 respectively.

3.1.2 Aggregate

Aggregates from natural sources shall be in accordance with IS:383. The contractor shall submit to the Engineer certificates of grading and compliance for all consignments of aggregate. In addition, at site from time to time, the contractor shall allow for carrying out such tests and for supplying test records to the Engineer. The aggregates shall be procured from approved sources only as directed by the Engineer from time to time.

For fair faced concrete, the contractor shall ensure that aggregates are free from iron pyrites and impurities, which may cause discoloration. Aggregates shall be stored on raised paved areas having proper drainage facility in different compartments according to their nominal size.

3.1.2.1 Fine Aggregate

The contractor shall provide complete facilities at site for determining grading of aggregates by sieves as per IS: 383, IS: 460, IS: 1607, and IS: 2386. The fine aggregate shall be river sand, pit sand, stone dust, manufactured sand or other approved sand. It shall be free from clay, loam, earth or vegetable matter, salt or other harmful chemical impurities. It shall be clean, sharp, strong, angular and composed of hard siliceous material. If considered by the Engineer as necessary, the sand shall be washed in screw type mechanical washers in potable water to remove silt, clay and chlorides. This shall be done at least one day before using it in concrete. The washed sand shall be stored on a sloping concrete platform and in such a manner as to avoid contamination. Such sand washing, storing, etc. shall be at the Contractor's cost. The grading of fine aggregate when determined as described in IS: 2386 (part I), shall be within the grading zones I, II, III. Water absorption shall be less than 3% by weight (ASTM C 128)

The contractor shall provide complete facilities at site as per codal provision:

- A) Proportion of clay, silt and fine dust by sedimentation method as per IS:2386 part II.
- B) Moisture content in fine aggregate as per IS: 2386 Part III.
- C) Bulk density/ Bulkage.

3.1.2.2 Coarse Aggregate

The coarse aggregate shall be crushed stone, crushed gravel, natural gravel or a suitable combination thereof. Coarse aggregate obtained from crushed or broken stone shall be angular, hard, strong, dense, durable, clean and free from soft, friable, thin plate, elongated or flaky pieces and any deleterious material.

River gravel or pit gravel shall be sound, hard, clean, non porous, suitably graded in size with or without broken fragments and free from flat particles of shale, clay, silt, loam, and other impurities.

Except where it can be shown to the satisfaction of the Engineer that a supply of properly graded aggregate of uniform quality can be maintained over the said period of the works, the grading of aggregate shall be controlled by obtaining the coarse aggregate in different sizes and blending them in correct proportions as and when required. Aggregate shall be stored in such a way as to prevent segregation of sizes and avoid contamination with fines.

All coarse aggregate shall conform to IS: 383 and tests for conformity shall be carried out as per IS: 2386, Parts I to VIII.

The maximum size of coarse aggregate shall be such that the concrete can be placed without difficulty so as to surround all reinforcement thoroughly and fill the corners of formwork. The grading of coarse aggregate shall be such that not more than 5% shall be larger than the maximum size and not more than 10% shall be smaller than the smallest size. Between these sizes the coarse aggregate shall be well graded. Unless otherwise permitted by the Engineer the nominal maximum size shall not exceed 20 mm.

Water absorption shall be less than 3% by weight (ASTM C127)

3.1.2.3 Chloride Content

The chloride content of aggregates shall be within the recommended limits stated in IS:383 or BS EN 12620 and the chloride content of the concrete mix shall be within the recommended limit of IS: 456 or BS EN 1992. Chloride levels of aggregate shall be determined in accordance with the methods described in BS EN 1744(Part-1).

3.1.2.4 Alkali-Silica Reactivity

If aggregates contain any materials which are reactive with alkalis in any of the constituents of the concrete, or in water which will be in contact with the finished work, then the Contractor shall take samples of these materials every week. The Contractor shall ensure that the concrete mix complies with the requirements of this Specification regarding "Minimising risk of alkali-silica reaction in concrete", Vide sub section 3.3.1. The results of the Contractor's weekly monitoring tests shall be submitted in writing to the Engineer.

3.1.2.5 Sulphate Content

The total acid soluble sulphate content of the concrete mix, expressed as SO₃, shall not exceed the recommended limit in IS: 456 or BS 8110.

3.1.3 Water

Water used in the works shall be potable water and free from deleterious materials. Water used for mixing concrete as well as for cooling and/or washing aggregate shall be fresh and clean free from injurious amounts of oil, salts, acids, alkali, sugar other chemicals and organic matter. Only RO treated water shall be used in all the works including curing. RO water shall also be tested for pH, TDS, Chlorides and Sulphates on daily basis.

Water shall be from the source approved by the Engineer and shall be in accordance with clause 5.4 of IS: 456 and/or BS 3148. However, chloride content in water for R.C.C. shall not exceed 500 mg/litre.

Before starting any concreting work and wherever the source of water changes, the water shall be tested in accordance with IS: 3025 for its chemical and other impurities to ascertain its suitability for use in concrete for approval of the Engineer. No water shall be used until tested and found satisfactory. Cost of all such Tests shall be borne by the contractor.

3.2 BLENDING OF AGGREGATES:

In order to obtain optimum workability, individual aggregates of nominal size 20mm, 10mm, 4.75mm and 2.36mm will be blended in such a way that the grading curve for all aggregates will be a smooth curve from size 0.15mm to 25mm falling within the established envelop grading curve. Contractor shall establish envelop grading curve for each grade of concrete for given maximum size of aggregates and get it approved by Engineer before finalizing the mix design.

3.3

ADMIXTURES:

- a) Chemical admixtures are not to be used until permitted by the Engineer. In case their use is permitted, the type, amount and method of use of any admixtures proposed by the Contractor shall be submitted to the Engineer for approval. The minimum cement content specified shall not be reduced on account of the use of the Admixtures.
- b) The contractor shall further provide the following information concerning each admixture to the Engineer
 - i. Normal dosage and detrimental effects if any of under dosage and over dosage.
 - ii. The chemical names of the main ingredients in the admixtures.
 - iii. The chloride content, if any, expressed as a percentage by weight of admixture.
 - iv. Whether or not the admixture leads to the entrainment of air when used in the manufacturer's recommended dosage.
 - v. Where two or more admixtures are proposed to be used in any one mix, the manufacturer's written confirmation of their compatibility.
- c) In reinforced concrete, the chloride content of any admixture used shall not exceed 2 percent by weight of the admixture as determined in accordance with IS:6925 and the total chloride and sulphate contents in concrete mix shall not exceed 0.15 and 4.0 percent respectively by weight of cement.
- d) The admixtures when used shall conform to IS: 9103 or BS 5075 and BS 1014. The suitability of all admixtures shall be verified by trial mixes.
- e) The addition of calcium chloride to concrete containing embedded metal will not be permitted under any circumstances.
- f) Retarding admixtures when used shall be based on ligno-sulphonates with due consideration to clause 5.2 and 5.3 of IS: 7861.
- g) Fibre reinforcement will be Propex (Fibermesh 300-e3 / Fiber mesh 150-e3) or equivalent make polypropylene fibres, shall be added to ready-mixed concrete wherever the material is to be used for parapet, box girder. Bar reinforcement is still considered primary reinforcement. Under normal condition, add to the ready-mix at the plant in the quantity recommended by the manufacturer subjected to the approval of Engineer. If job conditions warrant, fibre reinforcement may be added at the jobsite provided that fibers are evenly distributed in the mix.
- h) Micro silica (Silica fume) when used as mineral admixture in to concrete shall be conforming to IS 15388 or ASTM C 1240 latest standards to establish specified strengths, durability and to meet special design objectives.

3.3.1 Minimising the Risk of Alkali-Silica Reaction (ASR) in Concrete**a) Precautions against ASR in Concrete**

Concrete mixes for use in the Permanent Works shall comply with one of the Subsections (b), (c) or (d). The Contractor shall notify the Engineer of his proposals for complying with this requirement.

b) The cementitious material shall have a reactive alkali content not exceeding a maximum value of 0.6% by mass when defined and tested in accordance with Subsections 3.3.1 ((e) to (k) inclusive).

To combat the ASR, Microsilica shall be used in minimum 5% cement and shall not exceed 10% by the wt of cement in order to bind free alkalis early in plastic concrete and to reduce the permeability of concrete to prevent the moisture and external alkalis penetration.

OR

c) The total mass of reactive alkali in the concrete mix shall not exceed 3.0 kg/m³ of concrete when defined, tested and calculated in accordance with Subsections 3.3.1 ((e) to (k) inclusive) and 3.3.1 ((l) to (o) inclusive).

OR

d) The aggregate shall be classed as non-reactive in accordance with the definition in Subsection (n).**e) Cementitious Material (Hydraulic and Latent Hydraulic Binders):****f) The term alkali refers to the alkali metals sodium and potassium expressed as their oxides. The reactive alkali content of Portland cements shall be defined as the percentage by mass of equivalent sodium oxide (Na₂O) calculated from:-**

$$\% \text{ equivalent Na}_2\text{O} = \% \text{ acid soluble Na}_2\text{O} + 0.658 \times (\% \text{ acid soluble K}_2\text{O})$$

g) The method used in determining the acid soluble alkali content of the materials shall be in accordance with BS 4550: Part 2: Subsection 16.2.**h) The Contractor shall make available the certified average acid soluble alkali content of Portland cement on a weekly basis.****i) The Contractor shall give immediate notice of any change which may increase the certified average acid soluble alkali content above the level used in the mix design for the concrete. A revised mix design for any concrete which would be affected by the increased alkali content shall be submitted for consent with notification of the change.****j) Minimising the Risk by Using Cementitious material Containing less than 0.6% Reactive Alkali**

The requirements of Subsection (b) will be met by Subsection (k) provided that the contribution of alkalis from other sources does not exceed 0.2 kg/m³ (see Subsections (n) and (u)). Where alkalis exceed 0.2 kg/m³ the requirements of Subsections (l) to (o) shall apply.

k) The cementitious material shall be Portland cement complying with Indian Standard and shall have additionally a certified maximum acid soluble alkali content not exceeding 0.6%.

The Contractor shall provide on request weekly certificates which name the source of the cement and confirm compliance with the Specification.

- l) Minimising the Risk by Limiting the Reactive Alkali content of the concrete to 3.0 kg/m³. The requirements of Subsection (c) will be met provided that Subsections (m), (n) and (o) are satisfied.

- m) The reactive alkali content of the concrete contributed by the Portland cement to the concrete shall be calculated from:

Portland cement

$$A = \frac{C \times a}{100},$$

Where,

A = reactive alkali content of the concrete to the nearest 0.1 (kg/m³)

C = target mean Portland cement content of the concrete (kg/m³)

a = certified average acid soluble alkali content of the Portland cement (%).

- n) Where reactive alkalis in excess of 0.2kg/m³ are contributed to the concrete from sources other than the cementitious material the limit of 3.0 kg/m³ from the cementitious material shall be reduced by the total amount so contributed.

The reactive alkali contributed by sodium chloride contamination of aggregates shall be calculated from:

$$H = 0.76 \times \frac{\{(NF \times MF) + (NC \times MC)\}}{100} \text{ (kg/m}^3\text{)}$$

Where H = equivalent alkali contribution made to the concrete by the sodium chloride

NF = chloride ion content of the fine aggregate as a percentage by mass of dry aggregates and measured according to BS 812: Part 4

MF = fine aggregate content (kg/m³)

NC = chloride ion content of the coarse aggregate as a percentage by mass of dry aggregate and measured according to BS 812: Part 4: 1976 (now in draft as Part 117)

MC = coarse aggregate content (kg/m³).

The factor 0.76 is obtained from a consideration of the composition of sea water.

The chloride ion content of aggregate sources containing 0.01% of chloride ion by mass or more shall be determined weekly in accordance with BS 812 or another approved method. When the chloride ion level is less than 0.01% it shall be regarded as nil.

- o) The Contractor shall provide certificates on request confirming compliance with the Specification and stating:
- i. The target mean cementitious material content of the concrete.
 - ii. The names of the works manufacturing the cement.
 - iii. A weekly report of the cement alkali determinations in accordance with Subsection (f).
 - iv. The certified average acid soluble alkali content of the Portland cement.

p) **Minimising the Risk by Using Selected Aggregates**

Fine and coarse aggregate material shall comply with the requirements of IS:383 (and/or AASHTO Standard Specifications M6 and M80 respectively) to be taken out to conform to 512(2).

q) **Water**

Water for use in the manufacture of concrete shall be obtained from a public utility undertaking supply or from a source approved by Engineer and shall be of potable quality, and comply with the requirement of IS:456 and or BS 3148. Only RO treated water shall be used in all the works including curing. RO water shall also be tested for pH, TDS, Chlorides and Sulphates on daily basis.

r) Where a potable mains supply is not available the Contractor shall obtain confirmation of the quality and reliability of the proposed source from the appropriate water authority and shall thereafter seek consent from the Engineer to use the proposed source.

s) Water other than from a public utility undertaking supply shall be sampled at a frequency to be determined by the Engineer and tested in accordance with the relevant provisions of IS:3025 or BS 3148. The sodium oxide and potassium oxide content shall be declared and expressed as equivalent Na_2O and shall be taken into account when calculating the total reactive alkali content of the concrete mix.

t) **Admixtures and Pigments**

Admixtures and pigments shall comply with the requirements of IS 9103 and IS:6925 or BS 5075 and BS 1014. The manufacturer's declared equivalent acid soluble alkali content and the dosage rate of any admixture or pigment to be incorporated shall be included with details of all concrete mixes submitted for consent.

u) The alkali content of admixtures shall be taken into account when determining the total equivalent alkali content of the concrete mix.

v) Microsilica (silica fume) shall be used in 5% by the weight of cement and shall not exceed 15% by the weight of cement.

3.4 **BATCHING PLANTS, MIXERS AND VIBRATORS:**

a) Unless specified in the schedule of items, for all structural concreting work the Contractor shall provide automatic weigh-batching plant of suitable capacity. The plant used shall conform to IS: 4925. Calibration of the batching plant shall be done by reputed external agency accredited by NABCB and approved by the Engineer.

b) The Contractor shall provide Concrete mixers (IS: 1791 – Batch type concrete mixers, IS: 2438 – Roller Pan Mixer) and Vibrators (IS: 2505 – Concrete Vibrators Immersion Type, IS: 2506 – Screed board concrete vibrators, IS: 4656 – Form Vibrators for Concrete) supplied by recognised manufacturers.

3.5 **GRADE OF CONCRETE:**

The concrete is designated as follows:

a) Concrete M25/20

b) The letter M refers to the mix

c) The number 25 represents the characteristic compressive strength of 15cm cubes at

28days in MPa (Mega Pascal: 1 MPa: 10 kg/cm² approximately). M25 concrete thus has a characteristic strength of 250 kg/cm². Other mix design will also be denoted in same way.

- d) The number 20 represents the nominal size of the coarse aggregate in mm.

3.6 MIX DESIGN:

It is the complete responsibility of the Contractor to design the concrete mixes by approved standard methods and to produce the required concrete conforming to the specifications and the strength, workability requirements approved by the Engineer.

Mix Design Once approved must not be altered without prior approval of Engineer. However, should the contractor anticipate any change in quality of future supply of materials than that used for preliminary mix design, he should inform the Engineer quite in advance and bring fresh samples sufficiently in advance, to carry out fresh trial mixes. Design mix will indicate by means of graphs and curves etc., the extent of variation in the grading of aggregates which can be allowed.

3.6.1 Limits of Water and Cement Contents

Maximum water/cement ratio

a)	For RCC members including piles	-	0.40
b)	For PSC members	-	0.40

3.6.2 Cement Content

Minimum Cementitious content in concrete shall be as per IRS CBC. In case of piling work minimum cementitious content shall be as specified under Pile Foundations. However, this shall be limited to 500 kg/ cum of concrete. Ordinary Portland cement(OPC) / Portland Slag cement conforming to IS: 269 / IS: 455 shall be used. For pre-stressed concrete, cement conforming to codal specifications for OPC 53 grade cement shall be used. For structures exposed to sulphate sulphate attack, Table 4 of IS:456 shall be referred. However, for nominal mixes, CPWD specification and Delhi Schedule of Rates (DSR) will be followed.

As regards trial mixes, acceptance criteria, acceptance specification, lot size, sampling and testing and sampling size for piling work, PSC girders (cast-in-situ and precast post-tensioned) and general work, the requirement of the relevant codes, standards and directions of the Engineer shall be followed.

3.7 ADDITIONAL TESTS FOR CONCRETE:

As frequently as the Engineer may require, additional testing shall be carried out for concreting in addition to mandatory test specified in latest edition of CPWD specifications / relevant IS Code / MORTH latest revision Specifications. Destructive tests for concrete Core Cutting Test shall also be performed upon receiving the Engineer's Instruction or DMRC Design Department or advise of the Lead Designer of the Contractor/DDC. Acceptance criteria shall be followed as per relevant codes. Costs related to all such tests confirming the quality of structure shall be borne by the Contractor at his own cost.

3.7.1 Non-Destructive tests for concrete

1. Ultra sonic pulse velocity test
2. Rebound hammer test

In order to determine the following properties of concrete, non-destructive tests for concrete (ultra sonic pulse velocity test and rebound hammer test) in accordance with IS 516 (Part 5/Sec 1) and IS 516 (Part5/Sec4) shall be carried out. Minimum 10% of each type of structures shall be tested for NDT.

- i. the presence of cracks, voids and other imperfections
- ii. changes in the structure of the concrete which may occur with time
- iii. the quality of the concrete in relation to the standard requirements
- iv. the quality of one element of concrete in relation to the another, and
- v. the values of dynamic elastic modulus of the concrete

In view of the limitations of each method of the non-destructive testing of the concrete, it is essential that the results of tests obtained by one method should be complemented by other tests and each method should be adopted very carefully.

3.7.2 Permeability test for Concrete:

The concrete will be verified for permeability by the following procedure and shall conform to "Permeability of Cement Mortar & Concrete", Section 1717.7. 5 of MOST Specifications, DIN 1048 and IS 516.RCPT Test shall be performed as per ASTM C1202. No extra payment shall be made for this test and cost of the same will be included in his rate for concrete work.

3.7.3 Chlorides in Concrete

The levels of equivalent acid-soluble chlorides as NaCl ($\text{Cl} \times 1.65 = \text{NaCl}$) in the constituents of concrete as stated elsewhere are indicative and are subject to the over-riding limits for the mixes.

The total estimated content as a percentage by weight of the cement in the mix shall not exceed the following limits:-

- (a) For reinforced concrete
 - 0.5% if made with Ordinary Portland Cement (OPC)
 - 0.1% if made with Sulphate Resistant Portland Cement (SRPC)
- (b) For mass concrete
 - 1.0% if made with OPC
 - 0.2% if made with SRPC

The Contractor shall test the constituents of the concrete to establish these contents as provided for elsewhere in this Specification.

In addition, regular tests to BS 1881: Part 6 for chloride content shall be made on the hardened concrete. The following values are acceptable: -

- (i) For reinforced concrete made with OPC
 - 95% of the test results less than 0.40% NaCl by weight of cement and no result greater than 0.50% NaCl by weight of cement.

(ii) For reinforced concrete made with SRPC

95% of the test results less than 0.1% NaCl by weight of cement and no result greater than 0.14% NaCl by weight of cement.

(iii) For mass concrete made with OPC

95% of the test results less than 1.0% NaCl by weight of cement, and no result greater than 1.30% NaCl by weight of cement.

(iv) For mass concrete made with SRPC

95% of the test results less than 0.2% NaCl by weight of cement and no result greater than 0.25% NaCl by weight of cement.

In the event that the SRPC used contains a proportion by weight of tri-calcium aluminate which approaches 4 - 8%, then consent may be sought for an appropriate adjustment of the relevant chloride content limits.

Sulphates in Concrete

The level of acid-soluble sulphates (SO_3) in the mix shall be no greater than:

Coarse aggregate 0.4% by weight

Fine aggregate 0.4% by weight

Water 500 mg/l

The total estimated sulphate content (SO_3) of the mix including that present in the cement shall not exceed 3.7% by weight of cement in the mix.

In addition, regular tests to BS 1881: Part 6 shall be made on the hardened concrete to determine the total sulphate content, which shall not exceed 4% by weight of cement in the mix.

Permissible Level of Chloride and Sulphates

The permissible level of chlorides and sulphates quoted in the above Subsections shall not be considered as mean values for the whole of the Works, but shall apply to any concrete.

Concrete for water-retaining structures shall in addition be as per IS: 3370.

3.8 BATCHING OF CONCRETE INGREDIENTS:

Unless permitted by the Engineer, all concreting shall be either produced in automatic weigh batching plant installed at site or Ready-Mix Concrete manufactured in automatic weigh batching plant.

3.9 PLACING TEMPERATURES:

During extreme hot or cold weather, the concreting shall be done as per procedures set out in IS: 7861, Parts I & II.

In hot weather with temperature exceeding 40 degree C, the stock piles of fine and coarse aggregates for concreting shall be kept shaded from direct rays of sun and the concrete aggregates sprinkled with water for a sufficient time before concreting in order to ensure that the temperature of these ingredients is as low as possible prior to batching. The mixer and batching equipment shall be also shaded and if necessary

painted white in order to keep their temperatures as low as possible. The placing temperature of concrete shall be as low as possible in warm weather and care shall be taken to protect freshly placed concrete from overheating by sunlight in the first few hours of its laying. The time of day selected for concreting shall also be chosen so as to minimise placing temperatures. In case of concreting in exceptionally hot weather the Engineer may in his discretion specify the use of ice either flaked and used directly in the mix or blocks used for chilling the mixing water. In either case, the Contractor shall not be paid extra for cost of ice, additional labour involved in weighing and mixing etc. All salt and saw dust shall be removed from ice before use. Quality of water used for making ice shall conform to IS: 456.

3.10 TRANSPORTING, PLACING, COMPACTING AND CURING:

Transporting, placing, compacting and curing of concrete shall be in accordance with IS: 456.

3.10.1 Transporting:

The mix after discharging from the mixer shall be transported by transit mixers, buckets, pumps etc. or as approved by the engineer without causing segregation and loss of cement slurry and without altering its desired properties with regard to water cement ratio, slump, air content, cohesion and homogeneity. It should be ensured that the concrete is moved to its final destination before it attains an initial set.

The transportation is to be done by agitating transit mixers wrapped with wet hessian cloth, pumps or other approved methods.

3.10.2 Placing:

a) Placing General

Concrete shall be placed in the position and sequence indicated on the Drawings, or as directed. Placing shall not be commenced until the fixing and condition of reinforcement and items to be embedded and the condition of the containing surfaces or formwork has been approved. 24 hours written notification shall be given of the intention to place concrete.

Concrete shall be transported by means which prevent contamination (by dust, rain etc.) segregation or loss of ingredients, and shall be transported and placed without delay.

Concrete shall be placed directly in its final position without segregation/bleeding or displacement of the reinforcement, embedded items and formwork. Concrete shall not be placed in water, except as specified. Concrete shall not be dropped through a height greater than 1.5 metres.

b) Extent of Pours

The limit of individual pours and the height of lifts shall be as approved.

For walls, the length of panel placed at one time shall not exceed 6m; adjacent panels shall not be placed within 2 days, but shall be placed as soon as practicable thereafter. Subsequent vertical lifts shall not be poured within 2 days.

For piers and pier heads, portal columns the concreting is to be carried out in single

stage i.e. in first stage concreting will be from kicker to just below pier head bottom and second stage of concreting will be pier head including shear key and cross girder (in station zone stages as given in drawings for all heights by using tremie/ pumps at the rate not more than 1.5m / hr or as approved by the Engineer.

Floors, roofs and ground slabs shall be placed in a sequence of pours to the approval of the Designer and the consent of the Engineer's Representative.

If the use of slip-forms or paving trains is permitted, these limits may be revised.

The sequence of pours shall be arranged to minimise thermal and shrinkage strains.

c) **Placing Equipment**

Concrete shall generally be placed without segregation/bleeding by pumping or bottom-opening skips. If chutes are used their slopes shall not cause segregation and spouts or baffles shall be provided.

d) **Time for Placing**

Concrete and mortar must be placed and compacted within 30 minutes of water being added to the mix or otherwise included via damp aggregates, unless admixtures are in use. Partially-set concrete shall not be used in the Works.

e) **Continuity of Placing**

Placing in each section of work shall be continuous between construction joints. The Contractor shall make provision for standby equipment. If the placing of concrete is delayed due to breakdown, then the Contractor shall erect vertical stop-ends and form a construction joint or remove the concrete already placed and restart after repair of the breakdown, as directed.

f) **Placing in Inclement Weather**

Placing shall not take place in the open during storms or heavy rains. If such conditions are likely to occur the Contractor shall provide protection for the materials, plant and formwork so that work may proceed. If strong winds are prevalent protection from driving rain and dust shall be provided.

g) **Placing in High Temperature and Low Temperature**

The temperature of concrete shall not exceed 32° nor below 5°C or the temperature stated in the table of Mixes whichever is the lower at the time of placing concrete. Also the maximum concrete temperature after placing shall not exceed temperature 50°C or 30°C above the concrete temperature at the time of placing whichever is the lower.

"Concrete in hot countries" published by FIP congress at New Delhi 1986 shall be complied with. The procedures the Contractor wishes to employ shall be subject to the Engineer consent

The Contractor shall supply suitable maximum/minimum thermometers and record the shade and sun temperatures at locations where concrete is being placed. A recommendation for cold weather concrete can be had from IS: 7861 (Part 2).

h) **Placing at Night**

If consent has been given for placing at night or in dark interiors, adequate lighting shall be provided where mixing, transportation and placing are in progress.

i) **Placing Under Water**

Underwater concrete shall be placed with minimum disturbance of the water. Running water and wave wash shall be controlled. The specified concrete grade shall be used and the mix design shall provide for good flowing ability.

Tremie pipes, bottom-dump skips or other approved placing equipment shall be used. Segregation shall be avoided.

Placing shall be commenced in approved sections and continued to completion.

The tremie pipe shall be buried in the concrete for at least 1.5m and the pipe must not be emptied until the pour is complete. If a bottom- dump skip is used, the contents shall be covered by canvas or similar before lowering into the water. The doors shall be opened when the skip is resting on the bottom with no tension in the support cable, and the skip shall be lifted gradually so that the concrete flows out steadily.

j) **Preparation Before Placing**

Before placing concrete for reinforced work on the ground, the formation shall be compacted as specified and a screed of blinding concrete shall be applied to form a surface for construction.

Before placing concrete on or against rock, masonry, brickwork or old concrete, loose material shall be removed and the surface washed down; water seepage shall be stopped or channelled away from the work.

For mass concrete placed against masonry or brickwork the following shall apply: -

- The mortar joints in the facework shall have fully hardened.
- The water-cement ratio of the concrete shall be increased to compensate for the absorption of moisture by the existing work.
- The surface shall be soaked prior to placing.
- The concrete shall be worked around ties and bond stones and into open joints.

3.10.3 Compaction:

Internal (needle) and surface (screed board) vibrators of approved make shall be used for compaction of concrete.

Internal vibrators shall be used for compaction of concrete in foundations, columns, buttresses arch section, slabs etc, and if required surface vibrators shall also be used. Depending on the thickness of layer to be compacted, 25 mm, 40 mm, 60 mm and 75 mm dia internal vibrators will be used. The concrete shall be compacted by use of appropriate diameter vibrator by holding the vibrator in position until:

- a) Air bubbles cease to come to surface.

- b) Resumption of steady frequency of vibrator after the initial short period of drop in the frequency, when the vibrator is first inserted.
 - c) The tone of the vibrated concrete becomes uniform.
 - d) Flattened, glistening surface, with coarse aggregates particles blended into it appears on the surface.
 - e) After the compaction is completed, the vibrator should be withdrawn slowly from the concrete so that concrete can flow in to the space previously occupied by the vibrator. To avoid segregation during vibration the vibrator shall not be dragged through the concrete nor used to spread the concrete. The vibrator shall be made to penetrate, into the layer of fresh concrete below if any for a depth of about 150mm. The vibrator shall be made to operate at a regular pattern of spacing. The effective radii of action will overlap approximately half a radius to ensure complete compaction.
 - f) To secure even and dense surfaces free from aggregate pockets, vibration shall be supplemented by tamping or rodding by hand in the corners of forms and along the form surfaces while the concrete is plastic.
 - g) A sufficient number of spare vibrators shall be kept readily accessible to the place of deposition of concrete to assure adequate vibration in case of breakdown of those in use.
 - h) Form vibrators whenever used shall be clamped to the sides of formwork and shall not be fixed more than 450 mm above the base of the new formwork and concrete shall be filled not higher than 230mm above the vibrator. The formwork must be made especially strong and watertight where this type of vibrator is used.
- Care must be taken to guard against over vibration especially where the workability of the concrete mix is high since this will encourage segregation of the concrete.
- i) Plain concrete in foundations shall be placed in direct contact with the bottom of the excavation, the concrete being deposited in such a manner as not to be mixed with the earth. Plain concrete also shall be vibrated to achieve full compaction.

3.10.4 Concrete placed below the ground shall be protected from falling earth during and after placing. Concrete placed in ground containing deleterious substances shall be kept free from contact with such ground and with water draining there from during placing and for a period of seven days or as otherwise instructed thereafter. Approved means shall be taken to protect immature concrete from damage by debris, excessive loading, abrasion, vibrations, deleterious ground water, mixing with earth or other materials, and other influences that may impair the strength and durability of the concrete.

3.10.5 Curing:

- a) The curing compound material should be clear, water based, non-toxic, non-film forming, reactive silicate treatment for 12 months (1 year) shelf life suitable as a complete replacement to any water curing procedures such as water soak, ponding, blankets and plastic sheets for all horizontal and vertical surfaces. After completion of

curing process, there should not be any requirement of removal or special preparation for surface applied adhesives, flooring, coatings, patching, concrete stains, etc. Material test result should be in compliance with ASTM C 309 and ASTM 1315. No curing compound is allowed for segmental box superstructure, U-Girder & precast I girder.

- b) Method of curing and their duration shall be such that the concrete will have satisfactory durability and strength and members will suffer a minimum distortion, be free from excessive efflorescence and will not cause undue cracking in the works by shrinkage.
- c) Steam curing with approved methodology can be adopted if required, for precast components subject to the approval of Engineer. No extra payment will be made for adopting steam curing. Before concrete products are subjected to any accelerated method of curing, the cement to be used shall be tested in accordance with accepted standards (relevant IS codes) especially for soundness, setting time and suitability for steam curing. In the case of elements manufactured by accelerated curing methods, concrete admixtures to reduce the water content may be allowed to be as permitted by applicable codes of practice subject to the approval of the Engineer. The normal aeration agents used to increase the workability of concrete shall not be allowed. The steam curing of concrete products shall take place under hoods, under chambers or in tunnels. Use of insulated tarpaulin of double layer and approved quality may be permitted. The steam shall have a uniform quality throughout the length of the member. The precast elements shall be stacked with sufficient clearance between each other and the bounding enclosure, so as to allow proper circulation of steam. The surrounding walls, the top cover and the floor of steam curing chamber or tunnel or hood shall be so designed as not to allow more than 1 kcal/m²/h/ °C and approved by Engineer. The inside face of the steam curing chamber, tunnel or hood shall have a damp-proof layer to maintain the humidity of steam. Moreover, proper slope shall be given to the floor and the roof to allow the condensed water to be easily drained away. At first, when steam is let into the curing chambers, the air inside shall be allowed to go out through openings provided in the hoods or side walls which shall be closed soon after moist steam is seen jetting out. Preferably, steam should be let in at the top of the chamber through perforated pipelines to allow uniform entry of steam throughout the chamber. In no case shall steam impinge directly on concrete products. The fresh concrete in the moulds shall be allowed to get the initial set before allowing the concrete to come into contact with steam. The regular heating up of fresh concrete product from 20 °C to 35 °C shall start only after a waiting period ranging from 2 to 5 hours depending on the setting time of cement used. The second stage in steam curing process shall be to heat up the concrete elements, moulds and the surroundings in the chamber. The air-space around the member shall be heated up to a temperature maximum to 70°C at a gradual rate, not faster than 10° per hour. This process shall continue 1 1/2 to 2 1/2 hours depending upon the outside temperature. The third stage of steam curing shall be to maintain the uniform temperature and pressure for a duration depending upon thickness of the section. This may vary from 3 to 5 1/2 hours. The fourth stage of steam curing shall be the gradual cooling down of concrete products and surroundings in the chamber and

normalization of the pressure to bring it at par with the outside air. The maximum cooling rate, which is dependent on the thickness of the member, shall not exceed 30° per hour. In all these cases, the difference between the temperature of the concrete product and the outside temperature shall not be more than 60°C for concrete up to M 30 and 75°C for concrete greater than M 45. In the case of light weight concrete, the difference in temperature shall not be more than 60°C for concrete less than M 25. For concrete greater than M 50, the temperature differences may go up to 75°C. After the steam curing is completed, the elements shall be further water cured for about 3 to 7 days.

- d) In order to ascertain that the curing compound is applied properly and in desired quantity uniformly, the curing compound shall be applied with colour pigment and should be applied in two layers with each layer of having different colour and to use low pressure spray guns or roller while applying curing compound. The consumption of the curing compound shall be monitored.
- e) The warranty shall be given by supplier/manufacturer for satisfactory performance of the product including its application and supervision.
- f) Use of curing compounds may be permitted with specific approval of Engineer.

3.11 JOINTS:

a) Construction Joints

Construction joints shall be located and the sequence of placing arranged as approved, to minimise shrinkage and thermal strains in the concrete.

Concrete placing shall not be interrupted except where joints occur, and shall continue after normal hours if necessary to achieve this. Joints shall be formed square to the work with keyways included.

Before placing is resumed at a joint the set surface shall be roughened to remove laitance and expose the aggregate; the aggregate shall not be damaged. If damaging materials have come into contact with the surface of the joint the concrete shall be cut back and the roughened surface cleaned by compressed air or water jets and brushed and watered immediately before placing. If required the surface shall be coated with a layer of stiff cement- grout prior to placing the new concrete.

Chemical surface- retarders shall not be used. Construction joints shall be sealed with an approved sealant at external and liquid-contact faces. Construction joints in water-retaining structures and underground structures shall incorporate an approved water stop.

b) Expansion, Contraction and Movement Joints

Expansion, contraction and other movement joints shall be incorporated in the works as shown on the Drawings.

Where shown on the Drawings approved, expansion joint fillers shall be supplied and installed. Filler material shall be stored flat on a dry surface adequately protected from

rain or moisture in such a way that the material does not deteriorate. Filler material which has been damaged or has started to deteriorate shall not be incorporated in the works.

Movement joints shall be sealed with an approved sealant applied in strict accordance with the manufacturer's instructions to the dimensions shown on the Drawings. The surface of the concrete to which the sealant is to adhere shall be straight and cleaned of all filler material, dirt, oil, grease, paint and other foreign matter. The sealant shall be applied by methods recommended by the manufacturer so that the sealant is brought flush to the surface of structure and a smooth surface is achieved. Excess material and spillage shall be properly cleaned off and removed.

Dowel bars shall be installed and cast in across the movement joint were shown on the Drawings. The bars shall be straight with clean cut ends of the diameters and lengths as shown on the Drawings or in the Schedules. Cutting and cleaning of the dowel bars shall comply with the requirements of this Specification.

The bars shall be firmly supported in the positions shown on the Drawings so that they remain accurately parallel and are not displaced during the casting of the concrete in the first part of the structure. After the concrete has hardened and the formwork removed, the projecting ends shall be cleaned of all concrete spillage and painted with two coats of an approved bituminous paint and caps shall be fitted to the free ends of the bars. Dowel bar end caps shall be of cardboard or other material, of correct diameter for the dowel bar and of sufficient length to allow the specified movement of the two adjacent concrete structures. They shall be manufactured expressly for this purpose by an approved manufacturer.

The Contractor shall take care to protect the projecting ends of dowel bars from bending or other damage prior to concreting the succeeding bay. The bituminous paint shall be applied as soon as practicable, but end caps shall not be fitted until immediately prior to the succeeding concreting operations.

c) **Water-stops**

The layout and installation of the water-stops shall be in accordance with the manufacturer's recommendation and shall be subject to the approval of Designer and the Engineer.

d) **Bolts, Inserts and Openings**

All fixing blocks, brackets, built in bolts, holes, chases, etc., shall be accurately set out and formed and carefully sealed prior to the concrete being placed. No cutting away of concrete for any of these items shall be done without the permission of the Engineer.

Bolts and other inserts to be cast into the concrete shall be securely fixed to the formwork in such a way that they are not displaced during the concreting operations,

and that there is no loss of materials from the wet concrete through holes in the formwork.

Unless shown otherwise on the Drawings or the Engineer has given consent, reinforcement shall be locally moved so that the minimum specified cover is maintained at the locations of inserts, holes, chases, etc.

Temporary plugs shall be removed and the threads of cast in bolts shall be proved to be free and shall be greased before handing over any part of the Works. Construction joints in all concrete work shall be made as directed by the Engineer. Where vertical joints are required, these shall be shuttered as directed and not allowed to take the natural slope of the concrete.

3.12 CRACKS:

If cracks, which in the opinion of the Engineer may be detrimental to the strength of the construction, develop in concrete construction, the Contractor at his own expense shall test the structure as specified in "Loading Tests" of these Specifications.

If under such test loads the cracks develop further, the Contractor shall dismantle the construction, carry away the debris, replace the construction and carry out all consequential work thereto at his own cost and in a time bound manner as directed by the Engineer.

If any cracks develop in the concrete construction, which in the opinion of the Engineer, are not detrimental to the stability of the construction, the Contractor at his own expense shall grout the cracks with neat cement grout or with other composition as directed by the Engineer and also at his own expense and risk shall make good to the satisfaction of the Engineer all other affected works such as plaster, moulding, surface finish, which in the opinion of the Engineer have suffered damage either in appearance or stability owing to such cracks. The Engineer's decision as to the extent of the liability of the Contractor in the above matter shall be final and binding.

External crack width shall be as per IRS: CBC with latest addendums.

3.13 DEFECTIVE CONCRETE:

Should any concrete be found honeycombed or in any way defective, such concrete shall be cut out partially or wholly by the Contractor and made good at his own expense. If Engineer feels that repaired structure will not be having same strength or shape or uniformity with other exposed surface as original desired structure / original structure, the same shall be rejected by Engineer and required to be dismantled and disposed by contractor at his own cost as instructed by the Engineer. Decision of the Engineer shall be final and binding.

3.14 EXPOSED FACES, HOLES AND FIXTURES:

On no account shall concrete surfaces be patched or covered up or damaged concrete rectified or replaced until the Engineer or his representative has inspected the works and issued written instructions for rectification. Failure to observe this procedure will render that portion of the works liable to rejection.

Holes for foundation or other bolts or for any other purposes shall be moulded, and steel angles, holdfasts or other fixtures shall be embedded, according to the drawing or as instructed by the Engineer.

3.15 FINISHES:

Unless otherwise instructed the face of exposed concrete placed against formwork shall be rubbed down immediately on removal of the formwork to remove irregularities. The face of concrete for which formwork is not provided other than slabs shall be smoothed with a float to give a finish equal to that of the rubbed down face, where formwork is provided. The top face of a slab which is not intended to be covered with other materials shall be levelled and floated to a smooth finish at the levels or falls shown on the drawings or as directed. The floating shall be done so as not to bring an excess of mortar to the surface of the concrete. The top face of a slab intended to be surfaced with other material shall be left with a spaded finish. Faces of concrete intended to be plastered shall be roughened by approved means to form key.

3.16 CONCRETE FOR FLOORING ON GRADE:

Concrete for flooring on grade shall be placed in alternate bays not exceedingly more than 4m x 6m or as specified in the drawings including forming the joints or adjacent bays. The stiff mix shall be thoroughly vibrated and finished to receive the floor finish.

3.17 GROUTING OF BASE PLATES & BOLT HOLES:**a) Mixing:**

Dry grout should be mixed in a mechanical mixer: the conventional 200/400-litre capacity concrete mixer can be used to mix four bags of dry grout; alternatively, paddle type mortar mixers can be used. The quantity of grout to be mixed at one time should not exceed that amount which can be placed in approximately 10 to 15 minutes.

b) Batching:

Batching of grout by fraction of a bag is not allowed. The quantity of mixing water should be the minimum commensurate with workability, compaction, and filling of the grout in all corners and crevices. Mixing should be done for a minimum of three minutes to obtain a fluid grout of uniform consistency.

c) Cleaning and preparation of the surface:

The base concrete shall be clean and strong, and its surface shall be properly hacked;

all dust shall be removed suction or compressed air. The surface shall be thoroughly wetted with water for several hours. Before the Non-shrink grout is poured, all free water shall be removed and the flat surfaces coated with a thin cement slurry.

d) **Restraint:**

Heavy back-up blocks of timber or concrete shall be fixed on all sides of the base plate to prevent escape of the grout, when poured through the openings provided in the base plate. Adequate restraint must be ensured on all the sides for a period of 7 days to obtain effective expansion and shrinkage compensation.

e) **Curing:**

The grout should not dry out where external restraint is provided in the form of form-work, the top opening and all stray openings should be covered with wet sack for at least 7 days.

f) **Placing and Compaction:**

The grout should be placed quickly and continuously either through the holes in the base plates or from one side only to ensure complete filling without entrapment of air. Grout should be properly spread and compacted by rodding. Excessive vibration should be avoided.

Below the bed plates the grout should be compacted using long pieces of doubled-over flexible steel strapping or chains. The forward and backward movement of the strap or chain will assist in the flow of the grout into place. Steps must be taken to keep the grout in full contact with the underside of the bedplate until the grout sets; maintaining a small head of fresh grout in the forms.

g) **Shrinkage Compensated Grout:**

Shrinkage compensated grout or non-shrinkable grout of Associated Cement Companies Limited or any other approved manufacturer (Fosroc, Roff, Sikka, or equivalent) should be used. The batching shall be as per the manufacturer's specifications, other procedures being as above.

3.18 PRECAST CONCRETE:

3.18.1 Manufacture off the Site

- i. Casting of members shall not begin until consent to the shop drawings, required computation, prestressing system (if required) and method of manufacture has been given and is approved by Engineer.
- ii. When the drawings and method of manufacture have been approved, no changes shall be made without the approval of designer and consent of the Engineer
- iii. The Contractor shall inform the Engineer in advance of the date of commencement of manufacture and casting of each type of member. Concrete, reinforcement and workmanship shall be as per IS:456.

- iv. A copy of all cube test results to the work shall be sent to the Engineer as soon as they become available.
- v. Where the Engineer requires tests to be carried out, no members to which the tests relate shall be dispatched to the Site until the tests have been satisfactorily completed and accepted.
- vi. All members shall be indelibly marked to show the Member Mark as described in the Contract, the production line on which they were manufactured, the date on which the concrete was cast and, if they are of symmetrical section, the face that will be uppermost when the member is in its correct position in the works. The markings shall be so located that they are not exposed to public view when the member is in its permanent position.

3.18.2 Forms

- i. The design and engineering of the forms and falsework as well as their construction shall be the responsibility of the Contractor. Design of the falsework for all concrete shall be done by approved designer. All exposed surfaces of each element of the structure shall be formed with similar material to produce similar concrete surface textures, colour, and appearance. Forms shall be inspected and approved by the Engineer prior to authorizing casting operations. Details shown on the Drawings shall be built into the forms. Worn, damaged, or otherwise unacceptable forms shall be repaired before casting of any member will be authorised.
- ii. The forms may be made either of steel or plywood. If the Contractor elects to use plywood forms, it shall be a high-quality plywood, 19mm minimum thickness, marine grade and it shall be subject to the consent of the Engineer.
- iii. Forms shall be structurally adequate to support the members within permissible tolerances. The form design shall incorporate the method and the necessary hardware to adjust and maintain grade and alignment. Details of the hardware and adjustment procedure shall be included in the required plans.
- iv. Forms shall be coated with form release agent prior to use. Form release agent shall be a standard quality form oil or other equivalent as approved by the Engineer coating which will permit the ready release of forms and will not discolour the concrete. Excess form release agent shall not be allowed to stand in puddles in the forms nor shall coating be allowed to come in contact with reinforcing steel or hardened concrete.
- v. Anchor devices may be cast into the concrete for later use in supporting forms, provided the arrangement is approved by the designer and consented by Engineer. The use of driven or drilled types of anchorages for fastening forms or form supports to concrete will not be permitted.

3.18.3 Storage

When members are stored, they shall be firmly supported only at the points specified by the Designer. The accumulation of trapped water and deleterious matter in the units shall be prevented. Care shall be taken to avoid rust staining and efflorescence.

3.18.4 Handling and Transport

- i. Members shall be lifted or supported only at points specified by the Designer or otherwise agreed by the Engineer and shall be handled and placed without impact.

- ii. The method of lifting, the type of equipment and transport to be used, and the minimum age of the members to be handled shall be subject to the Designer's requirements.

3.18.5 Assembly and Erection

The method of assembly and erection described in the Contract shall be as practicable and be strictly adhered to on site. Immediately after a unit is in position, and before the lifting equipment is removed, temporary supports or connections between members, as necessary, shall be provided. The final structural connections shall be completed as soon as possible.

3.18.6 Forming Structural Connections

- i. No structural connections shall be made until the Engineer's consent has been given.
- ii. Unless otherwise agreed by the Engineer, the composition and water/cement ratio of the in-situ concrete or mortar used in any connection and the packing of joints shall be in accordance with the assembly instructions.
- iii. Levelling devices shall only be released or removed with the consent of Engineer.

3.18.7 Epoxy Grout for Structural Connections (if required)

i. Description

Epoxy shall be furnished as 2 components which shall be mixed together at the Site.

ii. Sampling and Testing

All tests will be conducted in accordance with the latest test methods of the American Society for Testing and Materials, Federal Test Method Standard No. 141 or equivalent British Standard.

iii. Packaging, Labelling and Storing

Each component shall be packaged in steel containers not larger than 20 litres in volume. When the components are to be mixed at a ratio of 2 parts A to one part B, by volume, the container containing component B shall be one half the volume of the container containing component A. The containers shall have lug type crimp lids with ring seals, shall be new, not less than 0.6 mm nominal thickness, and shall be of such character as to resist any action by the components. Each container shall be clearly labelled with the designation (Component A or B), type (Standard or Rapid) if applicable, manufacturer's name, date of manufacture, batch number (a batch shall consist of a single charge of all components in a mixing chamber), lot number, all directions for use specified elsewhere and the following warning

"CAUTION"

"This material will cause severe dermatitis if it is allowed to come in contact with the skin or eyes. Use gloves and protective creams on the hands. Should this material contact the skin, wash thoroughly with soap and water. Do not attempt to remove this material from the skin with solvents. If any gets in the eyes, flush for 10 minutes with water and secure immediate medical attention."

Attention is directed to the characteristic of some epoxy components to crystallize or

thicken excessively prior to use when stored at temperatures below 2°C. Any material which shows evidence of crystallization or a permanent increase in viscosity or settling of pigments which cannot be readily re-dispersed with a paddle shall not be used.

iv. **Directions for Use**

At the time of mixing, components A and B shall be at a temperature between 16°C and 29°C, unless otherwise specified. Any heating of the adhesive components shall be done by application of indirect heat. Immediately prior to mixing, each component shall be thoroughly mixed with a paddle. Separate paddles shall be used to stir each component. Immediately prior to use, the 2 components shall be thoroughly mixed together in the specified ratios. When mixed, all adhesives shall have a uniformly gray colour without black or white streaks. No solvent shall be added to any epoxy.

After mixing, all epoxies shall be placed in the work and any overlaying or inserted be cleaned and it shall have moisture content of not more than 0.50% when tested. The maximum size of the aggregate shall not exceed that of material which is to be bonded to the work by the epoxy. It shall also be placed before thickening of the epoxy has begun. Surfaces upon which epoxy is to be placed shall be free of rust, paint, grease, asphalt, moisture and loose and deleterious material. When epoxy is used as a binder to make epoxy concrete or grout, the 2 components of epoxy shall be thoroughly mixed together before the aggregate is added and, unless otherwise specified, the mix proportions shall consist of one part of binder to approximately 4 parts of aggregate, by volume. Aggregate for use in epoxy concrete and grout shall one-fourth of the thickness of the joint to be grouted. All surfaces against which epoxy concrete and grout are to be placed shall be primed with a coat of the epoxy used just prior to placing the grout.

No more material shall be mixed than can be used within 20 minutes from the time mixing operations are started. Pot life of the epoxy mixture shall be 45 minutes.

v. **Epoxy Grout Strength Requirements**

The compressive strength of 38 mm cubes of epoxy grout tested in accordance with ASTM C39 after 10 hours of curing at 20°C shall be not less than the design strength of the precast number.

Temporary Supports and Connections:

Temporary supports provided during erection should take into account all construction loads likely to be encountered during the completion of joints between any combination of precast and in-situ concrete structural elements. The supports should be arranged in a manner that will permit the proper finishing and curing of any in-situ concreting and grouting associated with the precast member being supported when the gaps of joints have to be filled with concrete or mortar. They should first be cleaned and faces of the joints should be wetted. The mixing, placing and compacting of cement and mortar should be done with special care. Mortar of a dry consistency should be in the proportion of 1:1½ (1 part of cement to 1½ parts of sand) and should be placed in stages and packed hard from both sides of the joint.

Tolerances:

The following tolerances apply to finished precast products at the time of placement in the

structure. The forms must be constructed to give a casting well within these limits:

- 1 Overall dimensions of members should not vary more than $\pm 6\text{mm}$ per 3m length with a maximum variation of $\pm 20\text{mm}$.
- 2 Cross-sectional dimensions should not vary more than the following:
 - + 3mm for sections less than 150mm thick
 - + 4mm for sections over 150mm & less than 450mm
 - + 6mm for sections over 450mm to 1000mm
 - + 10mm for sections over 1000mm
- 3 Deviation from straight line in long sections should not be more than $\pm 6\text{mm}$ up to 3m, $\pm 10\text{mm}$ for 3m to 6m, $\pm 12\text{mm}$ for 6m to 12m.
 - For tolerances on precast components, standard documents shall be followed
 - Structural steel inserts/bolts for connecting precast concrete elements (Parapet to Box Girder)

Connection of precast concrete parapet with segmental box girder:

Square rods with internal threading and base plate/stiffener, shall be firmly fixed in the mould to the true line, level and alignment as shown in drawings. If required by engineer MS template may use for above purpose. The threaded hole/pipe shall be properly protected so as to prevent ingress of mortar etc (by providing dummy bolts, PVC cover, cotton waste etc).

For connection of parapet with segmental box girder bolts of required length having threads at both ends shall be provided as shown in drawings. Grade of steel will be in accordance with the values specified in the drawing. Welding to bolts is not permitted. Grade of nuts will be same as grade of respective bolts. It is imperative to verify that that bolts can be threaded smoothly at all times. Dummy bolts shall be used in the stacking yard as a protection measure to keep the threads clean free of dust / rust. Threading, bolts materials, tests etc shall be as per IS: 1367 part 1 to 16,18, IS: 1821-1987, IS: 4206.

Levelling bolts as shown in tender drawings are for facilitating alignment of the precast parapet.

3.19 READY MIX CONCRETE AND PUMPING:

- i. Ready-mixed concrete may be manufactured in a central automatic weigh Batching plant and transported to the place of work in agitating transit mixers wrapped with wet hessian cloth to maintain required concrete temperature.

The maximum size of coarse aggregate shall be limited to one-third of the smallest inside diameter of the hose or pipe used for pumping. Provision shall be made for elimination of over-sized particles by screening or by careful selection of aggregates. To obtain proper gradation it may be necessary to combine and blend certain fractional sizes of aggregates. Uniformity of gradation throughout the entire job shall be

maintained.

The quantity of coarse aggregate shall be such that the concrete can be pumped, compacted and finished without difficulty.

ii. Fine aggregates:

The gradation of fine aggregate shall be such that 15 to 30 percent should pass the 0.30 mm screen and 5 to 10 percent should pass 0.15 mm screen so as to obtain pumpable concrete. Sands, which are deficient in either of these two sizes, should be blended with selected finer sands to produce these desired percentages. With this gradation, sands having a fineness modulus between 2.4 and 2.8 are generally satisfactory. However, for uniformity, the fineness modulus of the sand should not vary more than 0.2 from the average value used in proportioning.

iii. Water, Admixtures and Slump:

The amount of water required for proper concrete consistency shall take into account the rate of mixing, length of haul, time of unloading, and ambient temperature conditions.

Additions of water to compensate for slump loss should not be resorted to nor should the design maximum water-cement ratio be exceeded. Additional dose of retarder be used to compensate the loss of slump at contractor's cost, when permitted by Engineer. Retempering water shall not be allowed to be added to mixed batches to obtain desired slump.

iv. Transportation:

The method of transportation used should efficiently deliver the concrete to the point of placement without significantly altering its desired properties with regard to water-cement ratio, slump, and homogeneity.

The revolving-drum truck bodies of approved make shall be used for transporting the concrete. The numbers of revolutions at mixing speed, during transportation, and prior to discharge shall be specified and agreed upon. Reliable counters shall be used on revolving-drum truck units. Standard mixer uniformity tests, conforming to ASTM standards C 94-69 "Standard Specifications for Ready Mix Concrete", shall be carried out to determine whether mixing is being accomplished satisfactorily.

vi. Pumping of concrete:

Only approved pumping equipment, in good working condition, shall be used for pumping of concrete. Concrete shall be pumped through a combination of rigid pipe and heavy-duty flexible hose of approved size and make. The couplings used to connect both rigid and flexible pipe sections shall be adequate in strength to withstand handling loads during erection of pipe system, misalignment, and poor support along the lines. They should be nominally rated for at least 3.5 MPa pressure and greater for rising runs over 30 m. Couplings should be designed to allow replacement of any section without moving other

pipe sections, and should provide full cross section with no construction or crevices to disrupt the smooth flow of concrete.

All necessary accessories such as curved sections of rigid pipe, swivel joints and rotary distributors, pin and gate valves to prevent backflow in the pipe line, switch valves to direct the flow into another pipe line, connection devices to fill forms from the bottom up, extra strong couplings for vertical runs, transitions for connecting different sizes of pipe, air vents for downhill pumping, clean-out equipment etc, shall be provided as and where required. Suitable power-controlled booms or specialized crane shall be used for supporting the pipe line.

vii. Field control:

Sampling at both truck discharge and point of final placement shall be employed to determine if any changes in the slump and other significant mix characteristics occur. However, for determining strength of concrete, cubes shall be taken from the placement end of line.

viii. Planning:

Proper planning of concrete supply, pump locations, line layout, placing sequence, and the entire pumping operation shall be made and got approved from the Engineer. The pump should be as near the placing area as practicable, and the entire surrounding area shall have adequate bearing strength to support concrete delivery pipes. Lines from pump to the placing area should be laid out with a minimum of bends. For large placing areas, alternate lines should be installed for rapid connection when required. Standby power and pumping equipment should be provided to replace initial equipment, should breakdown occur. The placing rate should be estimated so that concrete can be ordered at an appropriate delivery rate.

As a final check, the pump should be started and operated without concrete to be certain that all moving parts are operating properly. A grout mortar should be pumped into the lines to provide lubrication for the concrete, but this mortar shall not be used in the placement. When the form is nearly full, and there is enough concrete in the line to complete the placement the pump shall be stopped and a go-devil inserted and shall be forced through the line by water under pressure to clean it out. The go-devil should be stopped at a safe distance from the end of the line so that the water in the line will not spill into the placement area. At the end of placing operation, the line shall be cleaned in the reverse direction.

3.20 ADDITIONAL SPECIFICATIONS FOR CONCRETE (M50 & Above)

- a) Mineral admixture in the form of micro silica or condensed silica fume shall be used in the design mix. It shall comply with ASTM C 1240 "Specifications for Silica Fume for use in Hydraulic Cement Concrete and Mortar". It shall be obtained from proven and reliable manufacturer/supplier to the satisfaction of the Engineer. Use of ultrafine fly ash conforming to IS 19058:2024 may be permitted by the Engineer in the range of 5% to 10% of cement quantity.

- b) Adequate and complete dispersal of the micro silica/Ultrafine Fly Ash during the concrete mixing shall be ensured.
- c) When micro silica/Ultrafine Fly Ash is used in powder form the contractor shall take all precautions against potential health hazards during handling of the material.
- d) Chilled water and/ or ice shall be used in the concrete mix depending on the ambient temperature, dimensions of the concrete element, rate of pouring and design mix constituents.
- e) Special profuse curing arrangements covering all parts of green concrete and approved by the Engineer shall be made for dissipation of the heat of hydration. The water curing shall be continued for a period of 21 days.
- f) The concrete design mix and arrangement for mixing, transportation, and curing of concrete shall be subject to the approval of the Engineer.
- g) The Engineer may approve for the use of Curing Compounds for curing of the Pre-cast tunnel Segments after Steam curing subject to fulfilment of the following conditions:
 - i. The application of curing compound shall be allowed only on the request of the contractor and no claim whatsoever on this account shall be admissible to the contractor under any circumstances.
 - ii. Curing Compound to be used in place of water curing shall conform to the provisions of ASTM C 309 and ASTM 1315. It shall meet all the technical requirements prior to application at site.
 - iii. Curing compound shall be applied to all exposed surface of the concrete immediately after the demoulding of segments.
 - iv. Specimen cubes with curing compound are to be prepared in same conditions of curing of segments i.e. after Steam curing. The strength of cubes with curing compound should meet the acceptance criteria of minimum characteristic compressive strength as per IS 456 and durability test results should meet the acceptance criteria given in the relevant Indian/ International standards. Strength and Durability to be checked and ensured after every change of Steam cycle regime.
 - v. The Quality of Curing Compound supplied at site shall be checked regularly.
 - vi. In order to ascertain that the curing compound is applied properly and in desired quantity uniformly, the curing compound shall be applied with colour pigment and should be applied in two layers with each layer of having different colour and to use low pressure spray guns or roller while applying curing compound. The consumption of the Curing Compound shall be monitored.

3.21 SPECIFICATION FOR CRYSTALLINE DURABILITY ADMIXTURE

Apart from the regular workability admixtures, Integral Crystalline Durability admixtures shall be added in the Concrete to enhance the Concrete Durability. It shall be used for structural concrete for all Underground structures (including Precast Tunnel Segment and shotcrete inside tunnel but excluding foundations of elevated structures such as pile , pile cap, etc). The Crystalline Admixture shall be added either at the time of batching at the

batching plant or in the drum of the transit mixer, when the concrete arrives the point of pouring.

The crystalline durability admixture must confirm to the Annexure-A of S.12.

Wherever the use of crystalline durability admixture (as per Annexure-A of S.12) is provided to reduce the carbonation/corrosion in the structure, the waterproofing over the same structure (if any) is achieved by providing crystalline slurry (as per Annexure-B of S.12) in addition to the already added crystalline durability admixture (as per Annexure-A of S.12).

3.22 TESTING CONCRETE STRUCTURES FOR WATER TIGHTNESS & ACCEPTANCE CRITERIA

a) Underground Structures, Pump Rooms and Sumps

In the case of structures whose external faces are submerged and are not accessible for inspection, such as underground structures, the structures shall be filled with water and after the expiry of seven days after the filling, the level of the surface of the water shall be recorded. The level of water shall be recorded again at subsequent intervals of 24 hours over a period of seven days. Backfilling shall be withheld till the tanks are tested. The total drop in surface level over a period for seven days shall be taken as an indication of the water tightness of the structure.

A structure shall be deemed to be water tight if the total drop in the surface level over a period of seven days does not exceed 40 mm. If this limit is exceeded then remedial action shall be taken and testing shall be repeated. Backfilling shall not be done without the consent of the Engineer.

b) Roofs

The roofs of liquid-retaining structures shall be water-tight and shall be tested on completion by flooding the roof with water to a minimum depth of 25 mm for 24 hrs. Where it is impracticable, because of roof falls or otherwise, to contain a 25 mm depth of water, the roof shall have water applied by a continuous hose of sprinkler system to provide a sheet flow of water over the entire area of the roof for not less than 6 hrs. In either case the roof shall be considered satisfactory if no leaks or damp patches show on the soffit. Should the structure not satisfy either of these tests, then after completion of the remedial work it should be re-tested in accordance with this clause. The roof insulation and covering should be completed as soon as possible after satisfactory testing. Contractor shall give warranty for leak tightness of joints for 10 years.

3.23. MEASUREMENT:

Concrete, formwork and reinforcement shall be paid separately unless otherwise specified. The volume of concrete measured shall include that occupied by:

- a) Reinforcement and other metal sections.
- b) Cast in components each less than 0.01 m³ in volume.
- c) Rebates fillets or internal splays each less than 0.005 m² in cross sectional area.
- d) Pockets and holes not exceeding 0.01 m³ in volume.
- e) For M-10 concrete no payment shall be made for any shuttering used.
- 6 Rates for precast concrete shall include demoulding, handling, storing, transporting and erecting at site, including all clamping, bracing that may be required during erection including erection equipment.

3.24 CONCRETE CUBE TESTS:

The quality of hardened concrete will be verified by the following procedure:

- a) The Engineer shall select random batches of concrete for examination without warning the Contractor and sampling will generally be done at the point of discharge from the mixer.
- b) From the batches thus selected 6 concrete cubes shall be made in accordance with Indian Standards. However not more than 2 cubes may be made from any single batch. Of these 6 cubes thus made 3 cubes (each cube representing concrete of different batches) shall be tested at 7 days and the remaining 3 cubes shall be tested at 28 days.
- c) All cubes shall be made, cured, stored, transported and tested in accordance with Relevant Indian Standards. The tests shall be carried out in a laboratory approved by the Engineer.
- d) At least 6 cubes shall be made on each day's concreting until 60 cubes have been made for each grade of concrete. This is the initial period.
- e) The frequency of testing shall be as per Clause 15.2.2 of IS 456:2000

3.25. FAILURE TO MEET SPECIFIED REQUIREMENTS:

- a) If from the cube test results it appears that some portion of the Works has not attained the required strength, the Engineer may order that portion of the structure be subjected to further testing of any kind whatsoever as desired by the Engineer, including, if so desired by him, full load testing of the suspected as well as adjacent portions; of the structure as specified in the Conditions of Contract. Such testing shall be at the Contractor's cost. The Engineer may also reject the work and order its demolition and reconstruction at the Contractor's cost.
- b) If the strength of concrete in any portion of the structure is lower than the required strength, but is considered nevertheless adequate by the Engineer so that demolition is not necessary, the Contractor shall be paid a lower rate for such lower strength concrete as determined by the Engineer.

3.26. PROTECTIVE COATING ON CONCRETE STRUCTURES OF VIADUCT & ELEVATED STATIONS:

1. Product Description:

The coating shall be a high-performance fire retardant anti-carbonation coating designed for use on concrete and masonry surfaces. It shall provide long-term protection against carbonation, fire, fungal growth, bacterial contamination, and mold formation. The coating shall also be high-build, offering superior durability.

2. Technical Requirements:

Carbonation Resistance:

Shall limit carbonation penetration to less than 5mm in 50 years as per DIN 50018.

Fire Retardant Properties:

Compliant with BS 476 Part 7 (Class 1)UL94 standards for fire retardancy.

Anti-Fungal and Anti-Bacterial Properties:

Certified to prevent microbial growth as per ASTM G21.

Anti-Mold Properties:

Effective in inhibiting mold growth under humid conditions.

Build Thickness:

Minimum dry film thickness (DFT) of 80-120 microns per coat, ensuring

high-build performance.

Water Vapor Permeability: <4 g/m²/24h, ensuring breathability.

UV Resistance:

Excellent UV stability for long-term exterior durability.

3. Application Areas:

Suitable for bridges, tunnels, high-rise buildings, industrial structures, and other concrete surfaces exposed to harsh environmental conditions.

4. Application Method

Can be applied by brush, roller, or airless spray.

Surface preparation: Ensure the substrate is clean, dry, and free from contaminants.

5. Certification

The product must be tested and certified by reputed laboratories such as CBRI, NABL, or equivalent for fire retardant and carbonation resistance properties.

6. Packaging and Shelf Life:

Supplied in moisture-proof containers with a minimum shelf life of 12 months from the date of manufacture.

7. Compliance

The coating must comply with relevant ISO, ASTM, and BS standards for fire retardant and anti carbonation performance.

SECTION – S.04

FORM WORK

4.1 These specifications shall be read in conjunction with the latest edition CPWD specifications 1996/2002 with up-to-date correction slips, MORTH latest revision Specifications and other relevant specifications described in the section 1.1 of these specifications.

4.2 MATERIALS:

Formwork shall be of timber, plywood (including marine plywood), steel or any other suitable material capable of resisting damage to the contact faces under normal conditions of erecting forms, fixing steel and placing concrete. The selection of materials suitable for formwork shall be made by the Contractor based on the quality consistent with the specified finishes and safety. For designated areas prominently in public view like piers, piers caps, portals, viaduct (cast-in-situ or pre-cast), parapet etc., only steel shuttering shall be used. Steel material shall be in good condition. It should not be corroded. Condition of material shall be decided by engineer and If find not as per Indian standards or not as per requirement it shall be replaced. Number of uses for steel shuttering shall be between 50 and 100. Uses shall be decided by engineer as per the condition of steel shuttering. Special finishes like grooves, logos, floral designs, engraving in inset and outset shall be provided by fixing monolithic rubber forms fixed on entire surface of the formwork. The minimum shore hardness of rubber shall be A-55 to ensure strength, flexibility & elasticity. The contours, design and edges of rubber form should be smooth to ensure minimal deposition of grime or dust. The material shall be approved by the Engineer before erected at site. However, the entire responsibility of planning, designing, erection, dismantling, shifting and safety of false work lies with the contractor.

All formwork and formwork support (centering, props, scaffolds etc.) shall only be in structural steel and preferably of pipes conforming to IS:806, IS:1161, IS:1239, IS:2750. Wooden ballies shall not be permitted as props/formwork supports. All props shall be properly braced using x & k bracings.

Timber:

Timber used for formwork shall be easily workable with nails without splitting. It shall be stable and not liable to warp when exposed to sun and rain or wetted during concreting.

Plywood:

Plywood used for formwork shall be minimum 12 mm thick. Shuttering quality plywood complying with IS: 4990 and of make approved by the Engineer. Suitable stiffeners and walers shall be provided depending on the shuttering design.

Steel:

Steel formwork shall be made of minimum 4 mm thick black sheets stiffened with angle

iron frame made out of M.S. angles 40mm x 40 mm x 6 mm minimum supported at suitable spacing.

4.3 **DESIGN & DRAWINGS:**

All temporary works such as formwork, false work, staging, launching girder, cantilever form traveller scheme etc. shall be got designed by the Contractor from a qualified designer approved by the Engineer. The permissible stresses in materials of formwork, false work, staging, launching girder & cantilever form traveller shall be limited as same as for permanent structure. All calculations and drawings of the same including construction sequence shall be checked and verified by independent agency appointed by contractor. Only after the checking of the same, the calculations and drawings (along with soft copy in CD ROM) shall be submitted to Engineer for no objection certificate (NOC) well in advance of work. All temporary works shall be also inspected by the independent agency and independent report shall be submitted to Engineer. All temporary works shall be constructed so that the concrete can be properly placed and thoroughly compacted to obtain the required shape, position and level subject to specified tolerances. It is the responsibility of the Contractor to obtain the results required by the Engineer, whether or not some of the work is sub-contracted. NOC of the temporary works by the Engineer shall not diminish the Contractor's responsibility for the satisfactory performance of the same, nor for the safety and co-ordination of all operations.

For pier formwork, it shall be ensured that total deflection (taking account of combined deflection of plate, stiffeners, walers or any other supporting arrangement) shall not be more than 3mm. All the formwork, launching truss and cantilever form traveller and other selected temporary works shall be tested for the load including factor of safety for which the truss/formwork is designed before use in works.

The design of false work should be such as to facilitate easy and safe access to all parts for proper inspection.

Methodology for removal of form should be planned as a part of total form work design and shall be approved by the Engineer. In case of pre-stressing concrete, careful consideration shall be given to re-distribution of loads due to pre-stressing.

4.4 **FORMWORK FOR EXPOSED CONCRETE SURFACES:**

The facing formwork, unless indicated otherwise on drawings, or specifically approved by the Engineer in writing, shall generally be made with materials not less than the thickness mentioned below for different elements of the structure:

- a) Plain slab soffit and sides of beams, girders, joists and ribs and side of walls, fins, parapets, piers, sun-breakers, etc shall be made with:
 - i. Steel plates not less than 4mm thick of specified sizes stiffened with a suitable structural framework, fabricated true to plane

- ii. Timber planks of 20mm actual thickness and of specified surface finish, width and reasonable length,
 - iii. Plywood not less than 12mm thick (IS:4990 - Specification for Plywood for Concrete Shuttering Work) or 3mm thick plywood with a 20mm timber plank backing, of specified sizes stiffened with a suitable timber framework. At joints 6mm/10mm sponge to be provided.
- b) Bottoms of beams, girders and ribs, sides of columns shall be made with:
- i. Steel plates not less than 5mm thick of specified sizes stiffened with a suitable structural framework, fabricated true to plane
 - ii. Timber planks of 35mm actual thickness and of specified surface finish, width and reasonable length,
 - iii. Plywood plates not less than 12mm thick, of specified sizes stiffened with a suitable timber framework.
- c) For Precast segments, piers, piercaps, cross-arms, pier heads, portals etc. suitable steel form work is to be used unless as specified by Engineer.

4.5 FORMWORK FOR SLOPED SURFACES:

- a) Forms for sloped surfaces shall be built so that the formwork can be placed board-by-board immediately ahead of concrete placement so as to enable ready access for placement, vibration inspection and finishing of the concrete.
- b) The formwork shall also be built so that the boards can be removed one by one from the bottom up as soon as the concrete has attained sufficient stiffness to prevent sagging. Surfaces of construction joints and finished surfaces with slopes steeper than 2 horizontal: 1 vertical shall be formed as required herein.

4.6 Formwork for Curved Surfaces:

- a) The contractor shall interpolate intermediate sections as necessary and shall construct the forms so that the curvature will be continuous between sections. Where necessary to meet requirements for curvature, the form lumber shall be built up of laminated splices cut to make tight, smooth form surfaces.
- b) After the forms have been constructed, all surface imperfections shall be corrected and all surface irregularities at matching faces of form material shall be dressed to the specified curvature.

4.7 FORMWORK FOR WAFFLE SLAB :

Shuttering for Waffle Slab/ Coffered Slab shall be with Fibre Glass moulds of approved design. They can also be of Precast concrete unit as per design to form as part of structural concrete. The moulds shall be of uniform shape and dimension to give the desired shape of Coffered slab.

4.8 ERECTION OF FORMWORK:

The following shall apply to all formwork:

- a) To avoid delay and unnecessary rejection, the Contractor shall obtain the approval of the Engineer for the design of forms and the type of material used before fabricating the forms. (Ref. ACI 347 Formwork for Concrete or equivalent I.S. Code).
- b) All shuttering planks and plates shall be adequately backed to the satisfaction of the Engineer by sufficient number and size of walers or framework to ensure rigidity during concreting. All shutters shall be adequately strutted, braced and propped to the satisfaction of the Engineer to prevent deflection under deadweight of concrete and superimposed live load of workmen, materials and plant, and to withstand vibration.
- c) Vertical props shall be supported on wedges or other measures shall be taken where the props can be gently lowered vertically during removal of the formwork. Props for an upper level shall be placed directly over those in the level immediately below, and the lowest props shall bear on a sufficiently strong area. Care shall be taken that all formwork is set plumb and true to line and level or camber or better where required and as specified by the Engineer.
- d) Provision shall be made for adjustment of supporting struts where necessary. When reinforcement passes through the formwork care should be taken to ensure close fitting joints against the steel bars so as to avoid loss of fines during the compaction of concrete.
- e) If the formwork is held together by bolts, these shall be so fixed that no iron will be exposed on surfaces against which concrete is to be laid. In any case wires shall not be used with exposed concrete formwork. The Engineer may at his discretion allow the Contractor to use tie-bolts running through the concrete and the Contractor shall decide the location and size of such tie-bolts in consultation with the Engineer. Holes left in the concrete by these tie-bolts shall be filled as specified by the Engineer at no extra cost. These tie-bolts are not to be provided in structures with exposed surfaces.
- f) Provision shall be made in the shuttering for beams, columns, and walls for a port hole of convenient size so that all extraneous materials that may be collected could be removed just prior to concreting.
- g) Formwork shall be so arranged as to permit removal of forms without jarring the

concrete. Wedges, clamps and bolts shall be used wherever practicable instead of nails.

The formwork for beams and slabs shall be so erected so that forms on the sides of the beams and the soffit of slabs can be removed without disturbing the beam bottoms or props under beams.

- h) Surfaces of forms in contact with concrete shall be oiled with a mould oil of approved quality, form releasing agent or clean diesel oil. If required by the Engineer the contractor shall execute different parts of the work with different mould oils to enable the Engineer to select the most suitable. The use of oil which results in blemishes on the surface of the concrete shall not be allowed. Oil shall be applied before reinforcement has been placed and care shall be taken that no oil comes in contact with the reinforcement while it is being placed in position. The formwork shall be kept thoroughly wet during concreting and the whole time that is left in place. Nothing extra shall be paid to contractor for oiling.
- i) Immediately before concreting is commenced, the formwork shall be carefully examined to ensure the following:
 - 1 Removal of all dirt, shavings, sawdust and other refuse by brushing and washing.
 - 2 The tightness of joints between panels of sheathing and between these and any hardened core.
 - 3 The correct location of tie bars, bracing and spacers, and especially connections of bracing.
 - 4 That all wedges are secured and firm in position.
 - 5 That provision is made for traffic on formwork not to bear directly on reinforcing steel.
- j) The Contractor shall obtain the Engineer's approval for dimensional accuracies of the work and for the general arrangement of propping and bracing. (IS: 3696 - Safety Code of Scaffolds and Ladders, IS: 4014 Steel Tubular Scaffolding I & II). All scaffolding and staging shall be either of steel tubes or built-up section of rolled steel with adequate bracing at several levels in each perpendicular direction connecting each prop. In addition to this diagonal bracing should be provided in elevation ideally at 45 degrees or between 30 and 60 degree. The Contractor shall be entirely responsible for the adequacy of propping, and for keeping the wedges and other locking arrangements undisturbed through the decentring period. (IS: 8989 Safety code for erection of concrete framed structures)
- k) Formwork shall be continuously watched during the process of concreting. If during concreting any weakness develops and formwork shows any distress the work shall be stopped and remedial action as directed by the engineer shall be

taken.

- l) Staging for portal girder and cross girder (in station zone) shall be in the form of portal frame. It shall be ensured that minimum two lanes of traffic with a restricted height of 5.5m can ply underneath it with adequate protection to portal legs.
- m) For concourse floor over road, the contractor shall design and fabricate prefabricated type of staging and shuttering which can be erected in very short duration. Such erection will be only permitted in the night. In such case staging has to span the full width of the road in a portal shaped profile. The portal frame shall have 4.5m (min) traffic clearance from the road for allowing safe movement of traffic below. In case no road runs beneath the concourse zone of station, the bidder may decide whether to use the above form of staging or any normal staging arrangement from the ground itself.

4.9 **CONCRETE FINISHES:**

This section deals with the surface of concrete on which forms had been fixed while concreting.

a) **Formed Surface:**

Allowable deviation from plumb or level and from the alignment profile, grades and dimensions shown on the drawings is defined as "tolerance" and is to be distinguished from irregularities in finishes as described herein. Tolerances in concrete construction are specified elsewhere.

The classes of finish and requirements for finishing of concrete surface shall be as shown on the drawings or as hereinafter specified. In the event of finishing not being definitely specified herein or in the drawings, finishes to be adopted shall be as directed by the Engineer.

Completed concrete surface shall be tested, where necessary to determine whether surface irregularities are within the limits specified hereinafter.

Surface irregularities are classified as "Abrupt" or "Gradual". Offsets caused by displaced or misplaced form sheathing, or form sections or by loose knots or otherwise defective timber form will be considered as abrupt irregularities, and shall be tested by direct measurements. All other irregularities shall be considered as gradual irregularities and will be tested by use of template, consisting of a straight edge or the equivalent thereof for curved surfaces. The length of the template shall be 150 cm for testing of formed surfaces and 300 cm for testing of unformed surfaces.

The classes of finish for formed concrete surfaces are designated by one of the symbols F1, F2, F3 and F4. Unless otherwise specified or indicated on drawings, these classes of finish shall apply as follows:

Finish F1: This finish applies to surfaces where roughness is not objectionable,

or surface that will otherwise be permanently concealed. Surface treatment shall be the repair of defective concrete, correction of surface depressions deeper than 25 mm and filling of tie rod holes. Form sheathing will not leak mortar when concrete is vibrated. Forms may be manufactured with a minimum of refinement.

Finish F2: This finish is required on surfaces permanently but not prominently exposed to public view for which other finishes are not specified except F1. Forms shall be manufactured in a workmanlike manner to the required offsets or bulges. Surface irregularities shall not exceed 5mm for abrupt and 8mm for gradual irregularities measured with a 1.5 m template.

Finish F3: This finish is required for coarse textured concrete surfaces intended to receive plaster, stucco or wainscoting. Surface irregularities shall not exceed 5mm for both abrupt and gradual irregularities.

Finish F4: This finish is designated for surfaces prominently exposed to public view where appearance is also of special importance. This shall include piers of bridges, viaducts, beams, parapets, railings and decorative features on the structure and on the bridges. To meet with requirements for F4 finish, forms shall be manufactured in a skilful, workmanlike manner, accurately to dimensions. There should be no visible offsets, bulges or misalignment of concrete. At construction joints, the forms shall be rightly set and securely anchored close to the joint. Abrupt and gradual irregularities shall not exceed 3mm. Irregularities exceeding this limit shall be reduced by grinding to a level of 1:20 ratio of height to length. Jute bag subbing or sand blasting shall not be used.

b) **Unformed Surfaces:**

The classes of finish for unformed surfaces are designated by symbols U1, U2, U3 and U4. Unless otherwise specified or indicated on drawings, these classes of finish shall apply as follows:

Finish U1: This finish applies to unformed surfaces that will be concealed permanently or otherwise where a screeded surface finish meets the functional requirements. Finish U1 is also used as the stage of finishes for U2 and U3. Finishing operations shall consist of sufficient levelling and screeding to produce an even uniform surface. Surface irregularities shall not exceed 10mm.

Finish U2: This is floated finish, and used on all outdoor, unformed surfaces. Finish U2 is also used as the second stage of finish for U3. Floating to be performed manually or mechanically on stiffened screed surface shall be minimum to produce textured surface. If finish U3 is to be applied, floating shall be continued till a small amount of mortar without excess water is brought to the surfaces so as to permit effective trowelling. Surface irregularities shall be removed as directed by the Engineer.

Finish U3: This is a trowelled finish and shall be used for tops of parapets, etc

prominently exposed to view. When the floated surface has hardened sufficiently, steel trowelling shall be started. Steel trowelling on hardened, floated surface shall be performed with firm pressure to produce a dense uniform surface free from blemishes and trowel marks and having slightly glossy appearance. Surface irregularities shall not exceed 5mm.

Finish U4: This is a steel-trowelled finish, similar to finish U3, except that light surface pitting and light trowel marks such as obtained from the use of machine trowelling will be acceptable, provided that surface irregularities do not exceed the limits specified for finish U3.

Unformed surfaces which are nominally level shall be sloped for drainage as shown on drawings or as directed by Engineer unless the use of other slopes or level surface is indicated on drawings. Narrow surface such as tops of parapets, walls and kerbs shall be sloped approximately 1cm per 30cm of width. Broader surface such as roadways, platform and decks, shall be sloped approximately half centimeter per 30cm of width. Finishes of floor and roof slabs shall be sloped, if required, by the Engineer.

4.10 EXPOSED CONCRETE WORK:

Exposed concrete surfaces shall be smooth and even originally as stripped without any finishing or rendering. Where directed by the Engineer, the surface shall be rubbed with Carborundum stone immediately on striking the forms. The Contractor shall exercise special care and supervision of formwork and concreting to ensure that the cast members are made true to their sizes, shapes and positions and to produce the surface patterns desired. No honeycombing shall be allowed. Honeycombed parts of the concrete shall be removed by the Contractor as directed by the Engineer and fresh concrete placed without extra cost, as instructed by the Engineer. Contractor shall ensure that no air bubbles are formed on the exposed surface. Concrete pouring sequence, vibration methodology etc shall be planned to avoid air bubbles. All materials, sizes and layouts of formwork including the locations for their joints shall have prior approval of the Engineer.

4.11 AGE OF CONCRETE AT REMOVAL OF FORMWORK:

Age of Concrete at Removal of Formworks shall be in accordance with latest edition CPWD Specifications 96 or IS: 456. The Engineer may vary the periods specified if he considers it necessary. Immediately after the forms are removed, they shall be cleaned with a jet of water and a soft brush.

4.12 STRIPPING OF FORMWORK:

The work of form work removal should be planned and a definite scheme of operation worked out. Formwork shall be removed carefully without jarring the concrete, and curing of the concrete shall be commenced immediately. Concrete

surfaces to be exposed shall, where required by the Engineer, be rubbed down with Carborundum stone or bush-hammer to obtain a smooth and even finish. Where the concrete requires plastering or other finish later the concrete surface shall be immediately hacked lightly all over as directed by the Engineer. No extra charge will be allowed to the Contractor for such work on concrete surfaces after removal of forms.

4.13 REUSE OF FORMS:

The Contractor shall not be permitted reuse of timber facing formwork brought new on the works more than 5 times for exposed concrete formwork and 8 times for ordinary formwork. 5 or 8 uses shall be permitted only if forms are properly cared for, stored and repaired after each use. The Engineer may in his absolute discretion order rejection of any forms he considers unfit for use for a particular item irrespective of no of items the shuttering has been used and order removal from the site of any forms he considers unfit for use in the Works. Used forms brought on the site will be allowed proportionately fewer uses as decided by the Engineer. Use of different quality boards or the use of old and new boards in the same formwork shall not be allowed. If any other type of special or proprietary form work is used, the no. of times they can be used will be determined by the Engineer.

4.14 FORMWORK FOR PRECAST/ PRESTRESSED CONCRETE:

- a) The provisions in this section shall be considered supplementary to the general provisions stated above and additional Technical Specifications for pre cast segments. Precast concrete members and panels shall be made in accurately constructed moulds, on a properly prepared casting bed. All aspects of the making, curing and erection of precast units shall be subject to the approval of the Engineer. the contractor shall submit detailed drawings of formwork for the approval of the Engineer. Finishing with cement mortar shall not be allowed.
- b) The formwork should be so designed that it does not restrain the shrinkage movements and possible shortening due to prestress of the concrete. The formwork shall be of sturdy construction with special considerations to shutter vibrators when used. All edges and joints of the formwork should be designed and sealed so that no cement grout can escape and there is no wedging or keying to the concrete. The effect of curing on the formwork should be given special consideration. Depending on care, curing erection and maintenance after stripping, the following number of uses can be made with different types of formworks.

Plywood with timber backed formwork - As per satisfaction of Engineer

Steel moulds -do-

No of uses of shuttering be as per approval of the Engineer

in cases concrete moulds can be satisfactorily provided by the contractor, the Engineer's approval shall be obtained before use on the works.

c) **Stripping:**

As soon as the precast units have attained sufficient strength, the formwork shall be stripped. The precast unit shall be lifted uniformly out of the formwork without being subjected to tilting or restraint effects.

If proprietary system of form work is used, detailed information as given in clause 4.16 shall be furnished to Engineer for approval before use.

4.15 MEASUREMENTS:

- a) Where formwork is paid for separately, measurements shall be of the area of finally exposed surface requiring shuttering including curves, angles, splays, mitres, bevels, etc. for which no special rate shall be allowed. The rates shall be inclusive of all work connected with provision of formwork, its erection and removal and treatment of the concrete surface immediately after removal of the formwork.
- b) No extra payment shall be made for holes to be made in formwork for inserting electrical conduits, grout, earth wiring etc.
- c) Where boxes or pockets are required to be formed in the concrete, they will be paid for separately at the Contract Rates, but in measuring the area of concrete surfaces shuttered, no deduction will be made for openings up to 0.4m². For voids larger than 0.4m² the surface of formwork forming the voids shall be paid at rates of formwork set out in the Schedule and the area of voids deducted from the face area of shuttering.
- d) No payment shall be made for temporary formwork used in concreting, nor for formwork required for joints or bulkheads, in floors, or elsewhere, whether such joints are to be covered later with concrete or mastic or other material.

4.16 INFORMATION TO BE SUPPLIED BY MANUFACTURERS OF PROPRIETARY SYSTEMS OF FORM WORK

a) **General**

- i. The information which the manufacturer is required to supply shall be in such detail as to obviate unsafe erection and use of equipment due to the intention of the manufacturer not having been made clear or due to wrong assumptions on the part of the user.
- ii. The user shall refer unusual problems of erection/assembly not in keeping with intended use of equipment, to the manufacturer of the equipment.

b) Information Required

The manufacturers of proprietary systems shall supply the following information;

- i. Description of basic functions of equipment.
- ii. List of items of equipment available, giving range of sizes, spans and such like, with manufacturer's identification number or other references.
- iii. The basis on which safe working loads have been determined and whether the factor of safety given applies to collapse or yield.
- iv. Whether the supplier's data are based on calculations or tests. This shall be clearly stated as there may be wide variations between results obtained by either method.
- v. Instructions for use and maintenance, including any points which require special attention during erection, especially where safety is concerned.
- vi. Detailed dimensional information, as follows:
 - 1 Overall dimensions, depths and widths of members.
 - 2 Line drawings including perspectives and photographs showing normal uses.
 - 3 Self-weight.
 - 4 Full dimensions of connections and any special positioning and supporting arrangements.
 - 5 Sizes of members, including tube diameters and thicknesses of material.
 - 6 Any permanent camber built into the equipment.
 - 7 Sizes of holes and dimensions giving their positions.
 - 8 Manner of fixing including arrangements for sealing joints.
- vii. Data relating to strength of equipment as follows:
 - 1 Average failure loads as determined by tests.
 - 2 Recommended maximum working loads for various conditions of use.
 - 3 Working resistance moments derived from tests.
 - 4 Working shear capacities derived from tests.
 - 5 Recommended factors of safety used in assessing recommended loads and deflections based on test results.
 - 6 Deflections under load together with recommended pre-camber and limiting deflections.
 - 7 If working loads depend on calculations, working stresses should be tested. If deflections depend on theoretical moments of inertia or

equivalent moments of inertia rather than tests, this should be noted.

- 8 Information on the design of sway bracing against wind and other horizontal loadings.
- 9 Allowable loading relating maximum extension of bases and/or heads.
- 10 Any restrictions regarding usage of any component or full assembly with regard to spans, heights and loading conditions.

4.17 For welded temporary structures and for bolted temporary structures, the provisions of Section 7.2 and 7.3 of OCS- Structural Steel works respectively shall be followed. Quality control and testing requirements for temporary structures shall be followed as per Section 7.5 of OCS.

All structural steel materials including bolts, nuts and welding electrodes shall be procured from the approved manufacturers by DMRC. Manufacture Mill test reports in respect of steel materials, bolts, nuts and welding electrodes shall be submitted to the Engineer.

SECTION S.05

REINFORCEMENT

- 5.1** These specifications shall be read in conjunction with the latest edition CPWD specifications 1996/2002 with upto date correction slips, MORTH latest revision Specifications and other relevant specifications described in the section 1.1 of these specifications.

Any steel specified for reinforcement shall conform in every respect to the latest relevant Indian Standard Specifications and shall be of tested quality under the ISI Certification Scheme.

All reinforcement work shall be executed in conformity with the drawings supplied and instructions given by the Engineer and shall generally be carried out in accordance with the relevant Indian Standard Specifications IS: 2502- Bending and Fixing of Bars for Concrete Reinforcement.

The reinforcement steel shall only be from primary producers as per approved vendor list and no re-rolled steel shall be supplied.

- 5.1.1** Mechanical couplers of threaded type with enlargement at connection by cold forging maybe used at appropriate locations after prior approval of engineer

5.1.2 Coupler Specifications

a) Introduction

Only cold-forged, standard parallel threaded mechanical coupler system are recommended. All mechanical couplers shall be of Type 2 (or Class H as specified in IS-16172) and should be simple to install and which can be confirmed by quick visual inspection to have been correctly installed and to have achieved the required full-strength connection. Any other types of mechanical coupler systems are not permitted provided the same meet the specification indicated below.

The couplers shall be of standard parallel thread type. Ends of the reinforcement bars, which are to be joined, shall be enlarged by cold forging/upsetting, threaded in such a way that root thread diameter is not lesser than the parent bar to be joined. The coupler shall be of TYPE – II and qualified/Certified as per UK CARES, IS code 16172, ACI 318, AC 133, ASME, Section III, and Div.2, Caltrans.

Couplers installed shall be strictly in accordance with the manufacturer's specifications complying to relevant codes. Couplers shall preferably be located away from high stress zones in the various structural elements and shall be staggered.

All the couplers shall be manufactured in a factory which is ISO 9001:2008 (or higher revision) certified for "Manufacturing of Mechanical Steel Rebar Couplers & Accessories" and also be certified for "Site Management of Threading & Processing of Rebar including Sales and Distribution". All the couplers shall

undergo quality checks on uniformity of threads, dimensional accuracy etc. Each coupler shall be clearly stamped indicating batch number and diameter. This number shall be traceable to the original cast. The relevant material mill certificate shall be submitted with supply of a particular lot. The certificate shall give salient material properties. The coupler manufacturer shall operate at least an ISO 9000 approved quality assurance programme or equivalent for the manufacture of couplers.

b) Threading of ends of the reinforcing bars:

This threading activity shall preferably be done at Site. The various stages involved in threading are as given below:

i. Cutting (Rebar End Preparation):

The ends of reinforcement bars shall be cut by mechanical means to get a perfect plain and surface perpendicular to the axis of the bar.

ii. Cold forging & threading:

After cutting the ends of the bar shall be enlarged by cold forging such that the area of cross section after threading shall not be less than the area of cross section of the parent bar. The length of cold forging shall be adequate for proposed thread length as per manufacturer's design. Threading shall be done preferably on threading machine. The threads shall be standard parallel type to suit the couplers. The thread length and depth shall be as per manufacturer's design. After threading is completed, the threaded length of the bars shall be protected by providing plastic end caps before taking the bars out of the shop.

c) Quality control in making of threads:

Double forging of bars is not permitted. In case of improper cold forging the forged end of the bar shall be square cut and fresh cold forging shall be undertaken. 100% threading at threaded rebars shall be checked with 'go' and 'no go' gauges and "thread length" for the correctness of the thread profile on the rebar. A proper record for same shall be maintained at site and shall be verified by the representative of the Engineer at regular interval.

d) Qualification tests

The coupler shall be qualified as per IS code 16172, AC 133, ACI 318, ASME - Section III, and Div.2, Caltrans and must have conducted & qualified for the following tests :

i. Static tensile test

Mechanical connections shall be tested for all reinforcing rebar sizes. For each rebar size, a minimum of three connections (3 joints + 1 Parent bar) in each load direction shall be tested in accordance with ASTM A370 test method to meet code requirement. A tensile test

on an unsliced specimen from the same bar used for the spliced specimens shall be performed to establish actual tensile strength. The tensile strength of an individual splice system shall be as per IS 16172.

If the couplers are delivered or stacked for more than three months at the site, the static tensile tests shall be repeated on the remaining couplers to ensure suitability of couplers. If tests are failed, the remaining couplers shall be rejected without retesting of the same.

ii. **Cyclic tension and compression test**

Mechanical connections shall be tested in all reinforcing rebar sizes. For each rebar size, a minimum of three connections shall be tested for cyclic tension & compression test. Each specimen shall withstand cycles of stress variation of the specified minimum yield strength of the reinforcing bar. The test should be carried out as per the table mentioned below:

Loading Stages and Cycles per stage for cyclic load test

Stage	Tension	Compression	Cycles
1	0.95 f_y	0.5 f_y	20cycles
2	2 ϵ_y	0.5 f_y	4cycles
3	5 ϵ_y	0.5 f_y	4cycles
4	Load in Tension till failure		

Note:

f_y is specified yield strength of the reinforcing bar.

ϵ_y is the strength of reinforcing bar at actual yield stress

iii. **Cyclic tensile test**

Mechanical connections shall be tested in all reinforcing rebar sizes. For each rebar size, a minimum of three connections shall be tested for low cyclic tensile test. Each specimen shall withstand 100 cycles of stress variation from 5% to 90% of the specified minimum yield strength (f_y) of the reinforcing bar. One cycle is defined as an increase from the lower load to the higher load & return. Cyclic Tensile Test are to be conducted at the time of source approval i.e. before using the material at site.

If the couplers are delivered or stacked for more than six months at the site, the cyclic tensile tests shall be repeated on the remaining couplers to ensure suitability of couplers. If tests are failed, the remaining couplers shall be rejected without retesting of the same.

iv. **Low cycle fatigue test (for 10,000 cycles)**

Fatigue test shall be conducted on splice sample from +173 Mpa to -173 Mpa for 10,000 cycles. A sine wave form @ 0.5 Hz shall be followed for bar dia 36 mm & above and 0.35 Hz shall be followed for bar dia less than 36 mm. Test shall be conducted confirming to IS 16172:2014 & Caltrans specifications. Low cycle fatigue test are to be conducted at the time of source approval i.e. before using

the material at site.

v. **High cycle fatigue test (for 2,000,000 cycles)**

In high cycle fatigue test, the test specimen is subjected to an axial tensile load which varies cyclically according to the sinusoidal wave form of constant frequency in the elastic range, as accordance with IS-16172. High cycle fatigue test are to be conducted at the time of source approval i.e. before using the material at site

vi. **Slip test**

Slip Test Shall be performed on each diameter coupler specimen as per ASTM A 370 section 10. Test shall be conducted confirming to IS 16172:2014 & Caltrans specifications. Total slip shall not exceed the max value of 0.1 mm. Slip test are to be conducted at the time of source approval i.e. before using the material at site.

vii. **Proof loading test**

Every cold-forged, threaded bar end shall undergo a proof load test prior to leaving system supplier's workshop. Every threaded bar must be subjected to proof load testing to a minimum test loading of 80% of the characteristic strength (theoretical fy). The system supplier shall essentially install a proof load tester equipment in accordance with Annex G, Clause G-2(d) of IS 16172 within its threading workshop premises and ensure to test each and every threaded bar. A positive indication shall be marked on the rebar to indicate that this operation has been carried out. A proper record for same shall be maintained at site and shall be verified by the representative of the Engineer.

INSTALLATION OF COUPLERS IN THE FIELD:

The installation of couplers in the field, for joining reinforcing bars shall be undertaken by trained manpower and as per manufacturer's instructions. Threads of both the couplers and the bars shall be thoroughly cleaned just before installation. Where couplers are cast-in the concrete, but connection is not to be completed immediately, the couplers shall be internally greased and plastic capped to a protection detail acceptable to the engineer. This cap shall be removed only when next bar is to be attached, then the same to be cleaned before joining the next bar.

The contractor shall arrange for a suitably qualified manufacturer's representative experienced in mechanically connecting reinforcement to be present at site before the start of work for initial training of personnel, and also to demonstrate the equipment and techniques as necessary. The threading workshop is to be fully supervised by the manufacturer's representative.

The contractor shall submit to the Engineer, for his acceptance a method statement for mechanically connecting the reinforcement and for the installation

and verification in the field. This shall take into account any special requirements for horizontal, vertical and inclined couplers and shall include a rectification procedure, if the connection is incorrectly made. It shall also cover the correct methodology for handling of tools and equipment for mechanical connection on site. The following information shall also be included:

- 1 Requirements for cleanliness
- 2 Equipment for threading bars
- 3 Method of locking the connections on both rebars
- 4 Method of verification of final rebars alignment and coupler integrity

Each coupler shall be visually examined prior to use to ensure the absence of rust and of any foreign material on the inside surface. All completed couplers shall be inspected and verified in accordance with the approved QAP. The Contractor shall ensure the acceptance of the Engineer for a procedure for documenting the inspection of the couplers. The contractor shall retain inspection records and shall submit copies to the Engineer within 7 days. The Couplers that do not meet the acceptance shall be completely removed and the bars re-connected as required.

5.2 REINFORCEMENT COATING

Reinforcement bars used for elevated structures shall not be coated as per IRS CBC clause 7.1.5, as the resistance against corrosion is provided by the use of anti-carbonation coating for elevated structures as stipulated in clause 3.26 of this specification.

For underground structures, the resistance against carbonation/corrosion is being provided by the use of crystalline durability admixture as stipulated in clause 3.21 of this specification.

5.3 INSPECTION & TESTING:

Every bar shall be inspected before assembling on the works and any defective, brittle, excessively rusted or burnt bars shall be removed. Cracked ends of bars shall be cut out.

No work shall be commenced without the Engineer's approval of the bar bending schedule.

Manufacturer's Certificate shall be supplied for each lot of supply.

The frequency of tests on reinforcement consignment delivered at site from one manufacturer should be as per CPWD specifications.

5.4 BAR BENDING AND BAR BENDING SCHEDULE:

All bars will be carefully and accurately bent by approved means in accordance with IS: 2502, and relevant drawings. It shall be ensured that depth of crank is correct as per the bar cutting and bending schedule and bent bars are not

straightened for use in any manner that will injure the material.

Prior to starting bar bending work, the Contractor shall prepare bar bending schedule from the structural drawings supplied to him and get the same approved by Engineer. Any discrepancies and inaccuracies found by the Contractor in the drawings shall be immediately reported to the Engineer whose interpretation and decision there to, shall be accepted.

5.5 LAPPING & WELDING/MECHANICAL SPLICING

- a) As far as possible bars of the maximum length available shall be used. Laps shown on drawings or otherwise specified by the Engineer will be based on the use by the Contractor of bars of maximum length. In case the Contractor wishes to use shorter bars, laps/couplers (approved make with permission the Engineer) shall be provided in the manner and at the locations approved by the Engineer.
- b) Bars having butt or lap welds shall be provided as specified in the drawings or as instructed by the Engineer.

5.6 SPACING, SUPPORTING AND CLEANING:

- a) All reinforcement shall be placed and maintained in the positions shown on the drawings to be prepared by contractor.
- b) The Contractor shall provide approved types of supports for maintaining the bars in position and ensuring required spacing and correct cover of concrete to the reinforcement as specified on the drawings. Cover blocks of required shape and size, M.S. Chairs and spacer bars shall be used to ensure accurate positioning of reinforcement. Cover blocks shall be cast well in advance and shall consist of approved proprietary pre-packaged free flowing mortars (Conbextra HF or Fosroc or equivalent). They shall be circular in shape for side cover and square for bottom cover. The cost of cover block shall be deemed to have been included in the rates. The strength of cover block shall be same or higher than the strength of concrete used.
- c) Bars must be cleaned, before concreting commences, of all scale, rust or partially set concrete which may have been deposited there during placing of previous lift of concrete.
- d) Only Fe500D/Fe550D TMT bars complying to IS:1786 and IRS-Seismic code shall be provided as per drawing. Intermixing of Fe500D & Fe550D shall not be permitted.
- e) G.I. wire shall be used for binding reinforcement and diameter of binding wire shall not be less than 1 mm.

5.7 WELDING:

- a) Wherever specified all lap and butt welding of bars shall be carried in accordance with IS: 816:1989. Only qualified welders shall be permitted to carry out such welding.
- b) For cold twisted reinforcement welding operations must be controlled to prevent a supply of large amounts of heat larger than that can be dissipated. The extreme non twisted end portion shall be cut off before welding. Electrodes with rutile coating should be used.
- c) For welding on TMT bars shall be only allowed for special welding grade reinforcement as per 1606.2 of MORTH specifications.
- d) Bars shall be free from rust at the joints to be welded.
- e) Slag produced in welding after alternative run should be chipped and removed by brush.
- f) Electrode should not be lighted by touching the hot bar.
- g) The welding procedure shall be approved by the Engineer and tests shall be made to prove the soundness of the welded connection.
- h) E8018 electrode shall be used for Fe500D/Fe550D above as per AWS (American Welding Society) standards.

5.8 MEASUREMENT:

- a) The weight of steel to be paid for at the contract rates shall be the weight of bars as mentioned on the drawings or as instructed by the Engineer including stirrups, ties, spacer bars, chairs specified as reinforcement but excluding binding wire and cover blocks.
- b) The weight of any stirrup, tie bar shall be computed from the dimensions given on the drawings or bending schedules. The weight in kg/metre shall be taken as 0.785 kg/metre per 100mm² of cross section. The rate shall take into account the rolling margin.

SECTION – S.06**PRESTRESSED CONCRETE**

Structural concrete containing prestressed steel reinforcement to introduce pre-compression is termed as prestressed concrete.

6.1 GENERAL

The work shall be carried out in accordance with the drawing and these specifications or as approved by the Engineer.

Concrete and untensioned steel for the construction of prestressed concrete members shall conform to the requirements of sections respectively in so far as the requirements of these Sections apply and are not specifically modified by requirements set forth herein.

Contractor shall ensure that different components of prestressing such as jacks, bearing plates, wedges, anchorages, strands and HDPE ducts are compatible to each other and the same shall be exchanged in between all the suppliers to ensure the same.

6.2 MATERIALS**6.2.1 Sheathing**

Material for all pre-stressing sheathing duct shall be HDPE in the form of corrugated. The Thickness of the HDPE sheathing ducts shall be as per conforming to IRS Concrete Bridge Code & IRC -112, with modifications as stated below).

For Anchorage system 19 K 15, HDPE ducts of 124mm OD/ 107mm ID (tolerance $\pm$ 1mm) with minimum thickness of ducts 3.00 mm

For Anchorage system 12 K 15, HDPE ducts of 100 mm OD/ 85 mm ID (tolerance $\pm$ 1mm) with minimum thickness of ducts 2.50 mm

For Anchorage system 7 K 15, HDPE ducts of 84 mm OD/ 69 mm ID (tolerance $\pm$ 1mm) with minimum thickness of ducts 2.50 mm

The material for the ducts shall be high-density polyethylene with more than 2 percent carbon black to provide resistance to ultra-violet degradation and shall have the following properties:

Density (IS 2530)	: 0.94 – 0.96 g/cm ³ at 23°C
Tensile Strength at yield (BS EN ISO 527-3)	: 20-26 N/mm ²
Shore Hardness D (BS EN ISO 2039-1)	: 55-65
Elongation at Yield (BS EN ISO 527-3)	: 7 % (min)
Melt Flow Index (MFI) (IS:2530)	0.5-1.2 g / 10 :minutes

(Temperature 190 °C under a mass of 5 kg)

Charpy Impact strength of notched specimen (BS EN ISO 179)

At 23°C :1 kJ/m²-40°C : 4 kJ/m²Coefficient of Thermal Expansion for 20°C – 80°C (DIN 53 752): 1.50×10^{-4} / °C

Environmental Stress Crack Resistance (ASTM D-1693) at 70° C: 192 Hrs

The residual wall thickness after loss (wear resistance) shall not be less than 1.5mm for ducts upto 85mm diameter and 2mm for ducts diameter above 85mm as per IRC – 112:2011.

The ducts shall be corrugated on both sides. The duct shall transmit full tendon strength from the tendon to the surrounding concrete over a length not greater than 40 duct diameters. Material and formulation of sheathing ducts shall conform to test and acceptance criteria of IRC-112.

These ducts shall be joined by adopting any one or more of the following methods, as convenient to suit the individual requirements of the location, subject to satisfactory pressure tests, before adoption.

- Screwed together with male and female threads
- Joining with thick walled HDPE shrink couplers with glue. This can also be used for connection with trumpet, etc
- Welding with electro fusion couplers.

The joints shall be able to withstand an internal pressure of 0.5 bar for 5 minutes as per water loss test procedure given in Appendix-B of IRS Concrete Bridge Code-1997

The initial acceptance tests such as bond test, compression test are required to be performed as acceptance criteria for system. In addition to above, the HDPE ducts supplier must have conducted friction test at least once as given in FIB bulletin No-7 to establish/confirm the friction values (K & μ) using the HDPE ducts produced by them, submit the test details and obtain approval prior to commencing supplies.

The routine test such as workability test, transverse load rating test, tension load test and water loss test shall be applicable for both post threading and pre – threading system of cables. Loads to be imparted on the 107mm ID sheathing during transverse load rating test and tension load test shall be extrapolated from values given for smaller dia sheathing as per IRC 112. At least 3 samples for one lot of supply (not exceeding 7000 meter length) shall be tested.

- 6.2.1.3** In viaduct constructed by precast segmental construction, cables shall be threaded after application of temporary prestressing. In continuous unit, constructed by cantilever construction techniques the cantilever cables will be stressed as various segments are cast progressively. Such cables shall be threaded after concreting. In such cases a temporary flexible PVC tube of 90 mm O.D shall be homed through sheathing which will provide adequate stiffness to sheathing during concreting and also prevent blockage of sheathing in case of possibility of leakage. The temporary PVC tube shall be pulled out before threading of the permanent cables.

6.2.2 Anchorages

- 6.2.2.1** Anchorages shall be procured from authorized manufacturers only. Anchorages shall conform to BS: 4447/FIP-1993/IS 1343.

Load transfer test and anchorage efficiency shall be conducted as defined in FIP-1993. Engineer shall select at random, the required anchorage / wedges sample from completed lots for testing by the manufacturer. The concrete unit of required size/R/F will be made by contractor using same design mix of concrete which will be required for the load transfer test. The load transfer test shall be conducted at the strength of concrete at which stressing are proposed in the drawings.

No damaged anchorages shall be used. Steel parts shall be protected from corrosion at all times. Threaded parts shall be protected by greased wrappings and tapped holes shall be protected by suitable plugs until used. The anchorage components shall be kept free from mortar and loose rust and any other deleterious coating.

After completion of pre-stressing and grouting of cable in PSC girders, the extra length pre-stressing strands projecting outside the anchorage are required to be cut and an anchored endis to be sealed.

- 6.2.2.2** Swages of prestressing strand shall develop strength of at least 95 per cent of the specified breaking load of the strand.

- 6.2.2.3** Untensioned Steel reinforcements, around anchorages shall be furnished by prestressing system supplier. Requirement of the same should be job specific and based on edge distance of anchorage and strength of concrete at the time of stressing of cables as defined in drawings. The same R/F shall be provided in unit required for load transfer test.

Minimum 3 tests each are required to be conducted for load transfer test and anchorage efficiency test. The manufacturer shall complete the required testing and determine compliance the result with FIP-1993 recommendations before transporting the lot to site.

6.2.3 Prestressing Steel

Uncoated stress relieved low relaxation steel conforming to IS: 14268, class – 2 shall be used. Nominal dia. shall be 15.2 mm with 1860 MPa tensile strength and minimum breaking strength of 259 KN and minimum 0.2% proof load of 228 KN. various test as recommended

in IS: 14268 shall be conducted before transporting the lot to site. Apart from 1000 hrs relaxation test conducted by manufacturer, at least two such tests are required to be conducted by independent agency in the beginning of project.

6.2.4 Prestressing Strands/Wires Storage

All high tensile steel for prestressing work shall be stored about 30cm above the ground in a suitably covered and closed space to protect it from dampness. It shall also be invariably wrapped in gunny cloth or tar paper or any other suitable materials, as per approval of Engineer. Even if it is to be stored in an area at the site for short time during transit it shall be suitably covered. Protection during storage and repacking or application of washable protective coating to the H.T. steel shall be given by the contractor at no extra cost if the packing of H. T. Strand/wire during unloading and storage / handling in the stores gets damaged.

Stock piling of H. T. Steel on the work site shall not be allowed any time, especially before and during the monsoon.

Engineer or his authorized representative shall always have an easy access to the store-yard for inspecting the H. T. Wire/strands/Bars and satisfying themselves regarding the condition thereof. Any modifications regarding storage suggested by Engineer shall scrupulously be followed by the contractor. During monsoon days, H.T wires/strands shall be kept in reasonable air tight store, if required by the Engineer, at no extra cost.

6.3 TESTING OF PRESTRESSING STEEL AND ANCHORAGES

All materials specified for testing shall be furnished free of cost and shall be delivered in time for tests to be made well in advance of anticipated time of use.

All strands to be transported to the site shall be assigned a lot number and tagged for identification purposes. Anchorage assemblies to be transported shall be like-wise identified.

All samples submitted shall be representative of the lot to be furnished and in the case of strand, shall be taken from the same master roll. The Contractor shall furnish samples of at least 5.0m length selected from each lot for testing. Also, two anchorage assemblies, complete with distribution plates of each size or types to be used, shall be furnished along with short lengths of strands as required.

6.4 WORKMANSHIP

6.4.1 Cleaning

Tendons shall be free from loose rust, oil, grease, tar, paint, mud or any other deleterious substance.

Cleaning of the steel may be carried out by immersion in suitable solvent solutions, wire brushing or passing through a pressure box containing Carborundum powder. However, the tendons shall not be brought to a polished condition.

6.4.2 Straightening

High tensile strand shall be supplied in coils of sufficiently large diameter such that tendons shall retain their physical properties and shall be straight as it unwinds from the coil. Tendons of any type that are damaged, kinked or bent shall not be used.

The packing of prestressing strand shall be removed only just prior to making of cable for placement. Suitable stands shall be provided to facilitate uncoiling of strands without damage to steel. Care shall be taken to avoid the possibility of steel coming into contact with the ground.

6.4.3 Positioning

6.4.3.1 Post-Tensioning

Prestressing tendons shall be accurately located and maintained in position, both vertically and horizontally, as per drawings.

Tendons shall be so arranged that they have a smooth profile without sudden bends or kinks.

The location of prestressed cables shall be such as to facilitate easy placement and vibration of concrete in between the tendons.

Sheathing shall be placed in correct position and profile by providing suitable ladders and spacers. Such ladders may be provided at intervals of approximately 1.0 m. Sheathing shall be tied rigidly with such ladders/spacer bars so that they do not get disturbed during concreting.

The method of supporting and fixing shall be such that profile of cables is not disturbed during vibrations, by pressure of wet concrete, by workmen or by construction traffic.

6.4.3.2 Each anchorage device shall be set square to the line of action of the corresponding prestressing tendon and shall be positioned securely to prevent movement during concreting.

The anchorage devices shall be cleaned to the satisfaction of the Engineer prior to the placing of concrete. After concreting, any mortar or concrete which adheres to bearing or wedging surfaces shall be removed immediately.

6.4.4 Cutting

Cutting and trimming of wires or strands shall be done by suitable mechanical or flame cutters. When a flame cutter is used, care shall be taken to ensure that the flame does not come in contact with other stressed steel. The location of flame cutting of strand shall be kept beyond 75 mm of where the tendon will be gripped by the anchorage or jacks.

In post-tensioning the ends of prestressing steel projecting beyond the anchorages, shall be cut after the grout has set.

6.4.5 Protection of Prestressing Steel

Prestressing steel shall be continuously protected against corrosion, until grouted. The corrosion protector shall have no deleterious effect on the steel or concrete or on the bond strength of steel to concrete. Grouting shall conform to these specifications or as directed by the Engineer.

6.4.6 Sheathing

The joints of all sheathings shall be water-tight. Special attention shall be paid to the junction at the anchorage end, where the sheathing must tightly fit on the protruding trumpet end of anchorage and thereafter sealed preferably with adhesive water proof tape as per approved manufacturer.

The sheathing and all joints shall be water tight. Any temporary opening in the sheathing shall be satisfactorily plugged and all joints between sheathing and any other part of the prestressing system shall be effectively sealed to prevent entry of mortar, dust, water or other deleterious matter. Sheathing shall be neatly fitted at joints without internal projection or reduction of diameter. Sheathing shall be firmly tied so that while concreting they should not float up. Sheathing shall be aligned accurately with respect to vertical and horizontal coordinate.

Enlarged portions of the sheathing at couplings or anchorages shall be of sufficient length to provide for the extension of the tendons.

6.4.7 Grout Vents

Grout vents of at least 20 mm diameter shall be provided at both ends of the sheathing and at all valleys and crests along its length. Additional vents with plugs shall also be provided along the length of sheathing such that the spacing of consecutive vents does not exceed 20 m. Each of the grout vents shall be provided with a plug or similar device capable of withstanding a pressure of 1.0 MPa without the loss of water, air pressure or grout.

6.4.8 Anchorages

All bearing surfaces of the anchorages shall be cleaned prior to concreting and tensioning. Anchor cones, blocks and plates shall be securely positioned and maintained during concreting such that the centre line of the duct passes axially through the anchorage assembly.

The anchorages shall be recessed from the concrete surface as per drawings.

After the prestressing operations are completed and prestressing strands are cut, the surface shall be painted with two coats of epoxy of suitable formulation having a dry film thickness of 80 microns per coat and entire recess shall be filled with concrete or non-shrink/pre-packaged mortar or epoxy concrete within 7 days of grouting (in case stressing and grouting are done in two or more stages, the recess filling should be done within 7 days of last stage grouting)but in no case it shall be more than 14 days.

6.4.9 Handling and Storage

Care shall be taken to avoid mechanically damaging, work-hardening or heating prestressing tendons while handling. All prestressing tendons shall be stored clear of the ground and protected from the weather, from splashes from any other materials, and from splashes from the cutting operation of an oxy-acetylene torch, or arc-welding processes in the vicinity.

In no circumstances shall prestressing tendons after manufacture be subjected to any welding operation, or 'on-site' heat treatment or metallic coating such as galvanising. This does not preclude cutting as specified.

All wires, strands or bars stressed in one operation shall be taken, where possible, from the same parcel. Each cable shall be tagged with its number from which the coil numbers of the steel used can be identified. Cables shall not be kinked or twisted. Individual wires and strands for which extensions are to be measured shall be readily identifiable at each end of the member. No strand that has become unraveled shall be used.

6.5 SUPERVISION

All prestressing and grouting operations shall be undertaken by trained personnel only. A representative of supplier of the prestressing system shall be present during all tensioning and grouting operations and shall ensure, monitor and certify their correctness.

6.6 TENSIONING EQUIPMENT

The tensioning apparatus shall meet the following general requirements: -

- a) The means of attachment of the tendon to the jack or tensioning device shall be safe and secure.
- b) Where two or more wires or strands are stressed simultaneously, they shall be approximately of equal length between anchorage points at the datum of load and extension measurement. The degree of variation shall be small compared with the expected extension.
- c) The tensioning apparatus shall be such that a controlled total force is imposed gradually and not dangerous secondary stresses are induced in the tendons, anchorage or concrete.
- d) The force in the tendons during tensioning shall be measured by direct-reading load cells or obtained indirectly from gauges fitted in the hydraulic system to determine the pressure in the jacks. Facilities shall be provided for the measurement of the extension of the tendon and of any movement of the tendon in the gripping devices. The load-measuring device shall be calibrated to an accuracy within $\pm 2\%$ and checked at intervals to the approval of the Engineer. Elongation of the tendon shall be measured to an accuracy within 2% or 2 mm, whichever is the more accurate.
- e) The tensioning equipment shall be got calibrated before the tensioning operation and at intervals of Six months or as approved by the Engineer.

Any indication in the loss of strength in tendons during the tensioning operation shall be brought to the attention of the Engineer. Any corrective measures which may be required in procedures and/or material shall be approved by the Engineer.

When friction must be reduced, water soluble oil may be used subject to the approval of the Engineer. This oil may be flushed from the duct as soon as possible after stressing is completed by use of water pressure. These ducts shall be flushed again just prior to the grouting operations. Each time the ducts are flushed, they shall be immediately blown dry with oil-free air.

6.7 **TESTING BY CONTRACTOR**

For the purpose of accurately determining the tendon elongations while stressing, the Contractor shall bench test two samples of each size and type of strand tendon to determine the modulus of elasticity prior to stressing the initial tendon. The bench should be at least 6 metres long, with concrete anchorage blocks having a constant area end section of at least four times that of the anchorage assembly area. The tendon shall be straight and centered on the cross-sectional area of the bench. The test procedure shall consist of stressing the tendon at an anchor assembly with the dead end consisting of a load cell. The test specimen shall be tensioned to 80 percent of ultimate to 0 in 10 increments. For each increment, the gauge pressure, elongation and load cell force shall be recorded. The data shall be furnished to the Engineer. The theoretical elongations shown on the post-tensioning working drawings shall be reevaluated by the Contractor using the results of the tests and corrected as necessary. Revisions to the theoretical elongations shall be submitted to the Engineer for approval. Apparatus and methods used to perform the tests shall be proposed by the Contractor and be subject to the approval of the Engineer. After the initial testing, five more tests of each size and type of strands shall be performed. These tests shall be spaced evenly throughout the duration of the Contract.

6.8 **PRETENSIONING**

Where pretensioning methods are used, the tension shall be fully maintained by some positive means during the period between tensioning and transfer. The transfer of stress shall take place slowly to minimize shock.

a) **Straight Tendons**

In the long line method of pretensioning, sufficient locator plates shall be distributed throughout the length of the bed to ensure that the wires or strands are maintained in their proper position during concreting. Where a number of units are made in the line, they shall be free to slide in the direction of their length and thus permit transfer of the prestressing force to the concrete along the whole line.

In the individual mould system the moulds shall be sufficiently rigid to provide the reaction to the prestressing force without distortion.

b) **Deflection Tendons**

Where possible the mechanisms for holding down or holding up tendons shall ensure that the part in contact with the tendon is free to move in the line of the tendon so that frictional losses are nullified. If, however, a system is used that develops a frictional force, this force shall be determined by test and due allowance made as agreed by the Engineer.

For single tendons the deflector in contact with the tendon shall have a radius of not less than 5 times the tendon diameter for wire or 10 times the tendon diameter for a strand, and the total angle of deflection shall not exceed 15°. Where the radius is less than 5 times the diameter of the tendon and the angle of deflection exceeds 15°, the loss of strength of the tendon shall be determined by test and due allowance made.

The transfer of the prestressing force to the concrete shall be effected in conjunction with the release of hold-down and hold-up forces as approved by the Engineer.

6.9 **POST-TENSIONING**

a) **Arrangement of Tendons**

Where wires, strands or bars in a tendon are not stressed simultaneously, the use of spacers shall be in accordance with the recommendations of the system manufacturer.

b) **Anchorage**

- i. Anchorages shall be tested in accordance with the requirements of BS 4447/FIP-1993 / IS 1343.
- ii. For each anchorage system used in the Works, the characteristic value for anchorage efficiency shall be not less than 95%.
- iii. Proprietary anchorages shall be handled and used strictly in accordance with the manufacturer's instructions and recommendations.

c) **Deflected Tendons**

The deflector in contact with the tendon shall, have a radius of not less than 50 times the diameter of the tendon, and the total angle of deflection shall not exceed 15 degrees unless otherwise agreed by the Engineer.

d) **Tensioning Procedure**

Before tensioning, the Contractor shall demonstrate that all tendons are free to move in the ducts unless the geometry of the ducts makes this impracticable as agreed by the Engineer. Tensioning shall be carried out in such a manner that the stress in the tendons increases at a gradual and steady rate.

Unless otherwise described in the Contract, concrete shall not be stressed until it has reached at least the age at which 2 test cubes taken from it attain the specified transfer strength. The test cubes shall be made and tested as described in BS 1881. They shall be cured in similar conditions to the concrete to which they relate in a manner approved by the Engineer.

The Contractor shall cast sufficient cubes to demonstrate that the required strength of the concrete at transfer has been reached.

The Contractor shall ensure that those carrying out the stressing are provided with particulars of the required tendon loads, order of stressing and extensions. Allowance shall be made during stressing for the friction in the jack and in the anchorage, although the former is not necessary when using load cells.

Any allowance for draw-in of the tendon during anchoring shall be in accordance with the Engineer instructions.

Stressing shall continue until the required extension and tendon load are reached or are approved by the Engineer.

The extension shall allow for any draw-in of the tendon occurring at the non-jacking end, but measurement shall not commence until any slack in the tendon has been taken up.

Immediately after anchoring, the forces in the prestressing tendons shall not exceed 70% of their characteristic strength. During stressing the value may exceed 70% of their characteristic strength, with the approval of the Engineer, but shall not exceed 80%.

After the tendons have been anchored, the force exerted by the tensioning apparatus shall be decreased gradually and steadily so as to avoid shock to the tendon or the anchorage. Full records shall be kept of all tensioning operations, including the measured extensions,

pressure-gauge or load-cell readings, and the amount of draw-in at each anchorage. Copies of these records shall be supplied to the Engineer within 24 hours of each tensioning operation.

Unless otherwise agreed by the Engineer tendons shall not be cut less than 3 days after grouting.

6.10 PRESTRESSING TENDONS - PROTECTION AND BOND

The prestressing tendons shall be protected in their permanent positions from both mechanical damage shall be applied to all unbonded prestressing tendons within 28 days of installation of the tendon in the duct.

The tendon protection compound applied to prevent corrosion as described in the Contract and the following sub-clauses.

The exposed tendons at the anchorages and the anchorages themselves shall be sealed within a closed box and protected from both mechanical damage and corrosion. Suitable access shall be left for jacking equipment for the later removal of the strands of unbonded tendons. The means of protection shall be designed by the prestress supplier and approved by the Engineer.

A tendon protection compound tendon shall be a micro-crystalline wax (petrolatum) base material containing additives to enhance the corrosion inhibiting, wetting, and moisture displacing properties, as well as the ability to form a polar bond with the tendon steel.

The compound Manufacturer shall provide test data verifying that the following properties are met for the service life of 100 years and temperature range of 0°C to 50°C evaluation and acceptance by the Engineers:

- i. Freedom from cracking and brittleness;
- ii. Continuous self-healing film over the coated surfaces;
- iii. Chemical and physical stability;
- iv. Non reactivity with the surrounding and adjacent materials such as concrete, tendons, and ducts;
- v. Moisture displacing characteristics.

Additionally, it shall remain flexible to allow removal and replacement of the tendons. The tendon protection compound and its method of installation shall be approved by the Engineer.

Provision shall be made for expansion of the tendon protection compound during the lifetime of the structure.

Before installing the tendon protection compound it shall be demonstrated that the ducts, U-bend anchorage and anchorages are clean and free of water and chlorides.

The tendons, internal face of the steel u-bend anchorage, stressing anchorages and any other metallic components of the prestressing system shall additionally be pre-treated with a protection compound before delivery to site. The protection compound shall be applied to each strand of the tendon and shall be compatible with the tendon protection compound injected into the ducts. The protection compound shall be approved by the Engineer.

The supplier of the tendon protection compound shall submit for the Engineer's approval proposals which shall describe how the tendon protection compound can be removed and re-injected into ducts, including buried ducts, within the permanent works.

All materials used in the prestressing systems shall not give off toxic fumes at temperatures below 50°C and shall not support combustion.

6.11 DUCTS FOR BONDED TENDONS

6.11.1 Ducts

Ducts for longitudinal, transverse or vertical tendons embedded into the concrete may be of flexible, semi-rigid, or rigid galvanized, ferrous metal capable of withstanding concrete pressures without deforming or permitting the entrance of cement paste during casting of the member. They must retain their shape and be capable of transferring bond stresses. The semi-rigid duct must be rigid enough to remain straight when supported at 1200 mm maximum intervals but flexible enough to allow 3600 mm radius curves. Flexible duct shall be secured or supported at not more than 300 mm intervals.

6.11.2 Grouting of Prestressing Tendons

a) General

The Contractor shall undertake grouting trials when required by the Engineer.

b) Materials

Unless otherwise directed or agreed by the Engineer as a result of grouting trials, the grout shall consist only of Ordinary Portland

Cement and water. The water/cement ratio shall be as low as possible consistent with the necessary workability, and under no circumstances shall the W/C ratio exceed 0.45 by weight.

The grout shall not be subject to bleeding in excess of 2% after 3h or 4% maximum when measured at 25°C or such other temperature as may be approved by the Engineer, in a covered cylinder approximately 100 mm diameter with a height of grout of approximately 100 mm, and the water shall be reabsorbed by the grout during the 24h after mixing.

Admixtures may be used with the written permission of the Engineer and shall be applied strictly in accordance with the manufacturer's instructions. Admixtures shall not contain chloride ions in excess of 0.25 percent by weight.

Dry materials shall be measured by weight.

c) Ducts

Air vents shall be provided at any crests in the duct profile and elsewhere as specified.

All ducts shall be thoroughly clean before grouting. Ducts formed without metal sheathing shall be provided with effective drainage and, unless otherwise directed by the Engineer, shall be flushed with water before grouting. All surplus water shall be removed by compressed air injection. All anchorages shall be sealed or fitted with grouting connections.

d) Grouting Equipment

The mixing equipment shall produce a grout of homogeneous consistency and shall be capable of providing a continuous supply to the injection equipment.

The injection equipment shall be capable of continuous operation with little variation of pressure and shall include a system for recirculating the grout while actual grouting is not in progress. Compressed air shall not be used.

The equipment shall have a sensibly constant delivery pressure not exceeding 1 N/mm². All piping to the grout pumps shall have a minimum of bends, valves and changes in diameter. All baffles to the pump shall be fitted with 1.18 mm sieve strainers. All equipment, especially piping, shall be thoroughly washed through with clean water after every series of operations and at the end of use for each day. The interval between washing shall not exceed 3h.

The equipment shall be capable of maintaining pressure on completely grouted ducts and shall be fitted with a valve that can be locked off without loss of pressure in the duct.

e) Mixing

Water shall be added to the mixer first, then the cement. When these are thoroughly mixed, the admixture, if any, shall be added. Mixing shall continue until a uniform consistency is obtained. Mixing shall not be by hand.

f) Injecting Grout

Grouting shall be carried out as soon as is practicable after the tendons in them have been stressed and anchors trimmed and the Engineer's permission to commence has been obtained. Injection shall be continuous, and it shall be slow enough to avoid producing segregation of the grout. The method of injecting grout shall ensure complete filling of the ducts and complete surrounding of the steel. Grout shall be allowed to flow from the free end of the duct until its consistency is equivalent to that of the grout injected. The opening shall then be firmly closed. Any vents shall be closed in a similar manner one after another in the direction of the flow. After an appropriate time, further injections shall be carried out to fill any possible cavities.

The injection tubes shall then be sealed off under pressure until the grout has set. The filled ducts shall not be subjected to shock or vibration within 1 day of grouting.

Not less than 2 days after grouting, the level of grout in the injection and vent tubes shall be inspected and made good as necessary.

The Contractor shall keep full records of grouting including the date each duct was grouted, the proportion of the grout and any admixtures used, the pressure, details of any interruptions and topping up required. Copies of these records shall be supplied to the Engineer within 3 days of grouting.

Where required by the Engineer, the Contractor shall provide facilities and attendance for the radiographic testing of duct.

g) Strength of Grout

The compressive strength of 100 mm cubes made of the grout shall not be less than 27 N/mm² at 28 days or the design strength of the structure, whichever is higher. Cubes shall be cured in a moist atmosphere for the first 24h, and subsequently in water.

6.12 DUCTS FOR UNBONDED TENDONS

Unless shown otherwise on the Drawings, ducts and injection tubes in the superstructure and substructure shall be formed from high density polyethylene (HDPE) which shall incorporate a stabilizing agent to prevent Ultra Violet Light (UVL) degradation.

The minimum wall thickness of the ducts shall be such that the ducts are capable of resisting the pressures developed during installation of the protection compound. The ducts shall be smooth bore.

Ducts with external diameters greater than 70 mm shall be transported and stored in straight lengths. The distance between supports shall be limited to 3m and the height of storage to 1.5 m. Alternatively, ducts may be transported and stored in coils provided that they are fixed to the tolerances required by the Designer.

Damaged ducts shall not be used in the Works.

Boring/drilling of any holes in the ducts shall be permitted once the tendons are installed.

U-bend anchorages shall be formed from smooth-bore unwelded steel tubes and shall comply with the requirements of EN 10025..

Joints between ducts, ducts and anchorages and ducts and U-bend anchorages shall be formed by a coupling device using thermo-fusion techniques which shall provide a watertight seal to the ducts and shall be capable of resisting the pressure developed during installation of the tendon protection compound. The inner surfaces of the joints shall form a smooth transition between ducts and U-bend anchorages to allow satisfactory installation of the tendons. All coupling devices shall be approved by the Engineer.

Injection tubes shall be provided at the U-bend anchorages, the stressing anchorages and at any other positions on the length of the ducts which are required to achieve satisfactory installation of the tendon protection compound. The injection tubes at the U-bend anchorages shall also be used as drainage points for the U-bend. The connection between the ducts and the injection tubes shall be watertight and capable of resisting the pressure developed during installation of the tendon protection compound.

All injection tubes shall be sealed after use to prevent the ingress of water to the satisfaction of the Engineer.

After completion of all duct joints and before completion of the insitu joints between precast segments and before installation of the tendons, all ducts shall be air tested to an equivalent 100 mm water gauge unless otherwise directed by the Engineer. The test shall be performed in accordance with BS 8301 Section 5.

Any ducts which do not contain tendons shall remain empty and shall be sealed at each end to prevent the ingress of water.

6.13 PRESTRESSING TENDONS - TRIAL CONSTRUCTION-UNBONDED TENDONS

Before commencing construction of the precast segments, a trial shall be carried out which shall demonstrate the satisfactory installation, removal and replacement of a prestressing strand together with the proposed techniques for duct jointing, duct testing and installation of the tendon protection compound.

- i. The tendons shall be stressed in accordance with this Specification.
- ii. The ducts shall be filled with a tendon protection compound in accordance with the specification as detailed in relevant sub-sections and the tendon extension and anchorage shall be protected as if they were to be included in the permanent works.
- iii. The trial shall demonstrate that any one strand may be destressed, removed, inspected, replaced and re-stressed and that no voids are created within the tendon protection compound, all to the satisfaction of the Engineer.
- iv. The trial shall also demonstrate that all of the strands in a duct may be removed and that the tendon protection compound can be removed from the ducts and U-bend anchorage to the satisfaction of the Engineer.

- v. The trial shall be undertaken using the prestressing system to be used in the permanent works and shall be approved by the Engineer.

6.14 PRESTRESSING TENDONS - TEMPORARY TENDONS

Temporary tendons may be re-used as temporary tendons elsewhere provided special precautions are incorporated at the anchorages to ensure tendons are not damaged. These precautions shall be approved by the Engineer.

The tendons shall be enclosed within a duct throughout their length.

The tendons shall be pre-treated in accordance with the specifications as detailed in relevant subsections and the protection compound shall be applied to the outer surfaces of the tendon after each use.

The maximum jacking force for the re-usable temporary tendons shall not exceed 70 percent of their guaranteed minimum breaking load.

After removal of the tendons the ducts shall be sealed at each end to prevent the ingress of water.

6.15 PREPARATION FOR CASTING

- a) The Contractor shall submit for approval, in accordance with the provisions of the Employer's Requirements, working drawings of the prestressing system proposed for use. For initial review, 3 sets of such drawings shall be submitted.
- b) After review, between 6 and 12 sets, as requested by the Engineer, shall be submitted for final approval and for use during construction.
- c) The working drawings of the prestressing system shall show complete details and be accompanied by substantiating calculations of the method and materials the Contractor proposes to use in the prestressing operations, including any additions or rearrangement of reinforcing steel from that shown on the Drawings. Such details shall outline the method and sequence of stressing and shall include complete specifications and details of the prestressing steel and anchoring devices, working stresses, anchoring stresses, type of ducts, and all other data pertaining to the prestressing operation, including the proposed arrangement of the prestressing steel in the members.
- d) Working drawings shall be A1 size and each drawing and calculation sheet shall include the job site, name of the structure as shown on the Contract Drawings and Contract name.
- e) Working drawings shall be submitted sufficiently in advance of the start of the affected work to allow time for review by the Engineer and correction by the Contractor of the drawings without delaying the work. Such time shall be proportional to the complexity of the work but in no case shall such time be less than eight (8) weeks.
- f) At the completion of each structure, one set of reproducible mylars of the corrected original tracing of all working drawings for said structure shall be furnished to the Engineer. Drawings which are common to more than one structure shall be provided for each structure. An index prepared specifically for the drawings for each structure containing sheet numbers and titles shall be included.
- g) Reinforcing steel shall be fabricated and placed in accordance with the Drawings and as required herein. No reinforcing steel shall be cut and removed to permit proper

alignment of stressing ducts. Any bar that cannot be fabricated to clear the conduits shall be replaced by additional bars with adequate lap lengths and shall be submitted to the Engineer for approval. In the plane of the steel parallel to the nearest surface of concrete, bars shall not vary from plan placement by more than 12 mm or one-tenth (1/10) of the spacing between bars, whichever is less.

- h) All prestressing steel shall be protected against physical damage and rust or other results of corrosion at all times from manufacture to grouting or encasing in concrete. Prestressing steel that has sustained physical damage at any time shall be rejected. The development of visible rust or other results of corrosion shall be cause for rejection, when ordered by the Engineer.
- i) Prestressing steel shall be packaged in containers or shipping forms for the protection of the steel against physical damage and corrosion during shipping and storage. A corrosion inhibitor which prevents rust or other results of corrosion shall be placed in the package or form, or shall be incorporated in a corrosion inhibitor carrier type packaging material, or when permitted by the Engineer, may be applied directly to the steel. The corrosion inhibitor shall have no deleterious effect on the steel or concrete or bond strength of steel to concrete. packaging or forms damaged from any cause shall be immediately replaced or restored to original condition.
- j) The shipping package or form shall be clearly marked with a statement that the package contains high-strength prestressing steel, and the care to be used in handling; and the type, kind and amount of corrosion inhibitor used, including the date when placed, safety orders and instructions for use.
- k) Prestressing steel for post-tensioning which is installed in members prior to placing and curing of the concrete, shall be continuously protected against rust or other corrosion, until grouted, by means of a corrosion inhibitor placed in the ducts or applied to the steel in the duct. The corrosion inhibitor shall conform to the requirements specified herein.
- l) When steam curing is used, prestressing steel for post-tensioning shall not be installed until the steam curing is completed.
- m) All water used for flushing ducts shall contain 1% of either quick lime (calcium oxide) or slaked lime (calcium hydroxide) in the amount of 13g. per litre. All compressed air used to blow out ducts shall be oil free.
- n) When acceptable prestressing steel for post-tensioning is installed in the ducts after completion of concrete curing, and if stressing and grouting are completed within 10 calendar days after the installation of the prestressing steel, rust which may form during said 10 days will not be cause for rejection of the steel. Prestressing steel installed, tensioned and grouted in this manner, all within 10 calendar days, will not require the use of a corrosion inhibitor in the duct following installation of the prestressing steel. Prestressing steel installed as above but not grouted within 10 calendar days shall be subject to all the requirements in this section pertaining to corrosion protection and rejection because of rust.
- o) Any time acceptable prestressing steel for pretensioning is placed in the stressing bed and is exposed to the elements for more than 36 hours prior to encasement in concrete, adequate measures shall be taken by the Contractor, as approved by the Engineer, to protect said steel from contamination or corrosion.

- p) All ducts shall be located within 5 mm of the locations given on approved fabrication plans. Method and spacing of supports for ducts shall be shown on the working drawings. After installation in the forms, the end of the ducts shall at all times be sealed to prevent entry of water and debris. Following each pour of concrete, the Contractor will be required to demonstrate that all empty ducts are free of water and are unobstructed and undamaged. Immediately prior to installation of the prestressing steel, the Contractor shall again demonstrate to the satisfaction of the Engineer that all ducts are unobstructed and that they are free of water and debris.

Where tendons are described in the Contract as debonded from the concrete they shall be covered with sleeves approved by the Engineer. The ends of the sleeves shall be taped to the tendon to prevent the ingress of grout.

- q) Concrete shall not be deposited into forms until the entire set-up of the forms, reinforcement, ducts, and anchorage has been thoroughly inspected and checked. The placing of concrete will not be permitted until the Engineer is satisfied that the rate of producing and placing concrete will be sufficient to complete the proposed pour and finishing operations within the scheduled time, that experienced concrete finishers are available where required for finish work and all necessary finishing tools and equipment are on hand at the site of the work and are in satisfactory condition for use.
- r) Conveying equipment shall be of a size and design that will permit the placing of concrete within the time limits specified. Conveying equipment shall be cleaned at the end of each operation or work day and just prior to reuse shall again be checked and cleaned of hardened concrete and foreign materials. Belt conveyors shall be horizontal or at a slope which will not cause excessive segregation or loss of ingredients. Concrete shall be protected against undue drying or rise in temperature. An approved arrangement shall be used at the discharge end to prevent aggregate segregation. Mortar shall not be allowed to adhere to the return length of the belt. Concrete shall be discharged into a hopper or through a baffle.
- s) The concrete shall be first placed in the web forms followed by placement at the bottom slab and then in the top form. Any alternate sequence shall be submitted to the Engineer for approval.
- t) All concrete shall be consolidated by means of approved vibrators together with any other equipment necessary to perform the work as specified. Internal vibrators shall have a minimum frequency of 8,000 vibrations per minute and sufficient amplitude to consolidate the concrete effectively. At least two (2) stand-by vibrators in working condition shall be provided for emergency use in case of malfunction. The use of external vibrators for consolidating concrete will be permitted and may be required when the concrete is inaccessible for adequate consolidation. When external vibration is used, the forms shall be constructed sufficiently rigid to resist displacement or damage. Vibrating of concrete shall be done with care and in such a manner as to avoid displacement of reinforcing, conduits, and other items to be fixed in place.

6.16 SAFETY PRECAUTIONS DURING TENSIONING

Care shall be taken during tensioning to ensure the safety of all persons in the vicinity. Jacks shall be secured in such a manner that they will be held in position, should they lose their grip on the tendons. No person shall be allowed to stand behind the jacks or close to the line of the tendons while tensioning is in progress.

The operations of the jacks and the measurement of the elongation associated operations shall be carried out in such a manner and such a position that the safety of all concerned is ensured.

A safety barrier shall be provided at both ends to prevent any tendon, which might become loose from recoiling unchecked.

During actual tensioning operation, warning sign shall be displayed at both ends of the tendon. After prestressing, concrete shall neither be drilled nor any portion cut nor chipped away nor disturbed, without express approval of the Engineer.

No welding shall be permitted on or near tendons nor shall any heat be applied to tendons. Any tendon which has been affected by welding, weld spatter or heat shall be rejected.

6.17 TOLERANCES

Permissible tolerances for positional deviation of Prestressing tendons in cast-in-situ construction shall be limited to the following

- a) Variation from the specified horizontal profile : 5 mm
- b) Variation from the specified vertical profile : 5 mm
- c) Variation from the specified position in member : 5 mm

Permissible tolerances for positional deviation of prestressing tendons in precast segmental construction shall be limited as defined in Clause 10.2.8

6.18 Transportation and Storage of Unit:

Precast members shall be transported in an upright position. Points of support and the direction of reactions with respect to the girder shall approximately be the same during transportation, and storage as when the girder is placed in final position.

When members are to be stacked, they shall be firmly supported at such bearing positions as will ensure that the stresses induced in them are always less than the permissible design stresses. Further, inclined side supports shall be provided at the ends and along the length of a precast girder to prevent lateral movements or instability.

Care shall be taken during storage, hoisting and handling of the precast units to prevent their cracking or being damaged. Units damaged by improper storing or handling shall be replaced by the Contractor at his expense

6.19 TESTS AND STANDARDS OF ACCEPTANCE

The materials shall be tested in accordance with these Specifications and shall meet the prescribed criteria.

The work shall conform to these Specifications and shall meet the prescribed standards of acceptance.

6.20 MEASUREMENT:

The measurement for prestressing steel wires shall be made on the actual length of wires from end to end of cut-face of anchorages for post tensioned concrete as per the profile drawing and shall not include the extra length of wires at both ends. For pretensioned concrete the measurements of high tensile steel wires shall be measured from end to end of concrete faces and shall not include extra length of wires at both ends. The rates for high tensile steel work shall include formation of cables in position including cost of spacers, transporting, anchorages, sheathing, grouting, stressing and all other relevant work including staging etc.

SECTION – S.07

STRUCTURAL STEEL WORKS

7.1 STRUCTURAL STEELWORK SPECIFICATIONS- GENERAL

7.1.1 Scope of Specification

This specification covers the scope of work of structural steel works, submittals by the Contractor, applicable codes of practice for structural steel work and the specifications for the materials to be used, including steel, bolts & nuts, washers etc and the storage thereof. These specifications shall be read in conjunction with the latest edition of CPWD specifications, latest revision of MORTH Specifications and other relevant reference specifications described in the section 1.1 of these specifications.

7.1.2 Scope of Work

The scope of work for the contractor in respect of structural steel work shall cover, but shall not be limited to the following:

- a) Preparation of complete detailed fabrication drawings and erection marking drawing based on the design drawings, required for all the permanent and temporary structures
- b) Submittal of revised design, with calculations and detailed fabrication drawings, in case any substitution of the designed sections is required.
- c) Submittal of design calculations for joints and connections to be developed by the contractor along with detailed fabrication drawings.
- d) Supply of all raw steel materials for fabrication, taking into account wastage margin, including storage and upkeep of the materials.
- e) Furnishing of all materials, labour, tools and plant and all consumable required for fabrication and supply of all necessary bolts, nuts, washers, tie rods and welding electrodes for field connections, with necessary wastage margins.
- f) Fabrication of the steel works in accordance with the approved fabrication drawings, including all shop assembling, matching and marking. Design, manufacture / fabrication and provision of all jigs, fixings, manipulators etc. required for the fabrication.
- g) Provision of shop painting and requisite site painting to all fabricated steelwork, as per requirements of the related specification of the painting.
- h) Suitability marking, bundling and packing for transport of all fabricated materials.
- i) Preparing and furnishing detailed bill of materials, drawing Office dispatch lists, Bolts Lists and any other lists of bought out items required in connection with the fabrication and erection of the structural steelwork.
- j) Loading, Transportation and unloading of all fabricated structural steel materials from site storage yard to erection site, handling, assembling, bolting, welding and satisfactory

installation of all fabricated structural steel materials in proper location, according to approved erection drawings and/or as directed by the Engineer.

- k) The contractor shall submit, for examination by the Engineer, detailed particulars of his proposed methods of erection of the superstructure steelwork, together with complete calculations relating to strength and deflection. If the erection scheme necessitates the attachment of strength steelwork to the permanent steel work, the contractor shall submit, for approval of the Engineer, the methods he proposes for making good the permanent steelwork after removing the temporary work. The contractor shall also submit the design and fabrication drawings of all temporary support, staging, braces etc. required for safe erection, for approval of the Engineer. All the enabling works, erection schemes, design and drawings of temporary structures shall be approved by an independent agency appointed by the contractor.
- l) The contractor shall provide all construction and transport equipment, tools, tackle, and consumables, materials, labour and supervision required for the erection of the structural steelwork.
- m) Receiving, unloading, checking and moving to storage yard, storage, guarding and upkeep of fabricated steelwork and other consumable materials and fasteners at site.
- n) Transportation of all fabricated structural steel materials from site storage yard, handling, assembling, bolting, welding and satisfactory installation of all fabricated structural steel materials in proper location, according to approved erection drawings and/or as directed by the Engineer.
- o) Setting out, aligning, plumbing, levelling, bolting, welding and securely fixing the fabricated steel structures in accordance with the erection scheme, or as directed by the Engineer.
- p) Provision of requisite site painting to all fabricated steelwork, as per requirements of related specifications of the painting.
- q) Providing protective treatment to the erected steel structures, as per Specification.
- r) All major modifications of the fabricated steel structures, as directed by the Engineer, including but not limited to the following:
 - i) Removal of bends, kinks, twists etc. for parts damaged during transport and handling.
 - ii) Cutting, chipping, filling, grinding etc. if required or preparation and finishing of site connections.
 - iii) Reaming of holes for use of higher size bolt if required.
 - iv) Re-fabrication of parts damaged beyond repair during transport and handling or re-fabrication of parts which are incorrectly fabricated.
 - v) Fabrication of parts omitted during fabrications by error, or subsequently found necessary.
 - vi) Drilling of holes which are either not drilled at all or are drilled in incorrect location during fabrication.
 - vii) Carry out tests in accordance with the related Specification.
- s) Preparing and furnishing detailed bill of materials of fabricated parts received from concerned

organisation or its authorized fabricator.

- t) The Contractor shall observe all safety requirements for erection of structural steelwork as covered in IS: 7205.

7.1.3 Submittals

- a) On commencement of the Project, the Contractor shall submit the following:
 - i) Prior to the technical submittals, the contractor shall submit the proposed overall schedule for documentation such as calculations, shop/ working drawings, plan/ procedures and records. Submission of samples, process of fabrication / delivery / erection for the approval of the Engineer.
 - ii) Complete fabrication drawings, materials lists, cutting lists, bolt lists, welding schedules and QC schedules, based on the design drawing furnished to him and in accordance with the approved schedule. It is highlighted that structural steel members dimensions indicated in tender drawings are tentative only, and may be modified during final design stage.
 - iii) Results of any tests, as and when conducted and as required by the Engineer.
 - iv) Manufacturers mill test reports in respect of steel materials, bolts, nuts and electrodes, as may be applicable.
 - v) A detailed list of all constructional Plant & Equipment, such as cranes, derricks, winches, welding sets, erection tools etc. their make, model calibration and fitness certificates as required present condition and location, available to the contractor and the ones he will employ on the job to maintain the progress of work in accordance with the contract.
 - vi) The total number of experienced personnel (with trade certificates) of each category, like fitters, welders, riggers etc., which he intends to deploy on the project.
- b) The contractor shall submit a detailed erection programme for completion of the work in time and in accordance with contract. This will show, in a performa approved by the Engineer, the target programme, with details of erection proposed to be carried out in each week, details of major equipment required and an assessment of required strength of various categories of workers.
- c) The contractor shall submit complete design calculations for any alternative sections proposed by him, for approval of the Engineer. Use of any alternative section shall be subject to approval of the Engineer. However, no escalation in unit rates of work shall be allowed for such cases.

7.1.4 Furnishing of Information

- a) Design drawings shall be furnished to the contractor and all such drawings shall form part of these Specifications.
- b) The Engineer reserves the right to make changes in the design drawings even after release for preparation of shop drawings to reflect addition, omission & modifications in data/details and requirements. Contractor shall consider such changes as part of these Specifications and the contract, and no extra claims shall be entertained on this account.
- c) Design drawings, approved by the Engineer, will show as appropriate the salient dimensions, design loads, sizes of members, location of openings at various levels and other necessary information required for the preparation of fabrication drawings, designs and erection details.
- d) It shall be clearly understood that the drawings of the Engineer are design drawings. The typical details of connection, cuts, notches, bends, etc. were shown in the design drawings are only for general guidance of the contractor. The contractor shall design and develop all such details based on the design forces and functional requirements.
- e) In case of variations in design drawings and specifications, the decision of the Engineer shall be final. Should the contractor, find any discrepancy in the information furnished by the Engineer, same shall be immediately brought to the notice of Engineer for resolution. The contractor shall obtain clarifications on discrepancies from Engineer before proceeding with the work.
- f) No detailed shop drawings, erection plants, enabling structures, lifting plants, temporary structures etc will be accepted for examination by the Engineer unless the same, have first been completely checked by the contractor's qualified structural engineer (independent agency to be appointed by contractor) and are accompanied by an erection plan showing the location of all pieces detailed. The contractor shall check and ensure that detailing of connections is carefully planned to obtain ease in erection of structures, including field-welded connections and/or bolting.
- g) No fabrication work shall be started by the contractor without having obtained approval of Engineer on the relevant drawings. Approval by the Engineer of any of the drawings shall not relieve the contractor of his responsibility to provide correct design of connections, workmanship, fit of parts, details, materials and errors or omissions of all work shown thereon. The approval of Engineer shall constitute approval of the size of members, dimensions and general arrangement, but shall not constitute approval of the connections between members and other details.

- h) Drawings, for approval, shall be submitted by the contractor in an orderly manner commensurate with erection sequence and approved construction programme.
- i) The contractor shall furnish ten prints of all approved final drawings for field use and record purpose.
- j) The drawings prepared by the Contractor, and all subsequent revisions thereof shall be at the cost of the Contractor, and no separate payments shall be made for the same. Revisions shall incorporate all modifications, field changes, substitutions etc. effected. The rates/prices quoted for fabrication work shall be deemed to include the cost of such drawing work.
- k) The Contractor shall give due consideration to the need of trial assemblage at shop, weight and size limitation of elements for transportation from shop to construction site, temperature variation of 25 degree centigrade between the fabrication shop and site, site measurements of the as-built dimensions and avoidance of site welding except for fixtures. All the drawings shall be prepared in metric units. The drawings should preferably be of A-1 standard size, and the details shown therein shall be clear and legible. These drawings shall include but shall not be limited to the following:
 - i) Assembly drawings, giving exact sizes of the sections to be used and identification marks of the various sections.
 - ii) Dimensional drawings of base plans, anchorages details in foundation, foundation bolts location etc.
 - iii) Complete Bills of Materials and detailed drawings of all sections including their billing weights.
 - iv) Shop details of temporary structures together with detailed calculations duly approved by an independent agency.
 - v) Detailed shop drawings for proper co-ordination with the concrete components to which the steel members shall be connected, as required.
 - vi) Any other drawings or calculations that may be required for proper completion of the works and clarification of the works or substituted parts thereof.
 - vii) All 'as-built' drawings.

7.1.5 Applicable Codes of Practice

The following specifications, standards and codes are included as part of this Specification. All Standards, specifications, codes of practice current on the date of signing of agreement and referred to herein shall be applicable

1.	IS: 800	Code of Practice for General Construction in Steel.
2.	IS: 808	Dimensions for Hot Rolled Steel Beam, Column, Channel and Angle Sections.
3.	IS: 814	Covered Electrodes for Manual Metal Arc Welding of Carbon & Carbon Manganese Steel.

4. IS: 816 Code of Practice for Use of Metal Arc Welding for General Construction in Mild Steel.
5. IS: 817 Code of Practice for Training and Testing of Metal Arc Welders.
6. IS: 919 ISO System of Limits & Fits (Part 1 & Part 2)
7. IS: 1148 Hot Rolled Rivet Bars (upto 40mm) for Structural Purposes.
8. IS:1182 Recommended Practice for Radio Graphic Examination of Fusion Welded Butt Joints in Steel Plates.
9. IS: 1363 Hexagon Head Bolts, Screws and Nuts of Product grade C. (Part 1 to Part 3)
10. IS: 1364 Hexagon Head Bolts, Screws and Nuts of Product Grades A &B (Part 1 to 5)
11. IS: 1367 Technical Supply Conditions for Threaded Steel Fasteners.
12. IS: 1821 Dimensions for Clearance Holes for Bolts and Screws.
13. IS: 4206 Dimensions for Nominal Lengths and Thread Lengths for Bolts, Screws and Studs.
14. IS: 1852 Rolling& Cutting Tolerances for Hot-Rolled Steel Product.
15. IS: 15911 Structural Steel (Ordinary Quality).
16. IS: 2016 Specification of Plain Washers.
17. IS: 2062 Hot Rolled Medium and high Tensile Structural Steel.
18. IS: 2595 Code of Practice for Radio Graphic Testing.
19. IS: 3600 Methods of Testing Fusion Welding Joints. (Part 1 to Part 9)
20. IS: 3613 Acceptance Tests for Wire Flux Combinations for Submerged Arc Welding.
21. IS: 3658 (Code of Practice for Liquid Penetrant Flow, Detection.
22. IS: 3757 High Strength Structural Bolts.
23. IS:4000 High Strength Bolts In Steel Structures-Code of Practice
24. IS: 4353 Recommendations for Submerged Arc Welding of Mild Steel and Low Alloy Steel.
25. IS: 4943 Assessment of Butt and Fillet Fusion Welds in Steel Sheet, Plate and Pipe.
26. IS: 5334 Code of Practice for Magnetic Particle Flow Detection of Welds
27. IS: 5369 General Requirements for Plain Washers and Lock Washers.
28. IS: 5372 Taper Washers for Channels
29. IS: 5374 Taper Washers for I Beams.
30. IS: 6623 Specification for High Strength Structural nuts
31. IS:6649 Specifications for hardening and tempering washers for high strength structural nuts
32. IS: 6755 Double Coil Helical Spring Washers.
33. IS: 7215 Tolerances for Fabrication of Steel Structure.
34. IS: 7318 (Part I) Approval Tests for Welders When Welding Procedure Approval is

not required -fusion Welding of Steel.

35.	IS:8500	Structural steel -Micro alloyed (Medium and High Strength Qualities) .
36.	IS:8910	General requirements of Supply of Weldable Structural Steel.
37.	IS: 9595	Recommendations for Metal Arc Welding of Carbon & Carbon-Magnese Steels.

7.1.6 Products

7.1.6.1 Materials

- a) All materials to be supplied by the Contractor shall conform to relevant Indian Standards or equivalent, as approved by the Engineer.
- b) Steel materials required for the work shall be free from imperfections, mill scales, slag intrusions, laminations, pittings, rusts etc. that may impair strength, durability and appearance. All materials shall be of tested quality only. If desired by the Engineer test Certificates in respect of each consignment shall be submitted in triplicate. Whenever the materials are permitted for procurement from identified stocks, a random sample shall be tested at an approved laboratory, as directed by the Engineer.

7.1.6.2 Structural Steel

All structural steel shall be of tested quality and shall conform to one of the following standards:

- i. IS: 2062 Grade –BR (with optional impact test) Structural steel (Fusion welding quality)
- ii. IS: 961 High Tensile Structural Steel (Ordinary)
- iii. IS: 1161 Steel Tubes for Structural purposes specifications
- iv. IS: 4923 Hollow steel section for structural use specification

The Contractor shall supply to the Engineer copies of the manufacturer certificate that the steel brought to the site for incorporation in the works is of a quality fully complying with the specification. If required by the Engineer, the Contractor shall arrange for testing of the steel samples as per IS: 1608/ IS: 1599.

7.1.6.3 Bolts and Nuts

For splicing of any structural member wherever required HSFG bolts and nuts of property grade-8.8 and above conforming to IS:3757 and IS:6623 (2004) respectively shall be used. Unless specified otherwise, the bolts shall be hexagonal.

All anchor bolts shall be of property class of 8.8 and above and nuts shall conform to IS:1363 (1992), IS:1364 (1992) and IS:1367, as applicable, and unless specified otherwise, shall be hexagonal. All nuts shall conform to property class compatible with the property class of the bolt used. Bolts of grade 8.8 shall be hot dip galvanised & Bolts of Grade 10.9 shall be coated with zinc flakes as per Fabrication code-B1.

7.1.6.4 Washers

For HSFG bolts, washer shall be conforming to IS:6649 (1985). Plain washers shall be conforming to IS:5369, unless otherwise specified. One washer shall be supplied with each bolt and, in case of special types of bolts, more than one washer as needed for the purpose shall be supplied. An additional double coil helical spring washer, conforming to IS:6755, shall be provided for bolts carrying dynamic or fluctuating loads and those in direct tension. Tapered washers, conforming to IS:5372 and IS:5374, shall be used for channels and beams respectively wherever required.

7.1.7 Storage of Materials

7.1.7.1 General

All materials shall be so stored as to prevent deterioration, and to ensure the preservation of their quality and fitness for the work. If required by the Engineer, the materials shall be stored under cover and suitably painted for the protection against weather. Any material, which has deteriorated or has been damaged shall be removed from site and replaced by new members, as directed by the Engineer at no extra cost and time.

- a) The steel to be used in fabrication shall be stored in separate stack clear of the ground section wise and lengthwise.
- b) The storage area shall be kept clean and properly drained. Structural steel shall be so stored and handled in such a manner that members are not subjected to excessive stresses and damage. Girders and beams shall be placed in upright position. Long members shall be supported on closely spaced skids to avoid unacceptable deflection.

7.1.7.2 Yard

- a) The Contractor shall be required to establish a suitable yard, in an approved location at site for storing the fabricated steel structures and other materials which will be delivered to site. The yard shall have proper facilities such as drainage and lighting including access for cranes, trailers and other heavy equipments.
- b) The Contractor shall have been deemed to have visited the site, prior to submission of his tender, to acquaint himself with the availability of land and the development necessary by way of filling, drainage, access roads, fences, sheds etc., all of which shall be carried out by the Contractor at his own cost and as directed by the Engineer

7.1.7.3 Covered Store

All field connection materials, paints etc. shall be stored on racks and platforms, off the ground in a properly covered building by the contractor.

7.2 STRUCTURAL STEELWORK SPECIFICATION -WELDED STRUCTURE

7.2.1 General

Scope of Specification

This Specification covers the supply, fabrication and delivery to Site of welded structural Steelwork, including the supply of all consumables, electrodes and other materials required for fabrication and field connections of all structural steelwork covered under the scope of the Specification.

7.2.2 Products

Ref. Specification 7.1.6 for Structural Steel

7.2.3 Execution

7.2.3.1 Workmanship

7.2.3.1.1 General

All workmanship shall be in accordance with the best practices in modern structural shops. Greatest accuracy shall be maintained in the manufacture of every part of the work and similar parts shall be strictly interchangeable. The contractor shall not proceed with any welding until the Engineer has approved his welding plan, which shall include.

- i. All information's on welding procedures, equipment, additives and preheating during welding operation.
- ii. Details of non-destructive testing methods
- iii. Precautions with regard to welding shrinkage
- iv. Possible treatment of completed welds by grinding
- v. Procedure and programme of welding sequence

7.2.3.1.2 Templates

Templates used throughout the work shall be of steel In cases where actual materials have been used as templates for drilling similar pieces, the Engineer shall decide whether such materials are fit to be used as parts of the finished structure.

7.2.3.1.3 Straightening

All materials shall be straight and free from twists, and if necessary, before being worked, shall be straightened and/or flattened by pressure, unless required to be of curvilinear form.

7.2.3.1.4 Clearance

The clearance between fraying surface of bolted connections shall not be greater than 1mm at each end. If separation is between 1 to 3mm, the surface should be tapered to eliminate the separation. Over 3mm separation shall be filled with filler plates.

7.2.3.1.5 Shearing, Cutting and Planning

Cutting shall be done automatically. Cutting by shearing machine may be used for plates not exceeding 10 mm in thickness provided that the plate edges be fully enclosed in a weld. Oxygen cutting may be used provided a smooth and regular surface free from cracks and notches is secured.

- i. Chipping of angle flanges and edges of plates, wherever necessary, shall be done without damaging the parent metal. Chipped edges shall be ground to a neat finish and sharp corners and hammered rough faces shall be rounded off.
- ii. The edges and ends of all cut/sheared plates members, flange plates, web plates of plate girders, and all cover plates, and the ends of all angles, tees, channels and other sections forming the flanges of plate girders, shall be planed/ground. Edge preparation for welding may be done by machine-controlled flame cutting, with edges free from burrs should be clean and straight.

The butting surfaces at all joints of girders shall be planed so as to butt in close contact throughout the finished joint.

- iii. All flame cut surfaces shall be ground to remove the burned/ hardened portion of the material for flame cut surfaces.

7.2.3.1.6 Assembly

- a) All parts assembled for welding shall be in as close contact as practicable over the whole surface.
- b) The component parts shall be so assembled that they are neither twisted nor otherwise damaged. Specified cambers, if any, shall be provided.
- c) All parts of bolted and welded members shall be held firmly in position by means of jigs or clamps while bolting or welding. No drifting of holes shall be permitted, except to draw the parts together and no drift used shall be larger than the nominal diameter of the bolt. Drifting done during assembling shall not distort the metal or enlarge the holes.
- d) Trial assemblies shall be carried out at the fabrication stage to ensure accuracy of workmanship. These checks shall be witnessed by the Engineer and such trial assemblies shall be at the cost of the Contractor.

7.2.3.2 Welding**7.2.3.2.1 General**

The welding and the welded work shall conform to welded bridge code, IS:816 and IS:9595, unless otherwise specified. As much work as possible shall be welded in shops and the layout and sequence of operations shall be so arranged as to eliminate distortion and shrinkage stresses.

7.2.3.2.2 Electrodes

All electrodes shall be kept under dry conditions. Any electrode damaged by moisture shall not be used unless it is guaranteed by the manufacturer that, when it is properly dried, there will be no detrimental effect. Any electrode, which has part of its flux coating broken away or is otherwise damaged, shall be rejected. Any electrode older than six (6) months from the date of manufacture shall not be used. Batch certificates for electrodes shall be submitted by the Contractor.

Manual Metal Arc Welding electrodes shall be adopted as per following details :

S No.	Classification	Remarks
1	E-6013	For Structural Steel having thickness upto 15mm
2	E-7018	For Structural Steel having thickness more than 15mm

For MIG and SAW welding the suitable product/brand of above-mentioned manufacturer shall be used.

7.2.3.2.3 Preparation of Joints

The edges shall be prepared, with an automatically controlled flame cutting torch, correctly to the shape, size and dimensions of the groove, prescribed in the design and fabrication drawings. In case of U-groove joints, the edges shall be prepared with an automatic flame cutting torch in two phases, following a bevel out with a gouging pass, or by machining.

The welding surfaces shall be smooth, uniform and free from fins, tears, notches or any other defects, which may adversely affect welding, and shall be free of loose scale, slag, rust, grease, paint, moisture or any other foreign material.

7.2.3.2.4 Welding Procedure

- a) All welding procedures shall be submitted to the Engineer for approval, well before starting fabrication.
- b) The welding procedures shall be arranged by the Contractor to suit the details of the joints, as indicated in the drawings and the position at which welding has to be carried out. Welding procedure shall cover the following:
 - 1 Type and size of electrodes
 - 2 Current and (for automatic welding) arc voltage
 - 3 Length of run per electrode; or (for automatic welding) speed of travel
 - 4 Number and arrangement of runs in multirun welds
 - 5 Position of welding

- 6 Preparation and set-up of parts
 - 7 Welding sequence
 - 8 Pre or post heating
 - 9 Any other relevant information.
- c) The welding procedures shall be so arranged that distortion and shrinkage stresses are reduced to the minimum, and that the welds meet the requirement of quality specified.
- d) Any weld found defective shall be removed, by using either chipping hammer or gouging torch, in such a manner that parent material is not injured in any way.

7.2.3.2.5 Fusion Faces and Surrounding Surfaces

- a) Fusion faces and the surrounding surfaces within 50mm of the welds shall be free from all mill scale and free from oil, paint or any substance which might affect the quality of the welds or impede the quality/progress of welding. These shall be free from irregularities, which would interfere with the deposition of the specified size of weld or be the cause of defects.
- b) All mill scale within 50mm of welds shall be removed prior to welding, either by pickling followed by thorough power wire brushing, or by other approved methods.
- c) If preparation or cutting of the fusion faces is necessary, the same shall be carried out by shearing, chipping, gas cutting or flame gouging.
- d) Where hand gas cutting or hand gouging is employed, the blowpipe or gouging blowpipe shall be properly guided.

7.2.3.2.6 Assembly for Welding

Parts to be welded shall be properly assembled and held firmly in position by means of jigs and clamps prior to and during welding.

7.2.3.2.7 Welded Girders and Other Plate Construction

Automatic submerged arc welding shall be employed for fabrication of welded girders and other plate construction, wherever specified. Metal inert gas welding (CO₂) may be done for short length where access to the location of the weld does not permit submerged arc welding subject to approval of Engineer.

7.2.3.2.8 Accuracy of Fit-Up

Parts to be fillet welded shall be brought into as close contact as practicable, and the gap due to faulty workmanship or incorrect fit-up shall not exceed 1.5mm. If greater separation occurs at any position, the size of fillet weld shall be increased at such positions by the amount of the gap.

7.2.3.2.9 Jigs and Manipulators

Jigs and manipulators shall be used, where practicable, and shall be designed to facilitate welding and to ensure that all welds are easily accessible to the operators.

7.2.3.2.10 Ends of Butt-Welded Joints

The ends of butt joints shall be welded so as to provide full throat thickness. This may be done by the use of extension pieces, cross-runs or other approved means.

7.2.3.2.11 Weld Face and Reinforcement of Butt welds

The weld face shall, at all places, be deposited projecting the surface of the parent metal. Where a flush surface is required, the surplus metal shall be dressed off.

7.2.3.2.12 Testing of Butt Welds

Butt-welded joints are to be 25% radiographically tested by the Contractor at his own cost. If such tests indicate the joints to be defective, the cost of rectification of defective welds shall also be borne by the Contractor.

7.2.3.2.13 Minimum Leg Length & Throat Thickness in Fillet Welds

The minimum leg length of a fillet weld as deposited shall be not less than the specified size. In no case shall a concave weld be deposited, unless specifically permitted. Where permitted, the leg length shall be increased above that specified length, so that the resultant throat thickness is as great as would have been obtained by the deposition of a flat-faced weld of the specified leg length.

7.2.3.2.14 Dislodging

After making each run of welding, all slag shall be thoroughly removed and the surface cleaned.

7.2.3.2.15 Quality of Welds

The weld metal, as deposited (including tack welds), shall be free from-cracks, slag inclusions, porosity, cavities and other deposition faults. The weld metal shall be properly fused with the parent metal without under cutting or overlapping at the toes of the weld. The surface of the weld shall have a uniform consistent contour and regular appearance.

7.2.3.2.16 Weather Conditions

Welding shall not be done under weather conditions, which might adversely affect the efficiency of welding.

7.2.3.2.17 Qualification and Testing of Welders

The Contractor shall satisfy the department that the welders are suitable for the work for which they will be employed, and shall produce evidence to the effect that welders, have satisfactorily completed appropriate tests, as described in IS:817 Part I (1992). The Engineer

may, at his own discretion, order periodic tests of the welders and/or of the welds produced by them. Such tests shall be at the expense of the Contractor.

7.2.3.2.18 Supervision

The Contractor shall employ competent welding supervisors to ensure that the standard of workmanship and the quality of the materials comply with the requirements laid down in this Specification.

7.2.3.2.19 Machining of Butts and Bases

Splices and butt joints of compression members, depending on contact for stress transmission, shall be accurately machined over the whole section. In column bases, the ends of shafts together with the attached gussets, angles, channels etc., after bolting and/or welding together as the case may be, shall be accurately machined so that the parts connected butt over the entire surface of contact. Care shall be taken that connecting angles or channels are fixed with such accuracy that they are not reduced in thickness by machining by more than 0.8mm.

7.2.3.2.20 Requirement of Welded Joints

Apart from the requirements of welding specified under the above sub clauses, sections above, the Contractor shall ensure the following requirements in the welded joints.

- i) Strength-quality with parent metal.
- ii) Absence of defects
- iii) Corrosion resistance of the weld shall not be less than that of parent material in an aggressive environment.

7.2.3.3 Shop Assembly

- a) The steelwork shall be temporarily shop assembled, as necessary, so that the accuracy of fit may be checked before dispatch. The parts shall be shop assembled with a sufficient number of parallel drifts to bring and keep the parts in place
- b) Since parts drilled or punched, with templates having steel bushes shall be similar and, as such, interchangeable, such steelwork may be shop erected in part only, as agreed by the Engineer.

7.2.3.4 Erection Marking

- a) Each fabricated member, whether assembled prior to dispatch or not so assembled, shall bear an erection mark, which will help to identify the member and its position in respect of the whole structure, to facilitate re-erection at site.
- b) These erection marks shall be suitably incorporated in the shop detail and erection drawings.

7.3 STRUCTURAL STEELWORK SPECIFICATION BOLTED STRUCTURE

7.3.1 General

7.3.1.1 Scope of Specifications

These specifications cover the supply, fabrication and delivery to site of bolted structural steelwork, including the supply of all consumables and other materials required for fabrication and field connections of all structural steelwork covered under the scope of the Specification.

7.3.2 Products

Ref. Specification 7.1.6 for Structural Steelwork -General

7.3.3 Execution

7.3.3.1 Workmanship

7.3.3.1.1 General

All workmanship shall be in accordance with the best practice in modern structural shops. Greatest accuracy shall be maintained in the manufacture of every part of the work and all similar parts shall be strictly interchangeable.

7.3.3.1.2 Templates

Templates used throughout the work shall be of steel. In cases where actual materials have been used as templates for drilling similar pieces, the Engineer shall decide whether such materials are fit to be used as parts of the finished structure.

7.3.3.1.3 Straightening

All materials shall be straight and free from twists, and if necessary, before being worked, shall be straightened and/or flattened by pressure, unless required to be of curvilinear form.

7.3.3.1.4 Clearance

The clearance between fraying surface of bolted connections shall not be greater than 1 mm at each end. If the separation is between 1 to 3 mm the surface should be tapered to eliminate the separation. Over 3mm separation shall be filled with filler plates.

7.3.3.1.5 Shearing, Cutting and planning

- a) Cutting shall be done automatically. Cutting by sheathing machine may be used for plates not exceeding 10mm in thickness provided that the plate edges be fully enclosed in a weld.

Oxygen cutting may be used provided a smooth and regular surface free from cracks and notches is secured.

- b) Chipping of angle flanges and edges of plates, wherever necessary, shall be done without damaging the parent metal. Chipped edges shall be ground to a neat finish and sharp and sharp corners and hammered rough faces shall be rounded off.
- c) The edges and ends of all cut/sheared flange plates, web plates of plate girders, and all cover plates, and the ends of all angles, tees, channels and other sections forming the flanges of plate girders, shall be planed/ground.
- d) The butting surfaces at all joints of girders shall be planed so as to but in close contact throughout the finished joint.
- e) The ends of all build up girders and of all columns shall be faced in an end-milling machine after the members have been completely assembled. Bearing edges for girder bearing stiffeners and column bases shall be machined.
- f) Unless clean, square and true to sharp, all flame-cut edges shall be planed. Cold sawn ends, if reasonably clean and flame-cut ends of sections not inferior to sawn ends in appearance need not be planned, except for butting ends.

7.3.3.1.6 Drilling

- a) Holes for bolts shall be drilled to conform to Clause 10 of IS:7215. Punching of holes shall not be permitted. All holes, except as stated hereunder, shall be drilled to the required size, 3mm less in diameter and reamed thereafter to the required size. All matching holes for bolts shall register with each other so that a gauge of 0.8mm less in diameter than the hole can pass freely through the members assembled for bolting, in the direction at right angle to such members.
- b) All drilling shall be free burrs.
- c) No holes shall be made by gas cutting process.

7.3.3.1.7 Assembly

- a) All parts assembled for bolting shall be in close contact over the whole surface
- b) The component parts shall be so assembled that they are neither twisted nor otherwise damaged. Specified cambers, if any, shall be provided.

- c) All parts of bolted and welded members shall be held firmly in position by means of jigs or clamps while bolting or welding. No drifting of holes shall be permitted, except to draw the parts together and no drift used shall be larger than the nominal diameter of the bolt. Drifting done during assembling shall not distort the metal or enlarge the holes.
- d) Trial assemblies shall be carried out at the fabrication stage to ensure accuracy of workmanship, and these checks shall be witnessed by the Engineer. Such trial assemblies shall be at the cost of the contractor.

7.3.3.1.8 Field Bolts

- a) Requirements stipulated under bolting shall apply for field bolts. Field bolts nuts and washers shall be furnished by the Contractor in excess of the nominal numbers required. He shall supply the full number of bolts, nuts and washers and other necessary fittings required completing the work, together with the additional bolts, nuts and washers totaling to 10% of the requirement subject to minimum of 10 Nos. Only HSFG bolts of class 8.8 shall be used.
- b) At the time of assembly, the surfaces in contact shall be free of paint or any other applied finish, oil, dirt, loose rust, loose scale, burrs and other defects which would prevent solid seating of the parts or would interfere with the development of friction between them.
- c) If any other surface condition, including a machined surface, is specified, it shall be the responsibility of the Contractor to work within the slip factor specified for the particular case.
- d) Each bolt and nut shall be assembled with washers of appropriate shape, quality and number in cases where plane parallel surfaces are involved. Such washers shall be placed under the bolt head or the nut, whichever is to be rotated during the tightening operation. The rotated nut or bolt head shall be tightened against a surface normal to the bolt axis, and the appropriate tapered washer shall be, used when the surfaces are not parallel. The angle between the bolt axis and the surface under the non-rotating component (i.e. the bolt head or the nut) shall be 90 ± 3 degree. For angles outside these limits, a tapered washer shall be placed under the non-rotating component. Tapered washers shall be correctly positioned.
- e) No gasket or other flexible material shall be placed between the holes. The holes in parts to be joined shall be sufficiently well aligned to permit bolts to be freely placed in position. Driving of bolts is not permitted. The nuts shall be placed so that the identification marks are clearly visible after tightening. Nut and bolts shall always be tightened in a staggered pattern and where there are more than four bolts in any one joint, they shall be tightened

from the centre of the joint outwards.

- f) If, after final tightening, a nut or bolt is slackened off for any reason, the bolt, nut and washer or washers shall be discarded and not used again.

7.3.3.2 Shop Assembly

The steelwork shall be temporarily shop assembled, as necessary, so that the accuracy of fit may be checked before dispatch. The parts shall be shop assembled with a sufficient number of parallel drifts to bring and keep the parts in place.

7.3.3.3 Erection Marking

Each fabricated member, whether assembled prior to dispatch or not so assembled, shall bear an erection mark, which will help to identify the member and its position in respect of the whole structure, to facilitate re-erection at site.

This erection mark shall be suitably incorporated in the shop detail and erection drawings.

7.4 STRUCTURAL STEEL SPECIFICATIONS -PAINTING WORKS

7.4.1 General

7.4.1.1 Scope of Specification

This Specification covers the scope of painting, methods for the surface preparation, application of paints and precautions to be taken for the painting of structural steel work. It covers the supply and delivery of all necessary materials, labour, scaffolding tools, equipment and everything that is necessary for the job completion on schedule.

7.4.1.2 Applicable Codes

The following Specifications, Standards and Codes are included as part of this Specification. All standards and codes of practice referred to herein shall be the current editions during the currency of project including all applicable official amendments and revisions.

In case of discrepancy between this Specification and those referred to herein, this specification shall govern. In case of discrepancy between Contract drawings and this specification, the Contract drawings shall govern.

- a) IS: 102 : Ready Mixed Paint, Brushing, Red lead, Non Setting, Priming.
- b) IS: 159 : Ready Mixed Paint, Brushing, Acid Resisting for .Protection against Acid Fumes, Colour as Required.
- c) IS: 341 : Black Japan, Types A, B & C.
- d) IS: 384 : Brushes, Paints and Varnishes, Flat.

- e) IS: 487 : Brush, Paint and Varnish i) Oval Ferrule Bound ii) Round Ferrule Bound.
- f) IS: 958 : Temporary Corrosion Preventive Grease, Soft Film, Cold Application.
- g) IS: 1153 : Temporary Corrosion Preventive, Fluid, Hard Film, Solvent Deposited.
- h) IS: 1477 : Code of Practice for Painting of Ferrous Metals in Building.
Part I -Pretreatment Part II -Painting
- i) IS: 1674 : Temporary Corrosion Preventive Fluid, Soft Film, Solvent Deposited.
- j) IS: 2074 : Ready Mixed Paints, Red Oxide -Zinc Chrome, Priming.

7.4.2 Products

7.4.2.1 Materials

7.4.2.1.1 Paint

- a) All paint delivered to the fabrication shop/Site shall be ready mixed, in original sealed containers, as packed by the paint manufacturers, and no thinners shall be permitted.
- b) Paint shall be stirred frequently to keep the pigment in suspension

7.4.2.1.2 Storage of Paints

- a) All paints shall be stored strictly in accordance with the requirements laid down by the paint manufacturers. The storage area shall be well ventilated and protected from sparks, flame, direct exposure to sun or excessive heat, preferably located in an isolated room or in a separate building.
- b) All paint containers shall be clearly labelled to show paint identification, date of manufacture, batch number, order number and special instructions in legible form. The containers shall be opened only at the time of use. Paints which have liveried, gelled or otherwise deteriorated during storage, shall not be used. Paints for which the shelf life specified by the supplier has expired shall not be used without inspection and approval by the Engineer.

7.4.3 Execution

7.4.3.1 Paint System

- a) Sand blasting where specified shall be carried out in accordance with IS:1477.
- b) Painting work shall be carried out as follows:

DESCRIPTION	GENERAL SURFACE	
FABRICATION SHOP	EXTERNAL SURFACES	INTERNAL SURFACES
Surface Treatment	Fire retardant Abrasive blast cleaning to minimum SA-2.5 SIS-055900 near – white blast cleaning	Fire retardant Abrasive blast cleaning to minimum SA-2.5 SIS-055900 near – white blast cleaning
1 st Under-Coat	Fire retardant Inorganic zinc silicate primer (self curing solvent type) DFT – 75 µm The primer should be applied by spray only as approved by Engineer.	Fire retardant Epoxy zinc phosphate primer polyamide cured DFT35 µm
2 nd Under-Coat	Fire retardant Epoxy zinc phosphate primer polyamide cured DFT-35 µm The primer should be applied by spray or brush only as approved by Engineer.	Fire retardant Epoxy zinc phosphate primer polyamide cured DFT35 µm Primer or approved equivalent The primer should be applied by spray or brush only
3 rd Under-Coat	Fire retardant Epoxy zinc phosphate primer polyamide cured DFT-35 µm. The Primer or approved equivalent. The primer should be applied by spray or brush only as approved by Engineer.	Fire retardant Polyamide cured coaltar epoxy coating DFT100 µm
4 th Under-Coat	Fire retardant Epoxy high build micaceous iron oxide coating polyamide cured DFT90 µm The primer should be applied by spray or brush only as approved by Engineer.	Fire retardant Polyamide cured coaltar epoxy coating DFT -100 µm
ERECTION SITE	EXTERNAL SURFACES	INTERNAL SURFACES
Intermediate Coat	Fire retardant Acrylic polyurethane finish aliphatic isocyanate cured DFT30µm shall be Berger thane or approved equivalent applied by spray or brush in approved colour.	NA
Finish Coat	Fire retardant Acrylic polyurethane finish aliphatic isocyanate cured DFT30µm shall be Berger thane or approved equivalent applied by spray or brush in approved colour.	NA

INTERNAL SURFACE = Internal surface are those which will become inaccessible after fabrication.

EXTERNAL SURFACE = All other surfaces which are prone to humidity and moisture from the atmosphere.

The following precautions must be taken:

- After abrasive blast cleaning, the first undercoat (primer coat) should be applied well before surface deterioration.
- At least EPOXY MIO coating application should be completed before giving any long overcoating interval for external surface.
- At least up to one coat of coaltar epoxy shall be completed before giving any long overcoating interval for internal surface.
- Overcoating intervals, application parameters shall conform to manufacturer's instruction manual.

- v. The DFT (Dry film thickness) shall be measured after completion of each coat.

7.4.3.2 Surface Preparation

7.4.3.2.1 General

All surfaces shall be cleaned of loose substances and foreign materials. e. g. dirt, rust, scale, oil, grease, welding flux etc so that the prime coat adheres to the original metal surface. The work shall be carried out in accordance with IS: 1477 (1971) (Part I). Any oil, grease, dust or foreign matter deposited on the surface after preparation shall be removed and care shall be taken to ensure that the surface is not contaminated with acids, alkalis or other corrosive chemicals. The primer coat shall be applied immediately after the surface preparation is completed. .

Before the application of any paint the surfaces to be treated shall be thoroughly cleaned freed from all scale, loose paint, rust and other deleterious matters. Oil and grease shall be removed from the surface by washing with solvents or with a detergent solution before blast cleaning operation of metal polish with metal pellets or any other material approved by the Engineer. If any traces of oil or grease remain after blasting they shall be removed by solvent cleaning and the area will be re-blasted thereafter.

All welding areas shall be given special attention for removal of weld flux slag, weld metal splatter weld head oxides, weld flux fumes silvers and other foreign objects before blasting. If deemed necessary by the Engineer, acid washing and subsequent washing with clean water shall be used.

Any rough seams will have to be ground and must be inspected and approved by the Engineer before application of the coatings.

All structural steel to be painted shall be cleaned blast cleaning in accordance with SA 2 1/2 Near- White Blast cleaning (equivalent Swedish Standard SIS 055900). For SA 2 1/2 the profile should be in the range of 40-70 microns and shall be measured with comparator. Mill scale, rust and foreign matter shall be removed to the extent that the only traces remaining are light stains in the form of spots or stripes. Finally, the surface shall be cleaned with a vacuum cleaner or clean dry compressed air.

The blast cleaning shall produce a surface roughness complying with the one specified by the paint manufacturer for the primer concerned. If, cleaned surfaces are rusted or are contaminated with foreign material before painting is accomplished, they shall be re-cleaned by the Contractor at his expenses.

The surface shall be cleaned by impingement of abrasive materials, such as grit of cast iron, malleable iron, steel or synthetic material, at high velocity created by clean and dry compressed air blast. Prior to application of the blast, heavy deposits of oil and grease shall be removed by solvent cleaning and excessive surface scale removed by hand tool or power tool cleaning.

The last finish paint shall be applied after structural steel erection and slab construction.

7.4.3.3 Mixing and Thinning

- a) All ingredients in a paint container shall be thoroughly mixed to break-up lumps and disperse pigments, before use and during application, to maintain homogeneity. All pigmented paints shall be strained after mixing to remove skins and other undesirable matters.
- b) Dry pigments, pastes, tinting pastes and colours shall be mixed and/or made into paint so that all dry powders get wetted by vehicles and lumps and particles are uniformly dispersed.
- c) Additives that are received separate such as curing agents, catalysts, hardeners etc. shall be added to the paint as per the manufacturer's instructions. These shall be promptly used within the pot life specified by the manufacturers and unused paint thereafter shall be discarded.
- d) Thinners shall not be used unless essential and permitted by the Engineer for proper application of the paint. Where thinners are used, they shall be added during the mixing process and the type and quantity of thinner shall be in accordance with the instructions of paint manufacturer.

7.4.3.4 Paint Application

7.4.3.4.1 General

- a) Paint shall be applied in accordance with the manufacturer recommendations, as supplemented by these Specifications. The work shall generally follow IS:1477 (1971) (Part II). Prior approval of the Engineer shall be taken in respect of all primers and/or paints, before their use in the works.
- b) Paint shall generally be applied by brushing except that spraying may be use for finish coats only when brushing may damage the prime coats. Roller coat or other method of paint application shall not be used unless specifically authorized.
- c) Spraying paint shall not be adopted on red lead or zinc rich paints. Daubers may be used only when no other method is practicable for proper application in difficult accessible areas.
- d) Paint shall not be applied when the ambient temperature is 10°C and below. For paints which dry by chemical reaction the temperature requirements specified by the manufacturer shall be met with. Also, paint shall not be applied in rain, wind, fog or at relative humidity of 80% and above or when the surface temperature is below dew point, resulting in condensation of moisture. Any wet paint exposed to damaging weather conditions shall be inspected after drying and the damaged area repainted after removal of the paint.

- e) Each coat of paint shall be continuous, free of pores and of even film thickness without thin spots. The film thickness shall not be so great as to detrimentally affect either the appearance or the service life of the paint.
- f) Each coat of paint shall be allowed to dry sufficiently before application of the next coat, to avoid damages such as lifting or loss of adhesion. Undercoats having glossy surface shall be roughened by mild sand papering to improve adhesion of subsequent coats. Successive coats of same colour shall be tinted. Whenever practical, to produce contrasts and help in identifying the progress of the work.

7.4.3.4.2 Brush Application

- a) Proper brushes shall be selected for a specific work piece. Round or oval brushes which conform to IS:487 are better suited for irregular surfaces, whereas flat brushes which conform to IS:384 are convenient for large flat areas. The width of flat brushes shall not generally exceed 1.25mm.
- b) Paint shall be applied in short strokes depositing a uniform amount of paint in each stroke followed by brushing the paint into all surface irregularities, crevices and corners and finally smoothening or levelling the paint film with long and light strokes at about right angles to the first short strokes. All runs and sags shall be brushed out. The brush marks left in the applied paint shall be as few as practicable.

7.4.3.4.3 Spray Application

- a) The spraying equipments shall be compatible with the paint material and provided with necessary gauges and controls. The equipment shall be cleaned of dirt, dried paint, foreign matter and solvent before use.
- b) The paint shall be applied by holding the gun perpendicular to the surface at a suitable distance and moved in a pattern so as to ensure deposition of a uniform wet layer of paint. All runs and sags shall be brushed out immediately. Areas not accessible to spray shall be painted by brush or dauber.
- c) Watertrap acceptable to Engineer shall be furnished and installed on all equipment used in spray painting.

7.4.3.5 Shop Painting

- a) The painting system specified in Table shall be followed.
- b) Surfaces in contact during shop assembly shall not be painted. Surfaces which can not be painted but require protection shall be given a rust inhibitive grease conforming to IS:958 or solvent deposited compound conforming to IS: 1153 or IS: 1674 or treated as specified in the drawing.

- c) Surface to be in contact with concrete shall not be painted.
- d) The shop coats shall be continuous over all edges, including ends meant for jointing at site by bolting, except where the paint could be detrimental to bolting. In such cases, no paint shall be applied within 50mm, and the unprotected surface shall be given a coat of corrosion inhibitive compound.
- e) The unpainted area shall be cleaned prior to welding. The welded joint shall be cleaned and deslagged, and immediately after covered by the same paint as has been used for the remaining surface.

7.4.3.6 Protection of Paintwork

- a) The Contractor shall provide measures as necessary to prevent damage to the work and to other property or persons from all cleaning and painting operations. Paint or paint stains which result in other unsightly appearance on surfaces not designated to be painted shall be removed or obliterated by the contractor at his cost.
- b) All painted surfaces that in the opinion of the Engineer are damaged in anyway, shall be repaired by the contractor at his cost with materials and to a condition equal to that of the requirements specified in these specifications.
- c) Upon painted surfaces that in the opinion of any other work that would cause dust, grease or foreign materials to be deposited upon the painted surfaces, the painted surfaces shall be thoroughly cleaned. At the time of opening the flyovers to public traffic, the painting shall be completed and the surfaces shall be undamaged and clean.
- d) The areas for high-strength bolts shall be protected by masking tape against undercoat application at the fabrication shop. Immediately prior to erection any rust in the paint area shall be removed by power wire brushing to a standard equivalent to SA3.

7.4.3.7 Site Painting

- a) After the erection of structures at the site, the contractor shall provide the necessary treatment as specified in Table "PAINTING SPECIFICATIONS".
- b) Surfaces which have not been shop coated, but require surface treatment shall be given necessary surface preparation and coats at site as specified in Table.

7.5 STRUCTURAL STEEL WORK -QUALITY CONTROL & TESTING REQUIREMENTS

7.5.1 General

7.5.1.1 Scope of Specification

The scope of work of these specifications is to establish the norms for ensuring the required Quality Control through established testing norms of the welded structural steelwork.

7.5.1.2 Codes / Standards

Relevant IS codes for tolerance and tests of welding procedures as specified in the specification for Structural Steelwork -General.

7.5.1.3 Submittals

The Contractor shall submit the followings:

- a) Proposed overall schedule for documentation of calculations, shop drawings, plan/procedures and records, submission of procedure of fabrication.
- b) The contractor shall himself inspect all materials, shop work and field work to satisfy the specified tolerance limits and Quality norms before the same are inspected by Engineer or his authorized representative.

7.5.2 Products

Make of approved manufacturer

7.5.3 Execution**7.5.3.1 Tolerances**

The contractor shall through appropriate planning and continuous measurements in the workshop and the erection at site, ensure that the tolerance specified below are strictly adhered to.

7.5.3.1.1 Dimensional & Weight Tolerance

The dimensional and weight tolerance for rolled shapes shall be in accordance with IS: 1852. The acceptable limits of straightness for rolled or fabricated members as per IS: 7215 are:

Struts and columns: $1/1000$ or 10 mm whichever is smaller where L is the length of finished member A limit for distortion in transverse direction δ from the true axis of plate and box girder shall not be more than $L/1000$ where L is the length of diagonal of profile.

Tolerance in specified camber of members shall be 3mm in 12m length

Tolerance in specified lengths shall be as follows:

-	Column finished for contact bearing	+ 1 mm
-	Other members (cols.) upto and over 10 m	+ 5 mm
-	Including 10 m L/2000 sub to max of	+ 8 mm
-	Other members (beams) upto 12 m	+ 3 mm
-	Over 12m L/4000 sub max. of	+ 5 mm

7.5.3.1.2 End of Members

Beam to beam and beam to column connection -Where the abutting parts are to be jointed by

butt welds, permissible deviation from the squareness of the end is :

Beam upto 600 mm in depth : 1.5 mm

Beam over 600 mm in depth: 1.5 mm for increase in depth of every 600 mm subjected to max of 3 mm.

Where abutting parts are to be jointed by bolting through cleats or end plates, the connections require closer tolerance, permissible deviation from the squareness of the end is:

Beams upto 600 mm in depth 1mm per 600mm of depth subject to a max of 1.5 mm.

For full bearing, two abutting ends of columns shall first be aligned to within 1 in 1000 of their combined length and then the following conditions shall be met :

- i. Over at least 80% of the bearing surface the clearance between the surfaces does not exceed 0.1mm.
- ii. Over the remainder of the surfaces the clearance between the surfaces does not exceed 0.3 mm.

Where web stiffeners are designed for full bearing on either the top flange or the bottom flange or both, at least half the stiffener shall be in positive contact with the flange. The remainder of the contact face could have a max. gap of 0.25 mm.

7.5.3.1.3 Depth of Members

Acceptable deviation from the specified overall depth as per IS:7215 (1974) is:

Upto and including 1000mm	: 1.0 mm
Over 1000 mm	: 2.0mm

7.5.3.1.4 Web Plates

An acceptable deviation from flatness in girder webs in the length between the stiffeners or in a length equal to the girder depth shall be:

Upto 500 mm depth	: 0.5 mm
Over 500 mm & including 1000 mm	: 1.0 mm
Over 1000 mm	: 2.0 mm

7.5.3.1.5 Flange Plates

A reasonable limit for combined warpage and tilt on the flanges of a built-up member is 1/200 of the total width of flange or 2 mm whichever is smaller measured with respect to centerline of flange.

Lateral deviation between centreline of web plate and centreline of flange plate at contact surfaces measured as the difference δ between diagonals of nominal length L shall not be greater than $L/1000$.

7.5.3.1.6 End Milling

Column ends bearing on each other or resting on base plates and compression joints designed for bearing shall be milled true and square to ensure proper bearing and alignment. Base plates shall also have their surfaces milled true and square.

7.5.3.2 Quality Control

In order to exercise proper control of the quality of the welding, Contractor shall enforce methods of control as tabulated below:

	Purpose	Control subjects	Methods of control
	1	2	3
1.	Control of welding materials and basic metal quality	Quality control of electrodes, welding wire, flux and protective gases Checking of quality and Weldability of the basic metal and welded members	Weldability test to determine the technological properties of materials. Mechanical test of weld metal Metallographical investigations of welds macro- structure and microstructure Checking of weld metal resistance for intercrystalline corrosion. Study of weld metal solidity by physical control methods.
2.	Checking of welders qualifications	Welding of specimens for quality determination	Mechanical tests, metallographical investigation & checking of welded joints by physical control methods
3.	Control of welded joint quality	Control of assembly accuracy and technological welding process	Checking of assembly quality & centering of welded members Checking of welding equipment conditions. Checking correctness of welding procedure. Visual examination of welds

7.5.3.3 Tests & Testing Procedures

Agency for testing of weld shall be approved by the Engineer prior to testing.

7.5.3.3.1 Visual Examination

The contractor shall conduct visual examination and measurement of the external dimensions of the weld for all joints. Before examining the welded joints, areas close to it on both sides of the weld for a width not less than 20 mm shall be cleaned of slag and other impurities. Examination shall be done by a magnifying glass which has a magnification power of ten (10) and measuring instrument which has an accuracy of ± 0.1 mm or by weld gauges. Welded joints shall be examined from both sides. The contractor shall examine the following during the visual checks.

- i) Correctness and shape of the welded joints
- ii) Incomplete penetration of weld metal.
- iii) Influx
- iv) Burns
- v) Unwelded craters
- vi) Undercuts
- vii) Cracks in welded spots and heat affected zones
- viii) Porosity in welds and spot welds
- ix) Compression in welded joints as a result of electrode impact while carrying out contact welding
- x) Displacement of welded element

The contractor shall, document all data as per sound practices.

7.5.3.3.2 Mechanical Test

The Contractor shall carry out various mechanical tests to determine weldability, metal alloyability, nature of break, correct size and type of electrodes, degree of pre-heat and post-heat treatment. The type, scope and sample of various mechanical tests shall be determined in agreement with the purchaser. The number of tests conducted shall depend on the result obtained to satisfy the Engineer that the correct type and size of electrode, degree of pre-heating and post-heating and weldability of metal are being followed.

7.5.3.3.3 Dye Penetration Test

All welds shall be tested by "Dye Penetration test" as per current practices.

7.5.3.3.3 Radiography Test

Radiography test shall be conducted by the contractor to determine gas inclusion (blow holes, hollows) slag inclusion, shallow welds and cracks for 50% lengths at all butt joints.

Before conducting the examination, the welded joints shall be cleaned of slag and scales and visually examined. The welds shall be marked into separate portions depending on the length of photograph. The length of photograph shall be such as to ensure that there are no distortions and shall reveal the defect correctly. The length shall not be more than 0.75 of the focal distance and the width of the photograph would depend on the width of the welded joint plus 20 mm on either side of the weld. The cassette with film shall be protected by sheet of lead or equivalent of proper thickness against incidental, diffused and secondary radiation.

The direction of the ray with relation to the film shall be as specified hereunder.

Welds of butt joints without edge slopes with edge processing shall be examined by central ray directed at right angles to the weld.

In special cases examination of welds with inclined rays directed along edge slopes may be permitted by the Engineer.

Lap joints shall be examined by directing rays at 45 degree to the bottom plate. Welds in T-joints without any edge preparation shall be examined by rays directed at 45 degree to the weld. Angle welds in lap and tee-joints shall be examined by the rays in opposite direction i.e. the film will be on the side of the weld. Weld in angle joints shall be checked by directing ray along the bisector of the angle between the welded elements. Opposite direction of the ray and location of the film may also be permitted by the Employer.

7.5.3.3.4 Ultrasonic Test

Ultrasonic test shall be conducted by the contractor to detect gas inclusion (pores), slag inclusion, shallow welds, cracks, lamination and friability etc. Prior to starting of ultrasonic test the welded joint shall be thoroughly cleaned of slag and other material. Surface of the basic metal adjacent to welded joint on both sides shall be mechanically cleaned by the grinder or a metal brush to provide the contact of the whole ultrasonic probe surface with surface of basic metal. The width of the clean surface shall be as directed by the Engineer. The welded joint then shall be covered with a thin coat of transformer oil, turbine or machine oil to ensure acoustic contact. The joints so treated shall be marked and the marks shall be entered into the documentation, subsequent to this, ultrasonic test shall be carried out as directed by the Engineer. At least 50% of butt weld shall be tested by ultrasonic testing

7.5.3.3.5 Magnetic Particle Test

Only where the Engineer requires that flaw-detection of welds be done by 'Magnetic Particle Test', in such cases the tests are to be done in accordance with IS: 3703. If heat treatment is performed, the completed weld shall be examined after the heat treatment. All defects shall be repaired and re-tested. Magnetic particle tests shall be carried out using alternating current. Direct current may be used with the explicit written permission of the Engineer.

7.6 STRUCTURAL STEEL SPECIFICATIONS -ERECTION

7.6.1 General

7.6.1.1 Scope of Specification

This Specification covers the delivery to site, storage and erection of structural steelwork at site. This includes plant and equipment requirements, installation of fabricated steel work in position and grouting all complete as per drawings, specifications and other provisions of the Contract.

7.6.1.2 Submittals

- a) Ref. Specification for Structural Steelwork -General
- b) The contractor shall submit for approval a full description of his proposed erection

method including sequence of erection, use of temporary supports, connection details and erection camber diagram and design calculations covering various stages of erection process.

7.6.2 Execution

7.6.2.1 Delivery, Storage & Handling

- a) Before the shop assembling is dismantled, all members and sections shall be appropriately marked with paint or grooved with their identification numbers as detailed in shop drawings.
- b) The Contractor shall deliver the fabricated structural steel materials to site, with all necessary field connection materials, in such sequence as will permit the most efficient and economical performance of the erection work. As per scheduled programme, the Engineer may, at his discretion prescribe or control the sequence of delivery of materials.
- c) Fabricated parts shall be handled and stacked in such a way-that no damage is caused to the components. Measures shall be taken to minimize damage to the protective treatment on the steelwork. All work shall be protected from damage in transit. Particular care shall be taken to stiffen free ends, prevent permanent distortion and adequately protect all machined surfaces. All bolts, nuts, washers, screws, small plates and articles generally shall be suitably packed and identified.

7.6.2.2 Plant and Equipment

All erection tools and plant & equipment proposed to be used shall be efficient, dependable and in good working condition, and the suitability and adequacy of such shall be determined by the Engineer. The Contractor shall, in his technical proposal submittal, specify the plant and equipment proposed by him for erection of structural steelwork at Site.

7.6.2.3 Storage

Materials to be stored shall be placed on skids above the ground and shall be kept clean and properly drained.

7.6.2.4 Method and Sequence of Erection

The method and sequence of erection shall have the prior approval of the Engineer. The contractor shall arrange for the most economic method and sequence consistent with the drawings and Specifications and such information as may be furnished to him prior to the execution of the Contract. The erection of steelwork shall be planned so as to ensure safe-working conditions at all times. The Contractor shall be solely responsible for enhancing the safety of his construction activities at Site.

7.6.2.5 Assembly & Erection

- a) During erection, the members and sections shall be accurately assembled as shown on the approved shop drawings and any matchmarks shall be followed. The material shall be carefully handled so that no sections will be bent, broken or otherwise damaged. Hammering which will damage or distort the members shall not be done. Bearing surfaces and surfaces to be in permanent contact shall be cleaned before the members are assembled. Splices and field connections shall have one half of the holes filled with bolts and cylindrical erection pins (half bolts and half pins) before bolting with high-strength bolts. Fitting-up bolts shall be of the same nominal diameter as the high-strength bolts, and cylindrical erection pins shall be 1 mm or larger.
- b) The correction of minor misfits involving harmless amounts of reaming, cutting and chipping will be considered a legitimate part of the erection. However, any error in the shop fabrication or deformation resulting from handling and transportation which prevents the proper assembling and fitting up of parts by the moderate use of drift pins or by a moderate amount of reaming and slight chipping or cutting, shall be reported immediately to the Engineer and his approval of the method of correction obtained. The contractor shall be responsible for all misfits, errors and injuries and shall make the necessary corrections and replacements.
- c) The straightening of plates, angles, other shapes and built-up members, when permitted by the Engineer, shall be done by methods that will not produce fracture or other damages. Distorted members shall be straightened by mechanical means or, if approved by the Engineer, by the careful planned and supervised application of a limited amount of localized heat, each application subject to the approval of the Engineer.
- d) The responsibility in respect of temporary bracing and guys shall rest with the Contractor until the structural steel is located, plumbed, leveled, aligned and grouted within the tolerances permitted under the Specification, and the permanent bracing/framing system has been installed.
- e) The temporary guys, braces, false work and cribbing shall not be the property of the department and may be removed by the Contractor, with the approval of the Engineer, without any charge, once the permanent framing system has been installed to the satisfaction of the Engineer and when the temporary bracing, guys etc. can be removed without any potential danger/damage to the erected structure.

7.6.2.6 Setting Out

- a) Positioning and leveling of all steelwork, plumbing and placing of every part of the structure, with accuracy, shall be in accordance with the approved drawings and to the satisfaction of the Engineer. The Contractor shall check the positions and levels

of the anchor bolts etc. before concreting and ensure that they are properly secured against disturbance during pouring operations. The Contractor shall remain responsible for correct positioning and shall set proper screed bars to maintain proper level. No extra payment shall be made on this account.

- b) No permanent field connections by bolting shall be carried out until proper alignment and plumbing guides have been attached.

7.6.2.7 Field Bolting

- c) Bolts shall be inserted in such a way that they remain in position under gravity, even before fixing the nut. Bolted parts shall fit solidly together when assembled and shall not be separated by gaskets or any other interposed compressible materials. When assembled all joint surfaces including those adjacent to the washers shall be free of scales. They shall be free of dirt, loose scales, burns and other defects that would prevent solid seating of the parts.
- d) Holes for turned bolts to be inserted in the field shall be reamed in the field. All drilling and reaming for turned bolts shall be done only after the parts to be connected are assembled. Tolerances applicable in the fit of the bolts shall be in accordance with relevant Indian Standard Specifications.
- e) All high tensile bolts shall be tightened to provide when all fasteners in the joint are tight, the required minimum bolt tension as per relevant Indian Standard/Specification.
- f) The manufacturer and use of high strength friction grip bolts shall comply with the requirements of IS:3757 .
- g) Load indicating bolts or washers may be used, subject to the approval of the Engineer.

7.6.2.8 Holes, Cutting and Fitting

- a) No cutting of sections, flanges, webs, and cleats, rivets, bolts, welds etc. shall be done unless specifically approved and / or instructed by the Engineer.
- b) The erector shall not cut, drill or otherwise alter the work of other trades, or his own work to accommodate other trades, unless such work is clearly specified in the Contract, or directed by the Engineer. Wherever such work is specified, the Contractor shall obtain complete information as to size, location and number of alterations, prior to carrying out any work.

7.6.2.9 Drifting

- a) Correction of minor misfits will be considered as permissible if approved by the Engineer. For this, light drifting may be used to draw holes together and drills shall be used to enlarge holes, as necessary, to make connections. Reaming, that weakens

the member or makes it impossible to fill the holes properly or to adjust accurately after reaming, shall not be allowed.

- b) Any error in shop work which prevents the proper assembling and fitting of parts by moderate use of drift pins and reamers shall immediately be called to the attention of the Engineer, and approval of the method of correction obtained. The use of gas cutting torches at the erection site is prohibited.

7.6.2.10 Grouting

- a) The positions to be grouted shall be cleaned thoroughly with compressed air jet and wetted with water, and any accumulated water shall be removed. Grouting shall be carried out under expert supervision, taking care to avoid air locks. Edges shall be finished properly.
- b) Whatever method of grouting is employed, the operation shall not be carried out until the steelwork has been finally leveled. Immediately before grouting, the space under steel is thoroughly cleaned. Where packing are to be left in place, they shall be placed such that they are completely covered with grout.
- c) The grout to be used shall be Non-shrink grout conbextra GP-2 of M/S Fosroc or equivalent.
- d) All steel in foundations shall be solidly encased in Portland Cement Concrete of minimum characteristic strength at 28 days as specified in the drawings, subject to a minimum of 35 N/mm². A minimum cover of 100mm shall be provided to all steelwork where surrounding concrete is in contact with soil.

7.6.2.11 Inserts And Embedment's

Various steel inserts and embedments are required under the contract to be fabricated, positioned and secured firmly into place inside the formwork prior to concrete being poured. There are also requirements of jointing, threading, bolting and welding inserts and embedments of different concrete and structural steel elements in order to establish structural continuity and connection. Great care shall be exercised by the contractor in executing all aspects of the work related to inserts and embedments, including tolerances, so that the final assembly of the concrete elements can meet satisfactorily the continuity and contiguity requirements intended in the structure.

7.6.2.12 Painting after Erection

- a) Steelwork coated with rust inhibitor shall not be left exposed for a period exceeding 15 days otherwise, such steelwork shall be re-cleaned and re-coated with such finish until encased in concrete.
- b) No steelwork with shop paint shall be left exposed at site for a period exceeding that approved by the Engineer.

- c) The surfaces required to remain unpainted at shop, shall be given a protective coating after the structure is erected, leveled, plumbed, aligned in its final position, and accepted by the Engineer. However, touch up painting, making good any damaged shop painting and completion of any unfinished portion of the shop coat shall be progressively carried out by the Contractor.
- d) Painting shall not be done in frost or foggy weather, or when humidity is such as to cause condensation on the surfaces to be painted. Before, commencing painting of steel, which is delivered unpainted, all surfaces to be painted shall be dried and thoroughly cleaned from all loose scale and rust.
- e) All field bolts, welds and abrasions to the shop coat, and surfaces delivered unpainted from fabrication shop, shall receive the full protective treatment as specified in Table defined in painting specifications before delivery to Site.
- f) Surfaces, which will be inaccessible after field assembly, shall receive the full-specified protective treatment before assembly. Bolts and fabricated steel members, which are galvanised or otherwise treated, shall not be painted.
- g) The contractor shall be responsible for any damage caused to other components of the structure including the substructure. In particular, he shall take all necessary precautions to minimise concrete splash onto completed steelwork or rust staining of concrete due to erected steel work and clean and/or repair all stains and other damages to completed work prior to tests on completion.

7.6.2.13 Final Cleaning up

Upon completion of erection, and before final acceptance of the work by the Engineer, the Contractor shall remove, free of cost, all falsework, rubbish and all temporary works, resulting from or in connection with the performance of his work.

SECTION - S.08

FOUNDATION

8.1 PILE FOUNDATION:

8.1.1 General

i) Piling plant and Methods:

Suggested method for piling is cast in situ-bored piles with hydraulic drilling rigs using partial depth casing with polymer and oscillator arrangement.

- a) Not less than 2 weeks before any piling work is commenced the Contractor shall submit to the Engineer for approval full details of his proposed piling plant and detailed method statements for carrying out the Works.

Details of casings and concreting methods in respect of bored cast in place concrete piles are to be provided.

- b) The Contractor shall not commence any piling until the plant and methods which he proposes to use have been approved by the Engineer but such approval shall not relieve the Contractor from any of his obligations and responsibilities under the Contract. If for any reason the Contractor wishes to make any change in the plant and methods of working which have been approved by the Engineer, he shall not make any such change without having first obtained the Engineer approval thereof.
- c) List and nos. of equipment & accessories proposed to be used for the present job shall be submitted along with the technical bid and Method Statement.

ii) Records:

The Contractor shall keep complete records of all data required by the Engineer covering the fabrication, driving, concreting and installation of each pile and shall submit two signed copies of these records to the Engineer not later than noon of the next working day after installation of the piles.

iii) Programme and Progress Report:

- a) The Contractor shall inform the Engineer each day of the programme of piling for the following day and shall give adequate notice of his intention to work outside normal hours and at weekends, where approved.
- b) The Contractor shall submit to the Engineer on the first day of each week, or on such other date as the Engineer may decide, a progress report showing the rate of progress to that date and progress during the previous week or period of all main items of piling works, as required by the Engineer.

iv) Setting Out:

The Contractor shall establish and maintain permanent datum level points, base lines and

grid lines to the satisfaction of the Engineer and shall set out with a suitable identifiable pin or marker the position of each pile. The setting out of each pile shall be agreed with the Engineer at least 8 working hours prior to commencing work on a pile and adequate notice for checking shall be given by the Contractor.

Notwithstanding such checking and agreement, the Contractor shall be responsible for the correct and proper setting out of the piles and for the correctness of the positions, levels, dimensions, and alignment of the piles.

- v) After all piles are cast and weak concrete is chipped out the Contractor shall submit the drawing showing the exact location of piles with respect to the column centre line.
- vi) Disturbances and Noise:
 - a) The Contractor shall carry out the piling work in such a manner and at such times as to minimise noise and disturbance.
 - b) The Contractor shall take precautions adequate enough to avoid damage to existing services and adjacent structures. IS: 2974 (Part 1) – 1982 may be used as a guide for studying qualitatively the effect of vibration of persons and structures. In case of deep excavation adjacent to piles, proper shoring or other suitable arrangement shall be done to guard against the lateral movement of soil stratum or releasing the confining soil stress. Any such damage shall be repaired by the contractor to the satisfaction of the Engineer.
 - c) The Contractor shall ensure that damage does not occur to complete piling works and shall submit to the Engineer for approval his proposed sequence and timing for driving or boring piles having regard to the avoidance of damage to adjacent piles.
- vii) Obstructions:

If during the execution of the Works the Contractor encounters obstructions in the ground, he shall forthwith notify the Engineer accordingly, submit to him details of proposed methods for overcoming the obstruction and proceed according to the Engineer instructions.

8.1.2 Scope of Work:

- a) These specifications cover the works of providing pile foundations. Work included consists of all necessary services and furnishing of all labour material, tools, equipment and related items for the full and satisfactory performance of the contract, conforming to these specifications and as shown in the Contract Drawings or reasonably implied therein or any authorised conditions or alterations thereof.
- b) The intending tenderer/contractor is advised to visit the site and familiarise himself with the conditions at site. The Engineer shall not be held responsible for the accuracy of the soil data, furnished in good faith with the tender.
- c) The construction of piles shall be in accordance with the following Indian Standard Codes of Practice for Design and Construction of Pile Foundations: IS: 2911 (Part 1/ Section

- 2) :2010Bored Cast in-situ Concrete Piles Or IRC:78 Standard specifications and code of practice for road bridges Foundation And Substructure
- d) With the tender the Contractor shall submit the detailed method of construction to be used. For cast-in-situ concrete piles the Contractor shall indicate the methods he proposes to concrete the piles in order to prevent necking of piles.
- e) The items of work will generally be as follows:
- i. Boring/drilling including provision of temporary casing.
 - ii. Supplying, fabrication, and placement of all reinforcing bars.
 - iii. Casting of concrete piles as per specifications.
 - iv. Load testing of piles.

8.1.3 Materials:

i) General:

Unless otherwise specified in this section all materials shall conform to the requirements specified in separate sections for Concrete, Formwork and Reinforcement.

ii) Cement:

The cement to be used for piling and all foundation work shall be conforming to Table 4 of IS: 456.

Cement shall be free from lumps and caking.

a) Concrete Mix Design:

The minimum grade of concrete shall be M35. The maximum size of coarse aggregate shall not exceed 20mm. For cast-in-situ piles concrete with a slump of 150 to 175mm (consistent with the method of concreting) will be required. For slumps more than 150mm the workability should be tested by "determination of flow" as per IS:9103. Minimum cementitious contents for design mix shall not be less than 400 kg/m³ of concrete in piling. For piling quantity of cement shall be as per the design mix or the minimum cementitious content whichever is greater shall be used.

The contractor shall submit mix design calculations and get the same approved by the engineer well before the starting of installation of piles and carry out adequate numbers of tests to ensure the minimum specified strength as indicated in drawings.

b) Concrete cube tests :

Concrete cubes shall be cast, tested and evaluated as specified in Section 3.

iii) Reinforcement:

- a) The reinforcement shall conform to the requirements specified in Section 5 extending for the full length of the pile and shall project above the cut off level as specified in the drawing. Only circular concrete cover blocks (of atleast same

grade as of the pile) threaded on to the outermost reinforcement shall be used for ensuring the specified cover.

- b) Joints in main longitudinal bars will be permitted only where, in the opinion of the Engineer, each bar cannot be supplied in one complete length. Where permitted, joints shall be provided at agreed centres, designed to develop the full strength of the bar across the joint, provided with adequate extra links or stirrups and staggered in position from those of adjacent longitudinal bars, all to the approval of the Engineer.
- c) All main longitudinal bars shall be tack weld at lapping if any and to the pile cap reinforcement. The last one circle of helical stirrups at each end shall be welded to main longitudinal bars.
- d) No L-Bend shall be provided at Base of pile and cover of 75mm at bottom shall be ensured.

iv) Casings and Tremie Pipes:

The casings and tremie pipes shall be in mild steel. The temporary casing plates and permanent liners shall have adequate wall thickness and strength to withstand driving stresses, stresses due to soil pressure, etc. without damage or distortion. All joints shall be water tight. The internal diameter of the casing shall not be less than the nominal diameter of pile.

8.1.4 Cast In-Situ Bored Piles:

- i) General:
 - a) Diameters of the piles shall be the concrete shaft diameters and shall not be less than the diameters specified in the drawing.
 - b) These shall be formed by boring to the founding strata specified on the drawings or as directed at site. The sides of the boring shall be prevented from collapsing by one of the following:
 - permanent mild steel liner (cased pile)
 - removable mild steel casing (uncased pile)
 - c) Piles shall be constructed in a sequence approved by the Engineer. During boring, the Contractor shall, where required by the Engineer, take soil, rock or ground water samples and transport them to an approved testing laboratory or carry out required tests.
 - d) The method adopted shall be chosen giving due consideration to the subsoil data, ground water conditions and to the other relevant conditions at site as well as to the presence of adjacent structures.
 - e) The bottom of the steel lining shall be sufficiently in advance of the boring tool so as to prevent settlement of outside soil and formation of cavities.

- d) Removable mild steel casings shall be used only with extreme caution. Individual casings shall be joined together by screwing or any other approved method and not by direct butting with external lug connections. The inner surface of casings shall be smooth and free of all internal projections.
- ii) Boring:
- a) Boring shall be done using hydraulic drilling rigs with oscillator arrangement suiting to different kinds of strata encountered.
- b) As a general guideline, size of cutting tool shall in no case be less than the diameter of the pile minus 75mm. However, the size of cutting tool shall be chosen by contractor depending on the type of substrata and equipment employed by contractor so that executable pile shall not have diameter less than nominal diameter of pile as specified in drawing. The contractor shall also ensure that there is no reduction in poured concrete quantities. These calculations shall be based on consumption of concrete poured in bore (as recorded in pour log) and actual concrete required in bore on theoretical basis i.e. based on nominal diameter of pile and actual bore hole length (based on actual sounding of founding level). Although 5% reduction in consumption of poured concrete quantities in pile may be rejected. In general piling shall be done by using hydraulic rig with temporary liner. Use of liner for top 4 to 6 metres from ground level or more depth, to protect loose soil falling in bore hole as directed by engineer, is essential. No extra payment shall be made to the contractor for using temporary liner, over the item of piling as in BOQ.
- c) Polymer Slurry as approved by Engineer shall only be used. Use of bentonite slurry is strictly prohibited. The polymer slurry shall conform to the following specifications:

Acceptable Range of Values for Polymer Slurry

Property	In Hole at Time of Test Concreting	Method
Density ⁽¹⁾ pounds per cubic foot (kilograms per cubic meter)	64 max. (1025 max.)	Density balance API 13B-1 ⁽²⁾ , Section 1
Viscosity Seconds per quart (seconds per liter)	32-135 (34-143)	Marsh Funnel AP 13B-1 ⁽²⁾ , Section 2.2
pH	8-11	pH paper or meter
Sand content,%	1.0 max.	API 13B-1 ⁽²⁾ ,Section 5

1 Density values shown are for fresh water. Increase density values by 2 pounds per

cubic foot (23 kilograms per cubic meter) for salt water. Perform tests when slurry temperature is above 40°F (4.5°C).

- 2 American Petroleum Institute, API 13B-1, *Recommended Practice for Field Testing Water-based Drilling Fluids*.

iii) Concreting :

- a) Prolonged delays in the commencement of concreting after the completion of the boring shall not be permitted. The time interval between the completion of boring and placing of concrete shall not exceed 6 hours. Measures to prevent collapse of bore shall continue to be in force during the gap between boring completion and concreting. The depth of bore shall be ensured before lowering of reinforcement and start of concreting.
- (b) The concrete shall have a minimum slump of 150mm and maximum 175 mm in case of concreting in a water-free bore. Suitable precautions shall be taken for prevention of segregation. Internal vibrators shall not be used unless the Contractor is satisfied that segregation will not result because of vibration and unless the method of use has been approved by the Engineer.
- (c) The concrete for piles underwater or in drilling mud shall be placed with a tremie pipe. The tremie pipe shall not be less than 200mm diameter for 20mm aggregate. The joint between the hopper and tremie pipe as well as the joints in the tremie pipe shall be water tight and the tremie pipes shall be thoroughly cleaned after each use. The concrete shall have a minimum slump of 150mm and maximum 175 mm.

It is essential that the water level within the pile bore be in equilibrium before commencement of concreting.

- (d) The Contractor shall ensure that heavily contaminated drilling mud has not accumulated at the base of boring since this could impair free flow of concrete from the tremie pipe.
- (e) If the specific gravity of the drilling mud at the base of the bore exceeds 1.20 the placing of concrete shall not proceed.
- (f) The first charge of concrete shall be placed in the hopper over a sliding plate of the bottom of the hopper. The charge should be adequate in volume to ensure flushing action to prevent mixing of water or drilling mud and concrete. Alternatively, floating plugs of approved specification may be used before the first charge of concrete.
- (g) The tremie pipe should always be kept full of concrete and should always remain at least one meter into the concrete in the bore hole with adequate margin against accidental withdrawal of tremie pipes. The tremie pipe shall not be withdrawn until the completion of concreting. At all times a sufficient quantity of concrete shall be maintained within the pipe to ensure that the pressure from it exceeds that from the seepage water.
- (h) Spot measurements shall be taken at suitable intervals to check that the tremie pipe has an adequate penetration into previous concrete.

- (i) Concreting of the pile shall be in one single and continuous operation. In case of long piles of large diameter, large size mixers or more mixers shall be used so that the entire concreting operation is completed in not more than two hours.
- (j) The top of concrete in a pile shall be brought above the cut-off level since the top concrete is loose and is weak because of contamination with water/drilling mud. This ensures good concrete at the cut-off level.
- (k) Cut off level (COL)

Cut off level of piles (50mm inside the pile cap) shall be indicated in working drawings or as indicated by the Engineer.

The top of concrete in pile shall be brought above the cut off level to remove all laitance & weak concrete and to ensure good concrete at cut off level.

As general guidelines, for cut off level up to 1.5m below working level, the concrete shall be cast of 300mm above COL. For each additional 0.3m increase in depth of COL an additional coverage of 50mm shall be required. In the circumstance where COL is below ground water level, the need to maintain a pressure should be observed & accordingly length of extra concrete above COL shall be determined by the Contractor and approval of Engineer obtained before concreting.

In case of concrete being placed by tremie method and pile cut off level less than 1.0meter below the ground level, concrete shall be cast to the piling platform level to permit overflow of concrete for visual inspection. In case COL of pile is more than 1.0 meter below working level then concrete shall be cast to a minimum of one meter above COL. Before concreting contractor shall obtain the approval of the Engineer of the height above COL up to which the concrete is to cast.

Any defective concrete in the head of the completed pile shall be cut away and made good with new concrete.

- (l) When a casing is being extracted a sufficient quantity of concrete shall be maintained within the bore to ensure the pressure from external ground water and soil is adequately exceeded by the pressure of concrete. Otherwise necking of the pile may result. A minimum embedment of 1.5 to 1.8 m is required.
- (m) No concreting shall be placed in the bore once the bottom of the casing has been lifted above the top of concrete.
- (n) After each pile has been cast any empty bore shall be protected and carefully backfilled as soon as possible with approved materials.
- (o) Complete boring and concreting records shall be submitted to the Engineer for each pile. The records shall include the duration of boring, concreting, tremie lengths (individual and cumulative), tremie pipe lengths removed, theoretical sounding, actual sounding, actual lengths of pile concreted and the volume of concrete placed, cut off level, founding levels etc. For piles with temporary casings, records of sequence of casing withdrawal and levels of concrete before and after withdrawal shall also be

included in the reports. Data about used polymer slurry and its specific gravity in the hole, before pouring of concrete shall also be placed on record.

8.1.5 Alignment of Piles:

- i) Piles shall be installed as accurately as possible according to the drawings either vertically or to the specified batter. All deviations will be measured at the cut off level of the piles. The deviation from the true axis shall not be more than 1.5% for vertical piles and 4% for rake piles. Piles should not deviate in location by more than 75mm when used in groups. For single or 2 piles used under columns, deviation shall not be more than 50mm. If the deviation is more than the permissible limits as above, the contractor shall take the Engineer's approval with suitable modifications, as required, before starting the pile cap work.
- ii) The Contractor shall maintain a record of actual pile locations (including any deviations) in the form of drawing and submit the information to the Engineer at regular intervals.

8.1.6 Pile Cap:

Pile caps shall be of reinforced concrete. A minimum offset of 250 mm shall be provided beyond the outer faces of the outer most piles in the group. If the pile cap is in contact with earth at the bottom, a leveling course of minimum 100 mm thickness of PCC of grade M15 shall be provided or as shown in the drawings.

The attachment of the pile head to the cap shall be adequate for the transmission of loads and forces. A portion of pile top may be stripped of concrete and the reinforcement anchored into the cap. Manual chipping may be permitted after three days of pile casting while pneumatic tools for chipping shall not be used before seven days after pile casting. The top of pile after stripping shall project at least 50mm into the pile cap. Concreting of the pile cap shall be carried out in dry conditions. All the operations and tools required for making the pile in dry condition is included in the item.

The road surface after casting of pile cap should be repaired immediately. If the surface is not repaired immediately, penalty will be imposed as decided by the Engineer.

8.1.7 Testing of Piles:

- i) The load tests shall be in accordance with the Indian Standard Code of Practice for Design and Construction of Pile Foundations IS 2911 (Part IV) Load Tests on Piles. For initial load test, test load will be 2.5 times the theoretical designed capacity of pile. For initial load, test arrangement to be designed shall also cater for additional 25% above test load and nothing extra will be paid on this account. Permissible stresses in test arrangement (steel truss or plate girder) to cater for test load plus additional 25% load shall be within permissible stresses as per IS: 800 (as for permanent structure). For test frame, steel of Grade –B conforming to IS: 2062 shall be used.
- ii) Engineer will decide the locations of initial and routine horizontal and vertical load test. One no. initial load test is to be performed in each km for each diameter of pile being used

in viaduct. The contractor shall undertake test piles required for initial pile load test in the initial stages of work using the same methodology and equipment which will be subsequently used for working piles. These tests shall be undertaken well in advance of working pile. No working pile would be allowed to undertaken till initial satisfactory initial pile load tests have been completed.

Non-granting of permission for pile/ pile cap by Engineer in such respect will not be considered as reason for delay or any claim thereof. The test arrangement to be employed shall be of nature which is quick to install and remove and easily transferable. At every one Kilometre of viaduct initial load test both vertical and horizontal, shall be performed by the contractor for each type of pile, also one initial load test both vertical and horizontal per station shall be performed by the contractor for each type of pile. Further, minimum 20% of the initial load test on piles in Viaduct and Station shall be carried out through cyclic load test.

- iii) Routine horizontal & vertical load tests are performed as a check on the load carrying capacity and settlements of the pile foundations. At least one routine test shall be performed for every 100 piles unless otherwise specified by the Engineer. Initial and routine vertical and horizontal load test shall be conducted on different piles.
- iv) The Contractor shall give the Engineer at least 48 hours notice of the commencement of construction of these piles which are to be subjected to Initial Tests.
- v) The load tests shall not normally be conducted unless the concrete is at least 28 days old. However, in special circumstances, permission can be given by Engineer for prior testing.
- vi) All testing shall be done under the direction of experienced personnel conversant with the equipment and the testing procedure.
- vii) Before the commencement of the tests all the particulars regarding the test pile including boring data and concrete cube strengths shall be made available at site and shall form a part of the test report.
- viii) On completion of each load test the Contractor shall submit a report of the load test which shall include the following information.
 - a) Description of soil conditions, ground water table, actual boring and installation records, concrete cube test results.
 - b) Method of load application
 - c) Load settlement readings during loading and unloading
 - d) Time load-settlement curve
 - e) All other observation relevant to the test being conducted.
- ix) Integrity test

Two types of pile integrity tests will be performed:

Dynamic Integrity Test:

The Dynamic Integrity test using pile driving analyser or approved equivalent for pile integrity shall be performed on all the piles. The top of the pile shall be made accessible, chipped off up to hard concrete, levelled by trimming it back as far as practicable. The reinforcing bars of the piles tested shall be bent sideways. The test shall be performed after removal of bad/weak concrete at top so that the wave propagation is steady through hard concrete. The test shall be carried out at minimum 3 locations on each pile in such a way that the entire cross section of the pile is evenly covered. The test shall be conducted with a minimum age of concrete of 15 days. A specialist approved agency shall be employed for the test and the tests shall generally be as per recommendations of the agency unless directed by the Engineer. A complete report indicating the graphical display of wave propagation under each flow shall be submitted along with interpretation of results showing discontinuities, cross-sectional changes or material changes if any are to be co-related with Site data.

Cross Sonic Logging Test

'Cross Sonic Logging' test shall be conducted to verify the structural integrity of piles by means of the measurement of the time travel of a sound waveform an emitter to a receiver through the concrete of a pile. The emitter and the receiver shall generally be at the same level. Cross-hole Sonic logging testing is compulsory for 25% of piles with 100% of piles installed with recess tubes and equipped for testing. The Engineer will randomly select the locations for conducting tests on 25% piles.

a) Sonic Logging Tubes**Material**

Every pile must be provided with sonic logging tubes cast into it. The tubes shall be manufactured from steel of 50mm ID and 1mm thick. The tubes assembly shall be manufactured in a factory which is ISO 9001 (or higher revision) certified. To form single tube the pipes to be connected with an enlarged end Bell Mouth – push fit arrangement provided with rubber gasket only. The bell mouth should have serrations so as to ensure the proper engagement of joint and avoid any leakages. The bell mouth connection should be provided strictly with rubber gasket to ensure a concrete-tight joint to maintain the tube integrity and prevent entry of foreign material. PVC or any kind of plastic material is strictly prohibited as it cannot resist great compression pressure. The expansion factor between PVC and concrete is not the same (unlike steel and concrete). When the concrete is setting, its temperature goes up and leads to the expansion of the PVC. Once the concrete has set and the temperature goes back to normal there will be a void between the tube and the concrete: this will lead to bad reading of the test and the rejection of the pile. One tube in each pile should be installed of internal diameter 75mm in order to allow for coring of the concrete at the base of the pile.

Tests to be conducted for Sonic Tubes assembly and desired results

The entire lot supplied to site shall be batch-tested for following test with pressure test conducted on 100% of sonic tubes. The supplier shall have in-house testing facility so as to ensure 100% pressure test and batch-test is conducted on sonic tubes before supply to site. The Sonic Tubes assembly shall be tested for following tests –

1. External Pressure Test –

The 50 mm diameter, 1 mm thickness should be applied with external pressure upto 5 Mpa.

Following are the desired results –

Description	Pressure in Mpa	Hold Time	Desired Results
Sonic Tubes Diameter 50 mm X 1.0 mm Thick	≥ 5 Mpa	≥ 60 Sec	No Leakages from Inner Surface of Tubes and No Distortion of Tubes

100% sonic tubes to be tested prior despatch

2. Pull Out Test for Tubes-

Description	Tensile Force to be applied	Desired Results
Sonic Tubes Diameter 50 mm X 1.0 mm Thick	≥ 0.5 KN	No Distortion found and should withstand the test load of ≥ 0.5 KN

Minimum 3 samples to be tested of the lot being despatched.

3. Pull Out Test for tubes ‘ Fixing Ears’

Description	Tensile Force to be applied	Desired Results
Sonic Tubes Diameter 50 mm X 1.0 mm Thick	≥ 0.5 KN	No Distortion found and should withstand the test load of ≥ 0.5 KN

Minimum 3 samples to be tested of the lot being despatched.

4. Crush Test –

For 50 mm diameter and 1 mm tick Tube following is the criteria for Crush test

Sr. No.	Descriptions	Test	Desired Results
1	Direction tube	1500 mm	1. No Cracks 2. After test 30 mm Steel ball can go through the tubes.
2	Drop Weight	4000 + 150/-0g	
3	Diameter of Drop	50.03 mm	

Minimum 3 samples to be tested of the lot being despatched.

Installation

The agency supplying sonic tubes should submit a detailed installation methodology and conduct a demo for one pile before being implemented for all piles.

Frequency

Four tubes shall be required for each pile, any other configuration is not allowed.

b) Sonic Logging Equipment

The equipment shall be properly maintained and calibrated. Where necessary, means shall be provided to centralise the probes within the tubes, so that variation in the separation of the emitter and receiver resulting from clearance between the probes and the tubes does not occur.

c) Test Procedure

The tubes shall be filled with water. The tests shall be repeated for each pair of tubes, i.e. three runs for a pile with three tubes and six runs for a pile with four tubes.

d) Analysis of Test Results

A report shall be prepared for each pile tested. The photographic record of the oscilloscope displays shall be analysed in detail. Any deviation from the record to be expected from a pile constructed entirely of sound concrete and without defect shall be reported. The report shall indicate the nature, location and severity of the defect and recommendations shall be made for further testing. The implication of the existence of the defect on the performance of the pile shall be evaluated.

e) Submission of Results

Immediately after testing, a signed copy of all the raw test data of a pile shall be given to the Engineer. A test report shall be submitted to the Engineer within 7 days after testing.

f) Anomalous Sonic Logging Test Results

The piles with anomalous sonic logging results shall be rejected at the Engineer discretion unless the Contractor is able to demonstrate that the pile integrity is acceptable through proof coring.

g) Grouting of Pile after Testing

Upon completion of sonic logging test, the access tubes, if any, shall be grouted up.

8.2 WELL FOUNDATION:**8.2.1 Description**

This work shall consist of construction of well foundation, taking it down to the founding level through all kinds of sub-strata, plugging the bottom, filling the well with approved material, plugging the top and providing a well cap in accordance with the details shown on the drawings and as per the latest MORTH Specifications, or as directed by the Engineer.

8.2.2 General

- i) Wells may have a circular, rectangular or D-shape in plan and may consist of one, two or more compartments in plan
- ii) In case of well foundations of size larger than 12 m diameter, supplemental construction specifications will be necessary.
- iii) The subsurface geotechnical investigations to be carried out before commencement of work of well foundation shall be in accordance with relevant clauses of Section 2400 of MORTH specifications.
- iv) In case ballasting is anticipated for facilitating sinking through difficult strata such as boulders and rock, special protective/strengthening measures for the curb and steining of the well will be required.
- v) Pneumatic sinking may have to be resorted to in cases where the well has to be sunk through rock/hard strata or where there are obstacles such as tree trunks, large sized boulders etc., which cannot be removed by open dredging. In such cases, the decision regarding adoption of pneumatic sinking shall be taken on the basis of results of confirmatory bores and as directed by the Engineer.

8.2.3 Setting Out and Preparations for Sinking

- i) Necessary reference points shall be accurately fixed to mark x-x axis along the direction of traffic and y-y axis normal to direction of traffic. Such reference points shall be away from the zone of blow-ups or possible settlements which may result from well sinking operations and shall be connected to the permanent stations with the base line on the banks. The center of the individual wells shall be marked with reference to these stations. The distances between the wells shall be checked with the help of accurate tapes and precision instrument. .
- ii) A temporary bench mark shall also be established near the well foundation, away from the zones of blow-ups or possible settlement. The bench mark shall be checked regularly with respect to the permanent bench mark established at the bridge site.

- iii) For well located in the banks of the river or in the dry area, the bed may be prepared by excavating the soil up to 1.5 m followed by leveling and dressing before placing the cutting edge.
- iv) For wells which are to be located in water, a sand island shall be constructed for laying the cutting edge and well curb. Sand islands are practicable for water depths up to 5 m under stable bed soil conditions. Where the depth of water is greater than 5m or in fast flowing rivers or for locations where soil is too weak to sustain sand island, floating caissons may have to be adopted.

The plan dimensions of sand islands shall be such as to have a working space of at least 2 m all around the steining. Sand islands shall be maintained to perform their functions, until the well is sunk to a depth below the bed level at least equal to the depth of water at that location.

The Sand Island shall be held in position and protected against scour by means of wooden ballies properly braced or sheet piles. the top level of sand island to be decided by the engineer, shall be sufficiently above the prevailing water level so that it is not affected by wave action.

v) Equipment

Equipment shall be deployed for construction of well foundation as required and as directed by the Engineer. Generally, the following equipments may be required for the work:

- a) Crane with grab buckets - capacity 0.5 to 2.0 cum
- b) Submersible pumps
- c) Air compressors, air locks and other accessories where pneumatic sinking of well is anticipated
- d) Chisels of appropriate sizes
- e) Aqua-header for cutting rocky strata
- f) Diving helmets and accessories
- g) Batching plants for concrete production
- h) Equipments for transportation, placing and compaction of concrete.

8.2.4 Cutting Edge

- i) The cutting edge shall be made from structural steel sections conforming to Section 1900 of MORTH specifications and shall be strong enough to facilitate sinking of the well through the type of strata expected to be encountered. The weight of the cutting edge shall not be less than 40 kg per metre length. It shall be properly anchored into the well curbs as shown on the drawing.
- ii) When there are two or more compartments in a well, the bottom of the cutting edge of the inner walls of such wells shall be kept at about 300 mm above that of outer walls.
- iii) In V shaped cutting edge, the inclined plate should meet the vertical plate in such a way that full strength connection by welding is feasible.
- iv) The parts of cutting edge shall be erected on level firm ground about 300mm above the prevalent water level. Temporary supports shall be provided to facilitate fabrication and maintaining the assembly in true shape. The fabrication may be carried out in the shop or at

site. Steel sections shall not be heated and forced into shape. However, “V” cuts may be made in the horizontal portion, uniformly throughout the length, to facilitate cold bending. After bending, such “V” cuts should be closed by welding. Joints in the lengths of structural sections, unless otherwise specified shall be filler welded using single cover plate to ensure the requisite strength of the original section.

8.2.5 Well Curb

- i) The well curb shall be such that it will offer minimum resistance while sinking, but will be strong enough to be able to transmit superimposed loads from the steining to the bottom plug. The shape and the outline dimension of the curb shall be as shown in IRC:78. The internal angle of the curb shall be about 30 degree to 37degree depending upon geotechnical data of strata through which the well is to be sunk.
- ii) The well curb shall be in reinforced concrete having concrete mix in accordance with Table 1700-2 & 1700-3 of MORTH specification and with the minimum reinforcement of 72 kg/cum excluding bond rods. The outer face of the curb shall be vertical. The steel shall be suitably detailed to prevent spreading and splitting of curb during sinking. The outer face of the curb shall be vertical. The bottom ends of vertical bond rods of steining shall be fixed securely to the cutting edge with check nuts or by welds. Concreting of the well curb shall be done in one continuous operation.
- iii) Steel formwork for well curb shall be fabricated strictly in conformity with the drawing. The formwork on outer face of curb may be removed within 24 hours after concreting. While that on inner face shall be removed only after 72 hours.
- iv) In case blasting is anticipated, the inner faces of the well curb shall be protected with the steel plates of thickness not less than 10 mm up to the top of the well curb. If it is the considered necessary, the thinner face of the steining may also be protected with steel plates of 6mm thickness up to a height of 3m above the top of the well curb or as specified by the engineer. The curb as well as 3m height of steining above the curb, shall be provided with additional hoop reinforcement of 10mm diameter bars at 150mm spacing. Additional hoop reinforcement shall be provided in the steining for the further height of up two times the thickness of steining above the plates, so as to avoid the cracking which may arise on account of sudden change in effective section due to curtailment of plate.

8.2.6 Floating Caissons

- i) Floating caissons are generally fabricated at or near the banks on dry land or in dry docks and then towed into position. For floating caissons, a detailed method statement covering fabrication, floating and sinking operations, shall be prepared and furnished to the Engineer. Such statement shall include the total tonnage of steel involved, fabrication and welding specifications, list of materials and plant and a description of operations and man power required for the work.
- ii) Floating caissons shall be of structural steel conforming to Section 1900 of MORTH Specifications. The joints of the fabricated structure shall be absolutely leak-tight and shall be checked against leakage before floating and being towed to site. The reinforcement of the curb and steining of the well shall be fixed inside the shell by welding before the caisson is floated. Stability of floating caissons shall be ensured against overturning and capsizing under the action of water current, wave pressure and wind while being towed and kept in position. To maintain the stability of the shell while being floated, it may be provided with ballast in the form of water filling up to required level or filling with small amount of concrete. It shall be

ensured that the draught of the floating caisson is always less than the depth of water available, so as to facilitate its smooth hindrance-free movement while being towed.

- iii) Height of caisson shall be planned to ensure that at any given time, at least one metre of the shell shall be above water level. In case the location is affected by the action of waves, the height shall be suitably increased to avoid water spilling into the caisson. In case the bed has soft soil, the caisson shall be provided with 3 to 5 metres of additional height, as it may sink by itself after grounding in bed. Simultaneous sinking and concreting is required to prevent caisson from tilting. In sandy stratum especially with strong water current, appropriate additional height of caisson is necessary for accommodating local scour.
- iv) The floating caisson shall be held in position against untoward movement by wire ropes/chains, using winches mounted on stationary suitable platforms/buoys or similar anchoring systems. Anchoring in minimum three directions, shall be provided to prevent unacceptable longitudinal and lateral movement. The anchoring system shall permit small movements in order to facilitate correct positioning of the caisson at the exact location of the well and until the stage when it is just getting grounded. Special care is necessary where variation in water level is frequent, e.g. in tidal zones.
- v) After being held in correct position, concreting of the floating caisson shall be commenced. The concrete mixed in batching plants, shall be carried to the floating caisson on barges and placed in position through concrete pumps or tremie. When large volumes of concreting are involved, the batching plant concrete pump, crane etc, may all be mounted on a barge kept in the vicinity of the caisson. As no vibration is possible inside the shell, it shall be ensured that the concrete has a slump of 150 to 200; alternatively, self-compacting concrete can be used. The concrete shall be carefully placed uniformly all around the caisson so that it settles vertically without any tendency to tilt.

8.2.7 Well Steining

- i) The dimensions, shape, concrete strength and reinforcements of the well steining shall strictly conform to those shown on the drawings. The formwork shall preferably be of M.S. sheets shaped and stiffened suitably. In case timber forms are used, they shall be lined with plywood or M.S. sheets.
- ii) The height of first lift of steining to be cast above the well curb shall not be more than 2m and subsequent lifts shall not exceed the diameter of the well or the depth of well to be sunk below the bed level at any time. For stability, the first lift of steining shall be cast only after sinking the curb at least partially. Concreting of steining may be carried out in subsequent lifts of about 2 to 2.5 m. Attempts should be made to minimize the number of construction joints. The concreting layers shall be limited to 450 mm restricting the free fall of concrete to not more than 1.5 m. Laitance formed at the top surface of a lift shall be removed to expose coarse aggregates before setting of concrete at the proposed construction joint. As far as possible, construction joints shall not be kept at the location of laps in the vertical steining bars.
- iii) The steining of the well shall be built in one straight line from bottom to top such that if the well is tilted, the next lift of steining will be aligned in the direction of the tilt. The work will be checked carefully with the aid of straight edges of lengths approved by the Engineer. Plumb bob or spirit level shall not be used for alignment. After sinking of a stage is complete, damaged portions if any, of steining at top of the previous stage shall be properly repaired before constructing the next stage.

- iv) For measuring the height of steining, it shall be marked with at least 4 gauges, two in traffic direction and two normal to traffic direction, distributed equally on outer face of the well. The marking shall be in form of a 100mm wide strip painted on the steining, with every metre marked in black paint. Marking of the gauges shall be done carefully and accurately with a steel tape, starting with zero at bottom of the cutting edge. The marking shall be continued upwards as each lift of steining is added.
- v) After reaching the founding level, the well steining shall be inspected to check for any damage or cracks. The Engineer will direct and the Contractor will execute the remedial measures required, before acceptance of the well steining. In case the well is found to be unacceptable even after remedial measures are carried out, then the well shall stand rejected.

8.2.8 Well Sinking

8.2.8.1 General

The well shall as far as possible be sunk true and vertical through all types of strata. No well shall be permitted to be placed in a pre-dredged hole.

Sinking or loading of the well with kentledge shall be commenced only after the steining has been cured for at least 48 hours or as specified in the drawings.

The well shall be sunk by excavating material uniformly from inside the dredge hole. Using cranes with grab buckets of appropriate capacity. Use of water jetting, explosives and divers may be adopted for sinking of wells through difficult strata with prior approval of the Engineer. Well sinking can also be carried out by jack down method.

Normally dewatering of well should not be permitted as a means for sinking the well. It shall never be resorted to if there is any danger of sand blowing under the well. Dewatering shall however be done when well is to be founded in rock. Pneumatic sinking may have to be resorted to where obstacles such as tree trunks, large size boulders, etc. are met or when there is hard strata which cannot be removed by open dredging. The necessity for adopting pneumatic sinking shall be decided by the Engineer.

Complete history of sinking of each well given details of concreting, sinking and problems met, if any, shall be maintained in the format given in Appendix 1200/I of MORTH specification.

8.2.8.2 Sand blows in wells

Dewatering shall not be carried out, if sand blows are expected. Any equipment or men working inside the well shall be brought outside the well as soon as there are any indications of sand blow. Sand blow can often be minimized by keeping the level of water inside the well higher than the water table and also by adding heavy kentledge.

8.2.8.3 Use of Kentledge as Sinking Load

Kentledge shall be placed in an orderly and safe manner on the loading platform and in such a way that it does not interfere with the excavation of the material from inside the dredge hole and also does not in any way damage the steining of the well.

Where tilts has occurred or there is a danger of well developing a tilt, the position of the load shall be regulated in such a manner as to provide greater sinking effort on the higher side of the well.

8.2.8.4 Use of Water Jetting

Water jetting can be used to facilitate sinking of wells through clay/hard strata. The decision regarding use of water jetting shall be taken at the design stage itself, based on geotechnical investigations which may be indicating presence of hard, clayey strata. For carrying out water jetting, the required number of steel pipes of 40 to 50 mm diameter shall be embedded in the steining of the well, spaced evenly around its periphery. The bottom of the steel pipe shall taper down to a nozzle exiting in the sloping face of the well curb. The diameter of the nozzle shall be 6 mm. The steel pipe shall be kept about 1 m above the top of each lift of steining, so that it can be extended by means of suitable couplers before the next lift of steining is cast. When the well reaches the hard strata and the need for water jetting arises, the tops of the embedded pipes shall be connected to pumps of required capacity for pumping in water at high pressure. The water jet issuing from the nozzle of the pipe under high pressure, cuts through the hard material and loosens it, permitting the well to sink at a faster rate than would otherwise have been possible. When water jetting is to be adopted, the Contractor shall furnish a method statement for approval of the Engineer covering all aspects of the work including the number, capacity and location of the high pressure pumps and other ancillaries required for executing the work.

8.2.8.5 Use of Jack Down Method

The jack down method of sinking shall be adopted as per requirement or as directed by the Engineer. The first step shall be to install ground anchors outside the periphery of the well. The number, location and depth of ground anchors are decided based on the properties of the surrounding soil to develop the necessary resisting force through skin friction. The drill holes of about 150 mm diameter along with casings shall be taken down to a depth of about 20 m or more below the founding level of the well, depending on requirements of design. After the holes have been drilled to the required depth, prestressing strands of adequate diameter and capacity are cut to the desired length and lowered into the holes. The holes shall then be grouted with cement slurry with non-shrink additive. Once the grouting is completed till the ground level, the casing is removed. The removal of the casing shall be done before the grout sets. In case rock is met with, the anchors shall be socketed into rock.

Heavy duty pressurization girders fabricated of steel, shall be placed over stools resting on the steining of the well, against which the hydraulic jacks connected to the ground anchors, can exert pressure to push the well down. The hydraulic jacks shall be of capacity 500 T or more as per requirement. Before applying pressure from the jacks, 1 m deep sump is created inside the well by dredging. Pressure on different jacks is exerted in such a manner as to neutralize any tendency of the well to tilt. With the use of the jacks and controlled dredging, high rates of sinking can be achieved and the chances of sand blowing can also be reduced.

For use of jack down method of sinking, the Contractor shall furnish a method statement for approval of the Engineer, giving full details of construction of ground anchors, fabrication of pressurizing girder, type, number and capacity of jacks to be used, method of dredging and application of jack down force and all other relevant aspects for proper execution of the work.

8.2.8.6 Use of Explosives

Mild explosive charges may be used as an aid for sinking of the well. All prevalent laws concerning handling, storing and using of explosives shall be strictly followed. All safety

precautions shall be taken as per IS:4081 "Safety Code for Blasting and related Drilling Operations" to the extent applicable, whenever blasting is resorted to.

When the likelihood of resorting to blasting is advance, protection of the bottom portion of the well shall be done as per Clause 1205.4 of MORTH specification.

Blasting of any sort shall be done only with prior permission and in the presence of the Engineer. Blasting shall not be done before the concrete in the steining has hardened sufficiently and is more than 7 days old.

After blasting operations are completed, the well curb and steining should be examined for any cracks and remedial measures taken if required.

If blasting has been done after the well has reached the design foundation level, normally 24 hours shall be allowed to lapse before the bottom plug is laid.

The charges shall be exploded well below the cutting edge by making a sump so as to avoid chances of any damage to the curb or to the steining of the well. A minimum sump of 1 m depth should be made before resorting to blasting. Use of large charges, 0.7 kg or above, may not be allowed, except under expert direction and with the permission of the Engineer. The pattern of charges may be suitably arranged with delay detonators so as to reduce the number of charges fired at a time. The burden of the charge may be limited to 1 m and the spacing of holes may normally be kept as 0.5 m to 0.6 m.

There should be no equipment inside the well nor shall there be any worker in the close vicinity of the well at the time of exploding the charges.

If rock blasting is to be done for seating of the well, the damage caused by flying debris should be minimised by covering blasting holes with rubber mats before detonating the charge

8.2.8.7 Use of Divers

Divers may be used for removal of obstructions during sinking, carrying out rock blasting and for inspection. All safety precautions shall be taken as per any acceptable safety code or any statutory regulations in force, when divers carry out work under water in the well.

Only persons trained in diving operations shall be employed after being certified fit for diving by an approved doctor. They shall work under expert supervision. The raising of the diver from the bottom of wells shall be controlled so that decompression rate conforms to the rate as laid down in relevant regulations.

The diving and other equipment shall be of acceptable standard and certified to this effect by an approved independent agency. They shall be well maintained as per requirements for safe use,

Arrangement of ample supply of low pressure clean cool air shall be ensured through an armoured flexible hose pipe. Standby compressor shall be provided to cover the contingency of breakdown of the compressor.

Separate high pressure connection shall be made for use of pneumatic tools. Electric lights where provided shall be at 50 volts (maximum).

8.2.8.8 Use of Pneumatic Sinking

i) General

The Engineer shall familiarize himself with particular reference to caisson diseases and working of the medical air-lock. A doctor competent to deal with cases of "Caisson Diseases" or other complications arising as a result of working under high pressure, shall be stationed at the construction site when pneumatic sinking is under progress.

The contractor shall provide complete facilities including the issuing of orders to ensure strict enforcement of the requirements outlined as per MORTH Specifications.

Safely provisions as contained in IS:4138/ MORTH Specifications shall be strictly followed.

Pneumatic sinking shall be restricted to a depth of 30.0 m. below ground level

ii) Man-Locks and Shafts

Locks, reducers, and shaft used in connection with caissons shall be of riveted construction throughout. The material used in their manufacture shall be steel plate with thickness not less than 6 mm.

Shafts shall be subjected to hydrostatic or air pressure test of at least 0.5 MPa, at which pressure they shall be tight. The pressure at which testing has been done shall be clearly and visibly displayed.

The Shaft shall be provided, with a safe, proper and suitable staircase for its entire length including landing platforms which shall be not more than 6 m apart. Where this is impracticable due to space constraint, suitable ladders along with landing platforms shall be installed. These shall be kept clear and in good condition at all times and shall be constructed, inspected and maintained to the entire satisfaction of the Engineer.

A 1.0 m wide platform with 1.0 m high railing shall be provided all round the caisson air locks.

Where 15 or more men are employed, caissons shall have two locks, one of which shall be used as a man lock.

Locks shall be located so that the lowest part of the bottom door shall not be less than 1 m above high water level.

The supply of fresh air to the working chamber shall at all times be sufficient to permit work to be done without any danger or excessive discomfort. All air supply lines shall be supplied with check valves and carried as near to the face as practicable.

A man-lock shall be used solely for the compression or de-compression of persons, and not for the passage of plant and material and shall be maintained in a reasonably clean and sufficiently warm state. However, any hand tool or hand instruments used for the purpose of the work may be carried into the man-lock.

Where it is not reasonably practicable to provide a separate man-lock for use by persons only, the lock when it is in actual use for compression or decompression of a person or persons shall not be put, simultaneously, to any other use and shall be in a reasonably clean and sufficiently warm state.

iii) Valves

Exhaust valves shall be provided, having risers extending to the upper part of the chamber. These shall be operated, whenever necessary specially after a blast. Precautions shall be taken that men are not allowed to resume work after a blast until the gas and smoke are cleared.

iv) Medical supervision and certification

Every employee absent from work for 10 or more consecutive days due to illness or any other disability, shall be required to pass the regular physical examination by the doctor before being permitted to return to work.

After a person has been employed continuously in compressed air for a period of 2 months, he shall be re-examined by the doctor and shall not be permitted to work until such re-examination has been made and the report is satisfactory.

No person known to be addicted to the excessive use of intoxicants shall be permitted to work in compressed air.

The doctor shall, at all times, keep a complete and full record of examination made by him, which shall contain dates of examinations, a clear and full description of the persons examined, his age and physical condition at the time of examination and a statement as to the period for which he has been engaged in such work. Records shall be kept at the place where the work is in progress and shall be subject to inspection by authorized officers.

Every man lock shall always have a doctor or a responsible person in attendance. In case the person in charge is not a doctor, he must have positive means of promptly communicating with and securing the services of a competent doctor in case of emergency. Such arrangements shall invariably be subject to the approval of the Engineer.

All cases of compressed-air illness shall be reported and copies of all such reports shall be kept in file at the place of work.

v) Lighting

All lighting in compressed air chambers shall be operated only by electricity. Two independent electric lighting systems with independent sources of supply shall be used. These shall be so arranged that the emergency source shall become automatically operative in case of failure of the regularly used source.

The minimum intensity of light on any walkway ladder, stairway, or lower working level shall be one-quarter (1/4) candlepower. In all work places, the lighting shall always be such as to enable workmen to see their way about clearly. All external parts of lighting fixtures and electrical equipment lying within 2.5 m above the floor shall be constructed of non-combustible, non-absorbing insulating materials. If metal is used, it must be effectively earthed. Portable lamp shall have non-combustible, non-absorbing insulating sockets, approved handles, basket guards and approved cables. The use of worn out or defective portable and pendant conductors is prohibited.

vi) Safety against fire hazard

No oil, gasoline, or other combustible material shall be stored within 30 m of any shaft, caisson or tunnel opening. It shall be positively ensured that leaking flammable liquids do not flow into such areas. Oil may be stored in suitable tanks in isolated fireproof buildings, which are not less than 15 m away from any shaft, caisson, or tunnel opening or any building directly connected thereto.

Where feasible, a fire hose connected to a suitable source of water shall be provided at the top of every caisson. Where fire mains are not accessible, water shall be stored in tanks near the top of every caisson, provided fire pails or suitable pumps are kept available. Approved fire extinguishers shall also be provided.

vii) Sanitation

Properly heated, lighted and ventilated dressing rooms shall be provided for all employees engaged in compressed air work. Such rooms shall contain lockers and benches and be open and accessible to person during intermissions between shifts. Adequate toilet accommodation of one for every twenty five employees shall be provided.

Care shall be taken to keep all parts of the caissons and other working compartments, including locker rooms, dry rooms, rest rooms and other equipment in good sanitary condition and free from refuse, decaying or other objectionable matter.

Smoking shall be strictly prohibited and matches and smoking materials shall not be allowed to be brought into the locker rooms.

A separate dry room shall be provided where working clothes may be dried in a reasonable time.

viii) Protection against gases

In all cases where release of gas is expected as in the case of sinking through alluvium impregnated with decayed vegetable matter, the use of Davy Safety Lamp shall be compulsory.

ix) Additional safety provisions

- a) The weight of the pneumatic platform and that of steining and kentledge, if any, shall be sufficient to resist the uplift from air inside, skin friction being neglected in this case. If at any section, the total weight acting downwards is less than the uplift pressure of air inside, additional kentledge shall be placed on the well.

If it is not possible to make the well heavy enough during excavation, "blowing down" may be used. The men should be withdrawn and air pressure reduced. The well should then begin to move with small reduction in air pressure. "Blowing down" should only be used when the ground is such that it will not heave up inside the chamber when the pressure is reduced. When the well does not move with the reduction in air pressure, kentledge should be added. "Blowing down" should be in short stages and the drop should not exceed, 0.5 m at any stage. To control sinking during blowing down, use of packing is recommended.

- b) The pneumatic sinking plant and other allied machinery shall not only be of proper design and make, but also shall be operated by competent and well trained

personnel. Every part of the machinery and its fixtures shall be minutely examined before installation and use. Availability of appropriate spares, standbys, safety of personnel as recommended in IS:4138 for working in compressed air must be ensured at site. Codes for safety and for working in compressed air and other labour laws and practices prevalent in the country, as specified to provide safe, efficient and expeditious sinking shall be followed.

- c) Inflammable materials shall not be taken into air locks and smoking shall be prohibited. Wherever gases are suspected to be issuing out of dredge hole, the same shall be analysed by trained personnel and necessary precautions adopted to avoid hazard to life and equipment.
 - d) Where blasting is resorted to, it shall be carefully controlled and all required precautions shall be observed. Workers shall be allowed inside after blasting only when a competent and qualified person has examined the chamber and steining thoroughly and found the same to be safe.
- x) Precautions during sinking
- a) When the wells have to be sunk close to each other and clear distance between them is less than the diameter of wells, sinking shall be taken up on all wells and they shall be sunk alternately so that sinking of wells proceeds uniformly. Simultaneous and even dredging shall be carried out in the wells in such a manner that the difference in the levels of the sump and cutting edge in the adjacent wells does not exceed half the clear gap between them. Plugging of all the wells shall be done together.
 - b) During sinking of dumb-bell or double D-shaped wells, the excavation in both the dredge holes should be carried out simultaneously and equally.
 - c) Bore chart shall be referred to constantly during sinking for taking adequate care while piercing different types of strata. The type of soil as obtained during the well sinking should be compared with bore chart so as to take prompt decisions.
 - d) Before seasonal floods, all wells on which sinking is in progress shall be sunk to sufficient depths below the designed scour level. Further, they shall be temporarily filled and plugged so that they do not suffer any tilt or shift during the floods.
 - e) All necessary precautions shall be taken against any possible damage to the foundations of existing structures in the vicinity of the wells, prior to commencement of dredging from inside the well.
 - f) The dredged material shall not be allowed to accumulate around the well. It shall be dumped and spread, as far away as possible, and then continuously and simultaneously removed, as directed by the Engineer. In case the river stream flows along one edge of the well being sunk, the dredged material shall not be dumped on the dry side of the bank but on the side on which the river current flows.
 - g) Very deep sump shall not be made below the well curb, as it entails risk of jumping (sudden sinking) of the well. The depth of sump shall be generally limited to one-sixth of the outer diameter/least lateral, dimension of the well in plan. Normally the depth of sump shall not exceed 3.0 m below the level of the cutting edge unless otherwise specially permitted by the Engineer.
 - h) In case a well sinks suddenly with a jerk, the steining of the well shall be examined to the satisfaction of the Engineer to see that no damage has occurred to it.

- i) In pneumatic sinking, the well shall not, at any time, be dropped to a depth greater than 500 mm by the method of "blowing down".
- j) Dewatering shall be avoided if sand blows are expected. Any equipment and men working inside the well shall be brought out of the well as soon as there are any indications of a sand-blow.
- k) Sand blowing in wells can often be minimized by keeping the level of water inside the well higher than the water table and also by adding heavy kentledge.
- l) In soft strata prone to settlement/creep, the construction of the abutment wells shall be taken up only after the approach embankment for a sufficient distance near the abutment, has been completed

8.2.8.9 Tilts and Shifts

Unless otherwise specified, the tilt of any well i.e. its inclination from the vertical, shall not exceed 1 (horizontal) in 80 (vertical). The shift of the well i.e. the horizontal displacement of the centre of the well at the founding level from its theoretical position, shall not be more than 150 mm in any resultant direction.

Tilts and shifts shall be carefully checked and recorded regularly during sinking operations in the format given in Appendix 1200/2 of MORTH specification. For the purpose of measuring the tilts along the two axes of the bridge, reduced level of the marks painted on the surface of the steining of the well shall be taken. For determination of shift, locations of the ends of the two diameters shall be precisely measured along the two axes, with reference to fixed reference points.

Whenever any tilt is noticed, adequate corrective measures like placing eccentric kentledge, pulling, strutting, anchoring or depositing more dredged material outside the tilted face, water/air jetting, shall be adopted before any further sinking. After correction, the dredged material shall be removed and disposed of sufficiently away from the affected well. In case of sinking by jack down method tilt can be controlled by suitably adjusting jack down pressure on one side.

A pair of wells close to each other have a tendency to come closer while sinking. Timber struts may be introduced in between the steining of these wells to prevent such movement.

Tilts occurring in a well during sinking in dipping rocky strata can be controlled by suitably supporting the curb.

In the event of a well developing tilt or shift beyond the specified permissible values, the Contractor shall have to carry out, at his own cost, suitable remedial measures to the satisfaction of the Engineer, to bring the tilt and shift within permissible values.

If the resultant tilt and shift of any well exceeds 1 in 80 or 150 mm respectively the well so sunk shall be regarded as not conforming to specification and classified as substandard work. The Engineer in his sole discretion, may consider accepting such a well, provided:

- i) Calculations for foundation pressures and steining stresses, accounting for the actual tilt and shift furnished by the Contractor show that the well is safe. remedial measures required to bring the stresses within permissible values (such as increase in the dimension of the well cap, provision of dummy weights on the well cap etc.), shall be carried out by the Contractor at his own cost.

- ii) The Contractor shall be subjected to reduction in rates as a penalty in accordance with Clause 1215(g) of MORTH specification.

In case the Engineer, in his discretion, rejects the well, the Contractor shall dismantle the rejected well to the extent directed by the Engineer and remove the debris. Further, the Contractor shall at his own risk and cost, complete the bridge with modified span arrangement acceptable to the Engineer.

8.2.8.10 Seating of Wells

The well shall be uniformly seated on the founding strata. It shall be ensured by test borings that the properties of the soil encountered at the founding level and up to a depth of one and a half times the well diameter, is identical to that adopted in the design. The procedure for test boring shall be in accordance with the provisions of MORTH Specifications. In case the soil encountered is inferior to that adopted in design, the well shall be re-designed by the Engineer adopting the soil properties actually encountered and the founding level intimated to the Contractor, who shall carry out the work accordingly.

In case of seating of wells in hard rocky strata, where the rock profile is steeply sloping, pneumatic methods of sinking may be adopted to seat the well evenly as directed by the Engineer. The decision of adopting pneumatic sinking shall be taken by the Engineer. The cutting edge may also be embedded for a suitable depth in the rocky strata, as decided by the Engineer keeping in view the quality of rock. A sump of depth 300 mm in hard rock or 600 mm in ordinary rock shall be made inside the well by chiselling or blasting as approved by Engineer. Diameter of sump shall be 1.5 m to 2 m less than that of the dredge hole. After the well has been evenly seated on good hard rock, arrangements shall be made to facilitate proper inspection in dry and visible conditions before the bottom plug is laid.

8.2.9 Bottom Plug

A bottom plug of concrete shall be provided in all wells, the top level of which shall be kept a minimum of 300 mm above the top of the curb, as shown in IRC:78. A suitable sump shall be made below the level of the cutting edge. Before concreting the bottom plug, it shall be ensured that the inside faces of curb and steining have been cleaned thoroughly.

The concrete mix used in bottom plug shall have a minimum cement content of 330 kg per cu.m with a slump about 150 mm, to permit easy flow of concrete through tremie to fill up all cavities. Concrete shall be laid in one continuous operation till the dredge hole is filled to the required height. For under water concreting, the concrete shall be placed by tremie under still water condition and the minimum cement content shall not be less than 330 kg/m³ inclusive of all mineral admixtures, if added.

In case of grouted concrete, the grout mix shall not be leaner than 1 :2. It shall be ensured that the grout fills up all interstices upto the top of the bottom plug by suitable means such as, controlling the rate of pumping etc.

Any dewatering required, shall only be done 7 days after casting of bottom plug.

The concrete production and placement equipment should be sufficient to enable under water concreting within stipulated time. Necessary standby equipment should be available for emergency situation.

Before commencing plugging, all loose material from the bottom of the well shall be removed. Concreting shall be done in one continuous operation till the dredge hole is filled up to the required height and thereafter soundings shall be taken to ensure that the concrete has been laid to the required height. Least disturbance shall be caused to the water inside the well while laying concrete in the bottom plug. The concrete after placing, shall not be disturbed in any way for at least 7 days.

In order to check whether there is any rise in the level of the bottom plug, soundings should be taken at the close of concreting and once every day for the next 3 days.

The soundness of the bottom plug may be tested by dewatering the well to a level 5 m below the surrounding water level and checking the rise of water. For foundation subjected to artesian pressure, the depth of dewatering by 5 m shall be measured from the still water level created inside the well by the construction of false steining. The rate of rise shall preferably be less than 10 cm per hour. In case the rate is higher, suitable remedial measures as directed by the Engineer, shall be taken by the Contractor at his own cost.

8.2.10 Sand Filling

Sand filling shall commence 7 days after laying of bottom plug. The level of the top of the bottom plug shall be verified before starting sand filling.

The sand shall be clean and free from earth, clay clods, roots, boulders, shingles, etc. and shall be compacted as directed. Sand filling shall be carried out up to the level shown on the drawing or as directed by the Engineer.

8.2.11 Top Plug

After filling sand up to the required level, a top plug of 300 mm thick concrete of grade M 15, shall be provided over it as shown on the drawing or as directed by the Engineer.

8.2.12 Well Cap

A reinforced cement concrete well cap will be provided over the top of the steining in accordance with the drawing. Formwork will be prepared conforming to the shape of well cap. In case sand filling has been carried out up to the top of the well, the concrete of the well cap may be laid directly on it after it has been suitably levelled. Otherwise, suitable shuttering supported on the inside of the steining, shall be provided for carrying the weight of the green concrete of the well cap.

Concreting shall be carried out in dry condition. A properly designed false steining may be provided where required, to ensure that the well cap is laid in dry condition.

The bottom of the well cap shall be laid preferably as low as possible but above the LWL in the active channel. Where the bed level is higher than the LWL, the top of the well cap may be suitably raised and kept 1 m below existing ground level.

Bond rods of steining shall be anchored into the well cap

8.2.13 Tolerances

The permissible tilt and shift shall not exceed 1 (horizontal) in 80 (vertical) and the shift at the well base shall not be more than 150 mm in any resultant direction.

For the well steining and well cap, the permissible tolerances shall be as follows:

a) Variation in dimension	:	+ 50 mm, -10 mm
b) Misplacement from specified position in plan	:	15 mm
c) Surface irregularities measured with 3 m straight edge	:	5 mm
d) Variation of level at the top	:	± 25 mm

8.2.14 Tests and Standards of Acceptance

The materials shall be tested in accordance with MORTH Specifications and shall meet the prescribed criteria.

The work shall conform to MORTH Specifications and shall meet the prescribed standards of acceptance.

8.2.15 Measurements for Payment

All quantities shall be measured from the drawing, or as ordered by the Engineer, excepting those required to be provided by the Contractor at his cost.

- a) The structural steel in cutting edge shall be measured in tonnes based on the net weight of metal used in it, as per Section 1900 of MORTH Specifications.
- b) The concrete in curb, well steining and well cap shall be measured in cubic metres in each of the items as per Section 1700 of MORTH Specifications.
- c) The steel reinforcement shall be measured in tonnes separately in each of the items, as per Section 1600 of MORTH Specifications.
- d) The measurement for well sinking shall be made in running metres for different depths and in different types of strata (e.g. predominantly sand/clay soil, ordinary rock, hard rock etc.) as specified in the contract. The depth of sinking shall be measured from the level specified in the contract. If no level has been specified in the Contract, sinking shall be measured from the low water level or from the level at which the cutting edge was laid, whichever is higher.
- e) The quantity of concrete in bottom and top plug shall be measured in cubic metres as per Section 1700 of MORTH Specifications.
- f) The quantity of sand filling shall be measured in cubic metres.
- g) Pneumatic sinking, where required, shall be paid as a separate item and shall be measured in cubic metres of material to be excavated.

8.2.16 Rate

- a) The contract unit rates of structural steel in cutting edge shall cover all costs of labour, material, tools, plant and equipment, including placing in position, sampling and testing, and, supervision, all as per Section 1900 of MORTH Specifications.
- b) The contract unit rates for concrete in curb, steining, bottom plug, top plug and well cap, shall cover all costs of labour, material, tools, plant and equipment, formwork and staging including placing in position, sampling and testing, and, supervision, all as per Section 1700 of MORTH Specifications and as described in this Section.
- c) The contract unit rates for reinforcement in curb, steining, and well cap, shall cover all

costs of labour, material, tools, plant and equipment, including bending to shape, placing in position, sampling, testing and supervision, all as per respective Section 1600 of MORTH Specifications and as described in this Section.

- d) The contract unit rates for sand filling shall cover all costs of labour, material, tools, plant and equipment, including placing in position and supervision.
- e) The contract unit rates for sinking of well shall cover the costs of labour, tools, and equipment and plant and for all operations and other incidentals for sinking of well including seating except pneumatic sinking as described in this Section. The unit rates shall specify the strata such as types of soil, rock, etc. The rate shall cover all testing and supervision required for the work.
- f) The contract unit rate of material to be excavated by pneumatic sinking shall cover all costs of labour, material, tools, plant and other equipment and other incidentals and safety provisions and supervision required for pneumatic sinking as per this Section.
- g) Reduction in contract unit rates for sinking as a penalty, as required under Clause 1208.10 of MORTH specification.

If any well with tilt and/or shift exceeding the permissible values is accepted by the Engineer, the Contractor shall be subjected to a reduction in the rates for the sinking of well as follows:

S. No.	Amount of Tilt and/or Shift	Percent Reduction on the Rate (s) for Sinking of Whole Well
1	Tilt exceeding the specified permissible value but equal to or within 1 in 60	5 percent
2	Tilt exceeding 1 in 60 but equal to or within 1 in 50	10 percent
3	Tilt exceeding 1 in 50	20 percent
4	Shift exceeding the specified permissible value but equal to or within 200 mm	2 percent
5	Shift exceeding 200 mm but equal to or within 300 mm	5 percent
6	Shift exceeding 300 mm	10 percent

8.3 SHALLOW FOUNDATIONS

8.3.1 Description

The work shall cover furnishing and providing plain or reinforced concrete foundation placed in open excavation, In accordance with the drawings and as per MORTH Specifications or as directed by the Engineer.

8.3.2 Materials

Materials shall conform to Section 1000 of MORTH Specifications.

8.3.3 General

A method statement indicating the following shall be submitted by the Contractor for approval of the Engineer, well in advance of the commencement of construction of open foundation:

- i) Sources of materials
- ii) Design, erection and removal of formwork
- iii) Production, transportation, laying and curing of concrete

- iv) Personnel employed for execution and supervision
- v) Tests and sampling procedures
- vi) Equipment details
- vii) Quality Management System to be adopted including Quality Manual
- viii) Any other relevant information

Details of necessary arrangements for execution under water wherever necessary, shall be included in the method statement.

Dimensions, lines and levels shall be set out and checked with respect to permanent reference lines and permanent bench mark so that the foundations are located correctly and in accordance with the drawings.

Formwork, steel reinforcement and structural concrete for open foundations shall conform to Sections 1500, 1600 and 1700 respectively of MORTH Specifications.

8.3.4 Workmanship

8.3.4.1 Preparation of Foundations

Excavation for laying the foundation shall be carried out in accordance with Section 300 of MORTH Specifications. The last 300 mm of excavation shall be done just before laying of lean concrete below foundation. Excavation shall be made only to the exact depth as shown on the drawing. In the event of excavation having been made deeper than that shown on the drawing or as ordered by the Engineer, the extra depth shall be made up with M10 concrete in case of foundation resting on soil and with concrete of the same grade as that of the foundation, in case of foundation resting on rock. This shall be done at the cost of the Contractor and shall be considered as incidental to the work.

Open foundations shall be constructed in dry conditions and the Contractor shall provide for adequate dewatering arrangements, wherever required, to the satisfaction of the Engineer.

Where light blasting is required for excavation in rock or other hard strata, the same shall be carried out in accordance with Clause 302 of MORTH Specifications. Where blasting is likely to endanger adjacent foundations or other structures, controlled blasting with all necessary precautions shall be resorted to.

8.3.4.2 Setting Out

The plan dimensions of the foundation shall be set out at the bottom of foundation trench and checked with respect to original reference line and axis.

8.3.4.3 Construction

- i) Excavation for open foundations shall be carried out in accordance with Section 300 of MORTH Specifications. For guidance regarding safety precautions to be taken, IS: 3764 may be referred.
- ii) For foundation resting on soil, a layer of M15 concrete of minimum thickness 100 mm shall be provided above the natural ground to provide an even surface to support the foundation concrete. Before laying of lean concrete layer, the earth surface shall be cleaned of all loose material and wetted. Care shall be taken to avoid muddy surface. If any part of the surface has become muddy due to over-wetting, the same shall be removed. If required, the M15 concrete may be laid to a thickness of more than 100 mm, as per the direction of the Engineer. No construction joint shall be provided in the lean concrete. For foundations resting on rock, the rock surface shall be cleaned of any loose material and then levelled with a layer of concrete of the same grade as that of the foundation, so as to provide an even surface.

- iii) No point of the surface of the lean concrete, in the case of foundation on soil or the surface of hard rock, in the case of foundation on hard rock, shall be higher than the founding level shown on the drawing or as ordered by the Engineer. Levels of the surface shall be taken at intervals of not more than 3 metres centre-to-centre in each direction, subject to a minimum of nine levels on the surface.
- iv) No formwork is necessary for the lean concrete layer. Side formwork shall be used for foundation concrete Work. When concrete is laid in slope without top formwork, the slump of the concrete shall be carefully maintained to ensure that compaction is possible without slippage of freshly placed concrete down the slope. In certain cases it may be necessary to build the top formwork progressively as the concreting proceeds up the slope. Reinforcement shall be laid as shown on the drawing.
- v) Before laying foundation concrete, the lean concrete or hard rock surface shall be cleaned of all loose material and lightly moistened. Foundation concrete of required dimensions and shape shall be laid continuously up to the location of construction joint shown on the drawing or as directed by the Engineer.
- vi) The concrete surface shall be finished smooth with a trowel. The location of construction joint and its treatment shall be done as per requirements of Section 1700 of MORTH Specifications. Formwork shall not be removed earlier than 24 hours after placing of concrete. Where formwork has been provided for top surface, the same shall be removed as soon as concrete has hardened. Curing of concrete shall be carried out by wetting of formwork before removal. After its removal, curing shall be done by laying not less than 100 mm thickness of loose moistened sand free from clods or gravel, over the concrete. The sand shall be kept continuously moist for a period of 7 days. Before backfilling is commenced, the loose sand shall be removed and disposed of as directed by the Engineer.
- vii) Normally, open foundations shall be laid dry. Where dewatering is necessary for laying of concrete, it shall be carried out adopting any one of the following methods or any other method, approved by the Engineer:
 - a) A pit or trench of suitable size, deeper than the founding level as necessary, is dug beyond the foundation excavation so that the water flows into it and the excavated surface at founding level is fully drained.
 - b) Water table is depressed by well point system or other methods.
 - c) Steel/concrete caissons or sheet piling are used for creating an enclosure for the foundations, which can subsequently be dewatered. No pumping of water shall be permitted from the time of placing of concrete up to 24 hours after placement.
- viii) In situations where foundations cannot be laid dry or where percolation is too heavy to keep foundation strata dry, concrete may be laid under water only by tremie. In case of flowing water or artesian spring, the flow shall be stopped or reduced to the feasible extent at the time of placing the concrete.
- ix) Where blasting is required, it shall be carried out in accordance with Section 300 of MORTH Specifications, observing all precautions indicated therein. Where blasting is likely to endanger adjoining foundations or other structures, necessary precautions such as controlled blasting, providing rubber mat cover to prevent flying of debris etc., shall be taken to prevent any damage.
- x) All spaces excavated and not occupied by the foundations or other permanent works shall be refilled with earth up to surface of surrounding ground with sufficient allowance for settlement. All backfill shall be thoroughly compacted and in general, its top surface shall be neatly graded. Backfilling shall be in accordance with Section 300 of MORTH Specifications.
- xi) In case of excavation in rock, the annular space around the footing shall be filled with M15 concrete up to the level of top of rock. Filling with M 15 concrete shall also be carried out for excavations having depth up to 1.5 m in ordinary rock or 0.6 m in hard rock. In case, the

excavations are even deeper so as to require further filling up to the level of top of rock, the same shall be done by boulders grouted with cement.

- xii) Protective works, where provided shall be completed before the onset of floods so as to avoid the risk of the foundation getting undermined.

8.3.5 Tests and Standards of Acceptance

The materials shall be tested in accordance with relevant Specifications and shall meet the prescribed criteria.

The work shall conform to relevant Specifications and shall meet the prescribed standards of acceptance

8.3.6 Tolerances

i)	Variation in dimensions	: +50 mm, -10 mm
ii)	Misplacement from specified position in plan	: 15mm
iii)	Surface unevenness measured with 3 m straight edge	: 5mm
iv)	Variation of levels at the top	: ± 25 mm

SECTION - S.09

MISCELLANEOUS

9.0 BEARINGS, SHEAR KEY DEVICES, HOLD DOWN DEVICES, EXPANSION JOINTS, WEARING COAT, RAILINGS, DRAINAGE SPOUTS AND DRAINAGE PIPE, CINDER, SEALANTS, FIRE PROOFING OF STEEL STRUCTURES, POLYCARBONATE ROOF/WALL PANELS, FLY ASH BASED PRODUCTS, ROOF TOP (SOLAR), TEMPORARY GROUND ANCHOR AND SOIL NAIL, JOINT FILLER BOARD, PAINTS FOR FINISHING WORKS)

9.1 BEARINGS, SHEAR & EXPANSION JOINT

GENERAL

This work shall consist of design supply and fixing in position of bearings for bridge girders in accordance with details shown on drawings and to the requirements of these Specifications, codes and standards quoted therein and as directed by the Engineer.

Bearing plates, assemblies and other expansion or fixed devices shall be constructed in accordance with details shown on drawings.

When bearing assemblies or plates are shown on drawings to be placed (not embedded) directly on concrete, the concrete bearing area shall be constructed slightly above grade and shall be finished by grinding.

It shall be ensured that the bearings are set truly level and in exact position as indicated on drawings so as to have full and even bearing on the seats. This shall be checked with spirit level in both directions. Thin epoxy mortar pads (not exceeding 5 mm) may be made to meet with this requirement.

It shall be ensured that the bottoms of girders to be received on the bearings are plane at the location of these bearings and care shall be taken that the bearings are not displaced while placing the girders.

When elastomeric bearing pads, or preformed fabric pads are to be provided, the concrete surfaces on which pads are to be placed shall be wood float finished to a level plane, which shall not vary by more than 1.5 mm from a straight edge placed in any direction across the area.

9.1.1 Pot Bearing

9.1.1.1 Material specifications of Pot bearing

The material such as PTFE lubrication, Confined elastomer, stainless steel & internal seal shall conform to requirement of IRC: 83 Part-III. The Pot base, saddle & top plate shall be of Cast steel conforming to IS: 1030 Gr 280-520 W. The anchor bolts shall conform to IS: 1364. All welding shall conform to IS: 816 & IS: 9595 with electrode as per IS: 814. Painting on non-working surface of bearing shall be as per IRC: 83 Part-III. The mating surface of Piston and cylinder shall be hardened to 350BHN (Min).

Guides of sliding pot bearing shall be monolithic to parent component.

Design of the bearing and all accessories shall be the responsibility of the Contractor and got approved from the Engineer.

9.1.1.2 Permissible stresses in steel component of Pot bearing

All the design requirements for Pot bearing as specified in IRC: 83 Part-III has to be fulfilled with following modifications.

(a) No increase in permissible stresses in any material of bearing or bearing stress between concrete and bearing is permitted in seismic condition.

9.1.1.3 Permissible bearing stresses in concrete

The allowable bearing stresses in concrete as defined in IRC: 83 Part-III has to be followed with following modifications.

a) No increase in permissible bearing stress between concrete and bearing is permitted in seismic condition.

9.1.1.4 Anchor sleeve

All the part of bearing such as anchor sleeves embedded in concrete shall be hot dip galvanized @ 300gm/ m² . The anchor sleeves have to be designed taking account of difference in elasticity of steel of sleeve and concrete. The effect of shifting of center of rotation of sleeve should be also taken into account

9.1.1.5 The contractor shall furnish along with tender documents in technical bid , the name of the manufacturer of bearings, his qualifications with all details including proof of satisfactory performance, certification and testing facilities of the bearing he proposes to use. Products of reputed manufacturers shall only be used. The design, drawings and detailed method statements for installation and replace ability of the bearings shall be checked and certified by approved independent agency before submitting to the Engineer for approval.

9.1.1.6 Pot bearings shall be measured in numbers, Pin Pot Bearing, Longitudinal guide pot bearing, transverse guide bearing & free pot bearing shall be counted separately, according to their capacities. The rate shall include the cost of supplying and fixing the bearing in position. The cost shall also include the cost of samples and their testing as required and conforming to specification.

9.1.1.7 Testing of Pot Bearing

a) Proof Load Test

A test bearing shall be tested as defined in IRC-83 Part-III.

The bearing will be visually examined both during the test and upon disassembly after the test. Any resultant visual defects, such as extruded or deformed elastomer or PTFE, damaged seals, or cracked steel, shall be cause for rejection.

During the test, the steel bearing plate and steel piston shall maintain continuous and uniform contact for the duration of the test. Any observed lift-off will be cause for rejection.

b) Sliding Coefficient of Friction

For all guided and non-guided expansion type bearing, the sliding coefficients of friction shall be measured at the bearing's design capacity.

The sliding coefficient of friction shall be calculated as the horizontal load required to maintain continuous sliding of one bearing, divided by the bearing's vertical design capacity.

The test result will be evaluated as follows: -

- i. The measured sliding coefficients of friction shall not exceed 3%.
- ii. The bearing will be visually examined both during and after the test. Any resultant visual defects, such as bond failure, physical destruction, cold flow of PTFE to the point of debonding, or damaged components shall be cause for rejection.

9.1.1.8 Sampling and Testing

a) Lot Size

Sampling testing and acceptance consideration will be made on a lot basis. A lot shall be defined as those bearings presented for inspection at a specific time or date. A lot shall be further defined as the smallest number of bearings as determined by the following criteria.

- i. A lot shall not exceed a single contract or project quantity;
- ii. A lot shall not exceed 25 bearings;
- iii. A lot shall consist of those bearing of the same type regardless of load capacity. (Fixed or expansion bearings types, Guided and non-guided expansion bearing shall be considered a single Type).

b) SAMPLING AND TESTING REQUIREMENTS

The manufacture shall furnish the required number of samples to perform testing in accordance with Table Given below: -

Sampling and Testing Requirement

Test Sample Required

Proof load	One production bearing per lot
Coefficient of Friction	One production bearing per lot
Physical Properties of elastomeric rotational elements	One elastomeric element per lot
Physical properties of PTFE sheet	One 10" x 15" sheet of PTFE material per project

A minimum of thirty (30) days shall be allowed for inspection, sampling and testing of production bearings and component materials.

All exterior surfaces of sampled production bearings shall be smooth and free from irregularities or protrusions that might interfere with testing procedures.

The manufacturer shall select, at random, the required sample bearing(s) from completed lots of bearings for testing by the manufacturer. He shall complete the required testing and determine compliance with this specification before submitting the lot(s) for inspection, sampling, and acceptance consideration.

The Engineer shall select, at random, the required sample bearing(s) from completed lots of bearings to be tested by independent agency approved by concerned organisation. The testing charges shall be borne by contractor.

Necessary test certificates for all raw material shall be furnished by manufacturer

Test specified in IS: 1030 for cast steel shall be performed. Casting shall be ultrasonically got tested by approved testing agency.

9.1.1.9 Fabrication Details

The Contractor shall provide the Engineer with written notification thirty (30) days prior to the start of bearing fabrication. This notification shall include all of the information shown on the shop drawings which are required as explained in subsequent section.

The finish of the mould used to produce the elastomeric rotational element shall conform to good machine shop practice.

All steel surfaces exposed to the atmosphere, except stainless steel surfaces and metal surfaces to be welded, shall be shop painted in accordance with the Contract Plans. Prior to painting, the exposed steel surfaces shall be cleaned in accordance with the recommendations of the coating's manufacturer. Metal surfaces to be welded shall be given a coat of clear lacquer, or other protective coating approved by the Engineer, if the time of exposure before welding takes place is to exceed three months, the coating shall be removed at the time of welding. No painting will be done to these surfaces prior to the completion of welding.

Stainless steel sheet shall be attached to its steel substrate with an approved epoxy to ensure complete contact and then sealed with a continuous seal weld.

The steel piston and the steel pot shall each be machined from a solid piece of cast steel.

The outside diameter of the piston shall be not more than 1mm less the inside diameter of the pot at the interface level of the piston and elastomeric rotational element. The sides of the piston shall be beveled to facilitate rotation. Except as noted all bearing surfaces of steel plates shall be finished or machined flat in accordance with tolerance written below:

Tolerances: -

Manufacture tolerance shall be as per IRC: 83 Part-III.

All these measurements were taken using dial height gauges, vernier caliper, surface finish measurement instrument etc has to be arranged by manufacturer at the workshop.

Every bearing shall have the Project Identification Number, Lot Number, and individual bearing number indelibly marked with ink on a side that will be visible after erection.

After assembly bearing components shall be held together with steel strapping, or other means, to prevent disassembly until the time of installation. Packaging shall be adequate to prevent damage from impact as well as from dust and moisture contamination during transportation and storage.

9.1.1.10 Shop Drawings

Along with detailed design of different types of bearing, shop drawings shall be submitted. The shop drawings shall contain the following information, which is necessary for proper design and detailing of the bearings.

Quantity, type (fixed, guided expansion, non-guided expansion), and location of all bearing units.

A table containing maximum and minimum vertical and horizontal loads, design rotation requirements, and magnitudes and directions of movements.

Allowable contact stresses, maximum dimensions, and anchorage requirements at the bearing interfaces; grades, bevels, and slopes at all bearings; and allowable coefficients of friction of all sliding surfaces.

The painting system to be used on the steel components to guard against corrosion.

Any special consideration such as earthquake requirements, uplift details, or temporary attachments.

Installation scheme of pot bearing

The Contractor shall submit detailed shop drawings in conformance with the applicable requirements.

9.1.2 Spherical Bearings

The material specifications, design, manufacturing, acceptance, testing & certification, packing, transportation & storage, performance & installation shall be as per the specifications & guidelines given in IRC 83-Part-IV (with all latest amendments). The contractor shall submit a document from International Approving Bodies like ETA, FHWA or similar which will guarantee the working life of the bearings to be not less than 50 years.

9.1.3 Elastomeric Bearings

The terms "bearing" in this case refers to an elastomeric bearing consisting of one or more internal layers of elastomer bonded to internal steel laminates by the process of

vulcanisation. The bearing shall cater for translation and/or rotation of the superstructure by elastic deformation.

a) **Raw Material**

Chloroprene (CR) only shall be used in the manufacture of bearing.

Grades of raw elastomer of proven use in elastomeric bearings, with low crystallization rates and adequate shelf life (as indicated in the latest revision of IRC 83-part 2)

No reclaimed rubber or vulcanized wastes or natural rubber shall be used.

The polymer content of the bearing shall not be lower than 60 percent and the ash content shall not exceed 5 percent. Polymer content shall be determined in accordance with ASTM-D297 and ash content as per IS: 3400-Part XXII.

EPDM and other similar candidate elastomer for bridge bearing use shall not be permitted.

b) **Properties**

The elastomer shall conform to the properties specified in Clause 4.2 of IRC:83 (Part-II) & Clause 5.2 of the IRICEN(Indian Railways Institute of Civil Engineering) latest publication titled "Bearings for Railway Bridges" and those specified in Table 5.2 of the publication titled "Specifications for Road and Bridge Works", published by IRC on behalf of MORTH (Roads Wing).

c) **Fabrication and Tolerances**

Fabrication and Dimensional tolerances shall be governed by the specifications laid down in Clause 4.3.2 of the IRICEN publication & Clause 2005.3 of the MORTH specifications and Table-5 of IRC:83 mentioned above.

d) **Acceptance Specifications**

For inspection and testing requirement Clause 5.7 of the above mentioned IRICEN publication shall be referred with modifications of lot size as mentioned below: -

Sampling testing and acceptance consideration will be made on a lot basis. A lot shall be defined as those bearings presented for inspection at a specific time or date. A lot shall be further defined as the smallest number of bearings as determined by the following criteria.

- i. A lot shall not exceed a single contract or project quantity;
- ii. A lot shall not exceed 50 bearings;
- iii. A lot shall consist of those bearing of the same type regardless of load capacity.

Accepting and testing requirements shall also conform to the specifications laid down in Clause 2005.4 of the referred MORTH specifications.

In addition to tests mentioned above, all bearings shall be also weight actually and compared with the theoretical weight.

All bearings shall carry a warrantee of not less than 15 years in an approved format. The contractor shall be responsible for immediate repair or replacement of the bearings in case of failure / distress to the satisfaction of the owner at no extra cost to the Owner within the warrantee period.

Criteria for Selection of bearing manufacturer shall conform to latest DMRC approved

items/ vendor list It is necessary that all manufacturers of all elastomeric bearings shall have in house facilities for carrying out Infrared Spectro-Photometry as per ASTM D-3677.

d) Design

The design of elastomeric bearings shall be in accordance with EN1337 Part 1 and Part III.

The design, drgs and detailed method statements for installation and replaceability of the bearings shall be checked and certified by approved independent agency appointed by the contractor before submitting to the Engineer for approval.

e) Storage and Handling

Each elastomeric bearing shall be clearly labeled or marked. The bearing shall be wrapped in a cover. They shall be packed in timber crates with suitable arrangement to prevent movement and to protect comers and edges.

Care shall be taken to avoid mechanical damage, contamination with oil, grease and dirt, undue exposure to sunlight and weather to the bearings during transport and handling prior to and during installation.

f) Installation

Installation procedure shall conform to the guidelines listed in Clause 5.8 of the IRICEN publication and Clause 2005.7 of the MORTH specifications. Cost of Non-shrink grout above and below the bearing is included in the cost of bearing.

9.1.4 Shear Key Device

a) GENERAL DESCRIPTION OF THE SYSTEM

i) General

The shear key is made of concrete cast in place in second pour after concrete decks are assembled.

The shear keys shall take all horizontal loads (longitudinal and transverse).

It is equipped with a system of fixation with high strength bars to one end of the deck, and with 5 vertical bearings taking the transverse horizontal loads and the rotations.

ii) Description of the proposed system

The system of fixation of the shear key to the deck is performed by high strength tensile bars installed.

The system shall satisfy with the two main following requirements:

- construction easiness
- maintenance easiness

The high strength tensile bars shall have a good resilience and a good resistance to fatigue because due to the rotation of the deck and the braking/acceleration loads the

bars are almost continuously loaded. The shear key supplier must be a manufacturer (not a trader, agent, distributor, etc.) having ISO 9001 certification for "Design and Manufacturing of Threaded Tensile Bars along with Nuts".

The elastomeric bearings shall be of sufficient quality to avoid premature ageing. All the external surfaces shall be made of polychloroprene.

b) MATERIALS CHARACTERISTICS

i) High tensile bars

Quality of steel: the quality of the raw material steel shall be according to the DIN EN 10083-1 or equivalent. The chemical composition shall be such as to guarantee the following mechanical characteristics:

- Yield stress $F_y > 1050$ MPa
- Tensile stress $F_u > 1200$ MPa
- Elongation at breaking $> 10\%$
- Relaxation at 1000 hrs $< 3.5\%$
- Resilience at $20^\circ\text{C} > 50$ Joules;

Due to high fatigue, resilience and ductility requirement for seismic cases, the properties or mechanical characteristics cannot be lower than as mentioned above. The threading of the bars shall be made by rolling method (cold plastic deformation of the metal between two dies). The threads shall have a triangular profile H7 according to ISO 262 - NFE 03014 and 03053.u

The tolerance of the length of the bars is ± 5 mm

Diameters of bars: the stress in the bar will not exceed $0.85 F_u$. The following U.T.S of bar are contemplated, but may be adjusted during detailed design phase:

U.T.S. of Shear Key Bar	Diameter of Shear Key Bar
2436 kN	53mm
2109 kN	49mm
1567 kN	43mm
1171 kN	37mm

Due to the repetitive loading that will be applied to the bars, some tests shall be carried out to demonstrate the fatigue resistance of the bars. The test criteria shall be as follows :

- mean stress : $0.57 F_y$
- stress range : $\pm 0.03 F_y$
- 4 millions cycles
- after 4 millions cycles, no breaking at less than $0.80 F_y$.

Ultimate tensile strength test shall be conducted at manufacturer's or any other

approved independent laboratory in presence of Engineer, same test conducted in the past will not be considered. 4 million cycles fatigue test report for tests conducted in last 5 years to be submitted. The test reports have to be issued strictly in the name of supplier responsible for supply of shear key bar to the project; its important to ensure the responsibility of supply and performance of the system.

ii) Other materials

The repartition plates shall be of S355 JR steel quality or equivalent, and each shall include an injection pipe.

The bars end shall be equipped with a protection cap filled up with grease and fixed on repartition plate by threading.

The nuts at the bars ends shall be spherical in order to ensure that the tensioning is well axed.

Sheaths shall be made with 2 mm thick steel / 5 mm thick HDPE pipe.

The injection product shall be high-density grease in order to provide a good time-resistance and to provide flexibility under the deck rotations. The product shall be equivalent as for use for protecting stay cables. The injection product at end caps would be wax or grease in order to facilitate site installation and inspection during service life.

iii) Elastomeric bearings system

On the movable side of deck, one sliding elastomeric bearing shall be installed longitudinally on each side of the shear key. This sliding elastomeric bearing shall be made of one laminated elastomeric pad and of one sliding plate.

On the fixed side of deck, one laminated elastomeric bearing shall be installed longitudinally on each side of the shear key. In addition, at the interface between the shear key, one laminated elastomeric with adequate recesses to allow for replacement without taking out the high tensile bars shall be installed transversally.

These elastomeric bearings shall be made of polychloroprene, and manufactured according to Euronorm EN 1337-3 or equivalent.

The sliding plate shall be PTFE, with elongation at break >300% and tensile strength from 29 to 40 MPa.

c) CORROSION PROTECTION

i) High tensile bars

The protection against corrosion of the high tensile bars shall be performed by using high-density grease injected in tube. So, the bars will be protected against corrosion only for the time of transportation and storage by means of sprayed oil or equivalent system.

ii) Other materials

The upper repartition plate and the protection cap shall be sandblasted and shall receive 3 layers of coating.

The articulation room, the coupler and the lower ring shall be sandblasted and shall receive 3 layers of coating and a petrolatum tape.

The articulation room and the upper protection cap shall be filled up with grease.

d) TRANSPORTATION & STORAGE

The bars and the accessories shall be transported in wooden cases and in containers, or equivalent.

The bar threading shall be temporarily protected against shocks by a greased tape and a steel ring, or equivalent. The protection of the threads shall be taken off only right before the installation of the bars.

The bars and accessories shall be carefully stored in the jobsite in the following conditions:

- They shall be protected from rain, and the storage room shall have ventilation.
- If the bars have to be kept stored for a long time, it will be necessary to protect them with a layer of solvable oil or equivalent in order to protect them against corrosion.
- Before installation of the bars, if there is some corrosion, they shall be cleaned up.

Acceptance of the bars shall be subject to concerned organisation approval.

e) INSTALLATION PROCEDURE

Installation of these shear key high tensile bars must be done under the expert supervision of the system supplier agency. The agency here means "the direct manufacturer & supplier or its sister concern (legally affiliated) or holding company or 100% subsidiary". No agent, other representative or third party nominated by manufacturer or distributor shall be permitted. The agency supervisor must be available at site full time during installation. The installation procedure is proposed as follows. Alternate methods can be submitted by the contractor, subject to concerned organisation approval.

- Shear Key is poured before precast concrete deck segments are installed. The span must be assembled on higher level to avoid conflicts with already built concrete key.
- Superstructure should have recess of 20mm for grouting by non-shrinkage grout at later stage
- Erect the superstructure on temporary bearings/jacks with sliding surface at top at both ends
- Provide some arrangement to prevent deck sliding (e.g. under seismic load).
- Move the girder by hand screwing/jacking bar be nearly 20mm

- At this stage vertical faced elastomeric pad is in position (resting on tubes)
- Replace the temporary bearing with the permanent elastomeric bearing
- Grout the gap between the girder (with hacked surface at grouting location) and the elastomeric bearing
- Bar stressing
- Wax or Grease injection and capping

Notes:

- a) The bars are installed after alignment check, and the bars are installed inside the spherical nut at movable end. Then the bars are prestressed with jack. The bars are tensioned step by step (50% one bar, then 50% the other, then the remaining 50%).
- b) Injection is then made from the movable end, with heated wax or grease through injection tube. Alternatively pre-greased shear key bars can as well be used.

f) MAINTENANCE PROCEDURE

The system shall be such that any device can be replaced without any destruction of concrete part of the structure.

The system shall be such that the maintenance procedures described below can be undertaken.

i. Lateral elastomeric bearings

For the lateral vertical bearings, a theoretical gap of 2mm shall be provided on each side of the shear key. If it is needed to change one or all of these lateral bearings, then, as the deck will not be in contact on each side at a time, the lateral bearings on the non-compressed side are taken out first. First the sliding plate is taken out, then the elastomeric bearing. Then the deck may need to be translated laterally to take out the elastomeric bearings on the compressed side. For this, steel angles can be split in the concrete on each side of the elastomeric bearings to provide support for jacks or threaded bars. The needed force to distort the neoprene bearings supporting the deck will be calculated.

ii. Transversal elastomeric bearings

With provision of the opening on the bearing, it will only be necessary to un-stress temporarily the tie-bars to take out the bearings and replace it

iii. Prestressed tie-bars

Bars will be un-stressed, then simply taken out with provision of device provided at the movable end. Bars will be taken out easily because the connection between the spherical nut and the protection cap will not allow the spherical nut to turn. The wax or grease product will come out with bar. New bars are introduced as per first installation, then tensioned and wax or grease is injected.

9.1.5 **Hold-Down Devices**

9.1.5.1 **General Description of the System**

a) **General**

The holds down devices are designed to take the lifting loads between the pier caps and the girders that may occur mainly during earthquakes in curved sections. The system of hold down device must take relative horizontal movements between the pier and the girder without any significant tensile stresses in the bars due to these movements.

b) **Description of the proposed system**

i. **Movable end of the deck**

On the movable end, the system shall be composed of the 3 following devices:

- 1) A lower high tensile bar embedded in the pier cap concrete.
 - The bar is smooth and it is threaded only at its two ends. The bars are only threaded at their ends and they are smooth on the full length in order to increase the fatigue performances. The bar is equipped with a repartition plate and a nut.
- 2) A system of spherical articulation allowing the relative angular rotation between the lower and the upper bar. This device shall be composed with:
 - A washer with adequate thickness to permit a good setting of the articulation device. Between the washer and the concrete shall be installed an elastomeric membrane to provide the waterproofing of the device.
 - A lower nut with an internal threading to be assembled with the lower bar and an external threading to be assembled with the spherical room.
 - An articulation room equipped with a spherical contact surface.
 - A spherical nut in contact with the spherical surface of the articulation room.
 - A rubber protection skirt installed between the articulation room and the upper bar to avoid any dust in the upper opening of the articulation.
 - A rectangular repartition plate to take into account the oblong recess.
 - A spherical nut.
 - A protection cap that shall be equipped such as to avoid the rotation of the nut and to adjust precisely the gap between the nut and the repartition plate.
- 3) A high tensile upper bar installed in an oblong recess provided in the girder.

As for the lower bar, the upper bar shall be smooth and threaded at the two ends. The threading shall be made by rolling method. The corrosion protection of the bar shall be done by a heat shrinkable sleeve. In order to ensure that the lower bar will never break because this lower bar will not be replaceable, the diameter of the lower bar shall be always greater than the upper bar diameter, so that the upper bar shall always break (fuse principle) before the lower bar.

The upper threading shall be longer in order to take the variation of distance between the girder and the pier cap, and the variation of height of the lower part of the girder. It shall also take into account the construction tolerance.

Important:

- a) The articulation system will be designed in order to permit a rotation of at least 8° in all the directions without any tensile stress in the bar.
- b) The articulation system will be designed in order to avoid any rotation of any component under the vibrations.

ii. **Fixed end of the deck**

In that case, the articulation device can be simplified and replaced by a coupler having two different threading diameters. The other devices are the same as for the movable end.

Nevertheless, attention is brought to the fact that the design of the articulations and of the couplers shall be such that there is the possibility to replace a coupler by an articulation in case of non-verticality of the lower bar. Therefore the “fixed end” device may need to be replaced with the more complex “movable end” device if construction tolerances are not met.

9.1.5.2 **Materials Characteristics**

High tensile bars

Quality of steel: the quality of the raw material steel shall be according to the DIN EN 10083-1 or equivalent. The chemical composition shall be such as to guarantee the following mechanical characteristics:

- Yield stress $F_y > 1050$ MPa
- Tensile stress $F_u > 1200$ Mpa
- Elongation at breaking $> 10\%$
- Resilience at $20^\circ\text{C} > 50$ Joules;

The threading of the bars shall be made by rolling method (cold plastic deformation of the metal between two dies) in order to give a good resistance to the fatigue. The threads shall have a triangular profile H7 according to ISO 262 – NFE 03014 and 03053.

The tolerance of the length of the bars is ± 5 mm

Foreseen Diameters of bars:

The stress in the bar will not exceed $0.85 F_u$. The lower bar shall not reach the yield strength before upper bar is broken. The following upper/lower U.T.S bars are contemplated, but may be adjusted ($\pm$) during detailed design phase:

Upper Diameter (U.T.S)	Lower Diameter (U.T.S)
500kN	700kN

9.1.5.3 Corrosion Protection

a) High tensile bars

The protection against corrosion of the high tensile bars shall be performed by using a heat shrinkable sleeve in order to give a very good protection against corrosion due to humidity, ozone, UV rays and shocks.

b) Other materials

The upper repartition plate and the protection cap shall be sandblasted and shall receive 3 layers of coating.

The articulation room, the coupler and the lower ring shall be sandblasted and shall receive 3 layers of coating and a petrolatum tape.

The articulation room and the upper protection cap shall be filled up with grease.

9.1.5.4 Transportation & Storage

The bars and the accessories shall be transported in wooden cases and in containers, or equivalent.

The bar threading shall be temporarily protected against shocks by a greased tape and a steel ring, or equivalent. The protection of the threads shall be taken off only right before the installation of the bars.

The bars and accessories shall be carefully stored in the jobsite in the following conditions:

- They shall be protected from rain, and the storage room shall have ventilation.
- If the bars have to be kept stored for a long time, it will be necessary to protect them with a layer of solvable oil or equivalent in order to protect them against corrosion.
- Before installation of the bars, if there is some corrosion, they shall be cleaned up. Acceptance of the bars shall be subject to concerned organisation approval.

9.1.5.5 Installation Procedure

The installation procedure is proposed as follows. Alternate methods can be submitted by the contractor, subject to concerned organisation approval.

a) Installation of the lower bars

- Place the bar with the repartition plate and the nut into the reinforcement of the pier cap.

- Check that the length out of the concrete pier cap concrete is sufficient to install the articulation or the coupler.
- Check that the bar is installed vertically.
- Pour the pier cap concrete.

b) Installation of the articulation (or the coupler) and the upper bar

- Install the lower washer and the elastomeric pad on a plane and horizontal layer of mortar.
- Install the lower ring with the external and internal threading around the lower bar.
- Bring the upper bar equipped with the articulation room and the spherical nut and put in position the nut and the upper bar; the length of the pins installed between the nut and the ring shall be such to avoid any gap between the lower nut and the spherical articulation.
- Screw the articulation room until it is in contact with the lower washer.
- Apply a closing tape or equivalent between the bar end and the spherical nut.
- Fill the upper hole of the articulation room with grease or equivalent.
- Install the upper repartition plate on a plane and horizontal mortar.
- Apply a closing tape or equivalent between the end of the bar and the spherical nut.
- Install the upper spherical nut around the bar in order to be in contact with the spherical surface of the repartition plate. At this stage, there shall be no gap between the two spherical nuts, the articulation room and the repartition plate.

The installation of the protection cap will allow to give a 2mm gap necessary to let the system free of rotation when there is any horizontal movement.

- Install a tape around the articulation room and the lower ring.
- Install the rubber protection skirt between the articulation room and the upper bar (the rubber skirt shall be filled up with grease).

NOTE: the same procedure can be applied for the fixed end, where the articulation room is replaced by a coupler.

9.1.5.6 MAINTENANCE PROCEDURE

The system shall be such that the maintenance procedures described below can be undertaken.

a) Periodical inspection

- Every 5 years or after an earthquake, a visual inspection of the articulation room and the rubber protection skirt will have to be made to check the corrosion protection.
- At the same time, the upper protection cap will be taken off to check if the 2mm gap is still there and to adjust again this gap if necessary.
- The protection against corrosion of the upper bar will also be checked.

b) Maintenance

The system does not need any maintenance if it works in normal conditions. Nevertheless, if there is an earthquake, a special inspection will be carried out. If it is necessary to change the upper bar, the articulation device or the coupler, it will be necessary to take off the upper bar first, and to change the damaged devices according to the installation procedure.

9.1.6 Expansion Joints**9.1.6.1 Scope of Work**

The scope of work will include:

- a) Preparation of detailed engineering and installation drawings, supply and supervision during fixing of strip seal/compression seal expansion joints conforming to specifications. The expected expansion/contraction of the superstructure at the location of expansion joints are shown in relevant drawings.
- b) Design, manufacture, providing and seating of expansion joints by the specialised agency and approved by the Engineer.
- c) Necessary technical supervision for installation of each and every expansion joint during different stages of installation including rectification of any deficiency or defect attributable to fixing and installation will be provided by the manufacturer/supplier.
- d) The expansion joint shall be provided for the full width of viaduct including the railing.

Leak tightness of all joints shall be ensured which shall also carry a warranty of 10 years from the contractor.

The expansion joints provided over elevated structure decks should be so designed as to be compatible with the bearings wherever provided where the structure passes through stations, specially designed completely waterproof expansion joints should be provided.

The contractor shall submit design and drawing of expansion joints based on design criteria mentioned under "scope of Work" to the Engineer for approval. The design of expansion joint shall be done as per Revised Highways "Interim Specification for

expansion joint” issued by MOST circular No. RW/NH – 34059/1/96 – S & R dated 30th

November 2000 and 20th **February** 2001/IRC SP-69-2011 latest edition or latest IRC Codes and MORTH Specification for Roads and Bridges and Sound Engineering practices.

Any modification to the design and drawings submitted by the Contractor, if suggested by the Engineer, shall be incorporated without any reservations. The design and drawings including changes approved by the Engineer shall form basis of execution and the Contractor shall undertake all necessary action for ensuring execution of work on that basis.

For design, manufacture, testing and supply of strip seal/modular strip seal expansion joints, following will be followed in order of preferences:

- i) Details in this chapter and elsewhere in tender documents.
- ii) “Revised Interim Specifications for expansion joints” issued by MOST circular № No. RW/NH – 34059/1/96/ S & R dated. 30.11.2000 and 20th february 2001
- iii) IRC Codes and MORTH specifications for Roads and bridges published by Indian Road Congress.
- iv) Sound Engineering Practice (Decision of Engineer will be final in this case) which shall include specialized literature as decided by Engineer.

9.1.6.2 Building Expansion Joints

Specialised expansion joints consisting of extruded aluminum frame assemblies of suitable profile to receive free floating cover plate of required shape and profile / or elastomer suited to building applications shall be used. These will be provided for covering the structural gap at expansion joints along the horizontal faces of slabs and beams, vertical faces of retaining walls, etc. Necessary block-outs as per the manufacturer's recommendations shall be provided in the structure which shall be filled in the approved manner after placing the expansion joints.

The base of the expansion joint assembly shall be fixed onto the concrete base using anchor fasteners (not exposed to top surface) as per manufacturer's specifications. The joint shall have an anti-skid serrated top plate with a free-floating central plate. All aluminum in contact with concrete shall have zinc chromate finish. The joint assembly shall be capable of accommodating the specified movement without loss of cover and shall include all the necessary accessories, sealant etc as per manufacture's drawings. The joint fixing shall be carried out either by the main contractor under the supervision of supplier/manufacturing agency of approved expansion joint . The expansion joint cover assemblies shall withstand a minimum

500lb point load without damage or permanent deformation. The joint should be water tight and test on same if required on direction of Engineer shall be conducted without any extra payment for same.

9.1.6.3 Specification for Strip Seal Expansion Joint

Expansion joint type described here-after is the “strip seal” type, but alternate designs can be proposed for concerned organisation approval (e.g. elastomeric omega-shape cover joint, or any other suitable joint type)

a) Components:

Strip seal expansion joint shall comprise the following items:

i. Edge beam:

This shall be either extruded or hot rolled steel section or cold rolled cellular steel section with suitable profile to mechanically lock the sealing element in place throughout the normal movement cycle. Further the configuration shall be such that the section has a minimum thickness of 10mm all along its cross section (flanges and web). The minimum height of the edge beam section shall be 80mm. The minimum cross-sectional area of the edge beam shall be 1500mm^2 .

ii. Anchorage:

Edge beams shall be anchored to the deck by reinforcing bars or bolts or anchor plates cast in concrete or a combination of anchor plate and reinforcing bars. Anchor bars studs or bolts shall engage the main structural reinforcement of the deck and in case of anchor plates or loops, this shall be achieved by passing transverse bars through the loops or plates.

The minimum thickness of anchor plate shall be 12mm. Total cross-sectional area of bar on each side of the joint shall not be less than 1600mm^2 per meter length of the joint and the center to center spacing shall not exceed 250mm. The ultimate resistance of anchorage shall not be less than 600 kN/m in any direction.

b) Material

- i. The steel for edge beams shall conform to any of the steel grade corresponding to RST 37-2 or 37-3 (DIN), ASTM A36 or A588, CAN/CSA Standard G40.21 Grade 300W or equivalent.
- ii. Anchorage steel shall conform to IS:2062 or equivalent.
- iii. All steel sections shall be protected against corrosion by hot dip galvanizing or any other approved anticorrosive coating with a minimum thickness of 100 micron.
- iv. Chloroprene of strip seal element shall conform to Clause 915.1 of IRC:83 (Part-II). The properties of chloroprene shall be as specified in Table-1.

c) Fabrication (Pre-installation)

- i. The strip seal joint system and all its component parts including anchorages shall be supplied by the manufacturer /system supplier.
- ii. The width of the gap to cater for movement due to thermal effect, prestress, shrinkage and creep, superstructure deformations (if any) and sub-structure deformations (if any) shall be determined and intimated to the manufacturer. Depending upon the temperature at which the joint is to be installed, the gap dimension shall be preset.
- iii. Each strip seal expansion joint system shall be fabricated as a single entity unless stage construction or excessive length prohibits monolithic fabrication. It shall fit the full width of the structure as indicated on the approved drawing. The system shall be pre-set by the manufacturer prior to transportation. Pre-setting shall be done in accordance with the joint opening indicated on the drawing.
- iv. The finally assembled joint shall then be clamped and transported to the work site.

TABLE-1 STRIP SEAL ELEMENT SPECIFICATION

Sealing element is made of chloroprene and must be extruded section. The working movement range of the sealing element shall be at 70mm.

Property	Specified Value
Hardness*	63+ /-5 Shore A
DIN 53505	55 +/- 5 Shore A
ASTM D 2240 (Modified)	.
Tensile Strength*	Min 11 MPa
DIN 53504	Min 13 .8Mpa
ASTM D 412	
Elongation at fracture*	Min 350 per cent
DIN 53504	Min 250 per cent
ASTM D 412	
Tear Propagation Strength	Min 10 N/mm
Longitudinal	Min 10 N/mm
Transverse	Min 25 per cent
Shock elasticity	Min 220 Cu.mm
Abrasion	
Residual Compressive Strain (22h/70 deg C/30 per cent Strain))	Max 28 per cent
Aging in hot air (14days/70 deg C)	
Change in hardness	Max + 7 Shore A
Change in tensile strength	Max -20 per cent

Change in elongation at fracture	-20 per cent
Ageing in Ozone (24 h/50 pphm/25 deg C/20 per cent elongation)	No cracks
Swelling behaviour in Oil (168h/25 deg. C)	
ASTM Oil No. 1	
Volume Change	Max + 5 per cent
Change in hardness	Max –10 Shore A
ASTM Oil No. 3	
Volume Change	Max + 25 per cent
Change in hardness	Max –20 Shore A
Cold Hardening Point	Max –35 deg C

Only one set of specification viz. ASTM or DIN shall be followed depending on the source of supply.

- v. Each strip seal expansion joint system shall be fabricated as a single entity unless stage construction or excessive length prohibits monolithic fabrication. It shall fit the full width of the structure as indicated on the approved drawing. The system shall be pre-set by the manufacturer prior to transportation. Presetting shall be done in accordance with the joint opening indicated on the drawing.

- vi. The finally assembled joint shall then be clamped and transported to the work site.

d) Handling and Storage

- i. For transportation and storage, auxiliary brackets shall be provided to hold the joint assembly together.
- ii. The manufacturer/supplier shall supply either directly to the Engineer or to the Bridge Contractor all the materials of strip seal joints including sealants and all other accessories for the effective installation of the jointing.
- iii. Expansion joint material shall be handled with care. It shall be stored under cover on suitable lumber padding.

e) Supply/Installation:

Components of expansion joint such as edge beam and strip seal shall be imported from the specified foreign manufacturer / collaborator to ensure quality and performance. The joint shall be supplied and installed only by the approved manufacturer. The joint shall be supplied and installed only by the MOST approved manufacturer. Contractor shall furnish a warranty of trouble free performance for at least ten years and free rectification of defects / replacement, if any, during this period.

The joints shall be installed by the manufacturer/supplier (only MOST Approved) or their authorised representative who will ensure compliance to the manufacture's instructions for installation.

Taking the width of gap for movement of the joint into account, the dimensions of the recess in the decking shall be established in accordance with the drawings or design data of the manufacturer. The surfaces of the recess shall be thoroughly cleaned and all dirt and debris removed. The exposed reinforcement shall be suitably adjusted to permit unobstructed lowering of the joint into the recess.

The recess shall be shuttered in such a way that dimensions in the joint drawing are maintained. The formwork shall be rigid and firm.

Immediately prior to placing the joint, the presetting shall be inspected. Should the actual temperature of the structure be different from the temperature provided for presetting, correction of the presetting shall be done. After adjustment, the brackets shall be tightened again.

The joint shall be lowered in a pre-determined position. Following placement of the joint in the prepared recess, the joint shall level and finally aligned and the anchorage steel on one side of the joint welded to the exposed reinforcement bars of the structure. Upon completion, the same procedure shall be followed for the other side of the joint. With the expansion joint finally held at both sides, the auxiliary brackets shall be released, allowing the joint to take up the movement of the structure.

High quality concrete shall then be filled into the recess. The packing concrete must feature low shrinkage and have the same strength as that of the superstructure, but in any case, not less than M40 grade. Good compaction and careful curing of concrete is particularly important. After the concrete has cured, the movable installation brackets and shuttering still in place shall be removed.

The neoprene seal shall be field installed in continuous length spanning the entire roadway width. To ensure proper fit of seal and enhance the ease of installation dirt, spatter or standing water shall be removed from the steel cavity using a brush, scraper or compressed air. The seal shall be installed without any damage to the seal by suitable hand method or machine tools.

The deck surfacing shall be finished flush with the top of the steel sections. The horizontal leg of the edge beam shall be cleaned beforehand. It is particularly important to ensure thorough and careful compaction of the surfacing in order to prevent any premature depression forming in it.

f) Acceptance Criteria:

- i. All steel elements shall be finished with corrosion protection system.
- ii. For neoprene seal, the acceptance test shall conform to the requirements stipulated in Table-1. The manufacturer/supplier shall produce a test certificate accordingly, conducted in a recognized laboratory, in India or abroad.
- iii. The manufacturer shall produce test certificates indicating that anchorage system had been tested in recognized laboratory to determine optimum configuration of anchorage assembly under dynamic loading.
- iv. Prior to acceptance 25 percent of the completed and installed joints, subject to a minimum of one joint, shall be subjected to water tightness test. Water shall be

continuously pounded along the entire length for a minimum period of 4 hours for a depth of 25mm above the highest point of deck. The width of ponding shall be at least 50mm beyond the anchorage block of the joint on either side. The depth of water shall not fall below 25mm anytime during the test. A close inspection of the underside of the joint shall not reveal any leakage.

- v. As strip seal type of joint is specialized in nature, generally of the proprietary type, the manufacturer shall be required to produce evidence of satisfactory performance of this type of joint.

g) Test and Standards of Acceptance:

The materials shall be tested in accordance with these specifications and shall meet the prescribed criteria. The manufacturer/supplier shall furnish the requisite certificates from the recognized testing laboratory of India or abroad.

h) WATERBARS / WATERSTOPS

Where waterbars are required, the joints shall incorporate PVC water bar such as "Fixostop" or approved equivalent (conforming to IS: 12200). The water bars shall be complete with all the necessary moulded or prefabricated intersection pieces assembled with bends and butt joints in running lengths made by welding in an electrically heated jig. The fabrication drawing made by the manufacturer shall be submitted by the Contractor for approval of the Engineer

Jointing and fixing of waterbars shall be carried out strictly in accordance with the manufacturer's instructions which should be enumerated in a detailed method statement and submitted for approval / comments of the Engineer. The following types of waterstops are proposed to be used in the Work.

- i. 'FIXOSTOP' Type 230 KD or equivalent – To be used at construction joint in base slab
- ii. 'FIXOSTOP' Type 230 KV or equivalent – To be used at expansion joint in base slab
- iii. 'FIXOSTOP' Type 240 RS or equivalent – To be used at construction joint in between wall and base slab
- iv. 'FIXOSTOP' Type 240 H or equivalent – To be used at expansion joint in base slab

Waterbars shall be of approved and appropriate type obtained from approved manufacturers.

The waterbars shall be installed so that they are securely held in their correct position during the placing and compacting of the concrete. Necessary supporting devices to prevent sagging of the water bars shall be provided.

Where reinforcement is present adjacent to waterbars, adequate clearance shall be left between the reinforcement and waterbars to facilitate compaction of the concrete.

Double headed nails maybe used in the edge of the waterbar outside the line of the external grooves for fixing purposes, but no other holes shall be permitted through the waterbar.

A representative of the manufacturer shall be present at site during the operations of installing, jointing and embedment of waterstop. He shall monitor and certify that the work is being carried out strictly as per specifications and recommended practices.

9.1.7 **Specification for Omega Type Expansion Joint**

Expansion joint type described here-after is the “**OMEGA TYPE EXPANSION JOINT**”.

9.1.7.1 **Material.**

- a) **Anchorage:** The steel plate shall conform to IS: 2062 or equivalent. The bolt and nut shall be anchored to the deck by welding to the main reinforcement. Steel plate used for shall be 8 mm thick hot dip galvanized. The center-to-center spacing of bolts shall not exceed 400 mm.
- b) **Corrosion Protection:** All steel section shall be protected against corrosion by hot dip galvanising or any other approved anticorrosive coating with a minimum thickness of 100micron.
- c) **Joint Seal:**
 - i. The sealing element shall be a **preformed chloroprene with high tear strength**, insensitive to soil, gasoline and ozone. It shall have high resistance to ageing and ensure water tightness. The seal should be vulcanised in a single operation for the full length of the joint required for carriageway, kerbs and footpaths, if any. The seal shall cater for a horizontal movement up to **100mm** and vertical movement of 3mm.
 - ii. The physical properties of **chloroprene sealing** element shall conform to the following:
Elastomeric Seal:
 It shall be preformed extruded **Omega type** section of **Elastomeric Seal** of such a shape as to promote self removal of foreign material during normal service operations. **Elastomer** of joint seal shall conform to clause 4.2.1 of IRC:83 (Part-II) and satisfy the properties stipulated in IRC SP 69 which shall be as specified in CI **9.1.6.1 (c) – (i)** above.

9.1.7.2 Handling and Storage:

- a) The expansion joint material shall be handled with care and stored under cover.
- b) All joint material and assemblies shall be protected from damage and assemblies shall be supported to maintain true shape and alignment during transportation and storage.

9.1.7.3 Installation:

- a) The expansion joint shall be installed by the manufacturer/supplier or their authorities' representative, who will ensure compliance of installation procedure and instructions.
- b) The dimension of the joint recess **edge beam above deck slab** and the width of the gap shall conform to the approved drawing.
- c) Bolts shall be welded to the main reinforcement in the edge beam deck maintaining the level and alignment of the joint.
- d) Concreting of pocket/recess **edge** shall be done with great care using proper mix conforming to same grade as that of the deck concrete but no less than M30 grade in any case. The water-cement ratio shall not be more than 0.40. If needed, suitable admixtures may be used to achieve the workability. The width of pocket shall not be less than 300mm on either side of the joint. Care shall also be taken to ensure efficient bonding between already cast/existing deck concrete and the concrete in the joint recess **edge beam**.
- e) At the time of installation, joint shall be clean and dry and free from spalls and irregularities, which might impair a proper joint seal.
- f) Concrete or metal surfaces shall be clean, free of rust, laitance, oils, dirt, dust or other deleterious materials.
- g) The joint seal shall be compressed to the specified thickness for the rated joint opening and ambient temperature at the time of installation, which shall be between +05 to +35 degree C.
- h) The joint seal shall be installed without damage to the seal. Loose fitting or open joints shall not be permitted.

9.1.7.4 Acceptance Criteria:

- a) All steel elements shall be furnished with corrosion protection system.
- b) For the joint seal the acceptance test shall conform to the requirements stipulated in para **9.1.7.1 (c)** above. The manufacturer/supplier of this type of joint shall produce a test certificate to this effect conducted in a recognized laboratory in India or abroad.
- c) Prior to acceptance 25% of the completed and installed joints, subject to a minimum

of one joint, shall be subjected to water tightness test. Water shall be continuously ponded along the entire length for a minimum period of 4 hours for a depth of 25mm above the highest point of deck. The width of ponding shall be at-least 50mm beyond the anchorage block of the joint on either side. The depth of water shall not fall below 25mm any time during the test. A close inspection of the underside of the joint shall not reveal any leakage.

9.1.7.5 Tests and Standards of Acceptance:

The materials shall be tested in accordance with these specifications and shall meet the prescribed criteria. The manufacturer/supplier shall furnish the requisite from the recognized testing laboratory of India or abroad.

The work shall conform to these specifications and shall meet the prescribed standards of acceptance.

9.1.7.6 Rates:

The contract unit rate shall include the cost of all materials, labour, equipments, cost of testing including cost of test samples and other incidental charges for fixing the joints complete in all respects as per specifications.

9.1.8 Specification for Compression Seal Expansion Joint

Expansion joint type described here-after is the "Compression seal" type, but alternate designs can be proposed for the Engineer"s approval (e.g. elastomeric omega-shape cover joint, or any other suitable joint type)

9.1.8.1 Compression seal joint shall consist of steel armored nosing at two edges of the joint gap suitably anchored to the deck concrete and a preformed chloroprene elastomer or closed cell foam joint sealer compressed and fixed into the joint gap with special adhesive binder.

9.1.8.2 Material

e) Steel Nosing

The steel nosing shall be of angle section ISA 100 x 100 conforming to weldable structural steel as per IS:2062. The thickness of legs shall not be less than 12mm. The top face of the angle shall be provided with Bleeder holes of 12mm diameter spaced at maximum 100mm centre so as to ensure that there are no voided in the concrete beneath the angle.

f) Anchorage

The anchorage steel shall conform to IS:2062 or equivalent. The steel nosing shall be anchored to the deck by reinforcing bars or anchor plates cast in concrete or a combination of anchor plates and reinforcing bars. Anchor plates and anchor loops, this shall be achieved by passing transverse bars through the loops or plates. The minimum thickness of anchor plates shall be 12mm. Total cross sectional area of

bars on each side of the joint shall not be less than 1600sq mm per m length of the joint and the centre to centre spacing shall not exceed 250mm. The ultimate resistance of each anchorage shall not be less than 600 KN/m in any direction.

g) Corrosion Protection

All steel section shall be protected against corrosion by hot dip galvanizing or any other approved anticorrosive coating with a minimum thickness of 100micron.

h) Joint Seal

- i. The sealing element shall be a preformed continuous chloroprene or closed cell foam seal with high tear strength, insensitive to soil, gasoline and ozone. It shall have high resistance to ageing and ensure water tightness. The seal should be vulcanized in a single operation for the full length of the joint required for carriageway, kerbs and footpaths, if any. The seal shall cater for a horizontal movement up to 40mm and vertical movement of 3mm.
- ii. The physical properties of chloroprene/closed cell foam sealing element shall conform to the following:
 - a) Chloroprene Seal: It shall be preformed extruded multi-web cellular section of chloroprene of such a shape as to promote self removal of foreign material during normal service operations. Chloroprene of joint seal shall conform to clause 915.1 of IRC:83 (Part-II) and satisfy the properties stipulated in Table 2 strip seal element specifications of these specifications except in respect of the working movement range of the sealing element which shall be as specified above.
 - b) Closed Cell Foam Seal: It shall be of preformed non-extruded non cellular section made from low density closed cell, cross linked ethylene vinyl acetate, polyethylene copolymer that is physically brown using nitrogen. The material shall possess properties as indicated in the Table below.

c)

Table-I

S.No.	Property	Special Value
(i)	Density	41.7 – 51.3 kg/cum
(ii)	Compression set on 25mm	50% compression samples (ASTM D 3575) for 22 hours at 23 ⁰ C, 2 hour recovery; 13% set.
(iii)	Working temperature	-70 to +70 ⁰ C.

(iv)	Water Temperature absorptions (total Immersion for 3 months) (ASTM3575)	0.09766 kg/sqm
(vi)	Tensile strength	0.8 Mpa
(vii)	Elongation at break (ASTM D 3575)	195 +/-20%

i) **Lubricant cum Adhesive**

This type and application of material used in bonding the preformed joint seal to the steel nosing and concrete shall be as recommended by the manufacturer/supplier of the seal system.

9.1.8.3 Handling and Storage

- a) The expansion joint material shall be handled with care and stored under cover.
- b) All joint material and assemblies shall be protected from damage and assemblies shall be supported to maintain true shape and alignment during transportation and storage.

9.1.8.4 Installation

- a) The expansion joint shall be installed by the manufacturer/supplier or their authorities representative, who will ensure compliance of installation procedure and instructions.
- b) The dimension of the joint recess and the width of the gap shall conform to the approved drawing.
- c) Anchoring steel shall be welded to the main reinforcement in the deck maintaining the level and alignment of the joint.
- d) Concreting of pocket/recess shall be done with great care using proper mix conforming to same grade as that of the deck concrete but no less than M30 grade in any case. The water-cement ratio shall not be more than 0.40. If needed, suitable admixtures may be used to achieve the workability. The width of pocket shall not be less than 300mm on either side of the joint. Care shall also be taken to ensure efficient bonding between already cast/existing deck concrete and the concrete in the joint recess.
- e) At the time of installation, joint shall be clean and dry and free from spalls and irregularities, which might impair a proper joint seal.

- f) Concrete or metal surfaces shall be clean, free of rust, laitance, oils, dirt, dust or other deleterious materials.
- g) The lubricant cum adhesive shall be applied to both faces of the joint and joint seal prior to installation in accordance with the manufacturer's instructions.
- h) The joint seal shall be compressed to the specified thickness for the rated joint opening and ambient temperature at the time of installation, which shall be between +05 to +35 degree C.
- i) The joint seal shall be installed without damage to the seal. Loose fitting or open joints shall not be permitted.

9.1.8.4 Acceptance Criteria:

- a) All steel elements shall be furnished with corrosion protection system.
- b) For the joint seal the acceptance test shall conform to the requirements stipulated above. The manufacturer/supplier of this type of joint shall produce a test certificate to this effect conducted in a recognized laboratory in India or abroad.
- c) Prior to acceptance 25% of the completed and installed joints, subject to a minimum of one joint, shall be subjected to water tightness test. Water shall be continuously ponded along the entire length for a minimum period of 4 hours for a depth of 25mm above the highest point of deck. The width of ponding shall be at-least 50mm beyond the anchorage block of the joint on either side. The depth of water shall not fall below 25mm any time during the test. A close inspection of the underside of the joint shall not reveal any leakage.

9.1.8.5 Tests and Standards of Acceptance

The materials shall be tested in accordance with these specifications and shall meet the prescribed criteria. The manufacturer/supplier shall furnish the requisite from the recognized testing laboratory of India or abroad.

The work shall conform to these specifications and shall meet the prescribed standards of acceptance.

9.1.8.6 Mode of Measurement

The measurement for expansion joints as a finished work shall be in running meters nearest to a centimeter.

9.1.8.7 Rates

The contract unit rate shall include the cost of all materials (including cast-in-situ concrete), labor, equipments, cost of testing including cost of test samples and other incidental charges for fixing the joints complete in all respects as per specifications.

9.2 WEARING COAT

9.2.1 Asphaltic Wearing Coat

Wearing coat shall be provided as indicated on drawings. It shall consist of the following:

- i. A coat of mastic asphalt 6mm thick with prime coat over the top of deck before the wearing coat is laid. The prime coat of mastic asphalt shall be 30% straight run 30/40 penetration grade bitumen and 50% light solvent (benzol) to be laid over the deck slab. The insulation layer of 6 mm thick mastic asphalt with 75% limestone dust filler and 25% of 30/40 penetration grade bitumen shall be laid at 375 degree F with broom over the prime coat.
- ii. A layer of asphaltic concrete wearing coat of thickness 50 mm to be laid in a single layer.

9.2.2 Concrete Wearing Coat

9.2.2.1 Scope

The work shall consist of laying cement concrete layer of required thickness as indicated on the drawings, It shall not be laid monolithic with the slab.

9.2.2.2 Materials

Materials shall conform to ISI and / or IRC specifications.

9.2.2.3 Construction Operation

- a) For Weather and seasonal limitations shall be as per IRC Standards.
- b) The surface shall be thoroughly swept and scraped clean and made free of dust and other foreign matter. It shall be conditioned to the specified levels, grade and cross fall (camber) as directed by Engineer.
- c) Construction operations such as preparation of mix, laying of concrete, steel reinforcement shall conform to respective specifications in the relevant Chapters.
- d) Curing of wearing coat earlier than what is generally specified may be resorted to, so as to avoid formation of shrinkage cracks in hot weather.
- e) All carriageway and footpath surfaces shall have non-skid characteristics.

9.3 RAILINGS

9.3.1 General

Prefabricated railing as per approved details shall be erected at site Fixing arrangements with deck shall be carefully designed and incorporated.

Railing on bridge shall not be constructed until the centering or form work for the span has been released and the span is self supporting. For concrete and steel,

specifications of the items of controlled concrete and reinforcement mentioned under relevant specifications shall be applicable.

Railing shall be carefully erected true to line and grade. Posts shall be vertical with a tolerance not exceeding 6 mm in 3 m. The pockets left for posts shall be filled up with non-shrinkable mortar.

All edges and corners shall be straight and finished to true line and level. Forms shall either be of single width boards/ plates or shall be lined with suitable materials duly approved by Engineer. Form joints in plain surface will not be permitted. All mouldings, panel work and level strips shall be constructed according to the details shown on drawings.

9.3.2 Metal Railings

9.3.2.1 General

All complete steel/ aluminium railing elements, terminal sections, posts, and other fittings shall be of shape, size and designation of approved material and make as given in the item of work or as directed by Engineer. In case of steel railing all these elements shall be painted with an approved paint. If straightening is necessary, it shall be done by methods approved by Engineer.

Aluminium sections shall be of approved quality, designation and free from scratches, stains and discoloration.

The Contractor shall take every precaution against damage of the components during fixing in position.

Damaged galvanised surfaces shall be cleaned and regalvanised. Special care shall be taken to prevent staining of all products rust, mortar, etc. before it is put into use.

9.3.2.2 Fixing

The railing shall be carefully adjusted prior to fixing in place to ensure proper matching at abutting joints, correct alignment and camber throughout their length.

Fixing shall be strictly as per fixing details shown on drawing or as directed by Engineer.

If sections are not galvanised, railing shall be given one shop coat of paint, and three coats of paint after erection.

All necessary holes, chases, etc., required in fixing shall be made by the contractor and made good after installation, without any extra charge.

9.4 DRAINAGE SPOUTS AND DRAINAGE PIPE**9.4.1 General**

This work shall consist of supply and fixing in position of drainage spouts and drainage pipes for bridge decks and piers true to lines, levels and position in accordance with details shown on drawings and to the requirements of these specifications and drainage plan for structure. Where details are not given on drawings, contractor should prepare and submit his own drawings for approval of Engineer before commencement of work.

All drainage pipes to be embedded in pier shall be HDPE corrugated double wall as approved by the Engineer. The accessories like Tee, Bend, etc shall be jointed with leak proof approved material.

9.4.2 Fabrication

Drainage assembly shall be fabricated to dimensions shown in drawings. All materials shall be corrosion resistant; steel components shall be of mild steel conforming to IS:2062. The drainage assembly shall be seam welded for water tightness and then hot dip galvanised.

9.4.3 Placement

The galvanised assembly shall be given two coats of bituminous paint before placement. The whole assembly shall be placed in true position, lines and level as shown in drawing with necessary cut-out in the shuttering for deck slab and held in position firmly. Where reinforcement of the deck is required to be cut, equivalent reinforcement shall be placed at the corners of the assembly.

9.4.4 Finishing

After setting of deck slab concrete, shrinkage cracks around the assembly shall be totally sealed with polysulphide sealant or bituminous sealant as per IS:1834 and excess sealant trimmed to receive the wearing coat. After the wearing coat is completed, similar sealant, finished to cover the wearing coat surface all-around the drainage assembly, shall be provided at least 50 mm.

9.5 CINDER**9.5.1 General**

Cinder to be used for filling in floors shall be obtained from furnace of steam boilers using coal fuel only. It shall be clean and free from clay dirt, wood ashes or other deleterious matter. It shall pass through IS Sieve designation 3.35 mm with at least 50% of it passing through IS Sieve designation 1.70 mm. Cinder obtained from brick kilns shall not be used. At site of work, the cinder shall be protected from dirt collecting on it and could be used for filling in drops only.

9.6 **SEALANTS**

9.6.1 **General**

Joint sealing compounds shall seal joints in concrete against the passage of water, prevent the ingress of grit or other foreign material and protect the joint filler. The compound shall have good extensibility and adhesion to concrete surfaces and shall be resistant to flow and weathering.

Approved Sealant where specified on the drawings shall be provided strictly in accordance with the manufacturer's written instructions, such joints shall be formed to the correct dimensions, thoroughly cleaned and treated with recommended primer strictly in accordance with the manufacturer's written instructions prior to sealing. Wherever width of gap to be sealed is wide enough to necessitate the use of backer rod, the same shall be provided at no extra cost. The contractor shall use only competent personnel experienced in the application of sealant for such work.

Where specified in the drawings, silicon/ polyurithane/ polysuphide based sealants shall be of an approved manufacture. The treatment of the joint and the use of sealing compound shall be strictly in accordance with the manufacturer's written instructions. The entire work shall be carried out as per IS:3414, IS:6509, IS:11433.

Sealants shall be as follows:

Silicon sealant shall be one part gungrade type with minimum movement capability of 25% and elongation at break of 450% confirming to BS 5889 or TTS 001543A. This Sealant shall be of approved color and shall be non-staining to the parent concrete surface.

9.6.2 **Ancillary Materials**

The Contractor shall provide all ancillary materials such as cleaning solutions, epoxy mortar, primer, tool cleaner, bond breaker type, filler boards, back up material, backing rods, polyethylene foam, masking tapes, sealant slot former etc.

9.6.3 **Primer**

Primer for sealants shall only be as recommended by the sealant manufacturer and approved by Engineer, Primer shall have been tested for compatibility and durability with the sealant to be used and on samples of the surfaces to be selected.

9.6.4 **Backdrop Material**

Backdrop material shall be an expanded polyethylene of nominal density 35 kg/cum as recommended by the sealant manufacturer. It shall be of non-absorbent and non-staining material compatible with the sealant used. Tube or rod stock shall be rolled into the joint cavity.

9.6.5 Bond-preventive Materials

Bond-preventive materials shall be pressure-sensitive adhesive polyethylene tape or aluminium foil.

9.6.6 Equipment

The Contractor shall inter alia provide the following plant and equipment for the work.

T-paddle, follower plate, solid barrel gun, plastic nozzle, wire brush, heavy duty 500 rpm electric drill, palette knife, masking tape and paint brush for priming etc.

9.6.7 Working Life

Care shall be taken to ensure that material with adequate shelf life is provided. Material whose shelf life is over shall not be used in the works and shall be removed from the site forthwith. Depending on the storage, temperature and humidity, only one unit shall be drawn from the storage.

9.6.8 Curing Period

No portion of the work where sealant has been applied shall be allowed to be submerged or be wetted by any liquid for a period of 7 days after application of the sealant. This period may be modified depending on the temperature and humidity prevalent at the time.

9.6.9 Environmental Requirements

The ambient temperature shall be within the limits as given by the manufacturer, when the sealants are applied. The work shall not be carried out in a dusty atmosphere or when it is raining or when the humidity is high.

Sealants shall not be applied when the ambient temperature is below 4 degree C. When the ambient temperature is below 10 degree C but greater than 4 degree C, the sealant containers shall be stored for some hours at 21 degree C, to ease mixing and application.

9.6.10 Delivery and Storage

Materials shall be delivered to the job site in the manufacturer's original unopened containers.

The containers shall include the following information on the label.:

- a) Name of supplier,
- b) Name of material,
- c) Formula,
- d) Lot number,
- e) Colour
- f) Date of manufacture,
- g) Mixing instructions
- h) Shelf life and
- i) Curing time

Materials shall be carefully handled and stored to prevent contamination of foreign materials to exposure to temperatures exceeding 35 degree C.

9.6.11 Joints

The effective width to depth ratio shall be as per the table given below unless directed otherwise by the Engineer.

Table

Surfaces	Joint Width	Joint Depth	
		Minimum	Maximum
For concrete masonry or stone:	6 mm	6 mm	6 mm
	Over 6 mm upto 12 mm	6 mm	Equal to width
	Over 12 mm	½ of width	½ of width

9.6.12 Surface Preparation**General**

The surface of joints to be sealed shall be clean, dry, sound and free of all release agents, water repellents, laitance, oil, grease, dirt, chalk, particles of mortar, dust, loose rust, loose mill scale and other foreign substances. Oil and grease shall be removed with solvent and the surfaces shall be wiped with clean clothes.

9.6.13 Concrete and Masonry Surfaces

Where surfaces have been treated with curing compounds, oil or other such materials, the materials shall be removed by sandblasting or wire brushing. Laitance, efflorescence and loose mortar shall be removed from the joint cavity. The surfaces/edges shall be repaired with epoxy mortar to give smooth and even surfaces to correct lines and levels with a uniform gap for the length to be sealed.

9.6.14 Application**Masking Tape**

Masking tape shall be placed on the finished surface on one or both sides of a joint cavity to protect adjacent finished surfaces from primer or compound smears. The masking tape shall be removed within 10 minutes after the joint shall be filled and tolled.

9.6.15 Bond-preventive materials

Bond-preventive materials shall be installed on the bottom of the joint cavity and other surfaces to prevent the sealant from adhering to the surfaces covered by the bond-preventive materials. The materials shall be carefully applied to avoid contamination of adjoining surfaces or breaking bond with surfaces other than those covered by the bond-preventive materials.

9.6.16 Backstops

The back or bottom of joints constructed deeper than specified shall be packed tightly with an approved backstop material to provide a joint of the depth specified.

9.6.17 Primer

The primer shall be used in accordance with the manufacturer's instructions. The primer shall be applied to the joint surfaces to be sealed only and not spill over or be applied to surfaces adjacent to the joints.

9.6.18 Application of Sealant

The sealant shall be gun-applied with a nozzle of proper size to fit the width of the joint indicated and shall be forced into grooves with sufficient pressure to expel air and fill the groove solidly. The sealant shall be uniformly smooth and free of wrinkles.

The plastic nozzles shall be inserted on the gun and cut to appropriate size. The sealant shall be gunned into joints using an even trigger pressure. The nozzle shall be cleaned occasionally.

The sealant shall be pressed into joints with a wet spatula and tooled within five minutes of application. The joint shall be tooled slightly concave after the sealant is installed. The tooled joint shall present a smooth and professional joint giving the desired finish and shape. The masking tape shall be removed immediately after tooling.

Application equipment shall be cleaned with a tool cleaner, recommended by the manufacturer, after wearing PVC or rubber gloves and whilst the sealant is still in an uncured state.

9.6.19 Cleaning

The surfaces adjoining the sealed joints shall be cleaned of smears and other soiling resulting from the sealing application as the work progresses. Sealant adhering to, porous surfaces shall be left until it is just cured and then removed by abrasion or other mechanical means.

9.7. FIRE PROOFING OF STEEL STRUCTURES

It includes the supply, application, and testing of a three-layer fire-resistant coating system for structural steel, comprising:

- 1.1 Fire-resistant primer (silicon epoxy-based)
- 1.2 Fire-resistant base coat (silicon epoxy-based intumescent)
- 1.3 Fire-resistant topcoat (silicon epoxy-based)

The coating system must provide a fire resistance of 2-4 hours, ensuring protection against fire, corrosion, and environmental damage.

2. System Components and Technical Details

2.1 Primer

- i) Type: Silicon epoxy-based fire-resistant primer
- ii) Dry Film Thickness (DFT): Minimum 75 microns
- iii) Purpose: Provides adhesion and corrosion resistance

2.2 Base Coat

- i) Type: Silicon epoxy-based intumescent fire-resistant coating
- ii) Dry Film Thickness (DFT): Minimum 400 microns per coat
- iii) Purpose: Expands under heat to form a protective layer

2.3 Topcoat

- i) Type: Silicon epoxy-based fire-resistant topcoat
- ii) Dry Film Thickness (DFT): As required for environmental protection
- iii) Purpose: Provides UV, moisture, and mechanical resistance

3. Performance Requirements

- i) Fire Resistance: 2-4 hours as per UL 94, BS 476 Parts 20/21/22, ASTM E 119
- ii) Solids Content: Minimum 78% by volume (all layers)
- iii) Density: Above 1.30 g/cm³ for base and topcoats
- iv) Spreading Rate: 2 m² per kg per coat for base coat

Properties:

- i) Impact resistance
- ii) Air erosion resistance
- iii) Minimal water absorption
- iv) Anti-mold and anti-fungal properties

4. Application Methodology

1. Surface Preparation:

Steel surfaces shall be cleaned to SA 2.5 (near-white metal finish).

2. Primer Application:

Apply primer to achieve a DFT of 75 microns.

Allow sufficient curing before applying the base coat

3. Base Coat Application:

Apply the base coat in layers to achieve a DFT of 400 microns per coat.

Use airless spray, brush, or roller for uniform application.

4. Topcoat Application:

Apply topcoat after the base coat has fully cured.

5. Testing and Certification

5.1 On-Site Testing: Coating thickness, adhesion, impact resistance, and water absorption to be verified.

5.2 Fire Resistance: To be tested by NABL or Government of India-approved laboratories.

Mechanical Properties: Air erosion and fungal resistance to be certified.

6. Warranty

The coating system shall be covered by a 5-year warranty for performance and durability under specified conditions.

7. Environmental and Safety Compliance

Materials must comply with low VOC (Volatile Organic Matter) and environmental regulations.

Proper PPE must be used during application to ensure worker safety.

All materials and products shall conform to the relevant standard specification, IS codes and other relevant codes etc. and shall be of approved makes and design.

9.8

POLYCARBONATE ROOF/WALL PANELS

The multi-cell polycarbonate panel to be used for Roofing/Wall Panels should have the following specifications:

- a) Two side Co-extrusion for UV rays protection
- b) Panels have to be joined together by protected polycarbonate connector/aluminium connector/any other mechanism that makes joint perfectly water tight.
- c) 10 years warranty
- d) Thermal Insulation $\geq 1.50 \text{ W/m}^2\text{K}$ Acoustic Insulation $\geq 20\text{dB}$
- e) Linear Thermal Expansion $= .065\text{mm/m degree C}$ Temperature Range (-20 degree to 120 degree C) Fire Reaction BS1d0 or better as per EN 13501

9.9

FLY ASH BASED PRODUCTS:

Fly ash based products such as Mechanized Autoclaved Sand Lime Fly ash Bricks/ Fly Ash Lime Gypsum Bricks/Autoclaved Aerated Concrete (AAC) Blocks have to be used in all construction activities.

9.10**ROOF TOP(SOLAR)**

The roof top solar PV system shall be mandatorily implemented at depots and metro stations with the specifications as below.

- a) Hot dip galvanized MS mounting structures (with 1000 gm/m² zinc mass coating) may be used for mounting the modules/ panels/arrays. Each structure should have angle of inclination as per the site conditions to take maximum irradiation. However to accommodate more capacity the angle inclination may be reduced until the plant meets the specified performance ratio requirements.
- b) The Mounting structure shall be so designed to withstand the speed for the wind zone of the location where a PV system is proposed to be installed (like Delhi-wind speed of 180 km/ hour). It may be ensured that the design has been certified by a recognized Lab/ Institution in this regard and submit wind loading calculation sheet to DMRC. Suitable fastening arrangement such as clamping should be provided to secure the installation against the specific wind speed.
- c) The mounting structure steel shall be as per latest IS 2062 and as per Contract condition.
- d) Structural material shall be corrosion resistant and electrolytically compatible with the materials used in the module frame, its fasteners, nuts and bolts. Aluminum structures also can be used which can withstand the wind speed of respective wind zone. Necessary protection towards rusting need to be provided either by coating or iodization.
- e) The fasteners used should be made up of stainless steel. The structures shall be designed to allow easy replacement of any module. The array structure shall be so designed that it will occupy minimum space without sacrificing the output from the SPV panels. Installation of solar structure should not damage the roof in any way. If any concrete or foundation is required, it should be preferably precast type.
- f) The bidder needs to take care of the load bearing capacity of the roof and need arrange suitable structures based on the quality of roof.
- g) The total load of the structure (when installed with PV modules) on the terrace should be less than 80 kg/m².

9.11**TEMPORARY GROUND ANCHOR AND SOIL NAIL****SOIL NAILS**

Soil nailing usually involves the insertion of reinforcement bars (Hollow/solid) into the exposed slope followed by grouting, placement of a wire mesh and shotcreting before the testing and locking off of the nail through stressing jacks. Hollow soil nail bars can also be self-drilling thus acting as drilling rods with expendable drill bits. Testing, Test Frequency and Acceptance Criteria for Soil Nails shall be as per drawing/relevant codes.

The temporary ground anchors installed to support the diaphragm wall or secant piles shall be as follows:

9.11.1 General

This specification deals with temporary ground anchors and shall be read in conjunction with the conditions of contract and the Specification for Excavation. A temporary ground anchor means wherein the contractor proposes to use ground anchors as part of his Temporary Works. A ground anchor is a structural element installed in soil or rock that is used to transmit an applied tensile load (as a result of horizontal earth pressure) into the ground. The Contractor shall comply fully with the requirements of this specification in the design, erection and installation of ground anchors.

Where works are ordered to be performed by the Contractor but are not specified in this specification, the Contractor must carry them out with full diligence and expedience as are expected for works of this nature and shall comply with the relevant clauses of the codes – IS14448, IS10270, FHWA recommendations, BS 8081, ACI440.6, IS456 and PTI recommendations for prestressed rock and soil anchors (2004).

This contract to be carried out by specialised agency which has capability in following:

1. to design and supply the anchor
2. to assemble, install, grout and stress the anchor.

There can be one specialized agency for both above or there can be two separate specialized agencies for each of the activities. However, each of the specialized agency must have completed at least one project in India of similar material, nature and job application.

9.11.2 Reference Standards

IS14448, IS10270, FHWA recommendations, BS 8081, ACI440.3, ACI440.6, IS456 and PTI recommendations for prestressed rock and soil anchors (2004).

9.11.3 Design By Specialised Contractor

The Contractor shall include in the submission, for the Engineer's review, his proposed design of ground anchor with Assembly drawings. Unit rates of ground anchors shall be based on the allowable anchor forces required for the safe and adequate performance. The Contractor's submission of calculations and shop drawings shall include the following information:

- a) Anchor layout
- b) Anchor design details
- c) Anchor structural and geotechnical design capacity
- d) Grade and properties of the tendon material
- e) Percent of tendon ultimate load at working load
- f) Grout - cement type, strength, additives

- g) Anchor load, length, and bond diameter
- h) Anchor free stressing length and de-bonding details
- i) Initial lock-off load of anchor
- j) Anchor bond length or fixed length design details
- k) Endorsement by the Contractor's Professional Engineer
- l) Any other information required by the Engineer in his review of the Contractor's design.

The Contractor's design calculations and specifications shall comply fully with the relevant recommendations of reference codes. In matters not specifically covered by the reference codes and the Engineer's specifications, the Contractor's design shall be in accordance with accepted principles of good engineering practice. It shall be the Contractor's responsibility to clearly itemise those matters.

The review of the Contractor's design by the Engineer does not in any way absolve or reduce the duties and responsibilities of the Contractor to ensure the safety and adequacy of his works.

9.11.4 Method Statement For Construction Operations

Prior to commencement of works, the Contractor shall submit to the Engineer a detailed method statements, for the installation of ground anchors. For the purpose of this Clause, a method statements shall be a document containing

- a) A detailed construction sequence
- b) Proposed drilling method
- c) Proposed installation method
- d) Proposed grouting, stressing method and equipment
- e) Material and plant requirements at each construction stage.
- f) Shop drawings.
- g) Methods of testing.

The Engineer shall inform the Contractor in writing within 14 days after receipt of the Contractor's method statement either

- a) that the Contractor's proposed methods have the consent of the Engineer; or
- b) in what respect, in the opinion of the Engineer, the proposed methods fail to meet the requirements of the contract

9.11.5 Inspection & Testing

The Engineer shall inspect the installation of anchors and will monitor anchor stressing acceptance tests to ensure that the Contractor's anchor design and construction method

will produce the suitable anchorage system in the soil/rock conditions encountered on site.

The testing of concrete and grout shall be in accordance with the provisions for works concrete in the General Concrete Specification.

9.11.6 Compliance Inspection

The Engineer shall carry out inspection to ensure that the Contractor follows the approved shop drawings and good engineering practice.

9.11.7 Acceptability

Acceptance test shall be carried out on all temporary ground anchors; in accordance to EN1537. Failure of any anchor to meet acceptance test criteria will result in rejection of the anchor in question. Consistent failure of a given anchor type require reassessment of the anchor design and installation practices.

9.11.8 Materials

9.11.8.1 General Requirments

The temporary ground anchor should be a grouted multi-strand system that is post-tensioned prior to excavation.

The requirements listed in the following clauses shall apply, wherever relevant, to materials used in all anchors. The handling, storage and use of materials shall comply with manufacturers' instructions.

9.11.8.2 Tendons

Post-tensioned tendons shall comply with the following:

- a) Hybrid GFRP/Steel system with minimum system ultimate tensile strength of 250 kN
- b) GFRP bar shall be solid round bar of 19mm dia conforming to ASTM D2583, nominal c/s area 284sqmm, Ultimate tensile load of min 300 KN, modulus of elasticity of 50 GPa and ultimate strain of 2.11%.
- c) Stressing tail of not more than 2 metres to be made of high tensile steel strand with a diameter of 15.2mm and minimum ultimate tensile stress of 1860 MPa, a modulus of elasticity of 195 GPa, maximum relaxation of 2.5% and c/s area of 139mm²; conforming to IS14268 class 2.
- d) PT steel strand and GFRP bar to be connected with a steel coupler. Usage of glue or grout for bonding of the couplers with FRP profile is not permitted. The steel connection should not be more than 350mm in length.
- e) In case of GFRP tendon longer than 11.8m, steel coupler to be used. The steel

connection should not be more than 350mm in length.

A manufacturer's certificate shall be submitted to the Engineer containing all the relevant information as mentioned above. A full system ultimate loading (FRP+Coupler+PT Strand) to be submitted for at least 5 samples per lot.

GFRP material is cuttable or breakable in nature, with coherent inert properties, and so can be left inside the ground. Since both the free length and bond length of the temporary ground anchor is made of GFRP, it doesn't need to be removed from the ground once redundant.

9.11.8.3 Cement Grout

Grout shall consist of ordinary Portland cement OPC43/OPC53 grade or more obtained from approved manufacturer/supplier.

Admixtures shall comply with the requirements of BS 5075: Part 1: 1982 and BS 5075 : Part 3: 1985 and shall only be used with the prior agreement of the Engineer.

Grout cubes of 100mm size shall be prepared and cured in accordance with BS 1881 : Part 3 : 1970, and the strength of grout cubes shall be tested in accordance with BS 1881 : Part 4 : 1970. The grout shall have a minimum compressive strength measured on 100mm cubes 20 N/mm² at 3 days and 35 N/mm² at 28 days. Collection of grout shall be from the grout overflowing from the drill hole unless otherwise agreed by the Engineer.

Admixture, if used, shall be provided at the Contractor's own expense. Admixtures shall impart to the grout the properties of low water content, good flow ability, minimum bleeding and controlled expansion. Its formulation shall contain no chlorides or other chemicals in quantities that may have harmful effects on the cement or prestressing steel. The Contractor shall submit to the Engineer the manufacturer's literature indicating the type of admixture and the manufacturer's recommendations for mixing the admixture with the grout. All admixtures shall be used in accordance with the instructions of the manufacturer.

9.11.8.4 Plastics

PVC Pipe – UNBONDED LENGTH

A PVC sleeve encasing individual tendon shall be used as part of the corrosion The PVC tube shall be conforming to DIN 8074 & DIN 8075 and IRC:18-2000. The ends of the sleeve shall be sealed with neutral mastic.

9.11.9 Corrosion Protection

Being GFRP (an inert material) used for anchor, no specific corrosion protection is required for tendons.

9.11.10 System Components**9.11.10.1 General**

The anchor shall be designed to provide an ultimate load holding capacity of not less than specified.

9.11.10.1 Free And Fixed Anchor Length

The free anchor length is the distance between the anchor head and the proximal end of the grout. The fixed anchor length is the length of anchorage over which the tensile load is capable of being transmitted to the surrounding ground. The fixed anchor length shall not be less than 3m for all anchors subjected to acceptance tests.

9.11.10.1 Spacers & Centralizers

Spacers shall be provided on multi-tendon anchors to ensure separation between the individual components, and to ensure individual tendons are positioned uniformly over the cross-section of the drill hole.

Centralisers shall be provided on multi-tendon anchors to ensure separation between the individual components, and to ensure individual tendons are positioned uniformly over the cross-section of the drill hole.

9.11.10.1 Anchor Head Components

The anchor head components which retain the force in the stressed tendon shall comply with the requirements of BS 4447 :1973.

The anchor head shall be designed so as not to induce secondary stresses in the tendon. Wedges should be fitted between anchor head and support plinth, unless the anchor head permits compensation for angular deviations of the tendon from the axial position.

The anchor head design for temporary anchorages shall permit in-service tests to be made as long as such tests are required.

9.11.11 Equipment

All stressing equipment must be used in accordance with the specifications of the manufacturer and Clause 9 of BS 8081:1989 and must at all times be maintained in good condition.

The pumps, jacks and all tensioning equipment shall be calibrated. All calibrations must be conducted by an approved laboratory with the necessary equipment and must be certified. The calibrations shall be carried out no longer than 3 months prior to using the equipment on site. If any incident occurs during transportation, handling or tensioning which may have caused damage, the equipment must be recalibrated.

Anchor stressing shall be in the manner specified in the approved shop drawings and approved method statement. Stressing shall not be carried out until the grout has reached its specific strength.

All equipment used for fabrication, handling and placing shall be such that it will not damage the anchor tendons.

The grouting equipment shall be capable of continuous mechanical mixing to produce a grout free of lumps and undispersed cement. A manifold system with a series of valves and calibrated pressure gauge with a capacity of 10 N/mm² shall permit continuous circulation and pumping of grouting with accurate control of grout pressure.

Stressing equipment shall be capable of applying at least the specified test load to the anchor tendon. A calibrated pressure gauge indicating the hydraulic jack pressure should, as a minimum requirement, comply with class 2 of BS 1780. They should be supplied with a calibration certificate and shall read to an accuracy of at least $\pm 3\%$ of the load applied.

9.11.12 Anchor Fabrication

Anchors shall be either shop fabricated or field fabricated in accordance with approved shop drawings, using personnel trained and qualified in this type of work.

9.11.13 Drilling

Holes for anchors may be formed by drilling method. The drilling method used shall be subjected to the agreement of the Engineer. Full temporary casing shall be installed to maintain a clean and open shaft and prevent wash out of fines outside the casing in all holes. Grouting shall be carried out with the temporary casing inside the hole and after fresh grout emerge from the hole, then only the temporary casing can be slowly retrieved while grouting continue. Any alternative method shall be approved by the Engineer.

Drill holes for ground anchors shall be provided in accordance with the Drawings. The drill hole entry point shall be positioned within a tolerance of $\pm 75\text{mm}$. Deviation in alignment shall not exceed 1 in 30.

The Contractor shall keep a record of all drilling procedures and times, which shall be made available to the Engineer.

9.11.14 Anchor Installation

The installation of the tendons shall be supervised by suitably qualified personnel familiar with this type of work. All equipment used for handling and insertion of the anchor shall be such that it will not damage the anchor tendon and corrosion protection.

Grout tubes shall be flushed with water or compressed air to ensure that they are clear.

The anchor bonded lengths as indicated in the approved design submissions shall be considered the minimum bonded lengths, and shall be located within the specified bond zone of the anchorage stratum.

The Contractor shall maintain a record showing the anchor type, length, position and installation date for each anchor.

9.11.15 Anchor Testing**a) Suitability Test**

As per EN1537

b) Pull Out Test

As per EN1537

c) Performance Test

100% anchors will be stressed up to 125% of working load during installation and then reduced to lock-off load of 110% of pre-load (no incremental loading or hold time); such that all anchors will be subjected to performance test during installation.

9.12 JOINT FILLER BOARD

Synthetic Joint filler board for expansion joints shall be used only at abutting structures like bridges and shall be 20-25mm thickness within a tolerance of $\pm 1.5\text{mm}$ and of a firm compressible material and complying with the requirements of IS:1838, with a compressibility more than 25 percent. It shall be 25mm less in depth than the thickness of the slab within a tolerance of $\pm 3\text{mm}$ and provided to the full width between the side forms. It shall be in suitable lengths which shall not be less than one lane width. If two pieces are joined to make up full width, the joint shall be taped such that no slurry escapes through the joint. Holes to accommodate dowel bars shall be accurately bored or punched out to give a sliding fit on the dowel bars.

9.13 PAINTS FOR FINISHING WORKS

Various types of paints are used in the station areas for the finishing works. However, considering the advancements in the painting/coating system, the paints/coatings having

the necessary certificate for the fire-retardant properties shall be used for the finishing works only after the approval of engineer.

9.14 SPECIFICATION FOR FRP MANHOLE COVER

9.14.1 Material Specification

Manhole cover and its supporting frame shall be of FRP material. Cover shall have a clear opening of 600mm x 600mm with abrasion resistant top layer with locking and lifting arrangement. Cover and frame shall be UV, chemical, weather, and high impact resistant. FRP cover shall have min. 2.5 Tons load bearing capacity.

Contractor shall submit the manufacturer's specification for the approval of Engineer.

9.14.2 Testing

Testing shall be carried out as per manufacturer's specification and in line with BS EN124, IS 1726, IS 12592 and AASHTO standards. Nothing extra will be paid for the testing.

9.14.3 Fixing of Cover/Frame

Concrete bed shall be prepared considering the height of the frame. Frame shall be completely embedded in a minimum of M-35 grade concrete. The level of concrete bed must be flat so that entire frame is uniformly supported. The frame after fixing must be allowed to rest in concrete for a minimum of 48 hours before its use.

Contractor shall submit detailed shop drawing and method statement for approval of Engineer prior to the start of work.

SECTION S.10

SPECIFICATIONS FOR PRECAST CONSTRUCTION

10.0 GENERAL

There are different types of superstructure configurations being used in metro structures, viz I-Girder, U Girder/Twin U Girder, segmental box girder etc. Some special span superstructures are of Steel structure, composite steel structures, CLC structures etc.

Some Precast configurations are being used profusely in Metro constructions. The specifications for the same are being provided herewith.

10.1 U GIRDER

With the huge development of large cities worldwide, the need for efficient grade separated LRT or MRT systems is increasing significantly. In urban areas, developing countries, and where the geological conditions are unfavourable, the construction of tunnels leads to very high infrastructure costs and long construction period, which slows down the development of these transportation systems. So, LRT/MRT owners often decide to put transit systems on long viaducts. However, environmental considerations require that great attention is paid to landscaping, architectural appearance, and noise impact for these infrastructures, which are built amidst an urban environment. The U shape prestressed concrete deck is an economically efficient answer to requirement of urban development.

This U deck has many advantages compared to conventional box-girder type deck. But there are also Constraints to take into account for the design.

10.1.1 Construction Methods

Twin U-Girder

For long viaducts, it is obviously interesting to use precasting.

In the case of a single track section ("small U"), and moderate span lengths (up to 30m), the weight of a complete span is much reduced (below 220 t), so that full spans can be precast. In this case, longitudinal pre-tensioning is generally provided, since it is more economical than post-tensioning (no anchorages, no ducts, no grouting).

Generally, Two spans, i.e. four precast U girders, can be assembled each night, with the help of two cranes (average 1 hour per U girder including moving and adjustments of the cranes), subjected to traffic conditions and efficiency of machinery and personnel deployed



Figure 1: Placing full precast span (with crane)

Alternatively, elements can be transported at the deck level and erected with an overhead launching girder, particularly if the transport of the elements at grade is a problem (extremely congested cities).



Figure 2: Placing full precast span (with launching girder)

10.1.2 Material Specifications

10.1.2.1 Cement

Ordinary Portland Cement of 53 grade conforming to IS: 269 shall be used. For prestressed concrete, cement conforming to IRS T-40 specification or OPC-53 with flyash or without flyash Grade shall be used. All other specification will remain same as indicated in section S.03.

10.1.2.2 Reinforcement

Only TMT bars shall be used. All other specification will remain same as indicated in section S.05

10.1.2.3 Prestressing Steel

Uncoated stress relieved Low Relaxation Steel conforming to IS: 14268, Class 2, shall be used. Nominal dia. shall be 15.2 mm with 1860 MPa tensile strength and minimum breaking strength of 259 KN and minimum 0.2% proof load of 228 KN.

The prestressing steel accessories shall be subjected to an acceptance test prior to their actual use on the works. (Guidance may be taken from BS: 4447). Only multi-strand jacks shall be used for tensioning of cables. Direct and indirect force measurement device like Pressure Gauge) shall be attached in consultation with system manufacturer.

10.1.2.4 Concrete

The 28-day concrete strengths measured on 150mm cubes to be adopted for various structural elements have been indicated in the Bill of Quantities.

The physical and chemical properties of the constituents of concrete and so also of the green and hardened concrete shall meet the requirements of MORTH Specifications for Road and Bridge Works, where relevant or where the standard specifications referred to in the Technical Specifications are silent.

10.1.2.5 Permanent Prestressing

The permanent prestressing (for pre-cast piercap or other type of span where post tensioning is required cables shall generally be of the type 19K15 and 12K15, as suited to 19 nos. and 12nos. strands of 15.2mm nominal dia. Intermediate numbers of strands may also be specified in the design, for which suitable anchorage heads shall be used. All aspects of prestressing including the system proper shall be subject to the approval of the Engineer. The corrugated sheathing shall be of HDPE.

Maximum anchorage set- in shall be 6mm. Maximum friction ratios shall be 0.0020m-1 and 0.17 rad-1

10.1.3 Shop Drawings and Design Calculations for Construction Procedures

10.1.3.1 General

The Contractor shall submit according to a schedule, complete details and information concerning the method, materials, equipment and procedures he proposes to use. These shall be called "Method Statements". Method Statements shall be submitted sufficiently in advance of the start of superstructure field construction operations, so as to allow the Engineer adequate review period, which shall not be less than 30 days. The submittals shall invariably include step-by-step erection procedure.

The Contractor's Method Statements shall also include all calculations, drawings and information as may be relevant.

10.1.3.2 Design Calculations for Construction Procedures

Design assumptions and calculations shall be submitted for temporary prestressing, false work, erection devices, formwork or other temporary construction which may be required to complete the work.

Assumptions and Calculations shall also be submitted to substantiate the system and method of permanent and temporary prestressing proposed by the Contractor.

10.1.4 Casting, Handling, Transportation and Erection of Girder

10.1.4.1 General

The Contractor shall submit detailed Method Statements for casting, handling, transportation and erection of girder. The superstructure shall be erected by the method indicated in the tender or by alternate method submitted by the Contractor, subject to the approval of the Engineer. The stressing system, cage of reinforcement and lifting details shall be successfully demonstrated on sample segment prior to casting any permanent segments.

All handling and erection plant and equipment shall be load tested prior to their use at site or when specifically asked for by the Engineer. Any additional material required to cater to any temporary condition including temporary prestressing shall be borne by contractor and nothing extra will be paid in this account.

10.1.4.2 Casting

Casting bed and forms shall be structurally adequate to support the girders without settlement or distortion. The casting bed shall be designed for the hardware needed to adjust and maintain grade and alignment. Special consideration shall be given to those parts of the forms that have to change in dimensions. To facilitate alignment or adjustment, special equipment such as wedges, screws or hydraulic jacks shall be provided. Fittings shall not interfere with stripping of forms. External vibrators shall supplement the internal vibration if necessary and be attached at locations that will ensure maximum consolidation.

Details for casting bed and hardware for adjustment shall be submitted by the Contractor for the Engineer's approval. Casting of girders shall be done in a single pour. Construction joint is not permitted in girder.

Care shall be taken to ensure that deformations due to thermal gradients caused by the heat of hydration of the new cast concrete are negligible. These deformations shall be prevented by properly protecting with curing blankets and plastic sheeting.

Reinforcing steel shall be fabricated in cages and placed according to the Execution Drawing issued by concerned organisation. Any conflict or interference with the proper location of reinforcement or block-outs shall be promptly resolved and corrections made as directed by the Engineer/Engineer's Representative.

All girders shall be marked on the inside with a unique identification at the time of form removal.

10.1.4.3 Handling / Erection of Girders

The Contractor shall be responsible for the proper handling, lifting, storing, transporting and erection of all girders so that they may be placed in the structure without damage. Only HTS bar shall be used for lifting/handling of girder at any stage of construction, with due care for

fatigue considerations (multiple re-use).

Girders shall be maintained in an upright position at all times and shall be stored, lifted and/or moved in a manner to prevent torsion and differential deformation other undue stress. Members shall be lifted, hoisted or stored with lifting devices approved on the shop drawings.

The Contractor shall furnish calculations to establish that the stresses induced during any stages of construction shall not exceed 50% of the cube strength achieved at that stage, nor 40% of the specified 28days cube strength. In addition, the following limitations shall be observed:

- a) The girder shall not be lifted from the casting bed till the concrete reaches a minimum cylindrical strength of 20 MPa (or 25MPa Cube strength).
- b) The age of the concrete shall not be less than 14 days at the time of its erection provided it has achieved its specified strength as per design requirements.

Girders shall be stacked with three point support in curing tank / stacking yard as shown in tender drawing, or as approved by concerned organisation Curing shall be done using sprinkler system (assisted by steam curing in the initial stages if adopted) and it has to be ensured that all parts of girder are water cured during water curing period. Curing compound as per relevant specifications may be applied after approval of Engineer

10.1.4.4 Cleaning of Girders

Before transportation of girder, surface shall be cleaned by water rinsing or sand blasting as approved by the Engineer.

10.1.5 Miscellaneous

The entire construction work shall be geared towards minimising disruptions to road traffic. Also, the occupation of roads during all construction activities shall be reduced to a minimum and subject to the approval of the Engineer. Reinforcement shall be fabricated in cages in casting yard for piles, pile caps and piers before being brought into position for expediting the activities.

All elements of sub-structure below bearing pedestals viz piles, pile caps, piers and pier caps shall each be cast in single pour.

10.1.6 Load Testing of Standard Span of Superstructure

The contractor shall conduct full scale load test for one Girder (simply supported span, erected in position, including arrangements for applications of serviceable vertical load for measuring deflections and rotations and submit the report).

The sequence of placement and position of loading on the girder shall be as directed by the engineer.

10.1.7 Overhead Gantry Specifications For U Girder

10.1.7.1 Nomenclature

The following terms and abbreviations are used in this report:

LG	Launching Gantry or Erection Gantry
MT	Main Truss
UCB	Upper Cross Beam
LB	Lifting Beam
CB	Connection Beam
(F/R)RS	(Front/Rear) Roller Support
(F/R)LCB	(Front/Rear) Lower Cross Beam
LSF	Lower Support Frame
F/RS	Front/Rear Support Leg
Stress bar	Threaded stress bar
LSJ	Long Stroke Jack
Long.	Longitudinal
Trans.	Transverse
Ecc.	Eccentricity
-NA-	Information Not Available
EJ	Expansion Joint
TBA	To Be Advised

10.1.7.2 Structural design codes & load factors

The design of the gantry shall be based on a limit state design approach. The design codes used for the structural design of steelwork include the following:

- a) IS800 or any other suitable international code of practice.
- b) The load combinations, load factors and material resistance factors will be appropriate for each of the design code(s).

10.1.7.3 Stability factors of safety

For all possible scenarios of operation, the factor of safety for stability shall be established.

However, for certain controlled conditions, a reduction in the required factor of safety against instability can be considered, provided that the potential risks are assessed and it is deemed sufficiently safe. However, the factor of safety against overturning should not be less than 1.2.

10.1.7.4 Friction Factors

The following friction factors shall be assumed:

- a) Crane wheels (adverse): 1.0%
- b) Lateral guide wheels and flanges of crane wheels (adverse): included above
- c) Crane wheels (beneficial): zero
- d) Lateral guide wheels (beneficial): zero
- e) Teflon/stainless steel (adverse): 5%
- f) Teflon/stainless steel (beneficial): zero
- g) Ecotex (Nylatron)/stainless steel (adverse): 10%
- h) Ecotex (Nylatron)/stainless steel (beneficial): 5%
- i) Brass (or bronze)/steel – greased (adverse): 20%
- j) Brass (or bronze)/steel - greased (beneficial): 5%
- k) Steel/steel – greased (adverse): 30%
- l) Steel/steel – greased (beneficial): 5%

10.1.7.5 Dynamic factors & launching forces**a) Stationary MT**

The following dynamic factors are to be used for consideration of moving loads when the MT is stationary:

- i. Vertical
15% of moving loads
- ii. Parallel to movement direction
5% of moving load
- iii. Perpendicular to movement direction
3% of moving loads

b) Moving MT**i. Dynamic factors**

The following dynamic factors are to be used for consideration of MT launching and movement:

- Vertical
10% of moving loads
- Parallel to movement direction
5% of moving loads
- Perpendicular to movement direction
3% of moving loads

ii. **Launching forces for equipment**

For consideration of longitudinal forces on hydraulic jacks during launching of the MT, the force is derived considering longitudinal gradient and friction.

iii. **Launching forces for structure**

For consideration of longitudinal forces on the Roller support during launching of the MT, the force is derived considering longitudinal gradient and friction.

c) **Moving UCB/FSL/RSL**

i. **Dynamic factors**

The following dynamic factors are to be used for consideration of UCB/FSL/RSL movement:

- Vertical
10% of moving loads
- Parallel to movement direction
5% of moving loads
- Perpendicular to movement direction
3% of moving loads

ii. **Launching forces for equipment**

For consideration of longitudinal forces on chain blocks or other moving devices during launching of the UCB/FSL/RSL, the force shall be calculated considering longitudinal gradient and friction.

iii. **Launching forces for structure**

For consideration of longitudinal forces on the MT/UCB/FSL/RSL during launching of the UCB/FSL/RSL, the force shall be calculated considering longitudinal gradient and friction.

iv. **Longitudinal fixity**

During span erection shall have a longitudinal fixity with Roller support and shall be considered in design and stability of system.

10.1.7.6 Wind loading

All wind speeds referred beneath are based on gust speed.

In service wind (with span erection) ≤ 20 m/s

Gantry launching wind load ≤ 15 m/s

Tropical storm wind (with span erection) ≤ 42 m/s

Tropical storm is normally with advance warning and hence it is deemed to be possible that span under erection shall be completed and load transfer onto span jack prior to arrival of storm. Effect of gantry stability under self-weight only should be evaluated without any segment suspended and additional tie down system is to be provided if necessary.

Two types of wind loading shall be considered:

- In-service wind loading: wind while handling of span (lifting, lowering, etc)
- Out-of-service wind loading: Typhoon wind loading

10.1.7.7 Height Restriction

The gantry has to cross few existing structures. The height of top of main truss above pier cap top shall be limited to 6500mm

10.1.7.8 Minimum Horizontal Radius


The gantry shall have adequate functional and structural provisions to launch over spans with 200m horizontal radius

10.1.7.9 Reaction on Piers

The reaction on pier top due to operation of erection gantry, shall be limited to followings: -

		RSL [kN]		Pier N-1 [kN]							
Final Force at deck		Left	Right	Left				Right			
				3	5	3A	5A	4	6	4A	6A
FV	Max	--	--	802	512	145	-145	467	186	145	-145
FT	Max	--	--	14	14	14	14	14	14	14	14
FL	Max	--	--	33	33	33	33	33	33	33	33
		Pier N [kN]				FSL [kN]					
Final Force at Pier Top		Left		Right		Left	Right				
		5	7	6	8						
FV	Max	1149	499	499	1149	--	--				
	Min	-164	486	486	-164	--	--				
FT	Max	14	14	14	14	--	--				
	Min	14	14	14	14	--	--				
FL	Max	33	33	33	33	--	--				
	Min	33	33	33	33	--	--				

For nomenclature and location of reaction point definition refers to following drawings: -



10.1.7.10 Transfer Boogie

The U Girder shall be transported with two numbers of motorised bogies.

The Weight of each bogey, inclusive of all equipment, shall be limited to 5.5 t.

S. Nr	Item	Specification
1	Max Weight of each boggy	5.5 t
2	Max Speed (Loaded condition)	2 Km/hr
3	Max Speed (Unloaded condition)	3 Km/hr
4	Maximum gradient	4%

10.1.7.11 Specification On Safety**a) Illumination**

A lighting system for working area shall be provided to improve visibility in case of scarce day-light.

Anyway, personnel responsible of safety must make sure that there is a good visibility of every point, not be create dangerous reflex and allow a clear reading of control boards and identification of emergency push buttons.

b) Controls

Operating any control that creates a sharp variation in drive direction, such as halting the winch by engaging the opposite movement, is forbidden. The stresses which may arise are uncontrollable and may seriously damage the equipment, causing personnel and material risk.

Such controls may be operated in the event of an imminent danger to persons.

c) Safety devices

The GANTRY shall be provided with electrical and mechanical devices which reduce the danger that may occur during working phases. The safety devices are located in various points of the launching machine and can be listed as follows:

i. Protected walkways, ladders and platforms

Main walkways, placed inside the two trusses, allow safe access to working areas and all control units of supports, legs, winches, cranes. In order to reach walkways and platforms, protected ladders are mounted on both legs and supports.

ii. Limit switches

Electrical limit switches shall be installed on moving parts of the gantry. If actuated, they stop the related movement before mechanical stops are reached.

iii. Overspeed detection system

A safety system that monitors operating speed and stops the machinery in case of over speed shall be installed on winch drums.

iv. Inclination detectors

Electrical inclination detectors shall be installed on the winch drums.

v. **Load cells**

Gantry shall be equipped with load cells in order to constantly survey load conditions.

vi. **Emergency push buttons**

Emergency push buttons shall be installed in the gantry. If actuated by operators, they stop immediately all running movements.

vii. **Safety braking system**

Safety braking system shall be installed to stop the rope drum in case of failure of the control drive, motor, service brake or gearbox.

viii. **Encoders**

Lifting and lowering stroke shall be defined by an encoder mounted on each hoisting winch drum connected with a limit switch.

ix. **Digital speed gauges**

Speed gauge shall be mounted on each hoisting winch drum to continuously check for rope overspeed.

x. **Max relief hydraulic valve**

Each hydraulic motor shall be equipped with a hydraulic valve to limit oil pressure in the circuits.

xi. **Hydraulic pressure switch**

Winches hydraulic circuit shall be equipped with a hydraulic switch to control lifting pressure

10.2 BOX GIRDER**10.2.1 Construction Method**

The box girder superstructure for almost the entire length shall be constructed by precast segmental construction with epoxy bonded joints. The prestressing cables will be internal to the concrete. The methodology of construction will be "span by span". Only one end prestressing of permanent cables is contemplated, the other end of the cable being pre-blocked.

The usual segments shall be 3.0m in length except the pier segments which shall be 1.975m each. Standard spans shall be made to either add or subtract usual segments of 3.0m each.

Where this is not possible or advisable for some reason, the segments will be of length between 1.5m and 3.0m. Hence the mould / casting bed shall be adaptable to cast non-standard length of segment.

The maximum span length contemplated for precast segmental construction will be of the order of 37.0m.

Multiple Shear keys shall be provided at segmental joints at the webs as well as at top flange and soffit slab of the box girder.

Box girder segments shall be match cast at the casting yard and later transported to location and erected in position. Post-tensioned cables shall be threaded-in-situ and tensioned from one end. Box girder shall cater to two tracks.

10.2.2 Material Specifications

- a) **Cement**
Same as CI 10.1.2.1
- b) **Reinforcement**
Same as CI 10.1.2.2
- c) **Prestressing Steel**
Same as CI 10.1.2.3
- d) **Concrete**
Same as CI 10.1.2.4
- e) **Permanent Prestressing**
Same as CI 10.1.2.5
- f) **Epoxy Bonded Joints**

A minimum compressive stress of 3 kg / sq. cm shall be provided uniformly over the cross-section for the closure stress on the epoxied joint until the epoxy has set.

This temporary compressive stress can be applied by temporary prestressing bars.

The curing period for application of the compressive stress, method of mixing and application of epoxy and all related aspects including surface preparation shall be as per approved manufacturer's specifications.

The Epoxy shall be spread with the help of a stubby brush to a thickness of about 1.5 mm each on both the joining surfaces.

The purpose of the epoxy joint shall be to serve as lubricant during segment positioning, to provide water proofing of the joints for durability in service conditions and to provide a seal to avoid cross-over of grout during grouting of one cable into other ducts.

Prior to grouting, all cables shall be tested with water pressure of 0.3 MPa for approximately 3 minutes, to investigate leakages and connectivity of ducts. Since the epoxied joint is of paramount importance to ensure long-term durability of prestressing cables, this field test shall be taken as indication of the Contractor's quality of work in general and effectiveness of the epoxy joint executed by him. All other aspects of grouting of cables shall be governed by MORTH Specifications.

The epoxy shall be special purpose proprietary material for the proposed usage with proven past record. Selection of epoxy shall be subject to the approval of the Engineer. It shall meet the requirements of relevant provision of FIB (International Federation of Concrete, previously "FIP - International Federation of Prestressed Concrete"). For selection of epoxy, all tests which govern the properties of epoxy for its application and subsequently determine the durability of joint are required to be done in laboratory temperature controlled condition. Some tests for evaluating properties of epoxy are critical in the upper limit of specified

application temperature range while other tests are critical for evaluating the properties in the lower limit of specified application temperature range. The tests shall be conducted in laboratories equipped to handle controlled temperature conditions. All tests shall conform to FIB requirements.

After receiving every batch, all tests (except shear modulus, instantaneous and deferred modulus in compression and water absorption, heat resistance, shear strength and solubility in water) are required to be done at the site laboratory at prevailing ambient temperature to conform to the uniformity of standard of supplied product. In case the received batch is kept at site for a period of more than three months all tests are required to be re-done.

With every erection, tests for pot life and open time are required to be done at site at prevailing ambient temperature. Nothing extra shall be payable for providing epoxy and all related operations.

The uniform compressive stress during the curing period may be applied by approved external temporary bar prestressing. This shall be accomplished using short HTS bar connecting the adjoining segments. The bars shall be anchored on temporary steel frame, passing through dedicated holes within the girder through.. No passing-through holes shall be used in soffit slab or web. Passing-through holes used in soffit slab should be filled with free flow, high strength, non-shrink cement grout.

In order to prevent intrusion of epoxy in sheathing, an O-ring with diameter compatible with the size of HDPE sheathing (10-20mm wide and 4mm thick) of polypropylene shall be provided on both mating surfaces.

Nothing extra shall be payable for such temporary stress application including all related works.

g) Epoxy bonding agents

Epoxy bonding agents for match cast joints shall be thermosetting 100 percent solid compositions that do not contain solvent or any non-reactive organic ingredient except for pigments required for colouring. Epoxy bonding agents shall be of two components, a resin and a hardener. The two components shall be distinctly pigmented. So that mixing produces a third colour similar to the concrete in the segments to be joined, and shall be packaged in proportioned, labelled, ready-to-use containers.

Epoxy bonding agents shall be formulated to provide application temperature ranges that will permit erection of match cast segments at substrate temperatures from 5°C to 45°C. If two surfaces to be bonded have different substrate temperatures, the adhesive applicable at the lower temperature shall be used.

Epoxy bonding agents shall be insensitive to damp conditions during application and after curing, shall exhibit high bonding strength to cured concrete, good water resistivity, low creep characteristics and tensile strength greater than the concrete. In addition, the epoxy bonding agents shall function as a lubricant during the joining of the match cast segments, as a filler to accurately match the surface of the segments being joined and as a durable water light bond at the joint.

Epoxy bonding agents shall be tested to determine their workability get time, open time, bond and compression strength, shear, and working temperature range. The frequency of the tests shall be as stated in the Special Provisions of the Contract.

The contractor shall furnish the Engineer with samples of the material for quality assurance testing and a certification from a reputable independent laboratory indicating that the material has passed the required tests

Specific properties of epoxy and the test procedures to be used to measure these properties shall conform to FIP requirement.

Mixing and Installation of Epoxy

Instructions furnished by the supplier for the safe storage, mixing and handling of the epoxy bonding agent shall be followed. The epoxy shall be thoroughly mixed until it is of uniform color. Use of a proper sized mechanical mixer operating at no more than 600 RPM will be required. Contents of damaged or previously opened containers shall not be used. Surfaces to which the epoxy material is to be applied shall be at least 40°F and shall be free from oil, laitance form release agent or any other material that would prevent epoxy from bonding to the concrete surface. All laitance and other contaminants shall be preferably removed by water rinsing, or, alternatively, by light sand-blasting. Wet surfaces shall be dried before applying epoxy bonding agents. The surface shall be at least the equivalent of saturated surface dry (no visible water).

Mixing shall not start until the segment is prepared for installation. Application of the mixed epoxy bonding agent shall be according to the manufacturer's instructions using trowel rubber glove or brush on one or both surfaces to be joined. The coating shall be smooth and uniform and shall cover the entire surface with a minimum thickness of 1/16-inch applied on both surfaces and 1/8-inch if applied on one surface. Epoxy should not be placed within 3/8th inch of prestressing ducts to minimise flow into the ducts. A discernible bead line must be observed in all exposed contact areas after temporary post-tensioning. Erection operations shall be coordinated and conducted so as to complete the operations of applying the epoxy bonding agent to the segments erection assembling and temporary post-tensioning of the newly joined segment within 70% of the open time period of the bonding agent.

The epoxy material shall be applied to all surfaces to be joined within the first half of the gel time as shown on the containers. The segments shall be joined within 45 minutes after the application of the first epoxy material placed and a minimum required temporary prestress over the cross section should be applied within 70 percent of the open time of the epoxy material. The joint shall be checked immediately after the erection to verify uniform joint width and proper fit. Excess epoxy from the joint shall be removed where accessible. All tendon ducts shall be swabbed immediately after stressing while the epoxy is still in the non-gelled condition to remove or smooth out any epoxy in the conduit and to seal any pockets or air bubble holes that have formed that joint.

If jointing is not completed with 70 percent of the open time, the operation shall be terminated and the epoxy bonding agent shall be completely removed to the maximum possible extent from the surfaces. The surface must be prepared again and fresh epoxy shall be applied to the surface before resuming jointing operations. As general instructions cannot cover all situations specific recommendations and instructions shall be obtained in each case from the Engineer.

10.2.3 Shop Drawings And Design Calculations For Construction Procedures

10.2.3.1 General

The Contractor shall submit according to a schedule, complete details and information concerning the method, materials, equipment and procedures he proposes to use. These shall be called "Method Statements". Method Statements shall be submitted sufficiently in advance of the start of superstructure field construction operations, so as to allow the Engineer adequate review period, which shall not be less than 30 days. The submittals shall invariably include step-by-step erection procedure.

The Contractor's Method Statements shall also include all calculations, drawings and information as may be relevant.

10.2.3.2 Design Calculations for Construction Procedures

Design assumptions and calculations shall be submitted for temporary prestressing, false work, erection devices, formwork or other temporary construction which may be required to complete the work.

Assumptions and Calculations shall also be submitted to substantiate the system and method of permanent and temporary prestressing proposed by the Contractor.

In the sections that follow, specific recommendations for precast segmental construction for superstructure are given apart from certain special aspects of construction.

10.2.3.3 Shop Drawings for Precast Segmental Construction

The Contractor shall submit detailed shop drawings for approval. The shop drawings shall be based on Execution Drawings issued by concerned organisation to the Contractor and shall include:

- a) Fully and accurately dimensioned views showing the geometry of segments including all projections, recesses, notches, openings, block-outs, blister if any and where acceptable, as well as other relevant details.
- b) Details of any special reinforcing required for handling of segments or for other purposes. Also all bar bending schedules shall be presented based on reinforcement schedules given in Execution Drawings issued by concerned organisation.
- c) Sheathing supports, grout tubes, vents and drains shall be shown including size, type and locations.
- d) Details and locations of all other items to be embedded in the segments such as inserts, lifting devices and post-tensioning hardware shall be shown.
- e) Prestressing system details shall include sizes and properties of tendons, anchorages,

plates, assemblies and stressing procedure, and details and locations of additional reinforcement necessary to resist anchor block stresses.

- f) Graphs, charts or tables showing the theoretical location of each segment, as erected or placed shall be furnished to the Engineer for his use in checking the erection of the superstructure. Detailed procedures for making geometry corrections shall be described.
- g) Details of grouting equipment, grout mix design and method of mixing and placing grout shall be provided.
- h) Method of installing bearings and expansion joints shall be given including approved manufacturer's recommendations.

10.2.3.4 Forms for Precast Segmental Construction

Forms for precast segmental construction shall be steel form work only. Shop drawings shall be submitted for all formwork. The segments during storing /curing shall always be supported as shown in tender drawings or as approved by Engineer only.

In addition to the requirements of the Standard Specifications, the forms used for precasting the concrete segments shall be capable of:

- a) Match casting for precast segmental construction.
- b) Producing the segments within the tolerances permitted in Section 10.2.8.
- c) Accommodating block-outs, openings and protrusions. Protruding re-bars will be needed at least for diaphragm segments and for second-pour plinths. Anchorages and inserts for OHE poles, signalling equipment and cable routing supports shall also be included where needed in precast segments.
- d) Adjusting to changes in segment geometry as shown in Execution Drawings issued by concerned organisation, or for correcting previous minor casting errors to prevent accumulation.
- e) Adjusting the profile to take into account design camber values
- f) Stripping without damage to the concrete.
- g) The form design shall provide a tight leak-proof jointing to the previous segment. The bulkhead must be capable of connecting the sheathing in a manner to hold their position and prevent intrusion of grout.

Joints in external formwork shall be avoided as far as possible. Where sections of forms are for some reason to be joined on the exterior face of the segment, an offset in excess of 0.5mm for flat surfaces and 1 mm for corners and bends will not be permitted.

Forms shall not be removed until the concrete has attained adequate strength. Care should be exercised in removing the forms to prevent spalling and chipping of the concrete.

All side, bottom, inside and header forms for precast segmental construction shall be constructed of steel.

Forms shall be of sufficient thickness, with an adequate external bracing and stiffeners, and shall be sufficiently anchored to withstand the forces due to placement and vibration of concrete. Internal bracing and holding devices in forms shall be limited to stay bolts in webs, which can be removed from the concrete surface to permit patching following form removal. Joints in the forms shall be designed and maintained for mortar tightness. The grade and alignment of forms shall be checked each time they are set and shall be maintained during the casting of concrete.

Metal forms shall be reasonably free from rust, grease or other foreign materials. All forms shall be cleaned thoroughly prior to each casting operation. End headers shall be maintained to provide a smooth casting surface.

All formed surfaces for casting members shall be constructed and maintained to provide segment tolerances in accordance with Section 10.2.8.

The faces of all forms, other than end headers, shall be properly cleaned and treated with form oil or other bond breaking coating prior to placing concrete. Between adjacent match cast segments and headers bond breaking materials shall be provided as indicated elsewhere in these Additional Specifications. The oil or other materials used shall be of a consistency and composition to facilitate form removal. Materials which stain or react with concrete shall not be used. Care shall be exercised to facilitate formwork and segment removals without damage to the concrete.

10.2.4 Casting, Handling, Transportation and Erection Of Precast segments

10.2.4.1 General

The Contractor shall submit detailed Method Statements for casting, handling, transportation and erection of precast segments. The superstructure shall be erected by the method indicated in the tender or by alternate method submitted by the Contractor, subject to the approval of the Engineer. The stressing system, cage of reinforcement and lifting details shall be successfully demonstrated on sample segment prior to casting any permanent segments.

All handling and erection plant and equipment shall be load tested prior to their use at site or when specifically asked for by the Engineer. Any additional material required to cater to any temporary condition including temporary prestressing shall be borne by contractor and nothing extra will be paid in this account.

10.2.4.2 Casting of Segments

Casting bed and forms shall be structurally adequate to support the segments without settlement or distortion. The casting bed shall be designed for the hardware needed to adjust and maintain grade and alignment. Special consideration shall be given to those parts of the forms that have to change in dimensions. To facilitate alignment or adjustment, special equipment such as wedges, screws or hydraulic jacks shall be provided. Fittings

shall not interfere with stripping of forms. Grading of the forms and the deck of each segment shall take into consideration the relative position of the member in the structure. External vibrators shall supplement the internal vibration if necessary and be attached at locations that will ensure maximum consolidation.

Details for casting bed and hardware for adjustment shall be submitted by the Contractor for the Engineer's approval. Casting of segments shall be done in a single pour. Construction joint is not permitted in segment.

After the first segment of each unit is cast, all succeeding segments shall be cast against previously cast segments to ensure complete bearing and proper alignment on all mating surfaces.

The anchorage system shall permit tendons to be inserted in the member after erection of segments and tensioned from one end only.

Care shall be taken to ensure that deformations of match cast segments due to thermal gradients caused by the heat of hydration of the new cast concrete are negligible. These deformations shall be prevented by properly protecting both the match cast and new cast segments with curing blankets and plastic sheeting. Both the previous segment and the new segment will be maintained at the same temperature.

Reinforcing steel shall be fabricated in cages and placed according to the Execution Drawing issued by DMRC. Any conflict or interference with the proper location of sheathing and / or reinforcement or block-outs shall be promptly resolved and corrections made as directed by the Engineer.

All segments shall be marked on the inside with a unique identification at the time of form removal. This identification shall be used to identify each segment on shop plans, post-tensioning details and calculations and any other document pertaining to the fabrication and erection of precast concrete segments.

Positive means of holding the sheathing in its correct position shall be provided in all cases and shall be indicated on the shop drawings submitted for approval. The sheathing shall be stiffened from the inside by rubber or plastic hoses or by inflatable rubber tubes.

10.2.4.3 Casting Methods

Match cast segments may be cast by the "long line" or "short line" method. The Contractor has to select the option carefully and provide appropriate type of formwork as well as casting and handling operations. The "short line" method requires much greater precision in the work as compared to the "long line" method.

10.2.4.4 The "Long Line" Method

The principle of the long line method is the casting of the segments, in their correct relative position, on a long line casting bed which exactly reproduces the profile of the structure. A long line is easy to set up, while the geometry of the segments is easily controlled. The segments shall be cast by long line method for spans curved in plan.

After stripping the forms it is not necessary to take away the segments immediately. Water

curing/curing compound as per relevant specifications shall be applied to segments immediately.

Substantial space may be required for the long line. The theoretical length for casting alone is normally slightly more than the length of the longest span of the structure. It must be constructed on a firm foundation which will not settle or deflect under the weight of the segments. In case the structure is curved, the long line must be designed to accommodate horizontal and vertical curvature as well as twists, if any, because the forms are mobile, equipment for casting, curing, etc has to move from place to place.

10.2.4.5 The “Short Line” Method

The short line method is mentioned here as a possible alternate.

The segments are cast at the same place in stationary forms and against a neighbouring element. After casting, the neighbouring element is taken away and the last element is shifted to the place of the neighbouring element, clearing the space to cast the next element.

The space needed for the short line method is small in comparison to the long line method, approximately three times the length of a segment for one short line. The entire process is centralised. Horizontal and vertical curves and twisting of the structure are obtained by adjusting the position of the neighbouring segment and through specified formwork.

To obtain the desired structural configuration, the neighbouring segments must be accurately positioned. Care must be taken that the formwork be sufficiently flexible to allow for adaptation at the joint with the accurately positioned matching segment.

If short line method is adopted, the deck segments should follow profile as given below: -

Suggested Deck Alignment on Vertical Curves

a) On Vertical Summit Curves

On vertical summit curves, deck will follow the path of straight line joining the two points on adjacent piers. These two points shall have the minimum offset from rail level to deck level as specified by Engineer at all points along the length of girder.

b) On Vertical Valley Curves

On vertical valley curves, deck will follow the path of straight line joining the two points on adjacent piers. The minimum offset from rail level to deck level as specified by Engineer shall be ensured at all points along the length of girder.

c) Suggested Deck Alignment on Circular / Transition Horizontal Curves

On circular / transition horizontal curves, each segment of the deck will follow the profile of short chord line. The bottom and side form for segment to be cast are positioned to span between the stiff fixed end bulkhead and the previously match cast segment. The previously match cast segment shall be oriented w.r.t. segment to be cast and it should be ensured that fixed bulkhead always remain perpendicular to end face of formwork.

Due to orientation of match cast segment, the length of segment towards inner side of curve will be less and towards outer side of curve will be more than segment length along centre line. The formwork to be used should have flexibility to adjust the segment length on both sides by adjusting the position of the match cast segment without any additional pieces and it shall be ensured that offset of match cast segment and segment to be cast is limited to value so calculated.

10.2.4.6 Separation of Match-Cast Segments

The Contractor shall provide equipment to be used for uniform separation of match case segments without damage. The method as well as details of the equipment to be used for separating match cast segments shall be included in the shop drawings. A bond breaking material shall be used in the form of wax only on the webs and soffit slab of the previously cast segment and a newly cast segment, as well as the end headers when required. The material shall not be injurious to the concrete and shall permit removal of a segment without adhesion of the concrete.

Any breakage in segment end face during separation / handling shall not be repaired, unless specifically accepted by the Engineer, in which case repairing at end face of segment shall be done with epoxy at the time of epoxy application. Segments with excessive breakage shall be rejected. Decision of the Engineer shall be final binding in this regard.

10.2.4.7 Handling / Erection of Segments

The Contractor shall be responsible for the proper handling, lifting, storing, transporting and erection of all segments so that they may be placed in the structure without damage. Only HTS bar such as Macalloy or Dywidag shall be used for lifting/handling of segment at any stage of construction, with due care for fatigue considerations (multiple re-use).

Segments shall be maintained in an upright position at all times and shall be stored, lifted and/or moved in a manner to prevent torsion and differential deformation other undue stress. Members shall be lifted, hoisted or stored with lifting devices approved on the shop drawings.

The Contractor shall furnish calculations to establish that the stresses induced during any stages of construction shall not exceed 50% of the cube strength achieved at that stage, nor 40% of the specified 28days cube strength. In addition, the following limitations shall be observed:

- a. The segment shall not be lifted from the casting bed till the concrete reaches a minimum cylindrical strength of 20 MPa (or 25MPa Cube strength).
- b. The age of the concrete shall not be less than 14 days at the time of its erection provided it has achieved its specified strength as per design requirements.

Segment shall be stacked with three point support in curing tank / stacking yard as shown in tender drawing, or as approved by concerned organisation Curing shall be done using sprinkler system (assisted by steam curing in the initial stages if adopted) and it has to be

ensured that all parts of segment are water cured during water curing period or curing compound as per the relevant specifications in this document

10.2.4.8 Cleaning, Transportation and Erection of Segments

Before transportation of segment, mating surface shall be cleaned by water rinsing or sand blasting as approved by the Engineer.

When sand blasting is employed surface shall be abraded to an extent that:

- i. Bond breaker such as wax applied during match casting is removed.
- ii. Laitance is removed so that small aggregates are just exposed.
- iii. Cleaned surface is neither polished nor excessively rough

Two methods of erection have been suggested: Side beams method, and as an allowed alternate, the top beams method. Only the side –beams method is referred to in these special specifications. The launching girder (or more accurately, the "assembly truss") must be capable of supporting all the loads within permissible limits as stipulated in codes and transferring it to the temporary cross girder, which transfer the loads directly on pier cap using trestles. The launching girder envisaged is slightly greater than 2 spans. It must also be able to negotiate curves and accommodate for the camber if any of the structure. As far as practical, the movement of segments shall be done at the deck level of the already constructed portion of the continuous length so that the disturbance to traffic at the ground level is minimised. Mobile crane of adequate capacity and boom length shall be mobilised by the Contractor for transferring the segment from ground level to deck level for the purpose. **The launching girder should be capable of lifting the segments for the span to be erected from below and in case required, it should also be capable of feeding the segments from the rear end over the already erected span.**

A suitable number of separate sets of launching girders are essential in order to proceed at the contemplated pace for completion of project in time. However, Contractor shall furnish the construction scheme and nos. of launching girders, he proposes to deploy in order to ensure completion of project within scheduled time.

It is emphasised that for precast segmental construction only one-end prestressing shall be used. The superstructure shall be constructed "span by span" sequentially.

The diaphragm segments shall need specific additional temporary supports under the webs during those various stressing operations. Those temporary supports shall be flexible enough in rotation. The precise load transfer during the stressing operations between the various supports shall be monitored at least once with adequate jacks during the destructive testing of one span in precast yard.

It is emphasised that

- i. The spans must be assembled on a higher level to avoid conflicts with already built concrete shear key.
- ii. The launching truss supports must be at same location than temporary bearings.

10.2.5 Miscellaneous

The entire construction work shall be geared towards minimising disruptions to road traffic. Also, the occupation of roads during all construction activities shall be reduced to a minimum and subject to the approval of the Engineer

All elements of sub-structure below bearing pedestals viz piles, pile caps, piers and pier caps shall each be cast in single pour.

10.2.6 Load Testing Of Launching Girder

Contractor shall conduct full scale load traveller test of all launching girder prior to using it for execution purpose. Such tests are required to be done for all the launching girders engaged for project, even if the similar design of launching is adopted.

Nothing extra will be payable for conducting such test and the rate shall be included in respective item.

10.2.7 Load Testing Of Standard Span Of Superstructure

The contractor shall conduct full scale load test for one critical span of each category of superstructure.

The sequence of placement and position of loading on the girder shall be as directed by the engineer.

NOTE

The provision of 3r Rail to be checked for DMRC Phase-IV.

10.2.8 Completed Segment Tolerance For Segmental Box Girder Bridge Construction.

Finished segment tolerances should not exceed the following:

Length of match-cast segment (not cumulative) $\pm 1/8$ in/ft.(10.4 mm/m, + 1 in. max. (25 mm)

Length of totally assembled span..... $\pm 1/2$ in.(12.5 mm)

Web Thickness..... $+3/8$ in. (9.5 mm)

Depth of bottom slab..... $+3/8$ in. (9.5 mm)

Depth of top flange..... $+1/4$ in. (6.5 mm)

Overall top flange width..... $+1/16$ in/ft (5.2 mm/m), $\pm 3/4$ in. max(25mm)

Top flange width (transverse position on track side) $+1/5$ in (5 mm). max

Diaphragm thickness $\pm 1/2$ in. (12.5 mm)

Grade of form edge and soffit..... $\pm 1/8$ in. in 10 ft (1.0 mm/m)

Tendon hole location..... $\pm 1/8$ in. (3.2mm)

Position of shear keys..... $\pm 1/4$ in. (6.3 mm)

Tolerance for erection of the span

Horizontal and vertical position of the at-pier-segment shall be within 15mm of the longitudinal alignment and grade.

10.3 PRECAST I/T GIRDER

10.3.1 General

The super structure of viaduct/concourse/platform may comprise of pre-cast RCC/pre-tensioned/post-tensioned T/I girders made monolithic by cast-in-situ deck slab and R.C.C. diaphragm. The concourse & platform superstructure may comprise of RCC/pretensioned pre-cast girders T/I girders made monolithic by cast-in-situ deck slab and R.C.C. diaphragm. The Pre-casting Yard shall be established by the contractor at site or at any other location approved by Engineer. These girders after attaining the required strength at the pre-cast yard shall be transported to site and eventually erected at appropriate position over the pier caps/cross arms.

Adequate Nos of casting beds and form work sets shall be established by the contractor for pre-casting of the I/T-girders so that progress of casting matches with the overall execution stand of the work.

The contractor shall submit detailed construction methodology for casting, curing, stacking, transportation, launching and equipment for shifting and launching of the girders for approval of Engineer.

10.3.2 Construction Sequence

The programme of casting shall be so planned that the girders are cast continuously so as to avoid age difference between adjacent girders in any span and to minimise the time lag (say up to 90 days) for casting of deck slab cross diaphragms at site.

10.3.3 Concreting for Precast Girders

Unless otherwise mentioned hereunder, the concrete shall be prepared, mixed and placed in position in accordance with the specifications given elsewhere in this specification. The Contractor shall maintain a record of the proportions of mix at the batching plant and produce the same for checking by Engineer whenever required.

The contractor shall take care in placing reinforcement cage so that cables/ strands are not disturbed and the minimum cover as recommended in the drawing is available.

The reinforcement protruding from each girder shall be bent to the shape so as to match with the reinforcement of cross diaphragm. The protruding reinforcement shall be coated with cement wash. Finished concrete shall have rough finish on top for proper bond with cast-in-situ deck/cross diaphragm at site.

The precast girders constituting the top flange, web and the bottom flange shall be concreted in single operation without any construction joint.

10.3.4 Forms for Precast Pre-stressed Girders

The precast girders shall be cast at casting yard. The steel formwork shall only be used for casting of girder. Top of casting bed shall also be provided with steel pining. The exposed surface of the concrete shall be shutter finished as mentioned elsewhere in the tender document.

10.3.5 Permissible Tolerances

The formwork of precast girder shall be so made as to produce a finished concrete true to shape, lines, levels, plumb and dimension shown on the drawings subject to the following tolerance unless otherwise specified in these documents or directed by Engineer.

10.3.6 Length of Girder

Per 3 m length	$\pm 3 \text{ mm}$
Maximum for entire length	$\pm 10 \text{ mm}$

10.3.7 Cross-Sectional Dimension

Web	-	$\pm 3 \text{ mm}$
Flanges	-	$\pm 3 \text{ mm}$
Depth	-	$\pm 3 \text{ mm}$
Plumb	-	1 in 1000

10.3.8 Marking of Precast Girders

Precast girders shall be marked immediately after removing the side forms with paint of approved quality. The girders shall be marked at minimum four places on both faces of web at the ends with the following details.

1. Girder Number
2. Date of casting of girder
3. Any other marking related to erection i.e. direction, station name, grid number etc.

10.3.9 Tests of Precast Girders**a) Initial Test**

The first precast girder shall be tested till its failure in order to determine the strength of girder during service. Stress and strain gauges shall be fixed in the test girder for observing the results of load testing. The contractor shall carry out the initial load test including providing all instrumentation, testing infrastructure, T&P, labour and incidental works at no extra cost to the department. The contractor shall submit testing methodology and final test report to the Engineer.

b) Routine Load Tests

Routine load tests shall be conducted on working pre-cast girders. Total number of such tests shall be 1% of the total number of girders. The girders shall be subjected to a midpoint load (in addition to the self-weight of the girder) so as to subject the girder equivalent to 1.5 times the moment during service.

Prior to carrying out initial and routine load tests, the contractor shall submit arrangement of testing, loading etc. and shall carry out any modifications, if needed, on the existing testing arrangement to the satisfaction of Engineer at no extra cost. The contractor shall submit a report containing test results and observations etc. to the department.

10.3.10 Handling, Stacking, Launching and Placing of precast girders

Handling of pre-cast members shall be allowed only after the same have attained the specified strength approved by Engineer. The members shall be lifted only from the positions specified for this purpose. All necessary precautions will be taken to avoid any accident and damage during handling of pre-cast units.

The contractor shall submit detailed plan showing stacking of precast girders at casting yard and at site and shall obtain approval of the Engineer. The precast girder shall be placed on concrete stacking pedestal with rubber pads installed at bearing points. Proper precautions shall be taken during handling of precast units during transportation and all traffic safety measures taken. The contractor shall be required to execute all handling and re-handling of girders including interim storages etc., till these are finally erected, within his quoted rate. Contractor can plan the activities in advance to reduce such handling if practicable.

When placing the precast units in position, care should be taken to place the right unit in the right position with minimum handling of units. Care should also be taken to prevent any damage to the precast units. Units damaged by improper storing or handling/re-handling shall be repaired for non structural damages and replaced if there is structural damage, by the contractor at his own expense. The methodology proposed by the contractor for placing these units, shall be got approved from the Engineer, before commencement of the work. The rate for the reinforcement in the girders shall also include cutting of temporary handles (rebar), if required. The contractor shall prepare and submit a plan for each span indicating the location and girder number of each girder.

The individual precast girders shall be erected at its exact location on pier caps/pier arms. The alignment should be true to the lines and levels placed adjacent to one another as per approved construction drawing. Unless otherwise mentioned hereunder, the concrete shall be prepared, mixed and placed in position in accordance with the specification given elsewhere in the tender documents.

Precast girders shall be accurately placed on bearings correct to exact line and levels. After completion of erection and alignment activities, the lifting holes shall be filled with non-shrink grout.

SECTION S.11

ROOF SHEETING & PRE ENGINEERED STRUCTURES

11.1 GENERAL

11.1.1 Description Of Work Site

The location of the work and the general site particulars are shown in the Site Layout enclosed in the tender drawings.

11.1.2 Scope Of Work

General

The work content in this contract consists of:

- i. Design, Fabrication, Supply and erection of PEB Structures for Workshop & Inspection bay, Blow Down Plant, Pit Wheel Lathe, Interior cleaning, Shed for RGM, S & T Stores, Cable & Diesel Store, Sheds and Watch Towers etc including gantry girders wherever required.
- ii. Design, fabricating and erection of hot dipped galvanized Rain Water Gutters
- iii. Providing and fixing pre coated galvalume sheets in single and double layer for roofing and side cladding. Double layer sheeting must be insulated by 50 mm thick glass wool of 24kg/cum density.
- iv. Providing and fixing 3 mm Polycarbonate sheets and 6mm thick toughened glass
- v. Design, fabrication, supply and erection of structural steel for roof inspection platforms, catwalks and cable tray support brackets & hangars.
- vi. Providing structural steel for rail track support columns and car/cycle/scooters sheds
- vii. Supply, Installation and testing of supporting structures for EOT cranes.
- viii. Roof structure shall be planned as per solar module installation arrangements.
- ix. Providing life line for maintenance / cleaning purpose
- x. Providing ladder to access roof.
- xi. Suitability marking, bundling and packing for transport of all fabricated materials

The work shall be carried out and maintained as per relevant IS Codes, Relevant International Standard, CPWD Specifications, Particular Specifications (latest edition), and Tender Drawings and or as directed by the Engineer.

Technical Requirements

The Intending Tenderer/Contractor must have their own fabrication unit with fully computerized and automatic machineries for cutting, bending, drilling, moulding, welding, grinding etc. with full flagged mechanised facilities of sand blasting, painting and testing equipment complete.

The following minimum requirements shall be followed by the Contractor:

- i. All aspects of quality assurance, including procurement & testing of materials and other components of the work, as specified or as directed by the Engineer;
- ii. Clearing of site and handing over of all the Works, as directed by the Engineer;
- iii. Successful & prompt Maintenance of the completed Work during the maintenance period.
- iv. Submission of Design Drawings, Erection Drawings, Fabrication Drawings, completion (i.e. 'as-built') drawings, calculation, analysis and other related documents as specified & directed by the Engineer;

11.1.3 Interfaces

The Scope of Work for the interfaces work for various interfacing Contracts. In brief, the interfaces include but are not limited to:

- i. Supply of anchor bolts to Civil contractor
- ii. Interfacing with OHE contractor
- iii. Interfacing with E & M contractor
- iv. Interfacing with Tracks contractor

11.1.4 Associated Works

Works to be performed shall also include:

- i. All general works preparatory to the PEB Structures, OHE arrangements and EOT Crane arrangements of Depot & Workshop for MRTS project
- ii. It is envisaged to provide retractable catenary arrangement of IBL (Inspection Bay Line) in Depot. Civil contractor shall interface with concerned traction contractor for providing necessary structural support arrangement OHE and related cabling support after getting details from the traction contractor.
- iii. Works of any kind necessary for the due and satisfactory construction, completion and maintenance of the works to the intent and meaning of the drawings adopted, technical specifications, to best Engineering standards and orders that may be issued by the Engineer from time to time, compliance by the agency with all Conditions of Contract,
- iv. Supply of all materials, apparatus, plants, equipment, tools, fuel, water, strutting, timbering, transport, offices, stores, workshop, staff, labour and the provision of proper and sufficient protective works, diversion, temporary fencing, lighting and watching required for the safety of the public and protection of works on adjoining land;
- v. First-aid equipment, sanitary accommodation for the staff and workmen, effecting and maintenance of all insurances,

- vi. The payment of all wages, salaries, provident fund, fees, royalties, duties or other charges arising out of erection of works and regular clearance of rubbish, clearing up, leaving the site perfect and tidy on completion.

11.2 DESIGN CRITERIA

The Design of temporary works covers all the items pertaining to:

- i. Form work, casting and stacking yard, staging, launching Scheme and/or transportation scheme.
- ii. Drawings furnished with the Tender Documents show the level of works based on available soil investigation data. These may require change at the time of actual execution of works.

11.3 STANDARD CODES OF PRACTICE

11.4 AVAILABILITY

The contractor shall provide at site all relevant Codes of practice, and CPWD Specifications (latest edition).

Legend

ASCE	American Society of Civil Engineers
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing Materials
BS	British Standard
CPWD	Central Public Works Department
DIN	Deutsche Institute for Normunge.V.
IRC	Indian Road Congress
IRS	Indian Railway Standards
IS	Indian Standards
JIS	Japanese Industrial Standard
MOST	Ministry of Surface Transport
MORTH	Ministry of Road Transport and Highways

11.5 ORDER OF PRECEDENCE

Wherever Indian Standards do not cover some particular aspects of design/construction, relevant standards will be referred to.

In case of discrepancy among Standard codes of practice, CPWD Specifications, General and particular Specifications, and Bill of Quantities, the order of precedence will be as below:

- i. Bill of Quantities
- ii. Particular Specifications
- iii. General Specifications
- iv. CPWD Specifications.
- v. Standard Codes of Practice.

In case of discrepancy among Standard Codes of Practice, the decision of Engineer will be final and binding.

11.6 APPLICABLE CODES

The summarized list of codes is applicable to structural and architectural works. This will not preclude the Engineers right to refer to any other code applicable for the satisfactory execution of the work.

11.7 DIMENSIONS

- i. Figured dimensions on drawings shall only be followed and drawings to a large scale shall take precedence over smaller scale drawings. All dimensions shall be checked on site prior to execution.

The dimensions where stated do not allow for waste, laps, joints, etc. but the Contractor shall provide at his own cost sufficient labour and materials to cover such waste, laps, joints, etc.

- ii. The levels, measurements and other information concerning the existing site as shown on the drawings are believed to be correct, but the Contractor should verify them for himself and also examine the nature of the ground as no claim or allowance whatsoever will be entertained on account of any errors or omissions in the levels or the description of the ground levels or starts turning out different from what was expected or shown on the drawings.

11.8 STEEL STRUCTURES

11.8.1 General

- 11.8.1.1** This section covers the general requirements of designing, preparing necessary drawings, and, providing, fabricating, painting, transporting, erecting, fixing in position structural steel

work for buildings, including all necessary temporary works and conducting of associated tests.

11.8.1.2 Contractor shall ensure that the Technical specifications detailed herein are carefully read and understood in conjunction with, and related to bill of quantities, and, the contractor in his rates includes all requirements defined herein and in other parts of the Contract Document.

11.8.2 Applicable Codes And Standards

The codes and standards generally applicable to the work of this section are listed below. These are in addition to all relevant Indian Standard Codes as specified in the referenced documents. Latest revisions of the codes shall only be applicable.

IS: 102	Ready mixed paint, brushing, red lead non-setting, priming
IS: 104	Ready mixed paint, brushing, zinc-chrome, priming
IS: 210	Gray Iron Castings
IS: 451	Technical Supply Conditions for Wood Screws
IS: 800	Code of Practice for General Construction in Steel
IS: 801	Code of Practice for use of Cold Formed Light Gauge Steel Structural Members in General Building Construction.
IS: 806	Code of Practice for use of Steel Tubes in General Building Construction
IS: 808	Dimensions of Hot Rolled Steel beam, channel and angle sections
IS: 811	Cold Formed Light Gauge Structural Steel Sections
IS: 813	Scheme of Symbols for Welding
IS: 814	Covered Electrodes for Manual Metal Arc Welding of Carbon and Carbon-Manganese Steel
IS: 816	Code of Practice for use of Metal Arc Welding for General Construction in Mild Steel
IS: 818	Code of Practice for Safety and Health requirements in electric and Gas Welding and Cutting Operations
IS: 822	Code of Procedure for Inspection of Welds
IS: 875	Code of Practice for Structural Safety of Building, Loading Standards.
IS: 1024	Code of Practice for use of Welding in Bridges and Structures Subject to Dynamic Loading
IS: 1030	Carbon Steel Castings for General Engineering Purposes

IS: 1120	Coach Screws
IS: 1161	Steel Tubes for Structural Purposes
IS: 1182	Recommended Practice for Radiographic Examination of Fusion Welded Butt Joints in Steel Plates
IS: 1363	Hexagon Head Bolts, Screws and Nuts (Grade-C)
IS: 1364	Hexagon Head Bolts, Screws and Nuts (Grades A & B)
IS: 1365	Slotted Counter-sunk Head Screws
IS: 1367	Technical Supply Condition for Threaded Fasteners
IS: 1852	Rolling and Cutting Tolerances for Hot Rolled Steel Products
IS: 1977	Low Tensile Structural Steel
IS: 2016	Plain Washers
IS: 2062	Steel for General Structural Purposes
IS: 2074	Ready Mixed Paint, Air drying, Red Oxide-Zinc Chrome Priming
IS: 3063	Fasteners- Single Coil Rectangular Section Spring Washers
IS: 3400	Methods of Test for Vulcanized Rubber
IS: 3443	Crane Rail Sections
IS: 3600	Testing Methods of Fusion Welded Joints and Weld Metal in Steel
IS: 3613	Acceptance Tests for Wire Flux combination for submerged, welding
IS: 3757	High Strength Structural Bolts
IS: 4000	Code of Practice for High Strength Bolts in Steel Structures
IS: 4923	Hollow Steel Sections for Structural Use
IS: 5369	General Requirements for Plain Washers and Lock Washers
IS: 5624	Foundation Bolts
IS: 6227	Code of Practice for use of Metal Arc Welding in Tubular Structures
IS: 6623	High Strength Structural Nuts
IS: 6639	Hexagonal bolts for steel structures.
IS: 8500	Structural Steel Micro-alloyed (Medium and High strength Qualities)
IRC : 83 (Part-II)	Elastomeric Bearings

11.8.3 Design

11.8.3.1 The contractor will be required to carry out detailed design of the structures, prepare engineering drawings and detailed 'shop drawings', get these approved from Engineer, and then carry out the fabrication work based on approved drawings.

11.8.3.2 Contractor's designs shall, unless otherwise specified, be based on provisions of relevant BIS codes. Design guideline and design parameters are mentioned in ANNEXURE - C to these specifications.

Where corresponding parameters mentioned in BIS codes are different from those mentioned in ANNEXURE-C, the latter shall take precedence.

11.8.3.3 Contractor's designs shall be based on general descriptions of buildings given in tender documents and those shown in Tender Drawings.

Where information given in tender documents do not tally with the Tender Drawings, information given in Tender drawings shall take precedence.

11.8.3.4 Where codes and standards listed in clause 11.8.2 do not cover the requirements of design, only in those cases the contractor may refer to other International Standards of design. However, such references should be made only with the approval of the Engineer.

11.8.3.5 Contractor shall submit his design calculations and 'Engineering Drawings' to the Engineer for his approval. The contractor is advised to discuss his design philosophy and design procedure with the Engineer before proceeding with the final design work.

11.8.3.6 It shall be the responsibility of the contractor to obtain all relevant design information from the Engineer for preparing his designs, including all special loading like loads from cranes and other utility services supported by the structure.

11.8.4 Drawings

11.8.4.1 'Tender Drawings' shall be the 'Basic' drawings for developing design drawings. Design drawings shall then be developed in to final 'Shop Drawings' to be prepared by the contractor. For preparing shop drawings, the contractor shall obtain written approval from the Engineer.

11.8.4.2 Tender drawings furnished to the Contractor shall form a part of these specifications. The Contractor shall consult these in detail for all the information contained therein, which pertains to and is required for his work.

11.8.4.3 Revisions to drawings, even after release for preparation of shop drawings, are likely to be made to reflect additional data, or, additional details defining updated requirements. Revisions to drawings and any new drawings made to include additional work for the

Contractor shall be considered a part of this specification and contract. Extra claims by the contractor on this account shall not be entertained.

- 11.8.4.4** Tender drawings show all relevant dimensions, and if necessary, clearances of structures, special loading where necessary, general location of openings at various levels and all other information required to enable the Contractor to prepare drawings for general engineering / fabrication and erection.
- 11.8.4.5** It shall be clearly understood that the Tender drawings are only informative drawings and are not intended to show exact and final information or specific connection details.
- 11.8.4.6** In case of variations in 'Drawings' and 'Specifications', the decision of the Engineer shall be final and binding. Should the Contractor during the execution of his work, find discrepancies in the information furnished to him, he shall refer such discrepancies to the Engineer before proceeding with such work.
- 11.8.4.7** Contractor shall prepare all fabrication and erection drawings necessary for completing the work satisfactorily.
- 11.4.8.8** Drawings shall be of one standard size, and shall be clear and legible. Drawings shall be based on Tender drawings supplied to the contractor, but he shall verify actual clearances and dimensions from site on works executed by other agencies and from Engineer
- 11.8.4.9** Shop drawings shall include, but not be limited to:
- (a) Detailed marking plans.
 - (b) Details of member connections and connections to other structures/ components of buildings.
 - (c) Detailed dimensions for fabrication indicating dimensional modifications required for field conditions.
 - (d) Welding and bolting procedures to be used both at shop and field.
 - (e) Cambers required to be provided, and permissible tolerances in fabrication.
 - (f) Assembly and erection sequences indicating components to be connected at field.
 - (g) Complete bill of materials for each component (preferably drawing wise).
- 11.8.4.10** Before submitting of shop drawings and calculations to the Engineer for his approval, these shall be checked and certified by the contractors own structural engineer. Till such time shop details of a component are approved by the Engineer, fabrication work for the component shall not be started.

11.8.4.11 If necessary and called for by the Engineer, shop drawings shall be revised to suit modified requirements as mentioned in 11.8.4.3, and these shall be resubmitted for approval of the Engineer.

11.8.4.12 While the shop drawings prepared by the contractor, and approved by the Engineer represent the correct interpretation of work to be done, the contractor is not relieved of his responsibilities for: -

- (a) Dimensional accuracy
- (b) Correctness of engineering and design of connections
- (c) Fit of parts
- (d) Details
- (e) Errors or omissions
- (f) Material and workmanship
- (g) Methodology of fabrication and erection
- (h) Safety of performance

11.9 SUBMITTALS

On commencement of the Project, the Contractor shall submit the following to the Engineer:

- (i) Prior to the technical submittals, the contractor shall submit detailed baseline program and methodology indicating the proposed overall schedule for documentation such as calculations, shop/ working drawings, plan/ procedures and records. Submission of samples, process of fabrication / delivery to site storage yard for the approval of the Engineer.
- ii) Complete fabrication drawings, materials lists, cutting lists, bolt lists, welding schedules and QC schedules, based on the design drawing furnished to him and in accordance with the approved schedule. It is highlighted that structural steel members, dimensions thereof indicated in tender drawings are tentative only, and may be modified during final design stage.
- iii) Results of any tests, as and when conducted and as required by the Engineer.
- iv) Manufacturer's mill test reports in respect of steel materials, bolts, nuts and electrodes, wires as may be applicable.
- v) A detailed list of all constructional Plant & Equipment, such as cranes, derricks, winches, welding sets etc. their makes, model, calibration and fitness certificates as required present condition and location, available to the contractor and the ones he

will employ on the job to maintain the progress of work in accordance with the contract.

- vi) The total number of experienced personnel (with trade certificates) of each category, like fitters, welders, riggers etc., which he intends to deploy on the project.
- vii) The contractor shall submit complete design calculations for any alternative sections proposed by him, for approval of the Engineer. Use of any alternative section shall be subject to approval of the Engineer. However, no extra payment will be entertained on account of this except as specified in BOQ.

11.10 MATERIALS

11.10.1 Structural Steel

- (i) All structural components other than purlins and side cladding runners shall be made from Hot Rolled Sections and plates with Grade-B0 (with mandatory impact testing) having a minimum yield stress of 250 Mpa conforming to IS:2062. Minimum metal thickness for Hot Rolled sections shall be 6mm. Such steel shall be procured from approved manufacturers.
- (ii) Whenever high strength steel is specified, it shall be conforming to IS: 8500.
- (iii) All steel tubes shall be hot finished seamless steel tubes (HFG) of the specified strength and as approved by the Engineer, and shall conform to IS: 1161. Tubes made by other processes and which have been subjected to cold working, shall be regarded as hot finished if they have subsequently been heat treated and are supplied in the normalized condition.
- (iv) Purlins and side cladding runners only shall be made from cold formed sections and shall conform to ASTM A570 Gr 50 with minimum yield strength of 345 Mpa. Minimum metal thickness for cold formed sections shall be 3.15mm UNLESS SPECIFICALLY recommended by the Structural Consultant and permitted by the Engineer.

11.10.1.1 Steel Supplied by the Contractor

- (i) The Contractor shall furnish to the Engineer all mill orders covering the material ordered by him for this project and also the test reports received from the Mills for his approval and information. It is not intended that all the steel materials to be supplied by the Contractor for the work shall be specially purchased from the rolling mills. The Contractor's stock material may be used, provided the mill test reports identified with the materials, satisfactorily demonstrate the specified grade and quality. The Engineer shall have the right to test random samples to prove authenticity of the test certificates produced by the Contractor, at the Contractor's cost.
- (ii) All steel materials supplied by the Contractor shall be in a sound condition, of recent manufacture, free from defects, loose mill scale, slag intrusions, laminations, pitting, flaky rust, etc. and be of full weight and thickness specified.

- (iii) Wherever the Contractor, in order to accommodate his other materials in stock, desires to substitute structural steels or plates for the sizes shown on drawings, such substitutions shall be made only after authorization in writing by the Engineer.
- (iv) The Engineer may direct that substitution be made, when he considers such substitutions is necessary.

11.10.2 Threaded Fasteners

- i) Technical supply conditions for bolts and nuts shall comply with IS: 1367. Unless specified otherwise all field connections shall be bolted with high strength bolts of property class 8.8. Unless specified otherwise, the bolts and nuts shall be hexagonal.
- ii) All anchor bolts and nuts shall be of property class 4.6 (Grade-B) of IS: 1367, and shall conform to IS: 5624. All nuts shall be hexagonal, and shall conform to property class compatible with the property class of the bolt used.
- iii) Plain washers shall conform to IS: 5369, unless otherwise specified. One washer shall be supplied with each bolt and, in case of special types of bolts, more than one washer as needed for the purpose shall be supplied. An additional double coil helical spring washer, conforming to IS: 6755, shall be provided for bolts carrying dynamic or fluctuating loads and those in direct tension.

11.10.3 Electrodes

- 11.10.3.1** Electrodes used for metal are welding of mild steel shall be heavy coated type electrodes conforming to IS : 814 (Part I & II) and shall be of the best quality approved by the Engineer. All electrodes/ wires / flux shall be kept under dry conditions. Any electrode / wires /flux damaged by moisture shall not be used unless it is guaranteed by the manufacturer that, when it is properly dried, there will be no detrimental effect. Any electrode, which has part of its flux coating broken away or is otherwise damaged, shall be rejected. Any electrode /wires/ flux older than six (6) months from the date of manufacture shall not be used. Batch certificates for electrodes/ wires /flux shall be submitted by the Contractor. Welding consumables for Manual metal arc welding shall conform to IRS-M-28, Wire and Flux combination for Submerged Arc welding to IRS-M-39 and filler wires for CO2 welding to RDSO/ M & C, Specification.

11.10.4 Handling and Storage

- 11.10.4.1** Proper storage of steel (sections and fabricated members) at the job site shall be the responsibility of the Contractor.
- 11.10.4.2** Structural steel shall be stored out of mud and dirt. Proper drainage of the storage area shall be provided. These shall be protected from damage or soiling by adjacent construction operations.

11.10.4.3 Fabricated steel shall not be handled until the paint has thoroughly dried. Care shall be taken to avoid paint abrasions and other damage. Steel work shall be transported in such a way so as not to over stress the fabricated sections. All pieces bent or otherwise damaged shall be rejected and shall be replaced by the contractor at his own cost.

11.10.4.4 Checking and inspection of fabricated structural steel work by the Engineer shall be done at various stages of completion of fabrication work. The contractor is required to ensure that fabricated steel work is properly stacked such that all joints of all members are either visible or accessible for inspection at all stages of inspection work. Care should also be taken to ensure that fabricated members are not subjected to stresses due to defective stacking.

11.11 FABRICATION

11.11.1 All fabrication work shall be done in accordance with IS: 800, read in conjunction with relevant codes mentioned therein.

11.11.2 Fabrication shall be done in workshops approved by Engineer, unless specifically permitted by Engineer that fabrication can be done at site. Under such circumstances work shall be done on a specially designed and constructed platform. Location, size, specification and construction of such a platform shall have prior approval of Engineer. Loads associated with such platforms shall be provided to Engineer.

11.11.3 Mild steel rolled sections and plates shall be cut by shearing/machining and grinding the surfaces to true sizes and shapes. Gas cutting of mild steel may be permitted by the Engineer, provided that every cut face and edge is smoothened by grinding operation. Prior approval of Engineer must be obtained for using gas-cutting techniques either by mechanized gas cutters or manually operated gas cutters. While, using gas-cutting methods, proper allowance must be made for grinding to bring the cut piece to exact required dimensions.

11.11.4 Extensive use of templates shall be made in doing fabrication work. Templates shall be clean and should have true surfaces prepared for every successive use. Reinforcements for the structural steel members if required shall be included. In case actual members are used as templates for similar pieces, it will be at the discretion of the Engineer to decide whether such pieces are fit to be incorporated in the finished structure. Jigs and manipulators shall be used, where practicable, and shall be designed to facilitate welding and to ensure that all welds are easily accessible to the operators.

11.11.5 All material shall be straight and free from twist and bends unless required to be curvilinear in form. If necessary the material shall be straightened and / or flattened / straightened by pressure. Heating of rolled sections and plates for purpose of

straightening shall not be permitted.

- 11.11.6** Curvilinear members shall be formed by bending with the help of pneumatic press. Final shaping, to a very limited extent, however, may be done by local heat application. This shall be done only on receiving approval from the Engineer.

11.11.7 Holing

- 11.11.7.1** All holes shall be made at right angles to the surface of the member. Holes shall be clean cut without any torn or jagged edges. Holes shall be done by drilling. Punching shall not be resorted to, unless previously approved by the Engineer. In any case, punching of holes in materials having a thickness in excess of the connector diameter, or, for materials thicker than 16 mm, the hole shall be punched 3 mm less in diameter than the required size and then reamed to the full size. Holes shall not be formed or enlarged by burning or gas cutting under any circumstances.

11.12 WELDING

11.12.1 General

In general only Automatic submerged arc welding will be used for fabrication. Subject to approval of Engineer, Metal inert gas welding may be done for short length where access to the location of the weld does not permit submerged arc welding. The welding and the welded work shall conform to IS: 816, unless otherwise specified. As much work as possible shall be welded in shops and the layout and sequence of operations shall be so arranged as to eliminate distortion and shrinkage stresses. Unless otherwise specified all weld shall be for full contact for all sides.

- 11.12.2** Electrodes for shielded-arc manual welds shall comply with the requirements of IS:814 and shall be amenable to radiographic tests and shall be of approved make. The electrodes for manual arc welding shall be suitable for use in the position and type of work, as laid down in the above specifications and as recommended by the manufacturers. Electrodes classification group 1 or 2 as given in IS: 814 shall be used for welding steel conforming to IS: 2062. Electrodes shall conform to IS-1442 for steel conforming to IS : 8500. Joints in materials above 20 mm thick, and, all important connections shall be made with low hydrogen electrodes Electrode flux covering shall be sound and unbroken. Broken or damaged coating shall cause the electrodes to be discarded. Covered electrodes for manual arc-welding shall be properly stored in an oven prior to use in a manner recommended by the Manufacturer and only an hour's quota shall be issued to each welder from the oven.

11.12.3 Electrodes larger than 5 mm diameter shall not be used for root-runs in butt-weld.

Welding plant and accessories shall have capacity adequate for the welding procedure laid down and shall satisfy appropriate standards and be of approved make and quality, the Contractor shall maintain all welding plant in good working order. All the electrical plant in connection with the welding operation shall be properly and adequately earthed and adequate means of measuring the current shall be provided.

All welds shall be made only by welders and welding operators who have been properly trained and previously qualified by tests to perform the type of work required as prescribed in the relevant applicable standards.

All welds shall be free from defects like blow holes, slag inclusions, lack of penetration, undercutting, cracks etc. All welds shall be cleaned of slag or flux and show uniform sections, smoothness of weld metal, feather edges without overlap and freedom from porosity.

11.12.4 Fusion faces and surfaces adjacent to the joint for a distance of at least 50 mm on either side shall be absolutely free from grease, paint, loose scales, moisture or any other substance which might interfere with welding or adversely affect the quality of the weld. Joint surfaces shall be smooth, uniform and free from fins, tears, laminations etc. Preparation of fusion faces shall be done in accordance with the approved fabrication drawings by shearing, chipping, machining or machine flame cutting except that shearing shall not be used for thickness over 8 mm.

11.12.5 In the fabrication of cover-plated beams and built up members all shop splices in each component part shall be made before such component part is welded to other parts of the member. Wherever weld reinforcement interferes with proper fit-up between components to be assembled for welding, these welds shall be ground flush prior to assembly.

11.12.6 Members to be joined by fillet welding shall be brought and held as close together as possible and in no event shall be separated by more than 3 mm. If the separation is 1.5 mm or greater, the fillet weld size shall be increased by the amount of separation. This shall only apply in the case of continuous welds. The fit-up of joints at contact surfaces which are not completely sealed by welds shall be close enough to exclude water after painting.

11.12.7 The separation between fraying surfaces of lap joints and butt joints with backing plate shall not exceed 1.5 mm. Abutting parts to be butt welded shall be carefully aligned and the correct root gap maintained throughout the welding operation. Misalignments greater than 25 percent of the thickness of the thinner plate or 3 mm whichever is

smaller shall be corrected and in making the correction the parts shall not be drawn into a slope sharper than 2 degrees (1 in 27.5).

- 11.12.8** Welding procedures recommended by appropriate welding standards and known to provide satisfactory welds shall be followed. A welding procedure shall be prepared by the Contractor and submitted to the Engineer for approval before start of welding.
- 11.12.9** Approval of the welding procedure by the Engineer shall not relieve the Contractor of his responsibility for correct and sound welding without undue distortion in the finished structure.
- 11.12.10** Voltage and current (and polarity if direct current is used) shall be set according to the recommendations of the Manufacturer of the electrode being used, and suitable to thickness of material, joint form etc. The work shall be positioned for flat welding wherever practicable and overhead weld shall be avoided.
- 11.12.11** No welding shall be done when the surface of the members is wet, nor during periods of high wind unless the welding operator and the work are properly protected. In joints connected by fillet welds, the minimum sizes of single run fillet welds or first runs and minimum full sizes of fillet welds shall conform to the requirements of IS: 816 and IS: 823. Fillet welds larger than 8 mm shall be made with two or more passes.
- 11.12.12** All 'full penetration butt welds' made by manual arc-welding, except when produced with the aid of backing material or welded in flat position, from both sides in square-edge material, not over 8 mm thick with root opening not less than one-half the thickness of the thinner part joined, shall have the root of the initial layer gouged out on the back side before welding is started from that side, and shall be so welded as to secure sound metal and complete fusion throughout the entire cross section.
- 11.12.13** Butt welds shall be terminated at the ends of a joint in a manner that will ensure their soundness. Where abutting parts are 20 mm or more in thickness, run-on and run-off plates with similar edge preparation end having a width not less than the thickness of the thicker part joined shall be used. These extension pieces shall be removed upon completion of the weld and the ends of the weld made smooth and flush with the abutting parts. Where the abutting parts are thinner than 20 mm the extension pieces may be omitted but the ends of the butt welds shall then be chipped or gouged out to sound metal and side welded to fill up the ends to the required reinforcement.
- 11.12.14** Each layer of a multiple layer weld except root and surface runs may be moderately peeled with light blows from a blunt tool. Care shall be exercised to prevent scaling or flaking of weld and base metal from over-peeling.

11.12.15 Before commencing fabrication of a member or structure in which welding is likely to result in distortion and/or locked up stresses, a complete programme of fabrication, assembly and welding shall be made and submitted to the Engineer for his approval. Such a programme shall, include, besides other appropriate details, full particulars in regard to the following :

- i) Proposed pre-bending of components such as flanges and presetting of joints to offset expected distortion.
- (ii) Make up of sub-assemblies proposed to be welded before incorporation in final assembly.
- (iii) Proposed joint forms, classification of wire and flux or covered electrodes, welding process including fitting and welding sequence with directions in which freedom of movement is to be allowed.
- (iv) Proposed number, spacing and type of strong details of jigs and fixtures for maintaining proper fit up and alignment during welding.
- (v) Any other special features like assembling similar members back to back or stress relief.

Suggestive Minimum Preheating Of Metals:

Thickness Of Thickest Part At Point Of Welding	Minimum Preheat & Inter-pass Temperature			
	Other than low-hydrogen welding electrodes		Low Hydrogen welding electrodes	
Applicable Codes	IS : 226 steel or IS : 2062 steel	IS : 961 steel	IS : 226 steel or IS : 2062 steel	IS : 961 steel
Upto 20 mm incl.	None	Welding with this process not allowed	None	10 ⁰ C
Over 20 mm to 40 mm incl.	65 ⁰ C		10 ⁰ C	65 ⁰ C
Over 40 mm to 63 mm incl.	110 ⁰ C		95 ⁰ C	110 ⁰ C
Over 63 mm	150 ⁰ C		110 ⁰ C	150 ⁰ C

Minimum preheat temperature for metal thickness up to 50 mm shall be 100C.

11.12.16 If so desired by the Engineer, mock up welding shall be carried out at the Contractor's cost to establish the efficacy of the proposed programme, with any modification suggested by the Engineer in limiting distortion or/and residual stress to acceptable levels. Such modifications will not relieve the Contractor of any of his responsibilities.

11.12.17 The ends of butt joints shall be welded so as to provide full throat thickness. This may be done by the use of extension pieces, cross-runs or other approved means. The weld face shall, at all places, be deposited projecting the surface of the parent metal. Where a flush surface is required, the surplus metal shall be dressed off. Splices and butt joints of compression members, depending on contact for stress-transmission, shall be accurately machined over the whole section. In column bases, the ends of shafts together with the attached gussets, angles, Channels etc., after bolting and/or welding together as the case may be, shall be accurately machined so that the parts connected butt over the entire surface of contact. Care shall be taken that connecting angles or channels are fixed with such accuracy that they are not reduced in thickness by machining by more than 0.8mm.

11.12.18 The minimum leg length of a fillet weld as deposited shall be not less than the specified size. In no case shall a concave weld be deposited, unless specifically permitted. Where permitted, the leg length shall be increased above that specified length, so that the resultant throat thickness is as great as would have been obtained by the deposition of a flat-faced weld of the specified leg length.

11.12.19 After making each run of welding, all slag shall be thoroughly removed and the surface cleaned. The weld metal, as deposited (including tack welds), shall be free from-cracks, slag inclusions, porosity, cavities and other deposition faults. The weld metal shall be properly fused with the parent metal without under cutting or overlapping at the toes of the weld. The surface of the weld shall have a uniform consistent contour and regular appearance.

11.13 INSPECTION OF WELDS

11.13.1 All welds shall be inspected for flaws by any of the methods described in these specifications, and as per IS : 822. The choice of the method to be adopted shall be determined by the Engineer.

11.13.2 The Contractor shall arrange for all tests as called for in the schedule of quantities, at his own cost.

11.13.3 In case the tests uncover defective work, such tests shall be at the Contractor's cost and the Contractor shall correct such defects at his own cost, and prove the soundness of rectified work.

11.13.4 The correction of defective welds shall be carried out as directed by the Engineer without damaging the parent metal. When a crack in the weld is removed, magnetic particle inspection or any other equally positive means as prescribed by the Engineer shall be used to ensure that the whole of the crack and material up to 25 mm beyond each end of the crack has been removed. Cost of all such tests and operations incidental to correction shall be to the Contractor's account.

11.14 FABRICATION TOLERANCES

11.14.1 Unless otherwise shown on drawings, the fabrication tolerances shall generally be as detailed hereunder.

11.14.2 Straightness

11.14.2.1 The dimensional and weight tolerance for rolled shapes shall be in accordance with IS: 1852 for indigenous steel and equivalent applicable codes for imported steel. The acceptable limits for straightness (sweep and camber) for rolled or fabricated members shall be: Struts and columns: $L/1000$ or 10 mm whichever is smaller for all other members not primarily in compression such as purlins, beams, bracings & web members of trusses and latticed girders: $L/500$ or 15 mm whichever is smaller. Where L is the length of finished member, or such lesser length as the Engineer may specify.

11.14.3 Twists

11.14.3.1 A limit for twist (prior to erection) in :-

Box girders and heavy columns: $L/1500$

Other members: $L/1000$

The twist of the member between any two sections shall be measured with the web vertical at one of the sections.

11.14.4 Camber

11.14.4.1 Tolerance in specified camber of structural members shall be + 3 mm.

11.14.5 Length

11.14.5.1 Tolerance in specified length shall be as follows :

<i>Type of Member</i>	<i>Tolerance</i>
A column finished for contact bearing:	+ 1 mm
Other members (e.g. beams) under 10 m:	+ 0 and - 3 mm
Other members (e.g. beams) 10 m long and over:	+ 0 and - 5 mm

11.14.6 Square-Ness at End of Members

11.14.6.1 Beam to beam and beam to column connections where the abutting parts are to be jointed by butt welds, permissible deviation from the square-ness of the end is :

Beams up to 600 mm in depth :	1.5 mm
Beams over 600 mm in depth :	1.5 mm every 600 mm depth
	Up to a max of 3 mm

11.14.6.2 Where abutting parts are to be jointed by bolting through cleats or end plates, the connections require closer tolerance. Permissible deviation from squareness of the end is -

Beams up to 600 mm in depth:	1 mm
Over 600 mm in depth:	max of 1.5 mm.

11.14.7 Butt Joints

11.14.7.1 For full bearing, two abutting ends of columns shall first be aligned to within 1 in 1000 of their combined length and then the following conditions shall be met:

- (a) Over at least 80% of the bearing surface the clearance between the surfaces does not exceed 0.1 mm.
- (b) Over the remainder of the surfaces the clearance between the surfaces does not exceed 0.3 mm. Where web stiffeners are designed for full bearing on either the top flange or bottom flange or both, at least half the stiffener shall be in positive contact with the flange. The remainder of the contact face could have a max. gap of 0.25 mm.

11.14.8 Depth of Member

11.14.8.1 Acceptable deviation from the specified overall depth is :

For depths of 900 mm and under:	+ / - 3 mm
For depths over 900 mm and under 1800 mm:	+ / - 5 mm
For Depths of 1800 mm and over:	+ 8 mm ; - 5 mm.

11.14.9 Web Plates

11.14.9.1 Acceptable deviation from flatness in girder webs in the length between the stiffeners or in a length equal to the girder depth shall be 1/150th of the total web depth.

11.14.10 Flange Plates

11.14.10.1 Limit for combined warp-age and tilt on the flanges of a built up member is 1/200 of the total width of flange or 1.5 mm whichever is smaller measured with respect to centre-line of flange.

11.14.10.2 Lateral deviation between centre-line of web plate and centre-line of flange plate at contact surfaces, in the case of built up sections shall not exceed 3 mm.

11.15 INSPECTION

11.15.1 The Contractor shall give due notice to the Engineer in advance of the materials or workmanship getting ready for inspection.

- i) All rejected material shall be promptly removed from the shop and replaced with new material for the Engineer's approval / inspection. The fact that certain material has been accepted at the Contractor's shop shall not invalidate final rejection at site by the Engineer, if it fails to be in proper condition or has fabrication in-accuracies which prevent proper assembly. No materials shall be painted or dispatched to site without inspection and approval by the Engineer unless, such inspection is waived in writing by the Engineer.
- ii) Shop inspection by the Engineer or his authorized representative, or, submission of test certificates and acceptance thereof by the Engineer, shall not relieve the Contractor from the responsibility of furnishing material conforming to the requirements of these specifications. Nor shall it invalidate any claim, which the Engineer may make because of defective or unsatisfactory material and/or workmanship.
- iii) The Contractor shall provide all the testing and inspection services and facilities for shop work except where otherwise specified. For fabrication work carried out in the field, the same standard of supervision and quality control shall be maintained as in shop fabricated work. Inspection and testing shall be conducted in a manner satisfactory to the Engineer

11.15.2 Testing

11.15.2.1 Material Testing

- i) If mill test reports are not available for any steel materials, the same shall be got tested by the Contractor to the satisfaction of Engineer to demonstrate conformity with the relevant specification.

11.15.2.2 Tests on Welds

Magnetic Particle Test

Only where the Engineer requires that flaw-detection of welds be done by 'Magnetic Particle Test', in such cases the tests are to be done in accordance with IS: 3703. If

heat treatment is performed, the completed weld shall be examined after the heat treatment. All defects shall be repaired and re-tested. Magnetic particle tests shall be carried out using alternating current. Direct current may be used with the explicit written permission of the Engineer.

11.15.2.3 Dye Penetration Test

Where welds are required to be examined by dye penetration inspection method, such tests shall be carried out in accordance with IS: 3658.

11.15.2.4 Radiographic Inspection

Whether instructed by Engineer, or not, all 'Butt' welds shall be fully inspected by radiographic examination method. Such examination shall be done in accordance with the recommendations of IS: 1182.

11.15.3 Test Failure

At any stage, in the event of any material or work failing to meet an inspection or test requirement, which is not overseen by the Engineer, the Contractor shall notify the Engineer immediately. The Contractor must obtain permission from the Engineer before repair is undertaken. The quality control procedures to be followed to ensure satisfactory repair shall be subject to approval by the Engineer. The Engineer has the right to specify additional inspection or testing as he deems necessary, and the additional cost of such testing shall be borne by the Contractor. The Contractor shall maintain records of all inspection and testing which shall be made available to the Engineer on demand.

11.15.4 Shop Matching

Some steel work, particularly columns along with tie beams, bracings etc. may have to be shop assembled to ensure satisfactory fabrication. If the Engineer so desires, he may order such assembly at shop for verification. The Contractor shall comply with such instructions without claiming any extra cost.

11.15.5 Shop Assembly

11.15.5.1 The steelwork shall be temporarily shop assembled, as necessary, so that the accuracy of fit may be checked before dispatch. The parts shall be shop assembled with a sufficient number of parallel drifts to bring and keep the parts in place.

11.15.5.2 Since parts drilled or punched, with templates having steel bushes shall be similar and, as such, interchangeable, such steelwork may be shop erected in part only, as agreed by the Engineer.

11.15.6 Assembly

- i) All parts assembled for bolting shall be in close contact over the whole surface.
- ii) The component parts shall be so assembled that they are neither twisted nor otherwise damaged. Specified cambers, if any, shall be provided.
- iii) All parts of bolted and welded members shall be held firmly in position by means of jigs or clamps while bolting or welding. No drifting of holes shall be permitted, except to draw the parts together and no drift used shall be larger than the nominal diameter of the bolt. Drifting done during assembling shall not distort the metal or enlarge the holes.
- iv) Trial assemblies shall be carried out at the fabrication stage to ensure accuracy of workmanship, and these checks shall be witnessed by the Engineer/ Authorised inspecting agency. Such trial assemblies shall be at the cost of the contractor.
- v) Field Bolts
 - a. Requirements stipulated under bolting shall apply for field bolts also. Field bolts nuts and washers shall be furnished by the Contractor in excess of the nominal numbers required. He shall supply the full number of bolts, nuts and washers and other necessary fittings required completing the work, together with the additional bolts, nuts and washers totaling to 10% of the requirement subject to minimum of 10 Nos.
 - b. At the time of assembly, the surfaces in contact shall be free of paint or any other applied finish, oil, dirt, loose rust, loose scale, burrs and other defects which would prevent solid seating of the parts or would interfere with the development of friction between them.
 - c. If any other surface condition, including a machined surface, is specified, it shall be the responsibility of the Contractor to work within the slip factor specified for the particular case.
 - d. Each bolt and nut shall be assembled with washers of appropriate shape, quality and number in cases where plane parallel surfaces are involved. Such washers shall be placed under the bolt head or the nut, whichever is to be rotated during the tightening operation. The rotated nut or bolt head shall be tightened against a surface normal to the bolt axis, and the appropriate tapered washer shall be, used when the surfaces are not parallel. The angle between the bolt axis and the surface under the non-rotating component (i.e. the bolt head or the nut) shall be $90 + 3$ degree. For angles outside these limits, a tapered washer shall be placed under the non-rotating component. Tapered washers shall be correctly positioned.
 - e. No gasket or other flexible material shall be placed between the holes. The holes in parts to be joined shall be sufficiently well aligned to permit bolts to be freely placed in position. Driving of bolts is not permitted. The nuts shall be placed so

that the identification marks are clearly visible after tightening. Nut and bolts shall always be tightened in a staggered pattern and where there are more than four bolts in any one joint, they shall be tightened from the centre of the joint outwards.

- f. If, after final tightening, a nut or bolt is slackened off for any reason, the bolt, nut and washer or washers shall be discarded and not used again.

11.15.7 Marking of Members

After checking and inspection, all members shall be marked for identification during erection. This mark shall correspond to distinguishing marks on approved erection drawings and shall be legibly painted and stamped on it. The erection mark shall be stamped with a metal dye with figures at least 20 mm high and to such optimum depth as to be clearly visible, even after a member is galvanized.

All erection marks shall be on the outer surface of all sections and near one end, but clear of bolt-holes. The marking shall be so stamped that they are easily discernible when sorting out members. The stamped marking shall be encircled boldly by a distinguishable paint to facilitate easy location. Erection marks on like pieces shall be at identical location. Members having lengths of 7.0 m or more shall have the erection mark at both ends.

Each fabricated member, whether assembled prior to dispatch or not so assembled, shall bear an erection mark, which will help to identify the member and its position in respect of the whole structure, to facilitate re-erection at site. This erection mark shall be incorporated in the shop detail and erection drawings.

11.15.8 Errors

Any error in shop work which prevents proper assembling and fitting up of parts in the field by moderate use of drift pins or moderate amount of reaming will be classified by the Engineer as defective workmanship. All charges incurred by the Engineer either directly or indirectly because of the poor workmanship will be deducted from the amount due to the Contractor before payment is made. The amount of such deduction will consist of the sum total of the costs of labour direct or indirect, material, plant, transportation, equipment rental and overhead expenses. In case the Engineer chooses to reject the material because of poor workmanship, the cost of all handling and returning the material to the Contractor, if he so desires, shall entirely be to the Contractor's account. All the replacement materials shall be supplied free and in all such cases, the cost of handling, transport and delivery to site shall be borne by the Contractor.

11.15.9 Erection

11.15.9.1 Erection of structural steel fabricated components shall be done generally in accordance with provisions of IS: 800.

11.15.9.2 Before starting of erection work, the contractor shall ensure the fulfilment of the following activities:

- i) The contractor shall submit, for examination by the Engineer, detailed particulars of his proposed methods of erection of the superstructure steelwork, together with complete calculations relating to strength and deflection. If the erection scheme necessitates the attachment of strength steelwork to the permanent steel work, the contractor shall submit, for approval of the Engineer, the methods he proposes for making good the permanent steelwork after removing the temporary work. The contractor shall also submit the design and fabrication drawings including detailed calculations of temporary nose, counter weight, all temporary support, staging, braces etc. required for safe erection, for approval of the Engineer.
- ii) The contractor shall provide all construction and transport equipment, tools, tackle, and consumables, materials, labour and supervision required for the erection of the structural steelwork.
- iii) Handling, assembling, bolting, welding and satisfactory installation of all fabricated structural steel materials in proper location, according to approved erection drawings and/or as directed by the Engineer.
- iv) Setting out, aligning, plumbing, levelling, bolting, welding and securely fixing the fabricated steel structures in accordance with the erection scheme, or as directed by the Engineer.

11.15.9.3 Grouting under base plates shall be done after erection of the structural steel, unless otherwise approved by the Engineer. All bearing plates and bearing assemblies shall be set level and to the elevations shown on drawings. These shall be shimmed with approved means and grouted to ensure full bearing on the supporting substrate regardless of the tolerances otherwise permitted. The grout to be used in superstructure or stanchion bases shall be shrink resistant grouting compound of approved make and manufacture and shall have a 28 days compressive strength of at least 30 N/sqmm. The surfaces which have to receive the grout shall be thoroughly cleaned immediately prior to the grouting operation. The grout shall be carefully worked under the base plates and shall completely fill the space under the base plates. After the grout has had its initial set, the grout shall be cut back flush with the base plate as shown in drawings and surplus grouting material removed. The surplus material thus

removed shall not be re-used. If inserts in concrete are required, the contractor shall furnish all inserts including any reinforcement required for embedding in the concrete to the concrete contractor. It should include providing layout drawings to the concrete contractor for placement of such inserts into concrete.

11.15.9.4 Erection Tolerances

Erection tolerances shall be as per table-1 of ANNEXURE-A.

11.16 QUALITY CONTROL & TESTING REQUIREMENTS

11.16.1 Quality Control through established testing norms of the welded structural steelwork as per clauses 7.2.2 to 7.2.3 mentioned below or Engineer.

- i) The Contractor shall submit the following:
 - Proposed overall schedule for documentation of shop drawings, plan/procedures and records, submission of procedure of fabrication.
 - The contractor shall himself inspect all materials and shop work to satisfy the specified tolerance limits and Quality norms before the same are inspected by Engineer.
- ii) The contractor shall through appropriate planning and continuous measurements in the workshop and the erection at site, ensure that the tolerance specified in ANNEXURE-A are strictly adhered to.

11.16.2 Fabricating agency shall have in house facilities for all testing of weld.

11.16.3 Visual Examination

The contractor shall conduct visual examination and measurement of the external dimensions of welds for all joints. Before examining the welded joints, areas close to it on both sides of the weld for a width not less than 20 mm shall be cleaned of slag and other impurities. Examination shall be done by a magnifying glass which has a magnification power of ten (10) and measuring instrument which has an accuracy of + 0.1 mm or by weld gauges. Welded joints shall be examined from both sides. The contractor shall examine the following during the visual checks.

- i) Correctness and shape of the welded joints
- ii) Incomplete penetration of weld metal.
- iii) Influx
- iv) Burns
- v) Unwelded craters
- vi) Undercuts
- vii) Cracks in welded spots and heat affected zones

- viii) Porosity in welds and spot welds
- ix) Compression in welded joints as a result of electrode impact while carrying out contact welding
- x) Displacement of welded element

The contractor shall, document all data as per sound practices.

11.16.4 In order to exercise proper control of the quality of the welding, Contractor shall enforce methods of control as tabulated below:

Purpose	Control subjects	Methods of control
1	2	3
(i) Control of welding materials and basic metal quality	Quality control of electrodes, welding wire, flux and protective gases. Checking of quality and Weldability of the basic metal and welded members	Weldability test to determine the technological properties of materials. Mechanical test of weld metal. Metalographical investigations of welds macro-structure and microstructure. Checking of weld metal resistance for intercrystalline corrosion. Study if weld metal solidity by physical control methods
(ii) Checking of welders qualifications	Welding of specimens for quality determination	Mechanical tests, metalographical investigation & checking of welded joints by physical control methods Checking of assembly quality & centering of welded members
(iii) Control of welded joint quality	Control of assembly accuracy and technological welding process	Checking of welding equipment conditions. Checking correctness of welding procedure. Visual examination of welds

11.16.5 Mechanical Test

The Contractor shall carry out various mechanical tests to determine weld-ability, metal alloy ability, and nature of break, correct size and type of electrodes, degree of pre-heat and post-heat treatment. The type, scope and sample of various mechanical tests shall be determined in agreement with the purchaser. The number of tests conducted shall depend on the result obtained to satisfy the Engineer that the correct type and size of electrode, degree of pre-heating and post-heating and weld-ability of metal are being followed.

11.16.6 Dye Penetration Test

All welds (100 %) shall be tested by "Dye Penetration test" in accordance with IS: 3658 (latest revision).

11.16.7 Radiography Test

Radiography test shall be conducted by the contractor to determine gas inclusion (blow holes, hollows) slag inclusion, shallow welds and cracks for 100 % lengths all butt joints. Before conducting the examination the welded joints shall be cleaned of slag and scales and visually examined. The welds shall be marked into separate portions depending on the length of photograph. The length of photograph shall be such as to ensure that there are no distortions and shall reveal the defect correctly. The length shall not be more than 0.75 of the focal distance and the width of the photograph would depend on the width of the welded joint plus 20 mm on either side of the weld. The cassette with film shall be protected by sheet of lead or equivalent of proper thickness against incidental, diffused and secondary radiation.

The direction of the ray with relation to the film shall be as specified hereunder.

Welds of butt joints without edge slopes with edge processing shall be examined by central ray directed at right angles to the weld.

In special cases examination of welds with inclined rays directed along edge slopes may be permitted by the Engineer/ Authorised inspecting agency.

Lap joints shall be examined by directing rays at 45 degree to the bottom plate. Welds in T-joints, without any edge preparation shall be examined by rays directed at 45 degree to the weld. Angle welds in lap and tee-joints shall be examined by the rays in opposite direction, i.e. the film will be on the side of the weld. Weld in angle joints shall be checked by directing ray along the bisector of the angle between the welded elements. Opposite direction of the ray and location of the film may also be permitted by the Employer.

11.16.8 Ultrasonic Test

Ultrasonic test shall be conducted by the contractor to detect gas inclusion (pores), slag inclusion, shallow welds, cracks, lamination and friability etc. Prior to starting of ultrasonic test the welded joint shall be thoroughly cleaned of slag and other material. Surface of the basic metal adjacent to welded joint on both sides shall be mechanically cleaned by the grinder or a metal brush to provide the contact of the whole ultrasonic

probe surface with surface of basic metal. The width of the clean surface shall be as directed by the Engineer/ Authorised inspecting agency. The welded joint then shall be covered with a thin coat of transformer oil, turbine or machine oil to ensure acoustic contact. The joints so treated shall be marked and the marks shall be entered into the documentation, subsequent to this, ultrasonic test shall be carried out as directed by the Engineer. Unless otherwise directed by the Engineer 10% of welds shall be subjected to ultrasonic testing. Engineer may at his discretion reduce the frequency of such tests depending on the performance record of earlier tests.

11.16.9 Magnetic particle Test

Based on other test results, or considerations that raises doubts on welded joints at important locations in the structure, the Engineer may call for Magnetic Particle Tests of joints. The Contractor shall comply with such requirements, and arrange for such tests at his own cost.

11.17 PAINTING OF PRE ENGINEERED STRUCTURAL STEEL WORK

11.17.1 Paint

- i) All paint delivered to the fabrication shop shall be ready mixed, in original sealed containers, as packed by the paint manufacturers. Addition of thinners shall not be permitted.
- ii) Opened containers of Paint shall be stirred frequently to keep the pigment in suspension

11.17.2 Storage of Paints

- i) All paints shall be stored strictly in accordance with the requirements laid down by the paint manufacturers. The storage area shall be well ventilated and protected from sparks, flame, direct exposure to sun or excessive heat, preferably located in an isolated room or in a separate building.
- ii) All paint containers shall be clearly labeled to show paint identification, date of manufacture, batch number, order number and special instructions in legible form. The containers shall be opened only at the time of use. Paints that have liveried, gelled or otherwise deteriorated during storage, shall not be used. Paints, for which the shelf life specified by the supplier has expired, shall not be used without inspection and approval by the Engineer.

11.17.3 Execution

- i) Paint System
 - a. In general, except where specified otherwise in approved shop drawings Sand blasting of steel surfaces shall be carried out in accordance with IS:1477.

b. Painting work shall be carried out as follows:

DESCRIPTION	GENERAL SURFACE	
Fabrication Shop	External Surfaces	Internal Surfaces
Surface Treatment	Abrasive blast cleaning to minimum SA-2.5 (ISO 8501-1:1988) – near white blast cleaning. If oxidation occurs between blasting and application of paint, the surface shall be re blasted to the specified standard.	Abrasive blast cleaning to minimum SA-2.5 SIS-055900 near – white blast cleaning
1 st -Coat	1 coat two component, high Solid Zinc Phosphate Epoxy primer and buildcoat, DFT-200 microns shall be Sigmafast 278 or approved equivalent applied by conventional/airless spray or brush only as approved by the Engineer in shop.	1 coat two component, high Solid Zinc Phosphate Epoxy primer and buildcoat, DFT-200 microns shall be Sigmafast 278 or approved equivalent applied by conventional/airless spray or brush only as approved by the Engineer in shop.
2 nd Under-Coat	1 coat two component, high solids, high-build Aliphatic Acrylic Polyurethane finish, DFT-50 microns shall be Sigmadur 550 or approved equivalent applied by conventional/airless spray or brush as approved by the Engineer in approved colour only in shop.	NA
Finish Coat	1 coat two component, high solids, high-build Aliphatic Acrylic Polyurethane finish, DFT-50 microns shall be Sigmadur 550 or approved equivalent applied by conventional/airless spray or brush as approved by the Engineer in approved colour. This coat shall be applied after transportation and erection of the structure.	NA

*** Note: The product shall be meet the requirement of ISO 12944.**

INTERNAL SURFACE = Internal surface are those which will become inaccessible after fabrication and are not prone to humidity and moisture from the atmosphere.

EXTERNAL SURFACE = All other surfaces which are prone to humidity and moisture from the atmosphere.

The following precautions must be taken:

- i. After abrasive blast cleaning, the first undercoat (primer coat) should be applied well before surface deterioration.

- ii. Over coating intervals, application parameters shall conform to manufacturer's instruction manual.
- iii. The DFT (Dry film thickness) shall be measured after completion of each coat.

11.17.4 Surface Preparation

11.17.4.1 General

All surfaces shall be cleaned of loose substances and foreign materials. e. g. dirt, rust, scale, oil, grease, welding flux etc so that the prime coat adheres to the original metal surface. The work shall be carried out in accordance with IS: 1477 (1971) (Part I). Any oil, grease, dust or foreign matter deposited on the surface after preparation shall be removed and care shall be taken to ensure that the surface is not contaminated with acids, alkalis or other corrosive chemicals. The primer coat shall be applied immediately after the surface preparation is completed.

Before the application of any paint the surfaces to be treated shall be thoroughly cleaned freed from all scale, loose paint, rust and other deleterious matters. Oil and grease shall be removed from the surface by washing with solvents or with a detergent solution before blast cleaning operation of metal polish with metal pellets or any other material approved by the Engineer. If any traces of oil or grease remain after blasting they shall be removed by solvent cleaning and the area will be re-blasted thereafter.

All welding areas shall be given special attention for removal of weld flux slag, weld metal splatter, weld head oxides, weld flux fumes, spatters and other foreign objects before blasting. If deemed necessary by the Engineer, acid washing and subsequent washing with clean water shall be used.

Any rough seams will have to be ground and must be inspected and approved by the Engineer before application of the coatings.

All structural steel to be painted shall be cleaned. Blast cleaning in accordance with SA 2 1/2 Near- White Blast cleaning (equivalent Swedish Standard SIS 055900). For SA 2 1/2 the profile should be in the range of 40-70 microns and shall be measured with comparator. Mill scale, rust and foreign matter shall be removed to the extent that the only traces remaining are light stains in the form of spots or stripes. Finally the surface shall be cleaned with a vacuum cleaner or clean dry compressed air.

The blast cleaning shall produce a surface roughness complying with the one specified by the paint manufacturer for the primer concerned. If, cleaned surfaces are rusted or are contaminated with foreign material before painting is accomplished they shall be re-cleaned by the Contractor at his own expenses.

The surface shall be cleaned by impingement of abrasive materials, such as grit of cast iron, malleable iron, steel or synthetic material, at high velocity created by clean and dry compressed air blast. Prior to application of the blast, heavy deposits of oil and grease shall be removed by solvent cleaning and excessive surface scale removed by hand tool or power tool cleaning.

11.17.5 Mixing and Thinning

- a) All ingredients in a paint container shall be thoroughly mixed to break-up lumps and disperse pigments, before use and during application, to maintain homogeneity. All pigmented paints shall be strained after mixing to remove skins and other undesirable matters.
- b) Dry pigments, pastes, tinting pastes and colours shall be mixed and/or made into paint so that all dry powders get wetted by vehicles and lumps and particles are uniformly dispersed.
- c) Additives that are received separate such as curing agents, catalysts, hardeners etc. shall be added to the paint as per the manufacturer's instructions. These shall be promptly used within the pot life specified by the manufacturers and unused paint thereafter shall be discarded.
- d) Thinners shall not be used unless essential and permitted by the Engineer for proper application of the paint. Where thinners are used, they shall be added during the mixing process and the type and quantity of thinner shall be in accordance with the instructions of paint manufacturer.

11.17.6 Paint Application

- a) Paint shall be applied in accordance with the manufacturer recommendations, as supplemented by these Specifications. The work shall generally follow IS:1477- (Part II). Prior approval of the Engineer shall be taken in respect of all primers and/or paints before their use in the works.
- b) Paint shall generally be applied by brushing except that spraying may be use for finish coats only when brushing may damage the prime coats. Roller coat or other method of paint application shall not be used unless specifically authorized.
- c) Spraying paint shall not be adopted on red lead or zinc rich paints. Daubers may be used only when no other method is practicable for proper application in difficult accessible areas.
- d) Paint shall not be applied when the ambient temperature is 10°C and below. For paints which dry by chemical reaction the temperature requirements specified by the manufacturer shall be met with. Also, paint shall not be applied in rain, wind, fog or at relative humidity of 80% and above or when the surface temperature is below dew point, resulting in condensation of moisture. Any wet paint exposed to damaging weather

conditions shall be inspected after drying and the damaged area repainted after removal of the paint.

Each coat of paint shall be continuous, free of pores and of even film thickness without thin spots. The film thickness shall not be so great as to detrimentally affect either the appearance or the service life of the paint.

Each coat of paint shall be allowed to dry sufficiently before application of the next coat, to avoid damages such as lifting or loss of adhesion. Undercoats having glossy surface shall be roughened by mild sand papering to improve adhesion of subsequent coats. Successive coats of same colour shall be tinted. Whenever practical, to produce contrasts and help in identifying the progress of the work.

11.17.7 Brush Application

- i) Proper brushes shall be selected for a specific work piece. Round or oval brushes which conform to IS: 487 are better suited for irregular surfaces, whereas flat brushes which conform to IS: 384 are convenient for large flat areas. The width of flat brushes shall not generally exceed 125mm.
- ii) Paint shall be applied in short strokes depositing a uniform amount of paint in each stroke followed by brushing the paint into all surface irregularities, crevices and corners and finally smoothening or levelling the paint film with long and light strokes at about right angles to the first short strokes. All runs and sags shall be brushed out. The brush marks left in the applied paint shall be as few as practicable.

11.17.8 Spray Application

- (i) The spraying equipment shall be compatible with the paint material and provided with necessary gauges and controls. The equipment shall be cleaned of dirt, dried paint, foreign matter and solvent before use.
- (ii) The paint shall be applied by holding the gun perpendicular to the surface at a suitable distance and moved in a pattern so as to ensure deposition of a uniform wet layer of paint. All runs and sags shall be brushed out immediately. Areas not accessible to spray shall be painted by brush or dauber.
- (iii) Watertrap acceptable to Engineer/ Authorised inspecting agency shall be furnished and installed on all equipment used in spray painting.

11.17.9 Shop Painting

- (i) The painting system specified in Table shall be followed. Surfaces, which will be inaccessible after field assembly, shall receive the full-specified protective treatment before assembly.
- (ii) Surfaces in contact during shop assembly shall not be painted. Surfaces which can not be painted but require protection shall be given a rust inhibitive grease conforming to IS:958-1975 or solvent deposited compound conforming to IS: 1153 (1975) or IS: 1674 (1960) or treated as specified in the drawing.
- (iii) Surface to be in contact with concrete shall not be painted.
- (iv) The shop coats shall be continuous over all edges, including ends meant for jointing at site by bolting, except where the paint could be detrimental to bolting. In such cases, no paint shall be applied within 50mm, and the unprotected surface shall be given a coat of corrosion inhibitive compound.
- (v) The unpainted area shall be cleaned prior to welding. The welded joint shall be cleaned and deslagged, and immediately after covered by the same paint as has been used for the remaining surface.

11.17.10 Protection of Paintwork

- (i) The Contractor shall provide measures as necessary as well as directed by the Engineer to prevent damage to the work and to other property or persons from all cleaning and painting operations. Paint or paint stains which result in other unsightly appearance on surfaces not designated to be painted shall be removed or obliterated by the contractor at his cost.
- (ii) All painted surfaces that in the opinion of the Engineer/ Authorised inspecting agency are damaged in anyway, shall be repaired by the contractor at his cost with materials and to a condition equal to that of the requirements specified in these specifications.
- (iii) Upon painted surfaces that in the opinion of any other work that would cause dust, grease or foreign materials to be deposited upon the painted surfaces, the painted surfaces shall be thoroughly cleaned.
- (iv) The areas for high-strength bolts shall be protected by masking tape against undercoat application at the fabrication shop. Immediately prior to erection any rust in the paint area shall be removed by power wire brushing to a standard equivalent to SA3.

11.17.11 Contractor shall make provision for requisite site painting to all fabricated steelwork, as per requirements of related specifications of the painting.

11.17.12 Repair of Paint Defects:

All damage to the previous paint shall be repaired. All loose paints shall be removed back to firm edge. Surface irregularities and contaminants shall be removed. Hard, glossy surfaces may require abrading to obtain a suitable surface for painting.

Surfaces, which are to be over coated and which have become contaminated shall be either be solvent cleaned in accordance with SSPC-SP-1 "Solvent Cleaning" or high pressure fresh water washed and if required, a suitable detergent may be used.

11.17.13 Inspection:

Testing:

The final paint shall be free from obvious defects and shall be tested by the contractor as follows:

Film Thickness:

All dry-film thickness limits as specified shall be strictly adhered to. It is recommended that, in order to achieve the specified dry-film thickness, frequent checks of ET-film thickness are to be carried during the paint application with wet-film thickness gauges such as the Elco-meter wheel or comb type wheel gauge. The dry film thickness of individual coats and of the total coating system shall be checked at random over an area representative of the total work. A minimum of 5 readings shall be taken for each 10 sqm of coated surface. For a surface area less than 10sqm minimum of 3 readings shall be taken. Additional readings shall be taken if there have been any changes in application of equipment, spray nozzle size, thinning of paint, etc.

Inspection:

The application work is to be inspected at all stages and finished paint work shall have the correct shade, degree of gloss and evenness and be free from defects such as cracks, holidays, runs sags, wrinkles, patches, brush or roller marks, or other defects that may be detrimental to the quality of the coating. Prior to acceptance of the paintwork, a final inspection shall be made

11.18 MEASUREMENT

11.18.1.1 Measurement for payment of PEB Structures shall be the plan area of the building calculated on the centre lines of peripheral columns.

For variation of height increasing/decreasing by 1 m over the stipulated height of building, no extra payment shall be made.

11.19 PRE-COATED STEEL SHEETING FOR ROOFS AND WALLS

11.19.1 Scope of Work

Coated steel profiled sheet of approved colour shall be installed at roof and side cladding on steel framing or on any other material at any other location as directed by the Engineer, and shall be executed as per the details shown on the "Good for Construction" and approved shop drawings and as per specialist manufacturers

recommendation, complete in all respects. The work shall be executed in flat, tapered, curved form both in plan and section as required.

11.19.2 Materials

The base material of sheet shall be polyester coated high tensile cold rolled steel as per AS 1397, coating class AZ 150 (min. 150 gm/m² zinc aluminium alloy coating mass, total of both sides) in 0.45 BMT (Base Metal Thickness) with hot-dip metallic coating of aluminium zinc alloy (ALUMINIUM 55% AND ZINC 45 %) and having a yield strength not less than 550 Mpa.

11.19.3 Coating

Exterior coating shall be fire retardant silicone modified polyester (SMP) with 30-50% silicone content (min.) or Super Polyster XRW quality paint coat of approved colour and 35 microns total thickness consisting of 20 microns top coat over 5 micron polyester back coat and a 5 micron primer coats on both surfaces including side and end laps.

11.19.4 Sheeting Profile

Sheets shall be profiled with 28-35 mm high crests at 200-300 mm centres, 1000-1015 mm cover width. Lengths up to 12 m shall be in single sheets. Larger lengths, if practicable should be used in longer slopes. Sheets to have wide pans with intermediate stiffening ribs for efficient water shedding and strength. Sheets shall be factory cut and supplied in required sizes based on approved shop drawings. The panels to possess a curved profile as per the overall profile of the roof.

11.19.5 Single Sheeting

Single skin trapezoidal profiled sheeting should have 1000-1015mm effective covered width 28-35 mm crests @ 200-300 mm pitch manufactured out of 0.5 mm TCT (Total Coated Thickness) Hi-Tensile Galvalume/zincalume steel. The sheets shall have wide pans with 2-3 nos. stiffening ribs for effective water shedding and special male/female ends with full return legs on side laps for purlins support and anti-capillary flute in side lap. The sheets shall have a hot-dip metallic Zinc-Aluminium alloy coating (150 gms/sq.m zinc (45%)/alum (55%). Coating mass total on both sides, AZ-150 or equivalent as per AS 1397-1993), minimum 550 Mpa yield strength with Silicon Modified Polyester (SMP) coating (min. silicone content 30%-50%) or Super Polyster XRW quality paint coat of approved colour. The coating shall be as per AS/NZS-2728 :1997 (category 3). The total coating thickness of 35 microns, comprising of 20 microns exterior coat of SMP over superpolyster XRW on top surface and 5 micron polyester reverse on back surface over 5 micron primer coats on both surfaces including side and end laps. End laps shall not be less than 225 mm.

11.19.6 Double sheeting with Insulation

The top and bottom sheets should be trapezoidal profiled sheeting with 1000-1015mm effective covered width and 28-35 mm crests @ 200-300 mm pitch manufactured out of 0.45mm BMT (0.5 mm TCT (Total Coated Thickness) excluding paint thickness) Hi-Tensile Zincalume steel. The sheets shall have subtle flute/wide pans with 2-3 nos. stiffening ribs for effective water shedding and special male/female ends with full return legs on side laps for purlins support and anti-capillary flute in side lap. The material shall be high tensile having 550 Mpa and shall be hot-dip coated with Zinc-Aluminium alloy (55% Aluminium, 43.5% Zinc, 1.5% Si) as per AS1397/ IS 15961 - AZ150 (minimum 150g/sqm total on both sides) with Silicon Modified Polyester (SMP) coating (minimum Silicon content 30% - 50%) or Super Polyester XRW quality paint coat of approved colour. The coating shall be as per AS/NZS-2728:1997 (category 3) and IS 15965. The total coating thickness of 35 microns, comprising of 20 microns exterior coat of SMP or super durable polyester XRW on top surface and 5 micron reverse polyester coat on back surface over 5 micron primer coat on both surfaces including side and end laps for the top and bottom sheets. End laps shall not be less than 225mm.

The paint system should have stable resin and inorganic pigments for paint durability and lead free for water harvesting. The fastener size shall be calculated as per the design for the top and bottom sheet. The sheets shall sandwich a Glass Wool insulation layer (24kg/cum density) of 50mm thickness with Single side Aluminium Foil facing. GI Spacer channel/sub girt shall be provided and fixed between the top & bottom sheets as per the design required and as recommended by the manufacturer. The entire double skin system shall be installed over the structure purlin.

11.19.7 Fixing

Sheets shall be fixed to roof purlins and side rails/runners at crest as per manufacturer's recommendation and water-tightness provisions using polymer coated galvanized hex head self-drilling self-tapping (SDST) screws with integral washers and EPDM seals. The side laps in sheets shall be provided with sealing tapes and screw fasteners with following properties.

- i. Case Hardened Carbon Steel AISI1018/10B21
- ii. Screw diameter 5.5mm (In case of Stitching 4.8mm)
- iii. Metal Bonded EPDM Washer 2-3mm width 16mm diameter (in case of stitching 14mm diameter)
- iv. Organic/Geomet/ Dorken/Xylin coating insuring 1000 hour salt spray life
- v. EOTA approved

Before laying the sheets the purlin spacing shall be verified. The sheets shall be laid starting from the eaves or from bottom upward in case of cladding (IS: 3007). The sheets shall be laid from the end of the building away from prevailing wind so that exposed edges face down wind. The laps shall be as shown in the approved shop drawing.

If slope of roof is less than 15 degree, the end lap on roof shall be minimum 225mm and single length sheets with joint sealed with double sided self-sticking tapes fixed between two sheets are to be provided.

The contractor shall ensure that panel erector is familiarized with erection procedure and all the supporting members are straight, level, plumb and true (according to AISC) before starting panel erection. Panels shall be erected according to approved shop drawings.

The steel sheet shall be fastened with min. 40 µm zinc coated or min. 20 µm Zinc-Tin alloy coated, Hex head, self-drilling screw as per AS 3566 Class 3 fasteners of approved make) with EPDM washer on each crest/ Valley of sheets for connecting with purlin (as per design). The panels to possess a curved profile as per the overall profile of the roof (as per the approved drawings).

Approved Sealing tapes shall be used on side laps and end laps of sheets and closers to be provided at the last end of sheet. Contractor shall give minimum 10 years warranty for the sheets against deterioration, disintegration, loss of lustre, variation in color etc. and leakages across laps, fasteners etc. All types of steel sheets shall be load tested to safely carry 1.10 times the design wind loads and coating thickness to the satisfaction of Engineer. Fasteners shall also be load tested. The contractor shall submit design and shop drawings for approval on the sheet profile, design and details before installation. The item includes all necessary flashings, trims ridge capping accessories and fasteners to ensure insulated buildings which is not only functionally compliant but aesthetically pleasing

With contemporary international look.

11.19.8 Shop Drawings and Approvals

Shop drawings shall be prepared for all sheeting work by the contractor showing the entire installation system including purlin layout, sheet layout, sizes and colour, fixing details etc. Shop drawings shall be submitted to the Engineer for his approval.

The Contractor shall submit catalogues, design calculations for sheet profile confirming safe distributed load capacity, samples of all items to be used and samples of workmanship for approval of the Engineer.

11.19.9 Accessories

The specification for capping, flashing and trims materials shall be same as that for sheeting and shall be factory formed to required shape and profile based on shop drawings.

Roofing accessories like flashings (straight or crimp curved), capping etc. shall be provided from similar coating as used for sheets and shall be fixed by means of self-drilling self-tapping screws with EPDM washer seals.

11.19.10 Tolerances

Length	: +0-10mm
Cover width	: + or -6mm

11.19.11 Structural Stability and Warranty against Rusting/Corrosion

The Contractor shall provide design calculations for sheeting taking into account wind loads, seismic and other code requirements and furnish warranty bond as per CPWD Specifications for structural stability.

The contractor shall also give guarantee for the sheets against rusting/corrosion, leakages through laps and fasteners, colour fading etc. for a period of ten years.

11.20 RAIN WATER GUTTER

Rain water gutters shall be fabricated out of 3.15 mm thick galvanized M.S. Sheets. All arrangements for incorporating outlets for rainwater down take pipes shall be incorporated in the fabrication, as per approved drawings and instructions. Gutters shall be Hot-dip galvanized and painted as per painting specifications of structural steel work. Thickness of galvanized coating shall not be less than 50 microns. Connections between each section shall be made water-tight by site seal welding without damaging the galvanization of the sheet.

11.21 SPECIFICATION FOR LOUVERS

The work for provision of Aluminium Louver pre powder coated for ventilation shall be for easy escape of hot air which accumulates at the roof of work shop shed to normalize the ambient temperature in depot shed and result the comfortable feeling of environment for workmen and normal working of machinery & plants. The work shall comprise:

- (i) Design, Fabrication, supply, modification, installation testing and commissioning as per drawing and BOQ.
- (ii) Louver shall consist extruded section of aluminium 4"x1" rectangular pipe frame, c-channel 2½" x ½ " with metal framework of 3mm thick sheets, 1.5mm thick S-type louvers as per drawing enclosed.

- (iii) Louver bracket/frame shall be permanently fastened to the existing structure without damage.
- (iv) Any additional support and angle etc. required shall be aluminium and pure polyester pre powder coated before fabrication/installation.
- (v) All friction parts, fastenings or any part remaining, as machined / unpainted shall be coated with a product to protect them from corrosion until the unit is commissioned.
- (vi) The paint (if required) shall be done by two coat of epoxy/polyester paint and one coat of epoxy primer.
- (vii) The contractor shall arrange free of cost supply of resources, scaffolding, materials, tools, plant, transportation and manpower for fabrication and installation of the Louver.
- (viii) The contractor shall arrange free of cost all material, equipment and accessories even if not particularly mentioned, necessary to achieve a complete installation in perfect operating condition.
- (ix) The quantity specified in BOQ is approximate and is likely to vary as per site requirement and performance at the same rate as accepted by competent authority.

Note :

- a) Before taking up mass production of louvers, contractor will offer one sample to the engineer for inspection and approval.
- b) Before taking up fitment of louvers on a large scale, contractor will set up a mock up free of cost at site and will offer it to engineer for inspection and approval.

11.22 POLYCARBONATE SHEETS FOR ROOF LIGHTING

11.22.1 General

11.22.1.1 This section covers the requirements of providing, erecting and fixing of polycarbonate sheets of approved colour and approved transparency on roofs for the purpose of lighting. Sheets shall be procured from established and approved manufacturers.

11.22.2 Material

11.22.2.1 Material to be used on roofs shall not be less than 3.0 mm thick, and shall be profiled to exactly match the profile of pre-coated metal sheets to be used for general roof and side claddings.

11.22.2.2 Sheets shall be supplied in maximum lengths that can be transported and erected without causing damage to the sheets, but in any case the lengths shall not be less than 10.0 m.

11.22.2.3 Material shall be free from scratches and other surface damages. These shall be stored in sheltered places and stacked with intermediate layers of soft puffed plastic sheets. Stacks shall be covered with and wrapped around with polyethylene sheets to prevent dust accumulation on the sheets.

11.22.2.4 Material shall be U-V treated and shall be of tested quality. The contractor shall ensure that the manufacturer provides with the test certificates for the following properties:

Test	Procedure	Results
<u>Flammability</u>		
Self ignition	ASTM 1929-23	570 °C
Smoke density	ASTM D 2843	54%
Burning extent	ASTM D 635	less than 1.0
<u>Weathering</u>		
Weathering evaluation	ASTM D 4364-13	Successful exposure to
Concentrated		Sunlight radiation
Colour change	ASTM D 2244	Not more than 3 units after 60 60 months
Light transmission	ASTM D 1003	Shall not decrease more than 10 points after 60 months
-Ditto-	-Ditto-	Shall not decrease by more than 6% after 10 years
Heat exposure	<u>300°F / 25 mins</u>	No darkening effect
Water penetration	ASTM E 331	No penetration
Impact	ASTM E 822-92	Repels hail storm of 25 mm at Velocity of 21m/sec
Expansion/contraction		Linear thermal change of 0.065 mm / m /°C

U-V Filtration	Australian Standard	Transmission less than
	No. 1067	0.1%
Modulus of Elasticity	DIN 53457	24000 kg / sq cm

11.22.3 Submittal

11.22.3.1 Contractor shall submit test reports from manufacturer on all tests.

11.22.3.2 The contractor shall also submit a guarantee that the performance of the sheets supplied by him shall meet with the requirements of the test certificates to be produced by him.

11.22.4 Installation

11.22.4.1 Sheets shall be installed in sequence as shown in approved shop drawings, and fixed to purlins with polymer coated, galvanized, hexagon headed self-drilling, self tapping screws.

11.22.4.2 Side laps shall be as per manufacturers specification. End laps shall be 225 mm. Joints with metal sheets shall be sealed with Butyl-based adhesive. The edges shall be sealed with silicone sealant as per manufacturer's specification, and then covered with butyl-based adhesive tapes.

11.22.5 Measurement

11.22.5.1 Contractors quoted rates for sheeting work shall include all materials, tools, plants, all accessories including fasteners, adhesives, sealants, tapes etc. and labour, all temporary works complete to the requirement of these specifications and instructions

Work shall be measured and paid for on the actual net area of clear opening, excluding all overlaps at sides and ends.

11.23 TOUGHENED GLASS FOR WINDOWS

11.23.1 General

11.23.1.1 This section covers the requirements of providing, erecting and fixing of 6mm thick glass (toughened) of approved color and approved transparency on windows and north lights for the purpose of lighting. Glass shall be procured from established and approved manufacturers.

11.23.2 Submittal

11.23.2.1 Contractor shall submit test reports from manufacturer on all tests.

11.23.2.2 The contractor shall also submit a guarantee that the performance of the toughened glass supplied by him shall meet with the requirements of the test certificates to be produced by him.

11.23.3 Measurement

Contractors quoted rates for glass work shall include all materials, tools, plants, all accessories including fasteners, adhesives, sealants, tapes etc. and labor, all temporary works complete to the requirement of these specifications and instructions

Work shall be measured and paid for on the actual net area of clear opening, excluding all overlaps at sides and ends.

Approved Manufacturers/ Supplier

All materials and products shall conform to the relevant standard specification, IS codes, ASTM and other relevant codes etc. and shall be of approved makes and design.

Annexure-A

Tolerances mentioned below shall be achieved whether the entire structure or part thereof is erected and made in line, level and in plumb.

S.No.	Structure	Tolerance
1	Columns	
a	Deviation of axes at foundation level or at top of anchor level with respect to true axes: - About both directions	+ 5 mm / - 5 mm
b	Deviation in level of bearing surface with respect to true level at centre line	+ 3 mm / - 3 mm
c	Out of plumb-ness of column axis from true vertical, measured at top of Column: - For columns up to 15 m in height:	+/- 1/1000 of column height in mm -or- +/- 15 mm whichever is less.
i	For columns up to 15 m in height:	1/1000 of column height in mm -or- +/- 15 mm whichever is less.
ii	For columns exceeding 15 m in height	+/- 1/1000 of column height in mm-or- +/- 20 mm whichever is less.
2.	Trusses and Beams	
a	Shift at the center of span of the top chord member with respect to vertical plane passing through the center of bottom chord member	+/- 1/250 of truss height in mm-or- +/- 10 mm whichever is less.
b	Lateral shift of top chord of truss / beam at center of span from the vertical plane passing through the center of supports of the truss	+/- 1/1500 of span of truss in mm-or- +/- 5 mm whichever is less.
c	Lateral shift in location of truss / beam from its true vertical position	+/- 5 mm

d	Lateral shift in in-plane location of beam / purlin from true position:	+/- 5 mm
e	Deviation in difference of bearing levels of trusses or beams from true levels	+/- 10 mm for trusses -and- +/-5mm for beams

Annexure – B

A. Approved Manufacturers/ Supplier

All materials and products shall conform to the relevant standard specification, IS codes, IRS and other relevant codes etc. and shall be of approved makes and design.

The list of approved makes for products and materials is given below. Other equivalent manufacturers will only be considered with prior approval of the Employer in case of non-availability or unforeseen difficulties.

B. List of Approved Manufacturers/ Suppliers

AS PER DMRC APPROVED LIST OF MANUFACTURER'S /SUPPLIERS

Annexure- C

Design Criteria and Material Specifications for Pre- Engineered Buildings (PEB)

- 1.0 The bidder/contractor is required to follow the general and special requirements of design criteria and material specifications as laid down in this Annexure to the particular specifications.
- 2.0 Requirements given below are in addition to the Particular specifications laid down for the various items of work.
- 3.0 The Engineer reserves the right to modify these requirements at the final design stage. Suppliers will not be entitled to claim extra over their quoted prices on account of such changes in requirements.

Part 1: General Requirements for all Buildings

4.1 General

Pre-Engineered Buildings or building components wherever specified shall be designed, supplied and erected by a specialist agency called PEB manufacturer approved by the Engineer. All codes and standards for material, design, fabrication and erection shall generally be as indicated for structural steel work unless the following specifications call for a deviation otherwise. PEB manufacturer shall use Submerged Arc Welding for built-up sections, meeting the applicable requirements of the American Welding Society (A.W.S) D1.1.98.

The agency responsible for design, fabrication and erection shall not be allowed to sub-let any of the activities/operations to another sub-agency in anyway unless a prior written approval of the Engineer is taken. The agency for PEB shall have an ISO 9001 certification for manufacture of PEBs. Contractor shall submit all design drawings, erection drawings, fabrication design and drawings for approval by DMRC/DDC prior to commencement of fabrication works.

4.2 Design Specifications for PEB Buildings

The PEB manufacturer shall be responsible for carrying out all the design of PEB's as per following relevant IS codes only.

- a) IS:800 Code of Practice for general construction in steel
- b) IS:801 Cold formed sections
- c) IS:811 Cold formed sections
- d) IS:875 Code of Practice for design loads for building and structure
- e) IS:2062 for Steel for General Structural Purposes

Only in absence of design criteria not available in mentioned IS codes, reference can be made to other international codes/manuals as applicable to PEB's and same shall be subject to approval of DMRC in case of deviation from IS codes.

A.0 LOADING

A.1 Dead Load

Self weights from all supported and supporting elements.

A.2 Live Load

A.2.1) As per provisions of IS: 875 (Part – 2)

A.2.2) Other Imposed loads -

Loads from suspended utilities, OHE fittings etc as per specific requirement of different buildings.

A.2.3) Material Handling loads supported on structures like EOT cranes, under-slung cranes, all as per specific requirement of individual buildings.

A.2.4) Solar Panels: 30 Kg/sqm in addition to (75 Kg/sqm and 150 Kg/sqm) for inaccessible and accessible roof respectively.

A.3 Wind Load

As The design of PEB's are mainly governed by Wind load, no increase in permissible stresses is allowed for wind load combinations as per IS:800.

Parameters

As per provision of IS: 875 (Part – 3), with the following parameters:

A.3.1) Basic wind speed: As per IS: 875

A.3.2) Value of k_1 , corresponding to mean probable design life of building of 120 years : as per table –1 of IS: 875 (part-3).

A.3.3) Value of k_2 , corresponding to Class – B/C structures as per Table –2 of IS: 875 (Part-3). Minimum value of k_2 shall be = 1.0

A.3.4) Value of k_3 , as per clause 5.3.3.1 of IS: 875 (Part-3)

- A.3.5) Local wind effects to be taken as per provisions of IS: 875 (Part-3), corresponding to building plan size, height, shape and direction of wind.

The local external wind pressure coefficient shall be taken strictly for the local zones as shown in relevant tables of IS:875. The internal and local external coefficients shall be combined for design of roof sheeting, glass panels, individual cladding units, girts and purlins falling in high local pressure zones shown in relevant tables of IS:875.

A.4 Earthquake Load

As per provisions of IS: 1893 for Zone –IV.

A.5 Temperature Effects:

As per IS: 875 (Part-5).

A.6 Load Combinations: As per IS: 800 (2007)

B.0 DESIGN REFERENCES

- B.1 All designs shall be done in accordance with BIS- Standards as per specification of works.
- B.2 Only in the case of design criteria not being available in Indian Standard Codes, reference can be made to other International Codes / Standards / Manuals, as applicable to Design of Steel structures of the type specified.

Use of standards other than BIS Codes shall be subject to approval of Engineer.

C.0 DEFLECTION LIMITS

Deflection limits of members shall generally be as per relevant clause of IS: 800, but with the following provision –

- ii) Maximum deflection limit for purlins checked under various combinations of dead loads and imposed loads is to be restricted to span/250.
For combinations of dead, imposed and wind loads, purlin deflection is to be limited to span / 200.

- iii) For columns in a single storey building, maximum horizontal deflection at the cap of columns due to worst combination of forces should not exceed the following limits:

Load combination	For columns not supporting	For columns supporting
(Worst of)	crane gantry girders	crane gantry girders
DL, LL, WL/EQ	1 / 325	1 / 425
DL, LL, WL/EQ & Temp	1 / 250	1 / 425

'l' is the actual length of the column.

- iv) Maximum permissible deflection at tip of cantilevers shall be limited to span / 750.. For deflection of cantilevers at any other locations a limit of Span / 500 shall be followed.
- v) For other load combination permissible deflection shall be as per Table 6, IS-800-2007 .For rafter L/750 for Inspection Bay only due to Under Slung Crane.

D.0 GENERAL INSTRUCTION & RESPONSIBILITY

- D.1 It's the responsibility of PEB manufacturer to account for design loads of the cranes, gantries, OHE drop arm loads etc. in design of PEB's. The connection detail and related accessories/fixtures to fix all above miscellaneous units to PEB frames is also responsibility of PEB manufacturer. Sufficient strengthening measures shall be taken in the portals due to these loads.
- D.2 The fabrication drawings along with necessary design calculation for connections etc. should also be submitted by PEB manufacturer before start of fabrication for DMRC's approval.
- D.3 The cold formed sections shall be designed strictly based on IS: 801-1975. The cold formed sections should be designed as stiffened /unstiffened section based on lip dimension satisfying the section requirements of stiffened/unstiffened section.
- D.4 The overlapping of two cold formed section to enhance section properties is normally not permitted. However if PEB contractor wants to use nested purlin then connection of nested purlin should also be designed to cater for in plane shear and moment so that nested behaviour can be achieved. At the locations of splicing in the continuous purlins separate splicing piece, suitably designed, shall be provided.
- D.5 Following items shall be reviewed/clarified and clearance obtained by the PEB manufacturer before start of design of PEB buildings:-
 - (i) Plan dimensions of the buildings.
 - (ii) Height of cladding for buildings.
 - (iii) Door opening sizes
 - (iv) Crane load requirement and OHE drop arm loading details.
 - (v) Specification for painting accounting for exposure condition.
 - (vi) Steel grade for portals and cold formed sections.
 - (vii) Minimum thickness requirements for cold formed sections and structural steel members.
 - (viii) Use of stiffener plates for built-up portals.
 - (ix) Use of HSFG bolts for base connections.
 - (x) Liberty of using portal spacing to achieve economy providing they satisfy the architectural/operational requirement and door/window opening sizes.

- (xi) Expansion joint requirements for PEB's.
- (xii) Pitch for rafter members.
- (xiii) No. of continuous span for design of purlin and roof sheeting.

D.6 Responsibilities

It may be noted that the foundation and pedestal upto plinth level including prior fixing of anchor bolts for steel column shall be constructed by the main civil contractor. All the steel work above this level shall be entirely carried out by the PEB manufacturer. All other civil work e.g. flooring, brickwork etc. shall be carried out by the main civil contractor and paid for as per the relevant item of BOQ.

- D.7 Upon receiving comments on the designs and drawings, PEB manufacturer shall carry out all modifications within the stipulated time schedule and get the same approved before carrying out any activity relating to the same.
- D.8 Well qualified, approved personnel of the PEB manufacturer shall be available at the site during all operations relating to the PEBs. Qualified personnel of the PEB manufacturer shall carry out the necessary assembly and erection at the site.
- D.9 All components of PEBs shall be fabricated, manufactured, sand blasted where required and primed at the PEB manufacturer's works. No site fabrication shall be allowed.

E.0 MATERIAL SPECIFICATION

- E.1 All structural components other than purlin /side runners shall be made from Hot Rolled sections and plates with Grade B0 having a minimum yield stress of 250 Mpa, conforming to IS 2062.

Minimum plate thickness shall be 6mm..

- E.2 Purlin and side runners only, shall be made of from cold form sections out of material shall conform to ST-34 -1079 of IS 1079/ASTM A570 Gr 50 with min Yield Strength of 345 Mpa or Equivalent (IS 5986:2009 –Gr Fe 490, Yst 355 Mpa/ IS 1079:2009, Gr HR5, Yst 340 Mpa).

Minimum metal thickness for Cold Formed Sections shall be 3.15 mm, UNLESS SPECIFICALLY PERMITTED BY Engineer / Structural Consultants.

- E.3 Unless noted otherwise all field connections shall be bolted with high strength bolts of Class 8.8. Close tolerance, or bolts in clearance holes may be used as per requirement of design.
- E.4 Holding down bolts shall be of property class 4.6 (Grade-B) conforming to IS: 1367

And shall be in accordance with IS: 5624.

- E.5 Cladding on roof and sides of buildings shall be done with pre-formed, polyester coated galvanized steel sheets of minimum thickness 0.50 mm (TCT) of approved colour.
- E.6 Roof lighting sheets shall be out of 3 mm thick, high impact strength, U-V treated, Polycarbonate sheets of approved colour / transparency, placed at suitable locations on roofs (in place of metal cladding sheets). Area of such sheets shall be generally limited to a maximum of 15% of the total roof area.
- E.7 Rainwater gutters for all buildings shall be made out of 3.15 mm thick hot dipped galvanized mild steel sheets, with provision for connecting down-take pipes of appropriate size and at designed locations. Sizes of rainwater pipes and their locations will be decided at the time of final design.

F.0 ROOF SLOPE

- F.1 All buildings in steel construction shall have normally slopes of 1-vertical to 10 –horizontal or as per drawing.

Purlins shall be placed normal to the slope.

G.0 LIMITATIONS ON DESIGN ASSUMPTIONS

G.1 Purlins & Side-Cladding Runners

- G.1.1 If purlins / runners are assumed to be continuous over supports, continuity shall have to be developed at supports through proper connections to absorb the continuity moments.
- G.1.2 In case of continuous purlins / runners, temperature effects need to be considered, and such forces need to be transferred down to the foundation through the main structure and appropriate bracing or other force transfer- systems.
- G.1.3 Sag-rods and / or sag-struts may be provided as per requirements of economic design.

G.2 Columns/Portal Frame

G.2.1 Portal Frame Not Supporting Crane Gantry Girder:

The portal frame shall be analyzed semi fixed base with 70% fixity and 30% release and hinge base and the combination of load cases which gives maximum forces shall be considered for design of foundation, holding down bolts, column main rafters and connections.

G.2.2 Portal Frame Supporting Crane Gantry Girder:

Column supporting crane gantry girder shall be considered as “Fixed Base”.

However portal frame shall be analyze for fixed base & hinge base the combination of load cases which gives maximum forces shall be considered for design of foundation, holding down bolts, column main rafters and connections.

- G.2.3 All columns shall be of ‘Solid web’ sections. These can be of standard hot rolled sections or ‘built up’ sections. Profiling of the sections is permissible if so desired by the suppliers.

G.3 Roof Rafters

- G.3.1 Roof rafters shall also be solid web sections, either standard hot rolled or built-up, depending on suppliers design. Trusses and castellated sections will not be acceptable.

- G.3.2 Connections of rafters to columns shall be through rigid welded/ bolted joints only.

G.4 Other Elements

- G.4.1 Eaves beams, other longitudinal beams along column lines shall also be of solid web sections. These may be connected through bolts or welds as per design requirements of supplier.

- G.4.2 Crane gantry girders shall be of solid-web sections, either compound or single built up.

- G.4.3 Foundation and other holding down bolts shall be sized as per design requirement of various components being connected.

- G.4.4 For the purpose of analysis and design of sections, starting level of columns at base shall generally be considered as 800 mm below floor level. The exact depth of fixity of columns shall be got clarified from Structural Consultants before the final analysis / design is taken up by the supplier.

Part 2: Special Requirements for Individual Buildings

A.0 INSPECTIONBAY

- A.1 Roof elements in the bay are required to support runway beams for under-slung EOT cranes. Deflection limit for these roof rafters shall be restricted to $\text{span} / 750$. Runway beams should be suspended from roof rafters such that bottom levels of all runway beams are at specified elevation (to be got confirmed from Engineer. All such hangers shall be properly braced longitudinally and transversely to prevent sway.

- A.2 Two under-slung cranes (lifting capacity of each cranes is 1.5T) are required to operate above two tracks within the bay. For the purpose of design, all cranes shall be considered to have wheel- bases of 1600 mm. Maximum wheel load shall be taken as 1.0T and

corresponding minimum wheel load shall be taken as 0.5 T. When the cranes are centrally positioned, all four wheels should be considered as transferring 0.75 T of reaction on to the runway beams. Roof rafters and runway beams shall be designed for these specific loads.

- A.3 A uniform load of 15 Kg/sqm of plan area shall be considered as load from suspended utilities to be supported by the structure.
- A.4 Inspection bay would have cantilevered elevated inspection platforms made in steel. The deck of the platform is to be built out of 5 mm thick chequered plates. The central platform is supported on posts at 8.0 m centres. Side platforms are alternately supported on main columns for each span and are cantilevered. The platforms shall be provided with handrails as indicated in Drawings. Design load for these platforms shall include a point load of 1.25 T that may be placed anywhere on the deck. When one such load is considered at one location, the other load need not be considered at less than a distance of 10m from the first load. In addition the platform shall be designed for a uniform imposed load of 250 kg/sqm. A uniform loading (DL) (Chequered Plate) of 40 Kg/sqm at Inspection Platform.
- A.5 Rail tracks in the Inspection bay are to be supported on steel posts spaced 1200 mm centers along the track as indicated in the drawings. The posts are to be designed for full axle load from a Standard Gauge [SG] Rail Coach, as given below: -

No. of axles per coach	= 4nos.
No. of bogies per coach	= 2 nos.
No. of axles per bogie	= 2 nos.
Coach axles centre to centre	= 15000 mm.
Overall Coach length	= 22,500 mm.
Axle load	= Maximum 17.0 T; Minimum = 8.0 T.

B.0 WORKSHOP

- B.1 The workshop is being planned with a single bay of 21m wide and 212.00 m length.
- B.2 The workshop bay shall have two EOT cranes that would operate in tandem for full length of shop. Crane rail level for all the bays shall be at an elevation of 8500 mm. from shop floor top level.(Top of Rail Level)
- B.3 Main hoist lifting : One EOT Crane in Workshop bay will have the main hoist capacity as 15T. and auxiliary hoist capacity shall be of 2T. The second EOT Crane main hoist capacity will be 5T and auxiliary hoist capacity shall be 05./1T.
- B.4 Wheel-base for all cranes should be considered as 3900 mm [This dimension of wheel base shall have to be got confirmed from the Engineer before starting 'Final Design'. Minimum distance between centres of wheels of two cranes in tandem shall be considered as 600 mm.
- B.5 For design of gantry girders and for arriving at maximum and minimum reactions at end and intermediate columns, wheel reactions for the cranes shall be as follows: -

- B.6 Uniform load of 15 Kg/sqm of plan area shall be considered as load from suspended utilities to be supported by the structure.

C.0 INTERIOR CLEANING BUILDING

- C.1 Special imposed load would include one number OHE-Drop arm and a uniform load of 10 Kg / sqm of plan area to be supported by the structure.
- C.2 Interior cleaning bay would have one elevated / roof level inspection platform made in steel.

D.0 PITWHEELATTHEBUILDING

- D.1 Wheel base for the Crane to be considered for design shall be 1300 mm. Maximum wheel reaction of 3.6 T, and corresponding minimum wheel reaction of 1.45 T. shall be considered for design of gantry girder and Structural Frame work.
- D.2 Pit Wheel Lathe would have one EOT Crane of 5.0 T. capacity.

E.0 BLOW DOWN PLANT

- E.1 Special imposed load would include one numbers OHE- Drop arms and a uniform load of 10 kg / sqm of plan area to be supported by the structure.

F.0 SHED FOR RGM

- F.1 Non-OHE shed to be utilized for parking of Rail Grinding Machine
- F.2 Shed would have one 30m long pit for maintenance of Rail Grinding Machine.

G.0 GANTRY FOR ETU BUILDING EOT CRANE

- G.1 Gantry girders to be provided for 5T crane in ETU Building

H.0 CAR PARKING, CYCLE SHED, CABLE STORE SHED (ETU), VANJEX PARKING, S & T, CABLE STORE AND DIESEL STORE

- H.1 These are proposed to be made out of tubular steel pipes/I-Sections. Cantilever structures supported with central row of built up columns supporting inverted butterfly roof in Metal sheet with no insulation are to be provided for car and cycle parking. For cable stores and Vanjex parking the structure is to be supported at all ends with tubular columns & beams/I - Sections and supporting inclined roof in metal corrugated sheeting.

I.0 WATCH TOWERS

These are proposed to be made out of I-sections. The structure is supported with built up columns and beams tied at approx. every 3m with overall height of approx. 15m from FFL. and supporting inclined roof in metal corrugated sheet with no insulation. It should also have a railing along the staircase and the upper deck level. The railing should have an overall height of 1200mm with metal sheeting upto a height of 1000mm. The watch towers are 4 in nos.

SECTION – S.12

WATER PROOFING

Cut and Cover Construction and Under Ground Station Buildings

12 WATERPROOFING

12.1 GENERAL

Submission, Requirements, Method Statement & Working Drawings.

The Contractor shall include details of his intended waterproofing methods in his design submission for acceptance by the Employer representative.

Manufacturer's literature shall be provided where necessary to confirm the suitability of the proposed details.

The contractor shall produce and submit comprehensive Working Drawings showing all details and procedures for Waterproofing of works.

12.2 WATERPROOFING APPLICATION

Waterproofing material shall be installed only by the manufacturer of the products or his approved applicator. The contractor shall submit a method statement prepared in conjunction with the applicator and certified by the manufacturer of the material, describing the details of waterproofing works including protective measures at all stages.

12.3 STRUCTURAL CONCRETE WORKS

Concrete Joints:

Notwithstanding the provision of waterproofing system, the contractor shall construct his concrete works so as to minimize the likely hood of water penetration. All construction joints shall be treated in accordance with Annexure D of this specification.

Water-stops:

Water-stops used in the work shall be Swell-able type Bentonite- Bitumen based material. The water-stop shall be installed so that they are securely held in their correct positions while the concrete is being placed. Further details of the Water-stops are provided in Annexure D.

Fillers and Sealants to Expansion Joints.

All materials used to fill expansion joints shall be such that they will accept the calculated movements of the joints without extrusion and shall not shrink away from either surface of the joints. Backing strips and fillers shall be used in accordance with the manufacturer's recommendation. Where joints are required to be filled with polysulphide or polyurethane sealants, the material shall comply with BS 4254 or BS 5212.

The appropriate sealant grade shall be used for horizontal & Vertical joints and the joints shall be thoroughly cleaned and primed with appropriate primer before applying sealant. The sealant shall be of colour as nearly as possible to the colour of the adjoining surface where it is permanently exposed.

The sealing material shall be used and applied strictly in accordance with the manufacturer's instructions. The Contractor's attention is drawn to undesirability of the sealant being smeared over the adjacent surface and appropriate precautionary measures, including the use of masking tape shall be taken to avoid this.

12.4 WATERPROOFING OF UNDERGROUND STRUCTURE.

The following requirements are applicable to all underground structures built by Cut and cover methods and underground station building where integral crystalline waterproofing method has been specified.

The complete method statement for the works shall be submitted to the Engineers with relevant method statement prior to application of the system. The method statement shall include all QC/QA procedure required to ensure the integrity of system.

Proposed manufacturer and applicator should have similar experience. The proposed manufacturer shall have an ISO certified and approved plant of international repute.

a) Base Slab.

Waterproofing shall be done using Integral Crystalline Waterproofing admixture admixed to the concrete in accordance with Annexure A

b)

i) External Walls to Structure Built in Open Excavation.

Waterproofing shall be done using Integral Crystalline Waterproofing admixture admixed to the concrete in accordance to Annexure A

ii) External Walls Built against piles or Rock or Soil Faces.

Waterproofing shall -be done using Integral Crystalline Waterproofing admixture admixed to the concrete in accordance to Annexure A.

iii) Diaphragm Wall

Waterproofing shall -be done using Integral Crystalline Waterproofing admixture admixed to the concrete in accordance to Annexure A.

For b (i to iii):

Where pipe penetration is required through wall, this shall be treated in accordance with Annexure E of this specification.

All construction joints shall be treated in accordance with Annexure D of this specification.

c) Roof/Top-Slab

Waterproofing shall be done using Integral Crystalline Waterproofing admixture admixed to the concrete in accordance with Annexure A of this specification. Construction joints shall be treated in accordance with Annexure D of this specification. The roof slab will be additionally waterproofed by using Polyurethane spray applied membrane with minimum 2mm thick to the concrete in accordance with Annexure B1 of this specification. Materials shall be sourced from Approved Manufacturers by the Engineer. The already casted roof slab shall be checked by performing pond test for a minimum of 24 hours. At the end of the pond test, cracks and faulty construction joints shall be marked. The same shall be treated as per Annexure C. The proposed treatment of applying two coats of crystalline slurry shall be carried out as per the attached Annexure B. Finally, the roof slab shall be checked again by performing Pond test.

d) Treatment to Faulty Construction joints, honey combs in the concrete:

The treatment to faulty construction joints, honeycombs in the concrete shall be carried out as per the methodology described in Annexure E.

(Note: Faulty Construction joints mean such joints where the Swell-able water stop could not be installed due to unavoidable circumstances or such joints that leak in spite of laying the Swell-able water-stops.)

All waterproofing system shall be guarantee, for a minimum period of 10 years from the date of completion of works against all defects. The warranties shall cover the whole of the waterproofing systems and shall be given jointly and severally by the contractor and the supplier/ applicator.

Contractor shall submit Performance Bank Guarantee for water proofing works (for 10% of the cost of water proofing item only) which shall be valid for the entire guarantee period.

ANNEXURE A

SPECIFICATION OF CRYSTALLINE PRODUCTS

Product - **Integral Crystalline Waterproofing/Durability Admixture**

CRYSTALLINE ADMIX

Dosage - minimum 0.8% by weight of cement + cementitious material (OR dosage as recommended by Manufacturer at which product meets the product qualification criteria listed in this document – Duly approved by DMRC).

Integral Waterproofing/ Durability admixture should be SINGLE part cementitious powder consisting of hydrophilic chemicals. When added to plastic mix, will permanently create impermeable hardened concrete by developing insoluble needle like crystals to seal the pores, capillaries, micro-cracks in the whole mass of concrete and enhances the durability of concrete. The crystalline admixture must be compatible with any other concrete admixture confirming to ASTM C494 and IS 9103. It shall be used for all underground structures (including shotcrete in tunnel lining). In addition, the waterproofing admixture shall be tested for confirmation of the following requirements before usage at site and subsequently at the frequency as directed by the Engineer:

- i. It shall possess CE approval as per EN934-2 OR the product shall be approved by MORTH & must have IRC accreditation for durability enhancement.
- ii. At the manufacturer's recommended dosage, material must fulfil the requirements of American Concrete Institute Guidelines ACI-212-3R-10 Chapter 15 and fall under PRAH (Permeability reducing Admixtures for HYDROSTATIC conditions) and must reduce Coefficient of Permeability of concrete by more than 90%(preferably zero permeability) , when compared to control concrete and tested as per DIN 1048 Part 5 by carrying out 4 cycles each of 5 bar Hydrostatic Pressure for 72 hours and drying for 48 hours between the cycles & Coefficient of Permeability calculated as per Darcy's Formula/ Valenta equation by incorporating penetration values obtained at the end of fourth cycle pressure.
- iii. At the manufacturer's recommended dosage rate, the material must reduce Chloride Diffusion Co-efficient by minimum 45% when tested as per ASTM C 1556 -4 / or its equivalent and compared with the control concrete, thereby prolonging the durability & service life of the treated concrete structure.
- iv. At the manufacturer's recommended dosage rate, the crystalline admixture treated concrete must be able to withstand high hydrostatic pressure of 16 bar (156 M of water head) when tested as per DIN 1048

- v. Must demonstrate minimum reduction of 20% in shrinkage cracks as compared to control concrete & no internal expansion under sulphate attack, when tested as per ASTM C-1012-12.
- vi. At the manufacturer's recommended dosage rate, the crystalline admixture must be capable of self-healing of cracks up to a width of 0.5mm
- vii. At the manufacturer's recommended dosage rate, the performance of the crystalline admixture must not be restricted by water/cement ratio of the concrete mix. In other words, the crystalline admixture must perform at any water / cement ratio of the concrete mix.
- viii. The recommended product must possess a third party assurance, confirming that the product, when used in the concrete, will have no detrimental side effects in terms of Alkali Silica Reaction(ASR), corrosion of steel re-enforcement etc., as per the requirements of DIN 18998 / or its equivalent.
- ix. It will not be affected by wear abrasion of the treated concrete surface and crystalline treated concrete shall not require protection layer.
- x. The recommended crystalline admixture must be non-toxic and must confirm to NSF 61 requirements of NSF USA. It must be certified as per NSF 61 guidelines.
- xi. The manufacturer must produce relevant test certificates from reputed laboratories, confirming that the product when added at the recommended dosage rate, meets the above requirements.
- xii. DMRC reserves the right to approve or reject the product proposed by the contractor based upon the credentials of the manufacturer and applicator, as submitted by the main contractor.

The Characteristics tests shall be conducted for the Integral Crystalline Waterproofing/Durability Admixture at the frequency as directed by the Engineer and shall meet the following requirements:

Dry Material Content:	>99.5%
Chloride Content:	<0.1%
Alkali Content:	< 9.3%

The Integral Crystalline Waterproofing/Durability Admixture shall be of grey colour and is in powder state. The shelf life shall be 12 months.

Quality Assurance:-

- i. **Manufacturer Qualifications:** A firm with experience in manufacturing crystalline waterproofing of the type specified, able to provide test reports showing compliance with specified performance characteristics, and able to provide on-site technical representation to advise on installation.
- ii. **Installer Qualifications:** Firm should be ISO 9001-2008 certified with minimum experience of 10 years in approved crystalline products. Further, the warranty should be given by supplier/manufacturer for satisfactory performance of the product including its application and supervision.
- iii. **Pre-installation Meeting:** Before installation, conduct a meeting with the waterproofing installer, installers of adjacent work and work penetrating waterproofing, and waterproofing manufacturer's representative to verify project requirements, substrate conditions, manufacturer's installation instructions, and manufacturer' warranty requirements; notify the Owner and Architect/Engineer at least one week in advance of meeting.

Preparation of mixing: -

Mix 3 parts CRYSTALLINE ADMIX powder with 2 parts water by volume to form a very thin slurry. Pour the required amount of material into the drum of the ready-mix truck and mix for at least 5 minutes to ensure even distribution of CRYSTALLINE ADMIX throughout the concrete.

Application:-

Concrete treated with CRYSTALLINE ADMIX should be placed and finished in accordance with good concrete practices. ACI guidelines and recommendations should be observed.

Special Consideration:-

When incorporating CRYSTALLINE ADMIX, the temperature of the concrete mix should be above 40°F (4°C).

Storage / Shelf Life:-

CRYSTALLINE products must be stored dry at a minimum temperature of 45°F (7°C). Shelf life is one year when stored under proper conditions.

Measurement:-

The quantity of Crystalline Admix will be measured as per the dosage i.e. minimum 0.8% of the weight of cement+ cementitious material or as recommended by the manufacturer. The total weight of cement is to be calculated as per the mix design of concrete on per cubic meter basis.

The material consumed will be calculated at the rate of minimum 0.8% to the weight of cement in per cubic meter of concrete or as per the recommended dosage of the manufacturer.

The crystalline admixed concrete must also be tested for the durability criteria, when tested at a reputed laboratory and meet the following requirement:-

1. Chloride Migration Coefficient		
Coefficient D of migration of chlorides tested as per Swiss Standard SIA 262/1-B:2013	$D \leq 2.00E-12$ m ² /s	Exposure Class XS3 as per BS-EN 206-1 (sea water splash, spray)
Coefficient D of migration of chlorides tested as per Swiss Standard SIA 262/1-B:2013	$D \leq 4.00E-12$ m ² /s	(Saline Fog)
2. Carbonation Resistance		
Coefficient K of migration of CO ₂ tested as per Swiss Standard SIA 262/1-I:2013	$K \leq 4.5$ mm/t ^{0.5}	Rain /River /Lake Water (Permanantly immersed or cyclically wet and dry) Exposure Class XC3, XC4 as per BS:EN 206:1
3. Water Absorption (Self-Healing performance)		
Water Absorption ratio (Self-Healing performance evaluation) all exposures to water (saline & fresh) and atmosphere	$R_{WP0.2} \leq 0.2$ & $R_{WP0.4} \leq 0.3$	Where: RWP _(0.2,0.4) – ratio between water absorption at 28 days of pre-cracked* concrete samples with crystalline water-proofer and water absorption at 28 days of pre-cracked concrete samples of the baseline mix (without water- proofer) - when tested in accordance to EN 13755 (Determination of water absorption at atmospheric pressure). *Flexural pre-cracking according to EN 197-1 of 40x40x160 mm prisms of concrete with 2-4 kg/m ³ of structural PP fibres to control crack opening. Controlled cracks width of: 0.2±0.05 mm, and 0.4±0.10 mm respectively.

ANNEXURE B

Product - Crystalline Waterproofing Coating

CRYSTALLINE Slurry

Recommended Uses: -

CRYSTALLINE Slurry waterproofing can be applied to all structurally sound concrete – new or old.

Basement retaining walls & raft Slabs:	Parking structures
Concrete slabs (floor/roof/balcony, etc.):	Tunnels and subway systems
Construction joints:	Foundations
Water retaining structures:	Underground vaults
Swimming pools:	Sewage and water treatment plants
Channels:	Reservoirs
Bridges, dams and roads:	Podiums

Characteristics:

- Must be supplied from approved manufacturing facility.

Aggregate State:	Powder
Colour:	Cement Grey
Pot Life:	20 Minutes
Setting time:	2 hrs.
Shelf life:	12 months
Speed of penetration:	31 cm. in 56 Days
Water Permeability:	More than 90% (preferably zero permeability) compared to control concrete when tested as per DIN 1048 part 5 by carryong out 4 cycles each of 5 bar hydrostatic pressure.
Potable Water Compatibility:	CFTRI Tested, Nontoxic and suitable for use in potable water facilities – NSF Listed as per ANSI 61 listing

- i. The manufacturer must produce relevant test certificates from reputed laboratories, confirming to above requirements.
- ii. DMRC reserves the right to approve or reject the product proposed by the contractor based upon the credentials submitted by the contractor.

Quality Assurance:-

- i. **Manufacturer Qualifications:** A firm with experience in manufacturing crystalline waterproofing of the type specified, able to provide test reports showing

compliance with specified performance characteristics, and able to provide on-site technical representation to advise on installation.

- ii. **Installer Qualifications:** Firm should be ISO 9001-2008 certified with minimum experience of 10 years in approved crystalline products. Further, the warranty should be given by supplier/manufacturer for satisfactory performance of the product including its application and supervision.
- iii. **Pre-installation Meeting:** Before installation, conduct a meeting with the waterproofing installer, installers of adjacent work and work penetrating waterproofing, and waterproofing manufacturer's representative to verify project requirements, substrate conditions, manufacturer's installation instructions, and manufacturer's warranty requirements; notify the Owner and Architect/Engineer at least one week in advance of meeting.

Surface Preparation:-

All concrete to be treated with CRYSTALLINE Slurry must be clean and have an "open" capillary surface. Remove laitance, dirt, grease, etc. by means of high pressure water jetting, wet sandblasting or wire brushing. Faulty concrete in the form of cracks, honeycombing, etc. must be chased out, treated with CRYSTALLINE SLURRY and filled with CRYSTALLINE MORTAR. Surfaces must be carefully pre-watered prior to the CRYSTALLINE SLURRY application. The concrete surface must be damp but with no wet sheen on the surface.

Mixing:-

CRYSTALLINE SLURRY is mechanically mixed with clean water to a creamy consistency or that resembling thick oil, in a mixing ratio as recommended by the manufacturer. Mix only as much material as can be used within 20 minutes and stir mixture frequently. If the mixture starts to set do not add more water, simply re-stir to restore workability.

Application:-

Apply Crystalline Slurry in two coats by masonry brush or appropriate power spray equipment. The second coat is applied while the first coat is still "green".

Application Rates:-

One / Two coats of Crystalline Slurry at 0.7kg / sqm as per manufacturer specification.

Post Treatment:

The treated areas should be kept damp for a period of five days and must be protected against direct sun, wind and frost, by covering with polyethylene sheeting, damp burlap or similar.

Special Consideration:

Do not apply CRYSTALLINE SLURRY at temperatures at or below freezing or to frozen or freezing surfaces. CRYSTALLINE SLURRY cannot be used as an additive to concrete or plasters. (CRYSTALLINE ADMIX should be considered for these applications).

Storage / Shelf Life:

When properly stored in a dry place in unopened and undamaged original packaging, shelf life is 12 months.

Measurement:

The quantity of crystalline slurry coat will be measured on sq.mtr. area basis. The measurement will be taken by measuring the length and width of the coating area.

ANNEXURE B1

Specification of Polyurethane liquid membrane.

Total Membrane thickness	2 mm minimum dry film thickness and sprayed in a minimum of two coats of contrasting colours, with the second coat applied to the first coat only after the first coat has cured.
Tensile Strength	4.0 MPa minimum in any of the three orthogonal planes of the Membrane.
Membrane elongation at break	130% minimum
Peel adhesion to concrete (ASTMD4541)	2.0 MPa minimum
Static crack bridging (Tested recognised international acceptable to the Engineer)	2 mm minimum

The spray applied liquid polymer membrane shall be suitable for use in an Ambient temperature range not greater than 40°C. It shall allow diffusion of water vapours to prevent any build-up of pressure between the membrane and substrate. The membrane shall meet or surpass the following requirements: -

The cured membrane shall be chemically resistant to the effects of hydraulic fluids, diesel fuel and diluted mineral acids etc.

The substrate shall be prepared and primed in strict accordance with the manufacturer's recommendations and requirements. The membrane shall be of a thixotropic nature and cold applied to ensure consistent thickness is achieved over all substrate irregularities.

The materials used must be based upon resin systems that do not react with moisture although the substrate should be dry during application.

The liquid polymer membrane shall be continued 1 meter down the vertical side of the roof slab where the roof is cast by bottom-up sequence.

All components of waterproofing system shall be provided by one manufacturer. All materials must be supplied to site in unopened packaging, with batch numbers marked and corresponding to the manufacturer's certificates of conformity, and must be used within the product's shelf life. All components of the system exposed to rain within the curing period shall be replaced unless agreed otherwise by the Engineer. The membrane wet film thickness should be checked every 10 square meter during Application of each layer, using a pin or comb gauge. Destructive testing to measure dry film thickness shall be carried out on the cured membrane at every 100 square meters or at every working shift, whichever occurs sooner, and shall be made good to the satisfaction of the Engineer.

ANNEXURE C

Product - Crystalline Waterproofing Mortar
CRYSTALLINE MORTAR

Recommended Uses:

- i. Applied in conjunction with Crystalline waterproofing slurry coat for:
- ii. Installation of seal strips, coves at joints to assure water tightness
- iii. Patching of tie holes and faulty construction joints
- iv. Patching and filling of routed out cracks
- v. Repairing of spalled and honeycombed areas

Characteristics:

Must be supplied from approved manufacturing facility.

Aggregate State:	Powder
Colour:	Cement Grey
Pot Life:	30 Minutes
Setting time:	2 hrs.
Shelf life:	12 months
Potable Water Compatibility:	Nontoxic and suitable for use in potable water facilities – NSF Listed as per ANSI 61 listing
Confirm to:	EN 1504-3 (For Structural Repairs – R4, Compressive Strength > 55 Mpa), Supplied from an approved manufacturing unit having CE approval confirming EN 1504-3 – R4

The product must have been proven track record of minimum 5 years in Indian conditions.

Quality Assurance:-

- i. **Manufacturer Qualifications:** A firm with experience in manufacturing crystalline waterproofing of the type specified, able to provide test reports showing compliance with specified performance characteristics, and able to provide on-site technical representation to advise on installation.
- ii. **Installer Qualifications:** Firm should be ISO 9001-2008 certified with minimum experience of 10 years in approved crystalline products. Further, the warranty should be given by supplier/manufacturer for satisfactory performance of the product including its application and supervision.
- iii. **Pre-installation Meeting:** Before installation, conduct a meeting with the waterproofing installer, installers of adjacent work and work penetrating waterproofing, and waterproofing manufacturer's representative to verify project requirements, substrate conditions, manufacturer's installation instructions, and

manufacturer' warranty requirements; notify the Owner and Architect/Engineer at least one week in advance of meeting.

- i. The manufacturer must produce relevant test certificates from reputed laboratories, confirming to above requirements.
- ii. DMRC reserves the right to approve or reject the product proposed by the contractor based upon the credentials submitted by the contractor.

Surface Preparation:

All surfaces to be patched, repaired or sealed with CRYSTALLINE MORTAR must be clean and sound. Cracks should be routed out to a U-shaped configuration, approximately 3/4" (20 mm) wide and a minimum of 3/4" (20 mm) deep. Tie holes should be roughened prior to filling. Spalled and honeycombed areas must be thoroughly cleaned and chiselled back to sound concrete prior to repair. Remove all dirt, cement laitance, form release agents, curing compounds, paints, coatings, etc. by means of wet or dry sandblasting, high pressure water jet or other suitable mechanical means. Surfaces must be well moistened to a dull dampness at the time of application. The concrete should be damp with no wet sheen on the surface.

Mixing:

For routed cracks, coves and non-moving joints, add water to CRYSTALLINE MORTAR until a medium stiff, trowel-able consistency is reached. The texture of the mix should be pliable enough to be trowelled into the cracks

With some pressure, but not so pliable that it would run out or sag out of the crack. Approximate mixing ratio (by volume) is 4½ parts powder to 1 part water. Alternatively, 100 ml of water to 450 g of CRYSTALLINE MORTAR powder. For tie holes and pointing applications, add only a small amount of water. Mixed consistency should be that of "dry earth", holding a shape when squeezed in your hand but easily crumbled when pressed between fingers. Mix only as much material as can be used within 20 minutes.

Application:

Cracks/Seal strips (reglets & coves) and faulty construction joints applications : After proper surface prime areas to be patched or repaired with a slurry coat of CRYSTALLINE and while "green" (tacky), fill cavity flush to surface with CRYSTALLINE MORTAR in mortar consistency. Once CRYSTALLINE Mortar is touch dry then 2 Coats Crystalline Slurry as final coat.

Spalled and honeycombed areas:

Prepare surface and chisel back to sound concrete. Prime area to be repaired with a slurry coat of CRYSTALLINE Slurry. While still "green" (tacky), apply CRYSTALLINE

MORTAR in layers of 1/2" (12.5 mm) not to exceed 2.5 in (approximately 6.5cm). Each layer should be allowed to set long enough that it will leave only a slight indent (approximately 1/16" or 1.6 mm) when pressed with a finger. Where possible, the surface of the repair should be packed tightly using a hammer and block of wood.

Tie holes and pointing applications:

Prepare surface and chisel back to sound concrete. Prime area to be repaired with a slurry coat of CRYSTALLINE SLURRY and while still "green" (tacky) apply CRYSTALLINE MORTAR in "dry earth" consistency. CRYSTALLINE MORTAR should be tightly rodded into tie holes or packed tightly using a hammer and block of wood.

Curing :-

Provide protection against extreme weather conditions such as heavy rain or freezing conditions during the setting period. Curing is not normally required except during hot, low humidity weather. In these conditions a light mist of water approximately 24 hours after the repair is completed will help to ensure a controlled cure. In extreme dry heat, water misting may be required more frequently.

Special Consideration:-

DO NOT apply CRYSTALLINE MORTAR at temperatures below 40°F (4°C), to a frozen substrate or if temperatures will drop below freezing during the curing period (approximately 24 hours). This product is not recommended for use in expansion or construction joints. CRYSTALLINE MORTAR can be applied in 1/2" (12.5 mm) layers not exceeding 2.5 in (approximately 6.5 cm) to prevent shrinkage cracks in the mortar.

Storage / Shelf Life:-

CRYSTALLINE MORTAR must be stored in a dry enclosed area off the ground at a minimum temperature of 45°F (7°C). Shelf life when stored in proper conditions in unopened, undamaged packaging is 12 months.

Measurement:

The consumption of Crystalline Mortar is measured in terms of actual quantity (Kg) of the material consumed based upon the actual consumption of the material for Faulty construction joint, repair of honeycombs, formation of coves at joints, seal strips and filling up of tie rod holes. The main contractor must take in to account the consumption of this material as part of post construction repairs and the same will not be paid extra.

ANNEXURE D

Product - SWELLABLE Cold Concrete Joint Water-stop

Recommended Uses:-

Typical Applications for SWELLABLE WATER-STOP include building foundations, slabs, retaining walls, storage tanks, and similar non-moving cold construction joints.

Characteristics :

Specific Gravity :	1.35
Hydro-carbon Content :	47% Min. Volatile Content: 1% Max.
Colour :	Black

Also:

- i. The Swell- able water stop must not exert swelling pressure > 5% of the dead weight of the concrete
- ii. The Swell-able water stop must be able to withstand hydrostatic pressure of 6 Bar for 7 days under lab test conditions
- iii. The Swell-able water stop must be manufactured at a approved manufacturing unit.
- iv. Material must be capable of expanding up to 215% in 120 hours, when immersed in potable water, having hydrocarbon content (ASTM D 297) of not less than 45% and volatile matter (ASTM D-6) not to exceed 1%.

Swell-able Water-stop Primer:

Colour:	Bright Orange
% Solid :	Min 20%
Flash Point :	93 deg C
Dry Time @ 25 Deg C:	10 min
Dry Time @4 DegC :	60 min

- i. The manufacturer must produce relevant test certificates from reputed laboratories, confirming to above requirements.
- ii. DMRC reserves the right to approve or reject the product proposed by the contractor based upon the credentials submitted by the contractor.

Direction for Use:

How to apply SWELLABLE WATER-STOP on poured-in-place construction joints:

- i. Carefully brush off all dust and debris and apply a coat of appropriate SWELLABLE WATER-STOP PRIMER to the area where the SWELLABLE WATER-STOP is to be placed.

- ii. Using the heel of the hand and moderate pressure, press a continuous bead of SWELLABLE WATER-STOP firmly into position. Check to be certain that the sealant has bonded to the primed area.
- iii. Splicing the ends to form a continuous, uninterrupted seal. For the best results, cut each end at opposite 45° angles and position the cut ends together. Gently kneed the spliced ends creating an uninterrupted seal.
- iv. Peel the protective backing from the exposed side of the SWELLABLE WATER-STOP.
- v. Pour the mating structural member into position.

NOTES:

Always use SWELLABLE WATER-STOP PRIMER to avoid displacement of the SWELLABLE WATER-STOP during concrete pouring. It may be necessary to utilize masonry nails or other mechanical means to hold the sealant in place on vertical surfaces.

Place SWELLABLE WATER-STOP so that it is not closer than 2" (5 cm) away from the outer surface of poured structure. If a Keyway is utilized, place the SWELLABLE WATER-STOP into the bottom of the formed Keyway area.

Special Consideration:

Always use SWELLABLE WATER-STOP PRIMER to ensure tight adhesion and to aid in preventing SWELLABLE WATER-STOP from moving during the concrete pour. For vertical surfaces, nails may be used to hold the product in place in conjunction with SWELLABLE WATER-STOP PRIMER.

SWELLABLE WATER-STOP should be used at a minimum depth of 50 mm (2") inside the concrete.

When used on pipes and other structural penetrations, SWELLABLE WATER-STOP should be cut to measured length and placed around the penetration with ends butted.

In all cases, SWELLABLE WATER-STOP should be in direct contact with the substrate along the entire length of the installation.

Storage / Shelf Life:

When stored in a dry enclosed area off the ground at a minimum temperature of 45°F (7°C) in unopened, undamaged cartons, shelf life is unlimited.

Measurement:

The measurement will be taken by measuring the length of SWELLABLE WATER-STOP in linear meter.

Annexure E

Treatment of faulty Construction Joints

Material Specification:

Cementitious based dry crystalline powder capable of creating crystals to seal the pores, microcracks in the concrete. This system become integral part of concrete and is not affected by surface wear and abrasion. This will be applied on wet saturated concrete surfaces. The material should be nontoxic and suitable for application in drinking water tanks. It should be able to withstand high hydrostatic pressure, stop moisture coming up through concrete. It should not contain stearates, sodium or silicate and should not be hydrophobic type. It should be able to grow crystals year after year & should seal micro cracks (not live/ moving crack) that may occur from subsequent damage to structure.

All along construction joints a groove of size for 20 mm wide and 25 mm depth shall be made. The construction joints to be treated shall be cleaned by water jet or other mechanical means and made free from all laitance. The saturated cleaned groove free from standing water shall be filled with Crystalline Mortar as per manufacturer specification and as per Annexure C. Treated joints shall be coated with a finishing coat by applying surface applied Crystalline Slurry coating for a width of 300 mm (150 mm on either side) .

Treatment along the circumference of pipes passing through concrete

Material Specification:

Cementitious based dry crystalline powder capable of creating crystals to seal the pores, microcracks in the concrete. This system becomes integral part of concrete and is not affected by surface wear and abrasion. This will be applied on wet saturated concrete surfaces. The material should be nontoxic and suitable for application in drinking water tanks. It should be able to withstand high hydrostatic pressure, stop moisture coming up through concrete 10 de-bond any overlay system. It should not contain stearates. sodium or silicate and should not be hydrophobic type. It should be able to grow crystals year after year & should seal micro cracks (not live/ moving crack) that may occur from subsequent damage to structure.

All along the circumference of pipe 20 mm wide and 25 mm deep rove shall be made.

The joints to be treated shall be cleaned by water jet or other mechanical means and made free from all laitance. The saturated cleaned groove free from standing water shall be filled crystalline mortar as -per manufacturer Specification and as per annexure C. The treated joints shall be coated with a finishing coat by applying surface applied Crystalline Slurry coating for a width of 300 mm (150 mm on either side).

SECTION S.13

DIAPHRAGM WALLING

13.1 GENERAL

The recommendations of BS 8004, BS EN 1538 shall be followed insofar as they are applicable to diaphragm wall construction. Similar Indian Standards for guidance or adoption are:- IS:9556, IS :4651 and IS : 456.

The attention of the Contractor is drawn to the fact that in some locations the walls may be close to existing structures and/or within a location where headroom is limited, and he shall take full account of such restrictions.

The Contractor shall pay particular attention to safety aspects of the work, employing barriers and covers as necessary.

13.2 METHOD STATEMENT

The Contractor shall submit a method statement giving the full details of materials, plant and operations involved in the construction of diaphragm walls. It shall include details of :

- a) dimension of walls and lengths of panels;
- b) dimensions and details of guide walls;
- c) the formation of the joints between panels, including sealing the joints and installation of water stop;
- d) the sequence of excavation and concreting of panels;
- e) the methods of monitoring and checking the stability of neighbouring properties, highways, services and other underground structures;
- f) the methods of monitoring by Kodan Machine/or related technology as approved by Engineer and checking the tolerances associated with the diaphragm wall panels;
- g) the methods of monitoring and checking the stability of the diaphragm wall trench;
- h) the mixing, transporting and placing equipment for the polymer slurry;
- i) the cleaning and re-use of polymer slurry;
- j) the method of disposal of contaminated polymer slurry;
- k) the type, source, chemical and physical properties of the polymer to be used;
- l) calculations to show that the density of the polymer and lowest head of slurry are sufficient to maintain the stability of the trench, in the ground conditions envisaged, to its entire length.
- m) Methods of protection of any adjacent structure and utilities existing close to the trench.

Construction of diaphragm walls shall not commence until the Contractor's proposals have received a 'Notice of No Objection' from the Engineer

Unless otherwise directed by the Engineer, the construction of panels shall be continuous once excavation has commenced. Excavated panels or part panels shall not be left open at night or during weekends.

13.3 LEVELS OF WORK

Diaphragm walls shall be concreted to the levels shown on the approved GFC drawing.

The effective trimmed final wall levels shall normally be taken as 250 mm below top of guide wall when concrete is cast-up to top of trench. If water table is high and if required cut off is low and water table is also at depth, concreting can be stopped at lower level subject to approval of the Engineer.

13.4 LENGTH OF PANELS

The length of the panels to be concreted shall be defined in the Contractor's method statement and- shall be subjected to a 'Notice of No Objection' from the Engineer.

13.5 TOLERANCES

Construction shall be carried out in accordance with the following normal tolerances, unless otherwise defined by the Contractor's drawings or procedures.

- (i) For straight or other specified profile panels, the minimum clear distance between the faces of the guide walls shall be the specified diaphragm wall thickness plus 25mm, and the maximum distance shall be the specified diaphragm wall thickness plus 50mm. The guide walls shall be propped as necessary, to maintain these tolerances, and the inner guide wall shall be constructed to the line as shown on the drawings. Finished faces of guidewalls towards the trench shall be vertical and shall have no ridges or abrupt changes. Variations from straight line or specified profile shall not exceed 25 mm in 3 m.

The trench face of the guide wall on the side of the trench nearest to the subsequent main excavation shall be vertical to within 1:200. The top edge of this wall face shall not vary from a straight line or the specified profile by more than +15mm in 3m and shall be without ridges or abrupt irregularities.

- ii) The plane of the wall face to be exposed shall be vertical to within a tolerance of 1:200, relative to a vertical line projected from the base of the guide wall. In addition to this tolerance, 75mm shall be allowed for protuberances resulting from irregularities in the ground excavated beyond the general face of the wall.
- iii) The ends of panels shall be vertical to within a tolerance of 1:200.
- iv) Where recesses are to be formed by inserts in the wall, they shall be positioned within a vertical tolerance of $\pm 75\text{mm}$, a horizontal tolerance measured along the face of the wall of $\pm 75\text{mm}$, and a horizontal tolerance at right angles to the face of the wall as constructed of $\pm 75\text{mm}$.

- v) The tolerance in positioning reinforcement shall be as follows:
- Longitudinal tolerance of cage head at the top of the guide wall and measured along the trench: $\pm 75\text{mm}$.
 - Vertical tolerance at cage head in relation to the top of the guide wall: $\pm 5\text{mm}$.
 - Lateral tolerance of reinforcement position in the direction across the width of the wall shall be $\pm 50\text{mm}$.
- vi) The tolerance in positioning couplers and starter bars for subsequent structural connections shall be as follows:
- Longitudinal tolerance measured along the trench: $\pm 75\text{mm}$.
 - Vertical tolerance: $\pm 50\text{mm}$.
 - Lateral tolerance in the direction across the width of panel shall be $\pm 50\text{mm}$.
- Note: For variation in rebar position beyond tolerances, Approval of the Engineer/designer shall be required for the Contractors corrective action.
- vii) A minimum cover to main reinforcement of 75mm shall be maintained. Minimum clear distance between reinforcement bars shall be 100 mm.
- viii) Notwithstanding the requirements of this Subsection the tolerances may be aggregated only to the extent that they do not exceed 250mm.

If, during the general excavation, it is detected that the above stated tolerances have been exceeded, the Contractor shall draw up proposals for remedying or compensating for the defects. The Contractor should review his method statement for all subsequent diaphragm wall construction.

13.6 ACCESS

The Contractor shall note the restricted access to portions of the Works and shall satisfy himself that his method of excavation, positioning of equipment, spoil handling, placement of reinforcement cages, stop ends, and concreting can be accommodated within these restrictions.

13.7 ADJACENT PROPERTIES

- i) The Contractor shall be responsible for any damage or movement in adjacent utilities, buildings, highways and underground structures of any type. Necessary instrumentation and monitoring shall be carried out.
- ii) Allowance shall be made for all ancillary treatment and all work necessary to ensure the stability of road works, adjacent structures and underground constructions and utilities.

13.8 REINFORCEMENT

Reinforcement shall comply with the requirements of Section 5. High strength deformed steel bars and wires for concrete reinforcement conforming to IS: 1786 and structural steel sections conforming to IS: 800 shall be used. Structural steel sections shall be inserted into the cage where openings shall be made at subsequent stages. All reinforcement bars and other structural steel section used shall be clean and free from loose mill scales, dust, rust, oils, grease, paint or other coatings which may reduce the bond with concrete. Front and rear of cages shall be marked on Site to identify them during placement, and lifting points and design of lifting lugs shall not cause distortion of the cage. Distance spacers shall be of an approved type, capable of resisting displacement during cage placement within the trench and shall not entrap slurry during cage placement or concreting. The reinforcement shall be adequately fixed to avoid displacement and to maintain the minimum specified cover during concreting. Welding of cold worked high tensile reinforcement bars shall normally not be permitted as a method of splicing cages. If permitted (with prior approval of the Engineer) the requirements of IS: 9417 shall be adhered to. Welding of hot rolled high tensile steel bars will be permitted provided that a method is used which will not adversely affect the properties of the bars. Mechanical splicing or welded splicing samples of rebar joints for each bar diameter of Diaphragm wall as per GFC as approved by the Engineer, duly witnessed and sampled by the Engineer, shall be third party tested and submit the test results to the Engineer's review and concurrence before start of Diaphragm wall cage tying works.

5% Diaphragm walls shall be fitted with approved Sonic tubes and tested for Cross Hole Sonic Logging (CHSL). Space between two tubes shall not exceed 750mm on edges and 1500mm in between pipes on the faces with pipes on both soil face and excavation face. Cost of CHSL pipes supplying, providing, testing and test results submission is the Contractor's own expenses. Contractor shall ensure that no sonic tubes are damaged or blocked. Blocked sonic tubes if any, shall be cleared with coring upto toe of the Diaphragm wall.

Cross Hole Sonic Logging (CHSL) Tests shall be conducted by approved third party.

13.9 CONCRETE

Concrete shall comply with the general requirements of Section 3. Structural concrete shall have a minimum cementitious content of 400kg/m³ where the concrete is being placed by tremie methods, in accordance with BS 8004 (or as per Cl. 5.2 of IS:456-2000). Usage of mineral admixtures such as Fly Ash, Ground Granulated Blast Furnace slag (GGBS) etc. shall be subjected to approval of the Engineer. Slump of the concrete shall be 150mm to 200mm and the mix shall flow easily within the tremie pipe and be designed to produce a dense impervious concrete. Such structural concrete shall have a minimum compressive cube strength of 35N/mm² at 28 days and the water cement ratio of the mix shall not exceed 0.40 or as required by the design.

Lean mix concrete as per IS: 456-2000 clauses 5 to 8 shall be employed as backfill above any cut-off level for structural concrete and be taken to the top level of the guide walls.

13.10 TEST CUBES

Test cubes shall be made and tested in accordance with the specification. Test cubes shall be taken for each panel constructed. Cubes shall be marked with the wall panel numbers and shall be sub-marked within each panel set to indicate a location within the panel.

13.11 PLACING CONCRETE BY TREMIE

Tremie pipes shall be clean, watertight and with a minimum internal diameter of 250mm. The tremie tube shall extend to the bottom of the trench excavation prior to concreting and care shall be taken to ensure that all polymer slurry is expelled from the pipe during the initial charging operation. The tremie pipe shall be maintained with a minimum embedment of 2.0m into the concrete to prevent the re-entry of slurry into the pipe. The Contractor shall ensure that an adequate supply of concrete to the tremie is available at all times so that placement is continuous until completion of the panel. The number of tremie pipes per panel shall be in accordance with the method statement. Where more than one tremie pipe is employed during concrete pouring to any one panel, the charging of concrete into the pipes shall be arranged so that it is evenly distributed between the pipes and so that no differential head exists at the concrete/slurry interface over the length of the panel. This level shall be confirmed by soundings taken during the concrete pour. Preferred rate of concrete height rise in Diaphragm wall is 5m to 7m per hour or as agreed the Engineer with maximum concrete layer wise height of 500mm each. Concrete compaction shall be ensured through tremie pipe up and down movement of minimum 1m height for minimum 90 seconds each with concrete layer wise thickness of not exceeding 500mm in Diaphragm walls. Care should be taken so that sonic tubes shall not be damaged and slurry or concrete shall not be entered in the tubes. If tubes are stuck with concrete or slurry leakage, same shall be cleared with coring before CHSL testing and CHSL tests shall be carried out without fail.

13.12 STOP ENDS

Stop ends, inserted before placement of concrete in the panel, shall be clean and have a smooth regular surface. Any shutter release agent shall have no detrimental effect on the finished works. Where stop ends are inserted in sections, adequate joint connections must be provided to ensure verticality of the complete tube.

The extraction of stop ends shall be carried out at such a time and in such a manner that no damage is caused to the concrete placed against them, or to the adjacent soil and structures

13.13 INSERTS

Inserts shall be formed at the locations shown in the Contractor's drawings and in accordance with his method statements and procedures. The Civil contractor shall coordinate with CSDs (Combined Services Drawings) and get clearance for system works related inserts, if any, with the DMRC system works Engineers or System works contractors as applicable.

13.14 CHECKING AND MONITORING

The Contractor shall provide all necessary monitoring instrumentation necessary for the close and continuous checking of the movements of adjacent structures, services and underground constructions. For all Dwall panels adjacent to highrise buildings or old structures or heavy traffic roads, the Contractor shall monitor the instrumentation and monitoring readings prior to

Dwall excavation and submit results for the Engineer's review. Upon obtaining clearance of the Engineer, the Contractor may proceed for Diaphragm wall excavation works with careful monitoring of Instrumentation and monitoring results frequently.

13.15 SAFETY AND EMERGENCY PROCEDURES

The Contractor shall take all necessary precautions to ensure stability of his excavations and guide walls and shall take all necessary precautions and be responsible for the safety of personnel in the area of operation. He shall maintain, available for immediate use, a sufficient quantity of slurry to allow for any sudden loss.

Should the loss continue despite the addition of the slurry and the stability of the trench be placed at risk, the Contractor shall backfill with leanmix concrete to preserve the stability of the trench and ensure the safety of neighbouring structures and utility services.

13.16 SITE CLEANLINESS

The Contractor shall ensure that the Site is cleared of slurry and that surplus or displaced slurry is disposed of safely and without nuisance. All operations shall be conducted in such a manner as to minimise any spillage of slurry over the Site, or accesses thereto.

13.17 OBSTRUCTIONS

An obstruction is defined as material, the excavation of which hinders normal progress and the existence of which could not have been foreseen. Upon encountering an obstruction, the Contractor shall determine the method to be employed in removing the obstruction.

13.18 DISPOSAL OF SPOIL

- i) Spoil removed from the excavation shall be separated from the slurry employed in the excavation process. It shall be disposed of as quickly as possible to locations as directed by the Engineer and in such a manner that spillage and annoyance be minimised.
- ii) Contaminated slurry, not suitable for re-use, shall be removed from the Site and disposed of as per specification.
- iii) Disposal of spoil includes multiple handlings in logistics with temporary stockpiles required to ensure continuous Workfront without obstructing further construction at the Worksite at the Contractor's own expenses.

13.19 JOINTS

All joints shall be fitted with a waterstop covering the full height of the wall. Where concrete is cast against previously completed wall panels, the previously formed concrete shall be cleaned so that solid substances are removed before the joint is formed. When the joint is exposed upon subsequent excavation, the Contractor shall immediately repair any joints which permit jetting or spraying of water or within which solid foreign substances greater than 3mm separate the concrete in adjacent panels. The walls formed shall be substantially watertight, that is, free from running or percolating water.

13.20 RECORDS

The following records shall be maintained and kept for each wall panel and such records shall be available for inspection by the Engineer.

- i) Name of work
- ii) Panel No and reference drawing no
- iii) Date and time of start and finish of panel excavation;
- iv) Details of any obstructions encountered; time spent and construction method adopted in overcoming such obstructions.
- v) Date and time of completion of cage placement;
- vi) Date and time of start and completion of panel concreting;
- vii) Length of panel and width and depth of panel from top of guide wall
- viii) Top of guide wall level and densities;
- viii) Top level of wall as cast, in relation to top of guidewall at the edges and at the centre.
- x) A log of soil type encountered from start to finish of excavation, and of slurry levels and densities;
- xi) Volume of concrete used and time of any interruptions in concrete supply where these exceed 15 minutes. Volumes of normal and lean mix concrete;
- xii) Cut-off level of concrete below top of guide wall level;
- xiii) Date, place and time of slurry control tests and results recorded;
- xiv) Concrete test cubes, w/c ratio, slump markings, date and results obtained on testing;
- xv) Details of reinforcement and cage type;
- xiv) Quantity of slurry removed from Site and spoil removed from Site recorded by date;
- xv) Along with Concrete Pour Card records a graph of theoretical and placed concrete volumes with concrete depth by sounding and tremie pipe insertion depth position ensuring minimum 2m immersion depth of tremie pipe in the Concrete at all times and shall attach to the RFI.

SECTION S.14

TUNNELING

14.1 INTRODUCTION

This section specifies materials, methods and workmanship required for the construction of tunnels, shafts and other underground structures.

14.2 GENERAL

- a) All works shall be carried out in compliance with the Health and Safety requirements as detailed in the appendix 20 to the Employer's Requirements and in the Contractors Safety Plan.

- b) All aspects of excavation in tunnels shall comply with the requirements of:

BS 6164:Safety in Tunnelling in the Construction Industry

CIRIA Report 80 A review of instruments for gas and dust monitoring underground.

All work shall be carried out in compliance with the Government of India Rules and Regulations & State Government Acts & Regulation like Building & Other Construction Works Act (BOCW) etc.

14.3 SURVEY

Before commencement of any work, the Contractor shall prepare and submit appropriate survey method statements relating to his proposed methods of working.

Contractor shall establish the system for underground surveying, setting out and correcting deviations from theoretical alignment, using a laser based system. Reference point and targets shall be used in conjunction with lasers to ensure the accuracy of the system and it should be easy to monitor by the Engineer. Laser based guidance systems shall have an alternative system as back-up.

14.4 Excavation

14.4.1 General

The Contractor shall perform all underground excavation, as well as that required in open cuts, in accordance with this Specification or as required by the Contract with the issue of notice from Engineer.

- a) Except where otherwise specified in this Section of the Specification, all excavations in tunnels, shafts and junctions shall also comply with the requirements of Earthworks, (Section 2) and shall conform to the dimensions shown on the approved drawings.
- b) Prior to commencing any excavation for temporary or permanent works, the Contractor shall prepare and submit appropriate designs, drawings and method statements relating to his proposed methods of working. Such methods shall ensure that there is no damage to or deterioration of the final surfaces of the excavations and ensure that surface settlement and distortion to underground structures are kept to acceptable limits.
- c) No pedestrian access along the tunnel trackway shall be permitted while haulage operations are in progress. Segregated pedestrian access should be provided where appropriate.
- d) The exhaust systems of any internal combustion vehicles used underground shall be fitted

with air cleaning equipment.

- e) The safety and security of all excavations, either surface or underground, shall, at all times during the construction, be the responsibility of the Contractor. The Contractor shall implement such measures, including supporting, dewatering and consolidation, as may be necessary to fulfil this obligation.

The design of temporary works and ground supports, particularly those for locations below residential areas, railways and highways should be verified as required under the Contractor's Quality Plan.

- f) All inclined tunnel drives shall have runaway vehicle protection.
- g) The Contractor shall construct the Works in such a way that the settlement effects are kept within the limits specified in Section 2.10 of Outline Design Specification.

Such measures might include:

- 1) special tunnelling methods to reduce ground loss;
- 2) protection measures such as:
 - underpinning
 - ground improvement
 - compensation grouting
 - structural jacking and supporting
 - structural strengthening
 - curtain walling
 - or other supporting methods

- h) Excavation with Care

All necessary precautions shall be taken in order to prevent softening or deterioration of excavation surfaces through exposure. The following is appropriate:

- i. Where necessary to ensure the safety and security of the Works, excavation for underground Works shall be continuous by day and night. The Contractor's procedures may allow intermissions at weekends and general holidays, providing the Works are safe and are inspected by the Contractor at appropriate intervals.
- ii. Where open faced tunnelling is to be carried out, the Contractor shall provide adequate means to support the face in an emergency. The support system shall be maintained in good order at all times and it shall be stored as close to the face as practicable. A detailed drawing of the support system shall be available close to the tunnel face for reference.
- iii. Temporary support will be required to the face at all times during manual excavation. The type of support provided must suit the actual and anticipated ground conditions. The ground must be carefully trimmed in order that the supports can be properly seated and bear fully onto the face with a minimum of wedging.
- iv. Where the excavation is to be discontinued for any period of time the face must be supported in such a manner that ground movement is prevented.

- v. A proper ventilation system for supply of fresh air to the workers in every work areas shall be installed.

In general, the Contractor shall at all times carry out excavation to the Works such that the minimum of ground movement is allowed to take place.

14.4.2 Soft Rock Excavation

In ground which is not self-supporting, measures shall be taken to ensure that no undue loss of ground occurs at the face, and that there is no run of material from behind support or lining.

Where excavation is discontinued for any reason, the Contractor shall take all necessary steps to secure and support the excavation, to ensure that ground movement is prevented.

14.4.3 TUNNEL AND SHAFT EXCAVATION IN ROCK

The contractor shall seek the prior consent of Engineer for Rock Excavation.

14.4.4 Hard Rock Excavation

a) Excavation Method

The Contractor shall provide to the Engineer full details of the proposed rock excavation methods for his approval. Excavation should be carried out by such manual/mechanical means or methods, so as to eliminate noise and dust upto the prescribed limits and without using any blasting and/ or any expansive chemicals. Similarly, the Contractor shall submit his plans for methods for monitoring vibration adjacent to residential area,

b) Rock Stabilisation

The Contractor shall carry out rock stabilisation measures with minimum delay after the excavation of each round. In order to facilitate this, the Contractor shall request that the Engineer always accompanies him when inspecting the existing structures and excavated rock surfaces revealed after excavation operations.

14.4.5 Exploration of Tunnel Face

Normally, at least one exploratory hole shall be drilled ahead of each tunnel face to probe the ground conditions ahead of the advancing tunnel. The drilling shall be made to such an extent that after excavation of a new tunnel round, the distance between the tunnel face and the end of the exploratory hole shall be at least 10 m or two tunnel diameters. The location and direction of exploratory holes shall be varied to take account of the actual geological conditions, as agreed by the Engineer.

The Contractor shall keep logs of all probe holes drilled. The following data, together with such additional data as the Engineer may direct, shall be given on the logs:

- i. The date and hours of the drilling.
- ii. The location, orientation and drilled length of each probe hole.
- iii. A plot of the rate of drill penetration versus drilled length. .
- iv. The location, nature and quantity of any water inflows.
- v. The location and extent of any changes in strata as determined by the penetration rate and based on analysis of samples taken.

The copies of each probe exploratory hole log shall be submitted to the Engineer within 24 hours of its completion.

14.4.6 Over Break

No projection of rock points will be accepted inside the theoretical excavation line. The Contractor shall remove all such rock points at his own cost.

All excavation outside the theoretical line will be classified as over break. Where over break occurs more than 150 mm beyond the theoretical excavation line of unlined rock surfaces, the Engineer will inspect the area and instruct if shotcrete or concrete shall be provided as backfill. In areas where there is to be a concrete lining or concrete structure adjoining the rock, the over break backfill shall be of the same quality as that required for the lining or structure.

14.4.7 Cleaning and Scaling

Scaling, involving the removal of loose rock from excavated walls and roofs shall be performed immediately after excavation and at intervals thereafter as necessary to prevent accidents. A complete final scaling of excavation surfaces which have not been covered with shotcrete or concrete shall be carried out prior to acceptance of the underground works.

The final cleaning of the invert of all excavations shall be carried out as carefully as possible using mechanised equipment.

14.4.8 Dental Excavation

Dental excavation shall include the removal of soil, rock fragments, decomposed rock etc. from seams, cavities, depressions or limited areas which requires the use of hand tools. The use of a high velocity air-water jet may be required to remove stiff or hard materials.

The Engineer will instruct such work and determine the extent to which materials shall be removed, including the depth, direction and dimensions of the dental excavation. The methods of dental excavation shall be such as to avoid fracturing the rock adjacent to the material being removed.

14.4.9 Disposal of Excavated Material

Excavated material, which is not acceptable or cannot be accommodated for use in the works, shall be disposed of in spoil dumps or elsewhere as approved by the Engineer. Disposal of earth includes multiple handlings in logistics with temporary stockpiles required to ensure continuous Work front for further construction at the Worksite such as TBM works, Station works etc. Excavated material, which can be used at a later stage in the works shall be temporarily stockpiled in a dumpsite as directed by the Engineer.

14.4.10 Excavation for Contractor's Convenience

Excavations for the Contractor's own use and convenience shall conform in every respect with this Specification. For this purpose, the Contractor shall submit detailed proposals to the Engineer. The proposals shall include the Contractor's method of backfilling and reinstatement.

Excavation for the Contractor's convenience, as described above, will not qualify for payment.

14.5 SUPPORT SYSTEMS**14.5.1 Tunnel Linings****a) Precast Concrete Lining Design**

The segments shall be designed to ensure that the full design life is achieved. To achieve full design life of concrete lining, impermeable concrete containing Microsilica in minimum 5% by

the weight of cement shall be produced and shall be tested in accordance with DIN 1048. Microsilica shall be used in minimum 5% by the weight of cement to ensure the protection of precast against corrosion of reinforcement. In the case of precast concrete linings special care shall be taken to ensure that corrosion of reinforcement or other cast in metal components does not affect the durability of the segments. Tunnel Rings segment system shall be followed as per the manufacturer's recommendations at the Contractor's cost. Details of RFID shall be mentioned in RFI document. As built records of RFID shall be submitted upon completion of Rings erection at the site to the Engineer's review and records.

b) Trial Assembly

There shall be a trial assembly, before commencement of the bulk manufacture, of three rings bolted together on a horizontal plane platform to demonstrate compliance with this Specification of rings of each material and diameter. The rings shall be built one above the other with the cross joints offset by half a segment as appropriate except for expanded linings. The fully bolted bottom ring shall be bolted to the platform or otherwise secured in position and shall be retained as a master ring until the completion of tunnel construction. From time to time, as may be required, segments shall be built to form two rings on the master ring to ensure that tolerances and interchangeability of the segments are maintained. Adequate notice of the trial assembly shall be given to the Engineer to enable him to arrange inspection and checking of the assembly.

c) Marking of Segments

a) All tunnel segments delivered to site shall bear the indelible marks described as below.

The information shall be marked on each segment of ring in two or three places so that it can be readable/ visible at all stages like transportation, erection & after erection in tunnel. Any segment which is delivered to site and upon which the markings cannot be read for whatever reason, shall not be used in the Works.

b) The markings must in no way compromise any requirement of this Specification, i.e.cover to reinforcement or waterproofing.

c) The following minimum information shall be included on the marking:

- (i) Internal diameter
- (ii) Type of segment:
 - `O` ordinary
 - `T` top (the T shall be put near the key end of the segment)
 - `K` key segment
 - `X` special or taper

For special or tapered rings each segment type shall be marked at each end to ensure the segments shall be built in the correct sequence and orientation.

- (iii) Date of Casting and Mark with figures not less than 50 mm high identifying the casting with the appropriate sample.

d) Transporting and Storing Segments

Segments shall be transported face up with timber spacers. When stored on site segments shall be stacked face up for segments storage, on a prepared level base with timber packing as necessary. The Contractor shall submit a typical storage drawing at Casting yard, at site,

during transport with tying details etc., and get the Engineer's approval before starting the segments storage and transportation. A dispatch checklist system duly approved by the Engineer shall be implemented enhancing safety in logistics and avoid cracks at stacking site etc.

e) Joints

The faces of joints shall be cleaned before bolting segments. Bolts shall be tightened at the time of erection of each ring. For a shield drive the circle bolts shall be retighten prior to release of the shoving jack force.

f) Rolled Rings

Rings may be rolled to facilitate the construction of openings, and may also be rolled to facilitate maintenance of the plane of the rings. Tapered rings shall be rolled as appropriate to achieve the specified alignments and gradients of the tunnels.

g) Bolts

The length of each bolt shall allow for two washers and two grommets and for all adjustments required in the alignment of the tunnels. When fitted in position the bolt threads shall be exposed for at least 3 mm clear of the nut. Bolts shall be designed for gasket closure force for required water tightness and shall conform to requirements of IS 1367.

h) Plane

- i. Errors in the plane of a ring should be kept to a minimum. When they occur, the plane of the ring shall be adjusted by packing of maximum practicable continuous lengths of resilient, durable consented-to material. Packing in a single joint shall not exceed 6 mm for concrete lining.
- ii. The packing shall be supplied in various thickness, as required, but not less than 2 mm, and when in place, shall be clear of the sealing strip.
- iii. In tunnel drives which utilise all tapered rings, packing shall not exceed 3 mm per circle joint.

i) Sealing Strips and gaskets

Composite type gasket (single strip containing hydrophilic strip pasted/ extruded over the EPDM strip) shall be provided at all faces between segments to provide a seal against ingress of ground water.

Immediately prior to the erection of a gasketed segment the gaskets shall be checked for cleanliness and position.

j) Caulking Grooves

Caulking grooves shall be formed in segments in accordance with the design and this Specification to ensure that caulking to circle joints and radial joints may be made effectively continuous, the depth of caulked material in the joints being not less than 25 mm.

Prior to caulking all joints shall be inspected and thoroughly cleaned out as necessary. Any packing, grout or other foreign material projecting into the caulking space shall be cut out by an appropriate method.

Immediately prior to caulking, the joints shall be blown out with a compressed air jet as necessary to remove any loose debris or water.

k) Grout Valves

For linings built behind tunnelling machines, having a pressurised face system, grout holes if provided in the linings segments shall incorporate one-way valves to prevent ground and water loss during the grouting operation.

l) As-built Tolerances

i) Employer's Requirement:

The Employer's Requirement is that the finished tunnel for single track after as-built tolerances (as per (l)-(ii) below) shall be of minimum 5600mm internal dia with the design axis of the tunnel. This means that at no point of circumference of as built tunnel, distance between designed axis of the tunnel and internal surface of tunnel shall be less than 2800 mm.

ii) As-built tolerances shall depend upon the Design Internal diameter of the tunnel for single track. The tolerances for the design internal dia of 5700mm for single track tunnel shall be as under:

- (a) The internal profile of lining shall not depart from its design position by more than 50mm. This means that the center of the tunnel at any cross section may deviate from the designed center upto 50mm, provided the internal dia at the cross section is equal to 5700mm.
- (b) The internal profile of any ring of shield-driven tunnels shall not deviate from a true circle by more than 25 mm. That is, any diameter of the as-built ring shall not differ from the design internal diameter by more than 50 mm. However, this tolerance shall not be permitted where tolerance at 12.2 (a) has been utilised.
- (c) The plane of the leading face of each ring, including a taper ring, shall not depart at any point from the plane surface by more than 6 mm.
- (d) Steps between abutting segments shall be as per IS 15026 part 2.
- (e) The roll of adjacent circle joint bolt holes shall not be greater than 5 mm; the maximum total allowable bolt hole roll of any ring is 40 mm from the design position.

iii) In case the contractor proposes the designed internal diameter other than 5700 mm for single track, the same may be up to maximum 5800 mm. As built tolerances as mentioned in 14.5.1(l)(iii) (c), (d) and (e) shall remain same. As built tolerances at 14.5.1(l)(iii) (a) and 14.5.1(l)(iii) (b) for the proposed dia shall be such that the employers requirement as stipulated in the para 14.5.1(l)(i) is fulfilled.

iv) It is once again reiterated that the employers requirement mentioned in para 14.5.1(l)(i) has to be met under all circumstances after taking into account the combined effect of all provisions in 14.5.1 (l)(iii) (a), (b),(c),(d) &(e).

v) **Additional requirements in construction of round tunnels for provision of Neutral section (in both Up & Down tunnels).**

For accommodating the Neutral section in the round tunnels, the contractor has to provide the modified tunnel construction arrangement as stated in drawing no DMRC/EI/UG-Tr/GA/Neutral Section-01/R0 (attached with tender drawings, if applicable). The summarized details of requirements are as below:-

- Niche of 70X1211X1400(Minimum) mm in bored tunnel where Neutral section is to be provided.

- Niche to be provided in alternate segment with segment length of 1400 mm (Minimum) for a total of 14 Mtr length. Segment length to be in the range of 1400 mm to 1500 mm.
- Minimum clearance of 5100 mm is required from top of rail (TOR) to the top of Niche (i.e. $AC=BD=5100$).
- Neutral section shall be provided at a location with zero gradient, no curve, no signal, no crossover and 250 Mtr away from Platform.
- The above mentioned drawing will be applicable for 5800 mm, 5700 mm diameter bored tunnels. In neutral zone section, the tunnel dia shall not be less than 5700 mm.
- Tunneling contractor should take care of eccentricity in centre axis of bored tunnel and interface with track contractor so that invert of tunnel till top of rail (TOR) should in no case exceed 630 mm while ensuring the minimum SOD clearances.
- Civil contractor to interface with track and traction contractor for construction of tunnel in neutral zone.

The construction tolerances for the tunnel axis alignment shall be limited to 25 mm and 50 mm for 5700mm and 5800mm internal finished dia tunnel respectively and it needs to be adjusted in such a manner that the minimum clearances of 5100 mm between top of rail (TOR) to the top of the niche is maintained in complete neutral section zone and also in sufficient adjacent zone to maintain same rail level. It is informed that the clearances shown in the drawing are bare minimum which the contractor has to maintain considering all the aspects of construction. The details of the interface requirement of the neutral section design are provided in the interface matrix table below.

Table

Interfacing Requirements for Design & Implementation of Neutral Section in Round Tunnels.

Item No.	Item Description	Tunnel Building Contractor	Traction Contractor	Track Contractor	Remarks
1.	Design of the tunnel alignment at the Neutral section Zone	Will provide the detailed design drawing along with construction tolerances to the traction & track contractors	Will provide the length of the Neutral section & the details of the tolerances in civil structure acceptable in construction to civil & track contractor	Will provide the details of the track levels to civil & traction contractor	
2.	As built details of level & alignment	Will provide to the traction & track contractor			
3.	Design of Neutral section		Traction contractor to design the neutral section in the round tunnels as per the clearances provided between the TOR & tunnel soffit. All the structural		

			requirements are to be provided to the civil contractor & same to be checked during construction of the tunnels in neutral zone area.		

m) Non-Compliance with Tolerances

Where any part of the lining does not comply with the specified tolerances the Contractor shall submit to the Engineer for consent, proposals for remedial or other measures to correct the defect or negate its effects as appropriate.

n) Damaged Segments

Any segments which are damaged or defective shall be indelibly marked and removed from the Site and replaced by the Contractor. Such damaged or defective segments shall be destroyed. No damaged or defective segments shall be used in the Works.

Rings which have been built and shoved and are subsequently damaged may have to be removed and rebuilt.

o) The grade of concrete shall be at least M45.

p) The contractor shall submit drawings and details of the moulds he proposes to use and details of working methods he intends to adopt for their manufacture, use etc. for consent. The moulds shall not be of a material, which may work through exposure.

q) Tolerances

The dimensions of precast concrete segments shall be within the following tolerances:

(a)	Circumferential Length	+3mm-0mm
(b)	Thickness	+5mm-1mm
(c)	Width	+1mm-1mm
(d)	Internal diameter of completed ring	+8mm-0mm
(e)	Bolt holes size	+1mm-0mm
(f)	Bolt holes position	+1mm-1mm

Steel templates fit for purpose shall be provided for the control of the production of segments to the required tolerances.

14.5.2 Alternative Tunnel Lining

If the Contractor has proposed in his design to use an alternative form or type of tunnel lining he shall submit for consent comprehensive details of his proposals. Such proposals shall include details of materials, method statement, specification and design sufficient to demonstrate compliance with the design requirements. If such proposals, or any modifications to them which may be submitted, cannot be consented to, the Contractor shall adopt the lining types and methods specified herein as appropriate to the Works.

14.5.3 Tunnel Support (NATM)

NATM Tunnel Support

14.5.3.1 General

- a) The type and amount of tunnel support to be installed immediately after excavation is directly related to the rock classification as established by the Contractor. The standard initial support associated with the established rock classification system shall be proposed by the Contractor for obtaining a Notice of No Objection from the Engineer. However, as a consequence of variations from the anticipated rock conditions the standard support systems as shown on the Construction drawings(prepared by the Contractor and noticed by the Engineer) for each rock class may require modifications and adjustments during construction for which a Notice of No Objection for the revised scheme shall be obtained from the Engineer.
- b) The Contractor shall ensure that support elements are installed or applied in such a manner, time and sequence as to prevent disintegration and loosening of the rock mass surrounding the excavated tunnel.

14.5.3.2 Initial Tunnel Support

- a) The initial tunnel support will generally consist of the following:
 - Steel ribs or lattice arches and wire/reinforcement mesh sprayed with shotcrete to an appropriate thickness
 - Shotcrete with wire/reinforcement mesh or fibre and rock-bolts/rock dowels
 - A combination of the above.
- b) Wherever ground conditions require pre-support, the contractor shall provide the same by way of inserting an 'umbrella' type forepoling either by installing a pipe roof that will be closed poled or spiling with grouted pipes or bars depending on the ground stability.
- c) The face support during stoppages or lining (support) installation will either consist of a spoil buttress which will be supported by shotcrete and mesh or shotcrete and mesh with grouted rock dowels inserted into the face.
- d) Where the water in-flow into the excavation is expected, ground treatment such as grouting etc. shall be done by the Contractor before commencing the excavation. However, the localised dewatering in the tunnel face can be carried out by either drainage pipes inserted into the face or a mild vacuum system duly ensuring that it doesn't lead to unacceptable ground surface settlements/distortions adversely affecting the EBS.
- e) The initial Support will be monitored continually for settlements/deformations throughout the stabilisation process. Other monitoring shall include force in rock bolts and stresses/strains in shotcrete lining.
- f) The initial support system including the design of the supporting pattern with respect to each Rock Class shall be determined and proposed by the Contractor for obtaining a Notice of No Objection from the Engineer before commencing the works.

14.5.3.3 Final Tunnel Support:

The final tunnel support shall comprise of reinforced concrete lining only.

a) Concrete lining

The Contractor shall design concrete linings to meet the requirements of the Contract Specifications pertaining to concrete.

b) Preparation of surfaces

The surface against which concrete is to be placed shall be cleaned of loose material and dirt. A waterproofing membrane shall be placed between the initial support and the final concrete lining. No concreting of final support shall take place before inspection of the initial support surface and the waterproofing membrane by the Engineer.

c) Placing of concrete

Concrete shall be placed so that the space between the lining form and the surface against which concrete is to be placed, is filled as completely as possible, to avoid any voids formation especially in the crown area. After the placed concrete attains a 28 days strength, the interface between the concrete lining and the initial support shall be contact grouted without damaging the waterproofing membrane.

14.5.3.4 Sprayed Concrete (Shotcrete)**14.5.3.4.1 General**

- a) Sprayed concrete may be applied by either a wet or dry mix process.
- b) The sprayed concrete after completion is not to be touched up, trowelled, smoothed off or worked in any way, but left undisturbed unless otherwise agreed by the Engineer.
- c) If required a layer of sprayed concrete (called flash shotcrete or sealing layer) shall be applied immediately following the excavation to stabilize the unstable/loose patches.
- d) Sprayed concrete shall be applied to the excavated rock surface with or without mesh reinforcement, as the case may be, and to the designed thickness as indicated in the construction drawings prepared by the Contractor and agreed by the Engineer.
- e) Sprayed concrete shall be applied in one or more layers of appropriate thickness to achieve the total designed thickness.
- f) All the provisions in the Contract pertaining to the concrete shall be applicable to the sprayed concrete (shotcrete) as well, to the extent found relevant.
- g) The type of cement to be used for shotcrete shall be according to IS 456. A specific fineness of the cement after Blaine between 2250 cm²/g and 3700 cm²/g can be used to achieve sufficient early strength of the shotcrete. Additives (conforming to the relevant BIS standards), such as fly ash, ground granulated blast furnace slag and silica fume for the improvement of performance, and workability etc. may be added to the shotcrete mix, with the approval of Engineer. The performance of the shotcrete mix with additives shall be determined by field suitability tests.

14.5.3.4.2 Aggregates

- a) The coarse aggregates shall not contain a large quantity of long stone pieces. The maximum size of the aggregates shall not exceed 12 mm for wet process or 16 mm for dry process. The proportion of aggregate larger than 8mm in size should not exceed 15% for the wet process in order to minimise rebound. The grain size distribution shall be as shown in Table 3.10.4-1. It is the responsibility of the Contractor to choose the most suitable grading for the process and materials available.
- b) The amount of fine particles under 0.1mm shall not exceed 8%. During rainy and cold weather periods, the aggregates for the dry process shall be stored undercover for at least 48 hours before being used and kept sufficiently dry.

Table 3.10.4-1 Recommended Grain Size Distribution of Aggregates with Wetmix Shotcrete

Standard Sieve	Sieve Size (mm)	Passing in %
ASTM	12.5	96 – 100
IS	10	92 – 98
IS	4.75	70 – 80
IS	2.36	50 – 60
IS	1.18	24 – 34
IS	0.60	20 – 28
IS	0.30	10 – 17
IS	0.15	5-12

14.5.3.4.3 Steel fibres

- a) Steel Fibres shall be used for all shotcreting works of temporary or permanent works in Tunnels, NATM works, cross passages, Stations and ancillary structures where the shotcreting works are left permanently in the ground. If the shotcrete works are removable such as temporary shoring works in the stations, ancillary building etc., use of Steel Fibres in shotcrete may be exempted with prior approval of the Engineer.
- b) The types and dimensions of steel fibres shall be suitable for shotcrete application and the requirements of shotcrete reinforcement. The steel fibres shall be supplied by a supplier as agreed by the Engineer before their use in the Works.
- c) Steel fibres shall be collated or uncollated deformed steel fibres conforming to the requirements of ASTM A820-90.

- d) Fibres shall be stored in dry sealed containers until ready for use and shall be free from corrosion, oil, grease, chlorides and deleterious materials which may reduce the efficiency of the mixing or spraying process, or which may reduce the bond between the fibres and the sprayed concrete.
- e) Fibres shall have an aspect ratio (ratio between fibre length and fibre diameter) in the range of 30 to 150 for lengths of 12.7 to 63.5 mm. Tolerances shall be in accordance with ASTM A820-90.

14.5.3.4.4 Accelerators

- a) Accelerators may be used to achieve a fast set and to get sufficient early strength development. The proposal along with references from suppliers shall be obtained and submitted to the Engineer for Notice of No Objection.
- b) Accelerating admixtures shall be compatible with the cement used. The compatibility shall be tested in the laboratory by the Manufacturer and verified by the Contractor in field suitability tests to achieve the required properties for early and final strength as proposed by the Contractor.
- c) Only alkali-free accelerators shall be used. The alkali content shall be less than 1% mass (Na₂O-equivalent, EN 480-12).
- d) The dosage rate determined by the field suitability tests shall not exceed 7% of the cement content of the mix design by weight. The dosage of accelerator shall be kept to the minimum required for spraying in-situ.
- e) Automatic devices shall be used to add the accelerator.

14.5.3.4.5 Plasticisers and retarders

- a) Plasticizers and super plasticizers, complying with BS 5075: Part 1, may be used to achieve pumpable shotcrete with minimum water content. Plasticizers shall be checked regularly, or as required by the Engineer, for setting time, water reduction and development of strength as compared with the design mix.
- b) Compatibility of plasticizers with cements, latent hydraulic binders and accelerators shall be verified by field suitability tests.
- c) The effects and optimum dosages of plasticizers and super plasticizers shall be determined by the field suitability tests to achieve the shotcrete properties as required.

14.5.3.4.6 Compressed air

Compressed air used in the process shall be clean, dry, contamination-free and free of oil.

14.5.3.4.7 Design of sprayed concrete

- a) The mix design shall be carried out by the Contractor and details submitted to the Engineer for Notice of No Objection.

- b) The mix for shotcrete shall be designed by field suitability tests to meet the requirements.

The following factors shall be taken into consideration:

- Material and gradation curves of aggregates
- Cement content
- Water-cement ratio
- Plasticizer or super plasticizer type and dosage, if any
- Hydration control admixture type and dosage, if any
- Internal curing admixtures, if any
- Accelerating admixtures
- Early and final strength
- Strength loss as compared to the design mix strength of the shotcrete
- Rebound
- Temperature of the mix
- Establishment of target slump and slump retention of the mix for optimum performance and placement
- Other additives, if any

- c) Cement Content

- i. For the dry shotcrete process the quantity of cement shall not be less than 350 kg/m³ of dry mix.
- ii. For the wet shotcrete process the minimum cement content shall be 400 kg/m³.
- iii. Variation from the above cement content shall require agreement of the Engineer. The cement content shall be designed to meet the strength requirements of shotcrete applied in the field.

- d) Requirements for shotcrete

- i. Early Strength

The early strength of shotcrete shall conform to the early strength class J2 according to Figure 3.10.4-1. For explanations regarding the use of Early Strength Classes J1, J2 and J3 Austrian Guideline for Shotcrete may be referred to.




Figure 3.10.4-1: Early Strength Requirement for Shotcrete

The Contractor shall conduct early strength test regularly for permanent or temporary works and submit the report to the Engineer. The measurement of early strength shall be done by using the penetration needle, Hilti Shotbolt(stud-bolt) system (or equivalent) according to the Austrian Guideline for Shotcrete, August 2006.

ii. Further Strength Development

The 72 hours strength of the shotcrete shall be at least 12.5 N/mm². The strength of the shotcrete after 7 days shall be at least 70% of the specified 28 days strength of the mix.

iii. Final Strength

The 28 days strength of shotcrete shall conform to the 28 days design mix strength. A maximum factor of 0.85(the ratio of in-situ strength to the design mix strength) shall be taken into consideration while designing the mix to account for the effects of in-situ installation conditions as compared to the conditions obtainable in the Field Suitability tests.

14.5.3.4.8 Equipment

- a) All the equipment used for batching and mixing of materials and the application of sprayed concrete shall be of noticed design and in proper working order. The sprayed concrete gun and ancillary equipment shall be of adequate capacity for the volumes to be applied. The equipment shall be capable of handling and applying 16 mm maximum size of aggregate. A stand-by gun and ancillary equipment shall be available at all times. Air for the equipment is to be provided at the equipment at not less than the required operating pressure.
- b) Dosing of additives by hand will not be permitted. Equipment for dosing the additives shall be adjustable for various quantities and provide a uniform rate of discharge evenly mixed with the other ingredients of the mix. The equipment shall be capable of delivering admixture to ensure the noticed dosage ratio to an accuracy of $\pm 5\%$.

- c) The working area shall be well illuminated to a minimum lighting intensity of 50 lux. Cap lamps attached to safety helmets will not be accepted as the sufficient measures. Dust pollution shall be minimised by means of predamping of materials, additional ventilation, water sprays, and maintaining equipment in good order. Protective clothing and dust masks shall be provided for and used by all sprayed concrete operators.
- d) If at any time the Engineer considers that the environmental conditions of the area where sprayed concrete is being applied are likely to cause a health hazard or affect the quality of the finished work because of excessive dust or lack of adequate ventilation or lighting, he may instruct the Contractor to suspend operations on sprayed concrete work until steps are taken to improve the conditions in the affected area. No additional payment shall be made to the Contractor either for the additional measures called for or for any delays resulting from such suspension of works.

14.5.3.4.9Batching

- a) Dry Shotcrete Process
 - i. Cement and aggregates shall be batched in the proportions as designed. Batching shall be done by weight. At the time of batching all aggregates shall have been dried or drained sufficiently to result in a stable moisture content, which shall not exceed 7%.
 - ii. Mixing of cement and aggregates shall be performed by a mechanical mixer. Shotcrete shall not be used unless placing can be completed within a period of 90 minutes from the time of mixing unless a hydration control admixture is used that is suitable to inhibit setting and retain consistency for the required time period till the placing of shotcrete. The hydration control admixture must have a notice of No Objection from the Engineer.
 - iii. The mixing time shall be in accordance with BS 5328.
 - iv. A system of delivery notes shall be maintained to record the date, the time of mixing, mix design number, quantity, delivery point, time of delivery and completion of placing. The delivery notes shall be available to the Engineer for inspection.
 - v. For the dry process, powder or liquid type accelerating admixtures shall be added to the dry-mix. The powder type accelerator shall be proportioned and added just before the dry mix enters the shotcrete machine through a mechanical device (dispenser). Periodic calibration checks shall be performed in accordance with the procedures prescribed by the manufacturer. Liquid type accelerator shall be delivered by a special dosage pump and added to the dry-mix at or near the nozzle. Dosage pump and the hoses to the nozzle shall be kept in good order.
 - vi. Dry-Mix delivered to the shotcrete machine shall have a minimum temperature of 5°C and a maximum temperature of 32°C.
 - vii. During hot weather periods the water content of the aggregates for the dry process shall be kept above 4%, in order to avoid cement loss at the rotor of the shotcrete machine.
 - viii. During transportation the dry mix shall be effectively protected against the influence of weather.

b) Wet Shotcrete Process

- i. Only liquid types of accelerator can be used in the wet process; these shall be added at or near the nozzle. The delivery from the accelerator pump must be controlled to be proportional to the output of the concrete pump. Accelerator pump calibration shall be periodically checked in accordance with the procedures prescribed by the manufacturer. The nozzle must be such as to ensure a homogeneous mixture of the accelerator with the wet-mix.
- ii. Shotcrete shall not be used unless placing can be completed within a period of 120 minutes from the time of mixing unless a hydration control admixture is used that is suitable to inhibit setting and retain consistency for the required time period till the placing of shotcrete. At high temperatures, hydration control admixtures shall be used to ensure fresh concrete and sufficient initial setting time.
- iii. Concrete delivered to the shotcrete machine shall have a minimum temperature of 15°C and a maximum temperature of 32°C.
- iv. A system of delivery notes shall be maintained to record the date, the time of mixing, mix design number, quantity, delivery point, time of delivery and completion of placing. The delivery notes shall be available to the Engineer for inspection.

c) Materials shall be batched by weight and cement shall not be added more than 1 hour before the anticipated time of placing the sprayed concrete. Aged material shall be discarded.

d) Batching and mixing equipment shall be cleaned at least once per shift to prevent accumulations of aged material.

e) The addition of steel fibres shall be at a stage in the mixing suitable for the sprayed concreting equipment. The procedure for the addition of steel fibres shall be determined during the Site trials. Fibres shall be added and mixed in a manner to avoid clumping and bending of the fibres. Any fibre clumps in the mix shall be diverted and removed by means of a screen placed over the concrete hopper. Fibres shall be uniformly distributed throughout the mortar matrix without isolated concentrations. Fibres shall not be added to the mix at a rate faster than that at which they can be blended with the other ingredients without forming clumps or balls.

14.5.3.4.10 Placing

a) Sprayed concrete shall not be applied to any surface without the prior inspection and a Notice of No Objection from the Engineer.

b) Preparation of surfaces

- i. Before sprayed concrete is applied, checking and correction of the excavated cross-section profile shall be carried out. The surfaces to which sprayed concrete is to be applied are to be barred down of all large loose material and the area cleaned down of all loose and foreign material with a mixture of water and air applied at high pressure.

- ii. The water inflow shall be controlled over the area on which shotcrete is to be applied such that the surface is not too wet. Where the inflow of groundwater renders the surface too wet for the normal application of sprayed concrete, the surface shall be treated by suitable measures to be proposed by the Contractor and as agreed by the Engineer.
 - iii. All surfaces to receive sprayed concrete shall be moist and free of all traces of dirt, oil, rebound or other deleterious material.
- c) If the design thickness is to be applied in more than one layer, then the previous layer must have developed sufficient strength to support the additional layer(s).
- d) Rebound shall be removed immediately after finishing of each shotcrete application. In particular at horizontal shotcrete connections and at all construction joints the rebound shall be removed, if necessary, by pneumatic hammers, prior to further application of shotcrete.
- e) Under no circumstances rebound material shall be worked back into the construction. The work shall be continuously kept free of rebound material.
- f) Measures to establish the thickness of shotcrete shall be set up by the Contractor and as agreed by the Engineer. These may include visual guides installed prior to shotcreting, holes drilled after completion of shotcreting or a full control by laser scanning.
- g) Curing of the shotcrete shall be performed after application by water spraying or other appropriate measures subject to the agreement of Engineer.

14.5.3.4.11 Operators for sprayed concrete

- a) Only trained and tested operators shall be used for sprayed concreting operations. The Contractor shall satisfy the Engineer that the personnel are capable of doing work of a high standard prior to any sprayed concrete work being undertaken in the Works. For this purpose each nozzleman and backup team shall carry out a series of trial applications in the presence of the Engineer to demonstrate their ability in applying sprayed concrete on vertical and overhead surfaces. Test panels shall be made by each operator. No operator will be approved unless the 28 days compressive strengths of all tests exceed the design strength requirements.
- b) The Engineer may at any time withdraw his Notice of No Objection given to the Contractor's personnel if the quality of sprayed concrete applied falls below the acceptable standard.

14.5.3.4.12 Initial Testing

- a) For the first 50 m² of sprayed concrete applied in each shift, test panels shall be prepared and tested. Initial testing of shotcrete shall consist of one test panel for every 10 m² of sprayed concrete applied. The test panels shall be prepared by the nozzleman doing the work during normal sprayed concrete operations.
- b) The test panels shall be made by spraying into moulds 750mm x 750mm x 150mm deep with sides splayed outwards at 45° to prevent entrapment of rebound. Panels shall be made for each mix and position sprayed (that is overhead, vertical, or downward) by fixing the moulds

to the surface being sprayed. Panels shall be clearly marked to identify the time and date of spraying, and the area where they were sprayed.

14.5.3.4.13 Acceptance for Initial and routine testing of sprayed concrete (shotcrete)

Prior to commencement of spraying concrete in the Works and also during the actual shotcreting works at site, testing shall be carried out by the Contractor as detailed below.

- a) Test panels shall be sprayed for each design mix and for each position of spraying required in the Works such as downward, vertical and overhead positions.
- b) Cores shall be cut from these panels and 3 cores tested for each strength requirement (8 hours, 24 hours and 28 days).
- c) The average of the 3 results tested at 8 hours, 24 hours, and 28 days age shall be not less than the 8 hours, 24 hours, and 28 days required strengths respectively. In addition, the value of each core tested shall be within 20 % of the average value.
- d) Sufficient tests shall be done to prove the acceptability of the sprayed concrete to meet the requirements with regard to:
 - Compressive strength at 8 hours, 24 hours and 28 days (as per the relevant standards)
 - Boiled absorption (as per ASTM C 642)
 - Volume of permeable voids (as per ASTM C 642)
 - Setting time; initial and final (as per the relevant standards)
- e) For this purpose the Contractor shall prepare and submit a test plan specifying the tests, test procedures , test frequencies and results to be obtained for acceptance and routine testing of shotcrete for obtaining a Notice of No Objection from the Engineer.

14.5.3.5 Rockbolts and dowels

14.5.3.5.1 General

For the purpose of this Specification rockbolts and dowels are defined as follows :

“**Rockbolt**” is a high yield deformed bar, or glass fibre reinforced resin rod, of specified diameter and length (in rock) which is end anchored with resin grout, fully column bonded with resin or cement grout, equipped with a faceplate, hemispherical washer and nut and tensioned to a specified load;

“**Dowel**” is a high yield deformed bar, or glass fibre reinforced resin rod, of specified diameter and length (in rock), which is fully grouted with either resin or cement grout. Dowels will not be fitted with accessories nor will they be tensioned.

14.5.3.5.2 Materials

- a) Rockbolts and dowels shall be manufactured from hot rolled deformed bars with a minimum steel grade of Fe 415, with the exception of areas to be excavated subsequently where glass fibre reinforced resin rods shall be used.

- b) Face plates, hemispherical washers and nuts for rockbolts shall be manufactured to suit the loading requirements.
- c) Resin grout shall be a commercially produced epoxy product in capsule form with both fast and slow setting times as applicable especially formulated for use with rockbolts or dowels, and transported, stored and utilised in accordance with the manufacturer's recommendations.
- d) Cement grout shall be a commercially prepared product in capsule form especially produced for use with rockbolts or dowels. The product shall not contain any material which could corrode the rockbolts or dowels.
- e) Alternatively, where a pumped cement grout is used for the installation of rockbolts or dowels, the materials shall comply with the requirements of the relevant Standards.

14.5.3.5.3 Manufacture of Rockbolts

- a) Rockbolts shall be manufactured from high yield deformed bar of appropriate diameter. The bar length shall be the required length of bar to be bonded to the rock with a due extra allowance for the cutting length including the threaded portion protruding from the rock as required for installation. One end shall be threaded with a coarse cut thread which shall not reduce the overall specified bar diameter by more than 3 mm. The other end shall be chamfered to facilitate installation.
- b) Face plates shall be of adequate size and thickness with a centralised slot to suit the dimensions of the rockbolts.

14.5.3.5.4 Manufacture of dowels

- a) Dowels shall be manufactured from high yield deformed bar, with the exception of areas to be excavated subsequently where glass fibre reinforced resin rods shall be used.
- b) Dowels shall be either straight bars or shall have the protruding end bent to facilitate the specified connection between the rock and surrounding concrete or sprayed concrete when so required.
- c) Dowels for installation with resin or cement cartridges shall be threaded at one end sufficiently for attachment of the installation equipment. The other end shall be chamfered to facilitate installation.

14.5.3.5.5 Testing of rockbolts

- a) Prior to installation of rockbolts in the Works, the Contractor shall carry out a series of tests as agreed with the Engineer to prove the efficacy of the system and the Contractor's capability to correctly install and tension the rockbolts.
- b) The tests shall demonstrate:
 - Number of resin cartridges required to provide the end anchorage with an applied load equal to the bar's characteristic strength and taking into account the over-length variation of holes.

- Number of resin or cement cartridges to fill the annulus around the rockbolt or dowel over the length of the hole between the anchorage and collar of the hole.
 - Strength of the resin grout to fully anchor the bars up to the characteristic strength of the rockbolts.
 - Capacity of the equipment to install the longest fully grouted rockbolts or dowels.
 - Equipment for tensioning the bolts to the specified loads.
 - Capability of each crew to correctly install and tension the rockbolts.
- c) The Contractor shall undertake the tests with the equipment to be used in the Works.
- d) The Contractor shall provide a suitably calibrated direct tensioning jack and/or load cell of capacities in excess of the characteristic strength of the rockbolts. Loads and bolt elongations shall be recorded during the tests.

14.5.3.5.6 Installation of rockbolts

- (1) The method of installation and tensioning of bolts must have a Notice of No Objection from the Engineer prior to commencement. Manufacturer's instructions for the use of proprietary components shall be followed wherever appropriate.
- (2) Unless otherwise proven acceptable by site trials, the rockbolts shall be installed in holes of diameter 10 mm to 15 mm greater than the maximum diameter of the rockbolt. The holes shall not be more than 100 mm longer than the grouted length of the rockbolt unless otherwise proven acceptable by site trials. A sufficient number of cartridges shall be used to ensure the annulus around the rockbolt is completely filled over the full length of the hole.
- (3) The effectiveness of the rockbolt installation during tunnel driving shall be checked by testing a minimum of 1 per 100 installed bolts to a load corresponding to 80% of yield load. Should the assemblies fail at tensions less than 80% of the yield load of the bolt, the Contractor shall investigate the cause and take such remedial measures as may be necessary. Tests shall continue thereafter at a rate of 1 per 50 bolts until the Engineer is satisfied that the cause of failure has been identified and adequately addressed.
- (4) Regular calibration of tensioning devices shall be carried out by the Contractor.

14.5.3.5.7 Installation of dowels

- a) The method of installation of dowels shall have a Notice of No Objection from the Engineer prior to commencement. Manufacturer's instructions for the use of proprietary components shall be followed wherever appropriate.
- b) Holes of diameter 10mm to 15mm greater than the maximum diameter of the dowel shall be drilled and cleaned. The gauged amount of pumped cement grout or cartridges of resin/ cement grout shall then be inserted and the bar driven firmly into the hole. If pumped cement grout is used, the grout shall be inserted using a tremmie pipe pushed down to the bottom of the hole and withdrawn slowly as the grout is placed. After installation the bar shall be vibrated for a short period to ensure the complete distribution of the grout around the full length of the bar. Additional grout shall be added to make up any shortfall. Where required,

grouting of the hole shall be carried out in stages to allow the flow of grout into cavities, each stage being topped up by the following stage.

14.5.3.5.8 Records

For each rockbolt or dowel installed the following information shall be recorded:

- reference number;
- type of installation;
- name of person taking record;
- date of drilling and installation;
- length and orientation of the drilled hole;
- length of installed rockbolt or dowel;
- tension applied to the rockbolt
- details of any tests carried out.

14.5.3.6 Lattice Girders

14.5.3.6.1 General

- a) This sub-section applies to the supply and installation of the lattice girders required and used as support in underground excavations.
- b) The Contractor shall be solely responsible for the design and manufacture of lattice girders.

14.5.3.6.2 General Requirements

- a) Lattice Girders shall be effective as initial support immediately after excavation and shall subsequently act as reinforcement and load distributing members for the initial shotcrete lining.
- b) The lattice girders shall be manufactured to meet the geometrical requirements for the excavation geometries including the construction tolerances for each rock class.
- c) During transport, storage and handling of lattice girders, adequate measures shall be taken by the Contractor to prevent their bending, scraping, overstressing or any other damage. The damaged pieces shall not be used in the works.

14.5.3.6.3 Submission

Shop Drawings for the fabrication of the lattice girders shall be submitted for Notice of No Objection from the Engineer prior to the commencement of the work.

The submission shall comprise the following:

- Complete fabrication details of the lattice girders.
- Installation procedures and layout.
- Details of joints, connections, spacers, geometry etc.
- Certificates of compliance for the materials.

14.5.3.6.4 Design of Lattice Girders

- a) Lattice girders are three dimensional, lightweight steel frames manufactured of round or corrugated steel bars in compliance with the required excavation geometry of the tunnel.
- b) Lattice girders shall consist of three primary bars, connected by stiffening elements as per the design. They shall be designed so as to:
 - i. Facilitate shotcrete penetration into and behind the girder, thereby minimizing the creation of projection shadows.
 - ii. Provide good quality bonding between the steel and shotcrete, to form a composite structure in the sense of a continuous reinforced shotcrete lining.
- c) A minimum 5% of the total moment of inertia shall be provided by the stiffening elements. This percentage is calculated as an average value along repeatable lengths of the lattice girder.
- d) To ensure stability against buckling, the maximum spacing between stiffening elements shall be less than three times the cross sectional height of the girder.
- e) In case of fabrication on site, the Contractor shall submit a detailed method statement for obtaining a Notice of No Objection from the Engineer.
- f) The Contractor shall submit related detailed drawings of the lattice girders, showing also the number of sections in the frame and details of the connection between the sections. The details with appropriate calculation shall be submitted to the Engineer for obtaining a Notice of No Objection.

14.5.3.6.5 Materials

- a) Each of the primary bars of a lattice girder segment shall be composed of only one piece of high strength steel having yield strength of 500 MPa or more.
- b) The connection elements at the end of lattice girder segments shall be constructed of angled structural steel having yield strength of 250 MPa or more, or of welded flat steel ensuring similar strength characteristics.

14.5.3.6.6 Manufacturing of Lattice Girders

- a) Geometry

The lattice girders shall be fabricated to meet the minimum clearances duly taking into account the permissible inaccuracy of placement during construction and the permissible material tolerances.

- b) Welding of Lattice Girders
 - i. Testing of materials and workmanship shall be carried out in accordance with AWS D1.4. A third party testing agency shall be employed by the Contractor to carry out the tests.
 - ii. The manual metal-arc welding process shall be employed. The Contractor shall be responsible for ensuring that the capacity of the welding plant and ancillary equipment is

- adequate for the welding procedure to be used and for maintaining all welding plant and ancillary equipment in good working order.
- iii. Covered electrodes complying with German Standard DIN 1913 shall be used. Electrodes shall be selected with regard to the particular application (welding position, joint design etc). Electrodes shall be stored in their original containers in a dry, preferably heated place, adequately protected from the effects of the weather and in accordance with the Manufacturer's Specifications.
 - iv. Surfaces to be welded shall be dry. Fusion faces and the surrounding surfaces shall be free from heavy scale, moisture oil, paint or any other substance which might affect the quality of the weld. Slag shall be removed from each run of weld metal before a further run is superimposed. The most favourable welding position for each case shall be chosen.
 - v. For the cutting of the steel profiles the manual flame cutting process may be employed. Sawing will also be permitted.
 - vi. Further preparation of joint and fusion faces shall be done by grinding.
 - vii. Parts to be welded shall be assembled such that the joints are easily accessible and visible to the operator.
 - viii. Slag shall be removed from all welds in order to allow visual inspection.
 - ix. Welding operations shall be supervised by a suitably trained supervisor who shall have particular production experience.

14.5.3.6.7 Installation of Lattice Girders

- a) Lattice girder shall be installed to conform to the excavated shape. The geometry of Lattice Girders shall take into account the permissible inaccuracy of construction and tolerances of materials.
- b) Lattice girders shall be erected to the lines and levels as required. The exact excavation levels will be determined by the Contractor suiting his equipment and construction method subject to a Notice of No Objection by the Engineer.
- c) Lattice girders shall be secured by use of spacers as well as temporary wood blocking or other appropriate means to maintain position during shotcreting.
- d) Butt plates for steel girder segments and expansion unit in invert shall be provided as required. Tight connection of all elements shall be ensured such that the static efficiency of the cross section is maintained.
- e) Lattice girders shall be embedded in shotcrete, in order to get contact between rock and lattice girder by a solid shotcrete packing which shall have a minimum cover to steel of 20 mm.
- f) The lattice girders shall be erected perpendicular to the tunnel axis.

14.5.3.7 Forepoling

14.5.3.7.1 General

Forepoling is a pre-excavation support element that may be required for tunnel excavation works. Forepoling shall be applied in rock and soil conditions, which tend to produce overbreak, collapses or material inflows immediately following excavation. Forepoling may be applied locally or systematically as per the requirement for the safety of the works and to prevent overbreaking. All forepolings must be fully grouted.

14.5.3.7.2 Material

- a) In case Boreholes are stable Steel pipes with a minimum outer diameter of 40 mm shall be used. Wall thicknesses of steel pipes shall not be less than 4 mm. Dowels (spiles) consisting of deformed high yield steel bars of grade Fe 500 with a minimum diameter of 32 mm may also be used instead of steel pipes, where found suitable.
- b) In case Boreholes are not stable Self-drilling bolts shall be used as forepoling elements where stability of the predrilled boreholes cannot be achieved, due to the encountered ground conditions. Self-drilling bolts shall be installed only if permitted by the Engineer and shall have a yield load of at least 200 KN. The grout used for self-drilling bolts shall be in accordance with the requirements specified by the bolt manufacturer. Grouting shall be carried out simultaneously with drilling to achieve a better grouting effect along the bolt.

14.5.3.7.3 Installation

- a) Forepoling shall be applied as shown on the drawings that have a Notice of No Objection from the Engineer.
- b) Forepoling elements at 300 to 500 mm centres shall be inserted into the predrilled holes (steel pipes or dowels) at the face or drilled into the face (selfdrilling bolts) towards the unexcavated ground.
- c) The length of forepoling elements shall be according to the design and drawings and shall be at least 1.50 meter longer than the excavation round length.
- d) Forepoling shall be used together with lattice girders or any other steel support system.
- e) Grouting of forepoling pipes and dowels shall be done with cement mortar, either before or after their insertion, as per the approved scheme.
- f) Forepoling shall be required to be properly supported by the lattice girder/steel sets and the shotcrete above the lattice girder/steel sets. Therefore, shotcreting of the gap between lattice girder/steel sets and rock in the portions of forepoling shall be completed only after the installation of forepoling.

14.5.3.7.4 Pipe Roof

A pipe roof is a special type of long forepoling (typically 9 – 15 m). The forepoling elements shall consist of steel pipes with a minimum outer diameter of 76 mm and a minimum yield

load of 1200 KN. The length and spacing of the pipes shall be as per the design and drawings and as agreed by the Engineer. The pipes shall be grouted with cement mortar.

14.5.4 Tunnel Permanent Lining

a) Concrete lining

The Contractor shall design concrete linings to meet the requirements of the specifications pertaining to concrete. Adequate measures shall be taken to prevent permeability, corrosion, alkali silica reaction, heaving, stray current and thermal cracking. To achieve durability in permanent concrete lining, micro silica shall be used in such proportion that shall satisfy the specified requirements.

b) Preparation of surfaces

The surface against which concrete is to be placed shall be cleaned of loose material and dirt. A waterproof membrane shall be placed. No concreting shall take place before the Engineer has inspected the surfaces which are to receive concrete.

c) Placing of concrete

Concrete shall be placed so that the space between the form and the ground/excavated profile is filled as completely as possible, especially any voids in the crown of arches. Not sooner than 28 days strength obtained after placing concrete, the interface between the concrete and the rock in the crown shall be contact grouted as directed by the Engineer.

d) Testing of concrete

Testing of samples shall be performed as set out in the specification pertaining to concrete.

14.5.5 Grouting

a) Definitions

- i. The term 'cavity grouting' shall mean the grouting required to fill the cavities or voids between the excavated profile and the permanent linings to the underground works, including voids due to ground relaxation, and/or the void between the permanent and temporary linings. Cavity grouting shall generally be carried out in two stages, primary and secondary grouting.
- ii. 'Primary grouting' refers to the initial cavity grouting which takes place immediately after the ring has been built, or in the case of a shield drive, during or on completion of the shield shove.
- iii. Primary grouting will be an initial void filler and be to a pressure of not more than 1 bar above the surrounding hydrostatic pressure.
- iv. 'Secondary grouting' refers to the subsequent re-grouting of rings. This shall be completed as soon as is practicable, but within 14 days of the ring build or 50 metres from the leading segment, whichever is more critical. Secondary grouting shall be at a pressure not greater than 6 bars, consistent with completely filling all voids.

b) Method

Prior to commencement, the Contractor shall submit proposals for cavity grouting and obtain the 'Notice of No Objection' from the Engineer. The proposals shall include details and location of the mixing plant and grout pump(s), mix design and constituents, pumping rates and pressures, injection points, the methods of monitoring, recording and controlling the

sequence and timing of grouting, the method of preventing grout leakage, and details of the relevant experience of the personnel and supervisors.

c) Mix

- i. The grout shall be a mixture of Ordinary Portland Cement and water with a water/cement ratio as approved by the Engineer in compliance to the design mix requirement appropriate to the circumstances. PFA, GGBS or additives such as plasticisers or non-shrink agents excepting those containing calcium chloride may also be proposed.
- ii. The grout shall be colloidal and the grout mixer shall be positioned near to the point of injection. The grout shall be sufficiently fluid to ensure that it flows freely into all parts of the cavities to be filled.
- iii. Other grouts compatible with the Contractor's tail seal system may be proposed.

d) Injection

- i. In soft ground, the grout shall be injected, continuously as the tunnelling machine moves forward through pipelines embedded within the shield tail skin, by positive displacement pumping. The Contractor shall ensure that grouting pressures used are consistent with his proposals and shall adopt appropriate methods and procedures for controlling and monitoring the process.
- ii. Cavity grouting to segmentally lined tunnels in rock shall proceed from an injection point in the tunnel invert and shall continue in such a manner that air and excess water are expelled from the cavity progressively ahead of grouting. Stopcocks may be used in order to allow the grout hose to be disconnected, so that the grout can be maintained under pressure until it has set. After the grout has set the stopcocks if used shall be replaced by the permanent plugs as a separate operation.
- iii. The Contractor shall ensure that the sealing material adopted at the leading edge of the ring shall prevent grout loss. Rings shall be restrained by packing or other means to prevent distortion or flotation, whilst allowing the free flow of grout in the void. The Contractor shall ensure that the sealing material remains clear of the leading edge and grout holes. The sealing material shall be removed upon completion of the cavity grouting.

e) Grout Plugs

Upon completion of grouting, all grout plugs shall be greased and shall be fully tightened into the segment. Hydrophilic 'O' rings shall be provided at all grout plugs.

f) Records

The Contractor shall record at each stage of the grouting process the quantity and type of grout and the pressure applied at each injection point. Grouting records shall be kept in the Contractor's offices and be available for inspection by the Employer.

g) Monitoring Pressures

The Contractor shall monitor secondary grouting pressures and quantities to ensure that grouting does not damage the Works or third party utilities or structures.

h) Caulking

Where caulking is specified it shall be carried out after completion of primary and secondary grouting.

i) In-situ Linings and Junctions

- i. All voids remaining unfilled outside the in-situ concrete permanent linings in tunnels, including junctions, headwalls and the like, shall be grouted as specified. For this purpose the grout shall be injected through pipes set in the concrete, through drilled holes, or, where appropriate, through grout holes in segmental linings or temporary supports. Drilled holes shall not be used where there is a possibility that damage to the Permanent Works could result, for example in puncturing of waterproofing membranes.
- ii. Where grout is to be placed in voids occurring within the design thickness of linings the grout shall have a characteristic strength equal to the required characteristic strength of the linings.
- iii. Injection points used for cavity grouting shall be provided at least one per 2.0 linear metres of tunnel and more frequently in any areas of excessive overbreak. The injection points for cavity grouting in arched roofs shall be located within 500 mm of the crown. The injection points for grouting of shafts shall be determined to ensure complete filling of the cavities.
- iv. Grout pipes set in concrete shall be fitted with means of preventing blockage and, before injecting grout, they shall be drilled or pricked through to provide a clear passage for grout. Grout pipes and grout holes for grouting shall be at least 40 mm diameter.
- v. The grouting of the upper surface of concrete works in junctions and the like shall be carried out through a series of grout pipes and vent pipes built into the concrete for the purpose and extending to the highest part of the excavation. The number and locations of pipes shall be determined to suit temporary ground supports left in place, sufficient to ensure that cavities are completely filled.
- vi. The grouting of the upper surface of concrete works shall be continued until the grout emerging from the vent holes or adjacent grout holes is of the same consistency as the grout being injected. No vented grout shall be re-injected.
- vii. Where in situ concrete tunnel linings are backed by a waterproofing membrane or a protective geotextile the grouting pressure shall not exceed 2 bars.
- viii. Grout and vent pipes shall not be permitted to remain within 50 mm of a finished concrete internal surface and, when no longer required, all holes in concrete linings shall be cleaned and filled with a consented-to polymer modified non-shrink mortar.

j) Performance

The minimum strength requirement for the grout as measured from testing 100 mm cubes at 24 hours shall be 1.5N/mm². The Contractor shall carry out his grouting operations consistent with his method statement and with due cognisance of the ground conditions at the time.

Setting times must be verified at Site with the aim of minimising ground movement and floating of the tunnel lining.

k) Verification

- i. The Engineer may require proof drilling to be carried out in the crowns of tunnels and/or elsewhere at suitable locations and frequencies depending on site observations. All voids encountered shall be fully grouted, and all drill holes filled

using approved grout mix with or without accelerators or non-shrink materials, as applicable with prior approval of the Engineer.

- ii. In the event that the cavities are not filled or the specification for watertightness is not achieved after secondary grouting, further grouting through additional injection points shall be carried out at contractor's cost. Re-grouting and the further grouting shall be continued until a consented-to grouting pressure of up to 6 bars can be sustained for 1 minute. This pressure shall be dependent upon the overburden and the presence of adjacent structures.

14.5.6 Watertightness of Tunnel & Cross Passage

14.5.6.1 General

a) Submission, Requirements, Method Statements and Working Drawings

The Contractor shall include details of his intended waterproofing methods in his design submissions for acceptance of the Engineer.

Manufacturer's literature shall be provided where necessary to confirm the suitability of the proposed details.

The Contractor shall produce and submit comprehensive Working Drawings showing all details and procedures for waterproofing of the Works.

b) Waterproofing Application

Waterproofing material shall be installed only by the manufacturer of the products or his approved applicator. The Contractor shall submit a method statement, prepared in conjunction with the applicator and endorsed by the manufacturer of the material, describing the details of the waterproofing works including protective measures at all stages.

14.5.6.2 Cross Passage

- (a) The watertightness of the tunnels including cross passages as completed is to be as per the specifications.
- (b) The defence against leakage into the Works shall be provided by the cavity grouting, the two sealing strips incorporated into the tunnel rings and as a final measure, grouting and caulking.
- (c) For cross passage works the water proofing (synthetic membrane lining) shall be as shown in tender drawing. The contractor shall submit a comprehensive method statement & construction sequence along with detail working drawing for the approval of Engineer before start of work. The method statement shall include all QA/QC procedures required to ensure the integrity of the system. Proposed manufacturers and applicators should have similar experience on previous metro projects in india.
- (d) All waterproofing systems shall be warranted for a minimum period of 10 years from the date of completion of the works against all defects. The warranties shall cover the whole of the waterproofing systems and shall be given jointly and severally by the contractor, and the supplier/applicator.

14.5.7 Steel Fibre Reinforced Concrete (SFRC) for Precast Tunnel Segmental Linings

These specifications shall be read in conjunction with the international journals fib Bulletins 83-v13, FIB ModelCodeForConcreteStructures_2010 , EN-14651and the document on

Guidelines for application of Steel Fibre Reinforced Concrete in Tunnel Segmental Lining issued by DMRC attached as Annexure-A of these specifications.

14.5.7.1 Steel Fibres:

- a. Fibres shall be produced from high tensile steel cold drawn wires conforming to EN 14889-1: Fibres for concrete - Part 1: Steel Fibres - Definitions, specifications and conformity.
- b. Fibre must carry CE label marking, system 1 (Fibres for structural use) along with DOP (Declaration of performance) and a minimum performance dosage.
- c. The length of the fibre shall be 60 mm and its diameter shall be 0.75 mm with minimum CE Level dosage of fibres.
- d. The nominal tensile strength of the fibres shall be minimum 2200 MPa with a tolerance of 7.5% as per EN14889-1
- e. Fibres shall be so manufactured to ensure development of optimal anchorage in the concrete matrix by way of hooked ends.
- f. Steel fibres shall be glued together with a water-soluble glue to prevent balling and to ensure good homogenous distribution in the concrete.
- g. The dosage of steel fibres in the concrete matrix shall be 45 kg/cum.

14.5.7.2 Dosing & Mixing of Steel Fibres:

- a. Steel fibres shall be added during concrete batching at the batching plant.
- b. Steel fibres shall not be added into the mixer of ready-mix trucks.
- c. Steel fibres shall be added to the batching plant mixer as per the steel fibre supplier's recommendation.
- d. Steel fibres shall be added via a fully automatic fibre dosing machine. The fibre dosing machine shall have a weighing/control system which integrates with a mixing computer. The fibre dosing machine shall achieve a weighing accuracy of $\pm 1.0\%$. The dosing capacity of the fibre dosing machine shall be compatible with the type of steel fibre, dosage of steel fibre and rate of concrete production. The fibre dosing machine shall be calibrated by an independent accredited agency at a frequency not longer than every six (6) months, subject to the Engineer's acceptance.

14.5.7.3 Concrete Grade M50 for Precast Tunnel Segmental Linings

- a. Fibre reinforced Concrete Grade C40/50
Cylindrical compressive strength- 40MPa
Cube compressive strength- 50MPa
- b. Performance Class of FRC as per fibmodel code 2010- 5d
- c. Steel Fibre Specifications- CE certified product conforming to ASTM A820, EN 14889-1 and ISO 13270 with min. 2200 Mpa tensile strength, min. 200 Gpa Young's modulus, and aspect ratio 80

- d. Residual flexural tensile strength for service load, f_{r1k} – minimum 5 Mpa
- e. Residual strength ratio- $f_{r3k} / f_{r1k} > 1.1$

Where, f_{r3k} – Residual flexural tensile strength for ultimate load

14.5.7.4 Test to be performed

Apart from the concrete tests mentioned in the Section S.03 of the OCS, additional test to be performed on SFRC:

a) Check on Fibre properties according to EN 14889-1


The length of the fibres is measured using a Vernier Caliper and the diameter is measured using a screw gauge. 30 randomly picked samples of the batch are checked for their dimensional properties.

b) Fibre Wash out test in accordance with EN 14721

Glued steel fibres tend to disperse homogenously in the concrete matrix thereby preventing “balling” and providing the desired properties to the matrix in an assured manner. The homogeneity of fibre dosage shall be typically checked on samples obtained from fresh concrete. The test methods are based on EN14721. It is recommended that the number of samples shall be at least 6, each with a volume of at least 10 litres for a batch of 5 cubic metres. Each fresh concrete sample shall be placed over a 5 mm sieve and washed with water to remove the fine contents. From the remaining mass of aggregates and fibres, the fibres are to be separated manually, dried and weighed. The average weight of fibres obtained is used to determine the nominal fibre dosage, which shall not be less than 90% of the specified fibre dosage. A magnet or an electromagnet may be used to extract the fibres from the mix.

c) Flexural toughness test in accordance with EN-14651

Flexural toughness test shall (Notch Beam Test) be done according to EN 14651 to get the LOP (Limit of Proportionality), f_{r1k} , f_{r3k} values.



Typical Load deformation Diagram

14.6 INVERT CONCRETE

The Contractor shall prepare the upper surface of the first stage concrete to meet the requirements of Track bed design specification. The minimum grade of concrete for primary/invert concrete shall be M-25 or as specified in GFC drawings whichever is higher.

14.7 FIELD CONTROL AND MONITORING EQUIPMENT

14.7.1 Setting out of line, level and profile

Prior to starting underground work, the Contractor shall submit to the Engineer proposals on the setting out the Works and for correcting any deviations.

14.7.2 Chainage markers and Bench marks.

Chainage markers shall be provided in tunnels at 10m intervals. The markers shall be painted in white durable paint. The contractor shall provide the Engineer the location and description of all survey stations, and all survey data.

14.7.3 Monitoring Equipment

The Contractor shall provide basic equipment for measurement of deformations along excavation perimeters and ground surface conditions. The types of basic underground equipment to be provided comprise: levelling instruments, wire extensometer for convergence measurement and bore hole extensometer. The equipment shall be installed where directed by the Engineer.

During the execution of excavation works, the Contractor need to procure supplementary types of equipment as may be required for standard tunnelling methods.

Measurements by all types of equipment shall be performed by the Contractor as directed by the Engineer. Results from each measurement shall be submitted to the Engineer expeditiously.

14.7.4 Backfilling of Shafts and Adits

Temporary shafts and adits shall be completely backfilled on completion of the Works. Backfill material shall be Grade M10 concrete covering 2m over the tunnel crown which may be placed either wet or dry. Adits shall be backfilled in sections working from the permanent Works.

Temporary bulkheads shall be formed at agreed intervals and the upper part of the adit completely filled by grouting through pipes which have been installed into the adit roof. The bulkhead shall be moved back in stages until the whole of the adit is backfilled. Shafts shall be backfilled in layers not thicker than 250mm, each layer being thoroughly compacted with an appropriate power rammer. The backfill material shall be homogenous, no large pieces of concrete or "plums" shall be used. As far as practicable all extraneous materials such as steelwork and temporary timbers shall be removed as the backfilling progresses. Shaft linings shall be dismantled to two metres below finished ground level and the site reinstated with suitable granular material compacted as specified in Earthworks. Details of temporary works left in place shall be included in the as-built information and drawings.

14.7.5 Geological Record

During excavation of the Works the Contractor shall compile a detailed and continuous geological record with photographs and cross-sections where appropriate. On completion of sections of tunnel the Contractor shall correlate all data into a Geological Report, in a form acceptable to the Employer. The Report shall include details of temporary supports built into the Works, the location and types of ground treatment and be issued to the Employer in triplicate. The timing of the submission of the Geological Report shall be in accordance with that for other submission of as-built information.

14.8 DAILY RECORDS

14.8.1 Daily Records

Daily records shall be maintained in the Contractor's site office where they shall be available for inspection by the Employer prior to submittal.

The Contractor shall keep records of:

- (a) Cycle time of each round of excavation, including location, bore hole diameters and lengths, drilling, charging, firing patterns and blast vibration records.
- (b) Rock stabilisation arrangements, including location, position, type and dimension of rock bolts, spray concrete, concrete, steel sets, etc.
- (c) Drainage arrangements including location, inflow rate, grout holes and grout take, etc.
- (d) The results of compressive strength tests of cores extracted from spray concrete, pull out tests on rock bolts, etc.
- (e) Relevant data pertaining to structural concrete and other ancillary work described in other Sections of this specification.
- (f) Details of linings erected.
- (g) Details of shotcreting and grouting done.

All the records shall be kept up-to-date and shall be made available immediately for the Engineer's inspection on request. The original records shall be kept at the Contractor's office. The Contractor shall furnish the Engineer with a copy of the records each day covering the

progress achieved during the previous day where work is being performed.

14.8.2 Other Records

The Contractor shall, on a daily basis, provide the Engineer with documentation in the form of geological maps and photographs showing the pertinent geological features as observed at excavations.

Similarly, the Contractor shall provide the Engineer with documentation recording the excavation's adherence to line, level and profile over break or under break, and instrumentation record for existing tunnel structures

14.8.3 Safety and Underground Facilities

14.8.3.1 Safety General

At an early stage of the work, the Contractor shall undertake the organisation, equipping and training of rescue teams. These teams shall be trained in underground rescue work and the administration of first aid.

No workmen shall be employed underground until they have shown themselves conversant with basic safety precautions. The Contractor shall strictly enforce all safety regulations and shall provide adequate protective clothing and safety gear for his workmen. The contractor shall evolve a entry/exit tally board system with the approval of engineer for restricted entry into tunnel during construction & interface period.

The Contractor shall observe all precautions to avoid accidents or injury to Workmen or the Works and to minimise the extent and severity of any accident or injury which may occur. Such precautions shall have due regard to the skill and training of the labour force employed underground and shall comply with local mining or other applicable regulations.

The Contractor shall be solely responsible for day and night warning systems (visual and sound) for machine operations and "clear off the track" warning shall be installed at the site and preventative measures taken against accident.

14.8.3.2 Underground Facilities

a) General

The Contractor shall submit descriptions of the installations he proposes to use for supply of water, ventilated air, compressed air, lighting, power supply, etc., and for the disposal of drainage and waste water, contaminated air, etc., for the approval of the Engineer in advance of starting underground works.

b) Telephone Communications

Telephone communications shall normally be provided between the working faces, portals and other areas where work is going on. Telephone locations shall be prominently displayed & shall meet BOCW requirements

Telephone network should be provided for Engineer's office including telephone connection to the work's place and tunnel shafts.

c) Electric Cables

All lighting and power cables installed underground shall be adequately insulate with joints made in an approved manner. All installation and maintenance work shall be done by qualified personnel to a high standard. Cables shall be securely fixed above floor level with the exception of cables needed for occasional work.

Separate circuits breaker systems shall be provided for the supply of power for equipment and for lighting, respectively, and they shall be kept well separated from signalling and telephone cables.

Circuits used for firing explosives shall be kept separate from all other circuits by placing them on the opposite wall.

All electric installations shall be adequately earthed in accordance with normal practice and local requirements and be approved by the Engineer. Installations shall furthermore be protected by earth-fault breakers, all in accordance with modern practice and safety standards and approved by Engineer.

d) Ventilation system

The underground ventilation system shall be capable of serving all areas where work is going on. After installation, the ventilation ducts shall be checked at regular intervals and any damage which might decrease their efficiency shall immediately be repaired. Spare ducts and spare ventilators shall be available on Site for this purpose.

The ventilation system shall be designed such that the temperature at the working face does not exceed 32 °C.

Diesel /Battery engines working underground shall be regularly checked and kept well adjusted so that all harmful substances in the exhaust gases and smoke are kept to the minimum. Petrol engines shall not be permitted underground.

The Contractor shall perform daily measurements of gas pollution underground in order to detect at an early stage the presence of carbon monoxide, nitrogen dioxide, methane and other harmful or explosive gases. In doing so, the Contractor shall ensure that pollution percentages including that resulting from dust are kept within acceptable limits according to internationally recognised standards. The results of measurements shall be recorded and submitted to the Engineer.

Satisfactory ventilation shall be maintained as long as any work is carried out underground and no part of any ventilation system shall be dismantled and removed without the permission of the Engineer.

e) Lighting

All underground areas where work is going on shall be illuminated with electric lights of adequate strength and number to allow work, inspection, mapping and surveying to be carried out in a proper and safe manner.

Generally, the illumination on a horizontal plane at floor level shall be not less than 10 lux. At working faces, the illumination shall be not less than 50 lux. Hand inspection lamps and electric battery torches shall be available at working faces at all times, together with emergency back up light for evacuation.

f) Dewatering

The Contractor shall keep all underground areas substantially free from water by providing drains, ditches, pipes, pumps, sumps, etc. to drain water away. The Contractor shall submit to the Engineer details of his proposals for dealing with water from any source prior to commencing underground work.

In the event that gravity flow cannot be satisfactorily arranged, the Contractor shall remove the water by pumping and he shall provide, install, operate and maintain all necessary pumps,

pipings and other equipment required. The Contractor shall also provide sufficient numbers of standby pumps and generator to serve during periods of breakdown or maintenance.

Where water bearing seams, fissures or broken ground are yielding undesirably large quantities of water, the Contractor shall grout such seams, fissures or broken ground to stem the same.

The Contractor shall provide devices for measuring the quantities of water removed from underground excavations, by pumping or by gravity as the case may be. The Contractor shall provide certified calibration charts for all measuring devices and shall submit to the Engineer a complete record of the quantities of water disposed either by pumping or by gravity and the times during which pumping has occurred.

The Contractor shall provide water treatment facilities for wastewater disposal that satisfies the stated environmental standards.

g) Stand-by Generator

The Contractor shall provide Stand-by generator for emergency case, details of proposals for this systems shall be submitted to the Engineer.

14.9 TUNNEL BORING MACHINES (TBM)

14.9.1 General

- a) The Contractor shall be fully responsible for the selection, design and supply of shield machines and ancillary equipment.
- b) The Contractor shall take into consideration the geological investigation data given in the tender and as per subsequent geotechnical investigation done by the contractor as per tender conditions and other relevant parameters/ provisions applicable for the contract. He shall satisfy himself as to the suitability of the TBM shield machines which he will provide.
- c) The Contractor shall make all arrangements and provide all the labour, plant, equipment and materials necessary for receiving the TBM at the launch sites. The Contractor shall co-ordinate the required delivery arrangements with the manufacturer suiting the site constraints.
- d) The Contractor shall be responsible, under the supervision of the TBM Manufacturer, for the erection and commissioning of the TBM and all back-up equipment required to allow the TBM to commence excavation in a fully operational condition in all respects and in accordance with the manufacturer's recommendations.
- e) The Contractor shall be responsible for the design and installation of the temporary TBM launch structures and for ensuring they are satisfactory in all respects for receiving and assembling the machine components. The shaft walls (or other structures) and surrounding ground shall have sufficient capacity to sustain without excessive deformation the thrust from the TBM shove-rams during the launch of the TBM.
- f) The Contractor shall be responsible for the design and installation of the temporary/permanent (part of station structure) TBM retrieval structures. The shaft walls (or other structures) and surrounding ground shall have sufficient capacity to sustain without excessive deformation the thrust and torque from the TBM during the breaking-in operations.
- g) The Contractor shall be responsible for the provision of all ancillary structures at the shaft bottoms (for example fixed or moveable cradles to act as a "base" for commencing

machine erection) and for design and configuration of such ancillary structures in co-ordination with the TBM manufacturer.

- h) The detailed TBM design, specifications and characteristics shall be submitted to the Engineer prior to procurement for issuing of Notice of No Objection . However issuing of Notice of No Objection from the Engineer shall not release the Contractor from any of his obligations under the Contract and the contractor shall remain fully responsible for the selection, design and adequacy of TBM machines.

14.9.2 General Requirements for TBMs

- a) All TBMs shall be robust with adequate safety margins for the anticipated duty, designed and manufactured to comply with all relevant safety standards.

The Tunnel Boring Machines shall be either:

- i. New machine; or
- ii. Remanufacturing type

The Remanufacturing type machines shall be as a minimum in accordance with ITAtech Report No.5-V2- "Guidelines on Rebuilds of Machinery for Mechanized Tunnel Excavations". The Refurbishment type machines referred in the above said Report shall not be allowed. The Remanufacturing of TBM shall be done under the full responsibility or with major support of OEM (Original Equipment Manufacturer) OR by an equally experienced alternative manufacturer from the same industry with adequate technical capability including expertise in control software and PLC programming for TBM . All the relevant details of the Remanufacturer regarding experience, technical capability etc is to be submitted beforehand to the Engineer for Scrutiny and issuing of Notice of No Objection. However issuing of Notice of No Objection by the Engineer shall not release the Contractor from any of his obligations under the Contract and the contractor shall remain fully responsible for competence of the remanufacturing agency.

New/ Remanufacture TBM shall be robust with adequate safety margins for the anticipated duty, designed and manufactured to comply with all safety standards as per BS 6164: Safety in tunnelling in the construction industry, BS EN 16191: Tunnelling machinery - Safety requirements and BS EN 12110: Tunnelling machines Air locks safety requirements, Certificate for compliance to the above safety standards shall be submitted by the contractor

- b) The external diameter of the Shield Machines shall be designed to produce minimum over-break and the least necessary clearance for the proper construction of the tunnels. Design shall take into account the horizontal and vertical alignment. Provision shall be made to limit and correct the roll of the machine.
- c) Whenever possible hydraulic piping shall be of rigid metal tubing, the use of flexible hose shall be kept to a minimum. Liquids for use with hydraulic equipment shall be non-toxic and of low flammability. Hydraulic equipment shall be designed to operate up to twice the working pressure but shall not exceed 500 bars.
- d) All machines and shields shall be self propelled. Where propulsion is by means of hydraulic rams thrusting off previously constructed segmental lining, shoveram shoes and shoe-facings shall be designed to distribute the thrust without causing damage to the as-built lining. Shove-ram shoe pads shall be adequately secured.
- e) Shove-rams shall be capable of operating individually or collectively in any combination. The shove-rams shall permit the insertion of a key closing segment, in any location.
- f) Segment erection system shall be capable of lifting and placing segment safely with 6 Degrees of freedom. Lifting and gripping system shall be designed to handle the loads with

- an adequate factor of safety without damaging the segment and segment seating systems. Segment erection system shall be capable of compressing all joint gaskets.
- g) The erector shall be in clear view of the operator. A safety device shall be fitted to avoid accidental release of segments during lifting, handling and placing.
 - h) There shall be adequate access to all areas of the TBM where work, including maintenance, may be carried out. A clear means of egress in an emergency shall be provided and maintained at all times. Minimum dimensions shall conform to the appropriate international standard.
 - i) Arrangements for extraction, transport and disposal of spoil (excavated materials) shall be appropriate for the material to be handled.
 - j) Alignment control
 - i. The Contractor shall ensure the TBM is provided with a suitable guidance and control system in English Language capable of providing the necessary survey information such that the TBM operator is able to accurately control the TBM and tunnel alignment to within the required tolerances.
 - ii. The guidance system shall have the capability to predict ahead of the face and to determine the inclination, line, level, roll and square of the TBM.
 - iii. Detailed guidance information shall be checked against the tunnel alignment control at regular intervals, as agreed with the Engineer.
 - k) All information and data shall be clearly displayed in the TBM operator's control panel and shall also be linked to a data-logging system.

14.9.3 Particular Requirements for TBMs

- a) The cutter-head shall be capable of clockwise and anticlockwise rotation at 3 to 5 RPM and shall only be able to excavate the ground whilst the hydraulic rams are being actuated. The design shall ensure that the cutter-head can be retracted back from the unexcavated ground to minimise the risk of the cutter-head jamming and to facilitate maintenance.
- b) The cutting tools shall incorporate wear detection systems. The cutter-head discs and/or picks shall be able to be renewed from the rear of the cutter-head and shall be interchangeable.
- c) Where boulders could occur on the tunnel face the TBM design shall permit a boulder of at least 300 millimeters across its smallest cross-sectional dimension to be pushed through the cutter-head. The TBM shall have the capability to handle, break up as required and remove such boulders through the screw conveyor, slurry discharge aperture or other spoil discharge system without special procedures.
- d) The TBM shall be designed to allow forward drilling through the cutter-head for the purpose of probing ground conditions and to carry out ground treatment to the face.
- e) Grouting facilities
 - i. The TBM shall be designed to enable the void behind the segments to be grouted continuously and completely from the shield as it is propelled forward. The grout ports shall be incorporated within the shield tail-skin rather than mounted externally on it.
 - ii. There shall be two grout ports (one working and one standby) in each quadrant of the shield tail-skin circumference. The TBM shall have the facility and the capacity to inject grout simultaneously through the grout ports
 - iii. The TBM design shall enable the grout pipes to any individual port to be cleaned or replaced from within the shield in the event of a blockage without impairing the performance or preventing the use of any other grout port. At least

one grout port in each quadrant of the shield shall be operational and available for grouting at all times during shield advancement.

- iv. Grout pressure and flow rates shall be maintained at all times whilst the shield is advancing. The shield shall incorporate automatic systems for monitoring and controlling the volume and pressure of the grout being delivered to the tail void.
- f) The TBM shall be equipped with the facility to generate foam conditioners and deliver them to the face during excavation.
- g) The TBM shall be designed for and equipped with a supplemental ground stabilisation system. This system shall comprise regularly spaced grout ports built into the shield for grouting the ground ahead of the tunnel face. The location and number of ports shall be adequate for implementation of face stabilization measures needed for access to the face in all ground conditions. All ports shall be readily accessible and fitted with valves.
- h) The cutter-head shall be articulated such that the cutter-head can be retracted from the excavated face and can be turned in any plane so that it is at an angle to the main body. The TBM shield must be capable of negotiating 200 meter radius horizontal curves.
- i) The TBMs to be employed for this Contract shall be capable of being operated in a closed face mode, such that they can be operated in a closed face mode wherever the encountered ground conditions and water in-flow conditions so demand. All closed face TBM shall be designed to maintain pressure on the excavated ground at all times. The TBM shall be able to at least balance the total overburden pressure (including hydrostatic pressure) and shall be capable of varying the face pressure as the overburden pressure changes. Earth pressure sensors shall be located at the crown, at TBM axis level and at the invert of the chamber.
- j) All closed face TBM shall incorporate a two compartment air-lock for man-access to the cutter head and face as per BS EN 12110. Pre and Main Chamber shall have capacity of three and two seats respectively with CCTV and drinking water facility .
- k) Where a screw-conveyor is used, the discharge gate on the screw-conveyor shall be fitted with an accumulator, which automatically closes the gate in the event of a power failure. The screw conveyor shall have a diameter of not less than 800mm. The screw flights and tube shall be protected with wear resistant plates of minimum HRC 42 on minimum the first half of their length. The screw conveyor drive shall have a minimum power 200kW
- l) All TBMs shall incorporate a system which enables the face to be closed expeditiously to avoid any ground loss in the event that unstable ground is encountered or water in-flow is encountered during the drive. This shall take the form of hydraulically operated gates on the cutter-head or a similar system to the notice of the Engineer.
- m) The TBM shall be fitted with a data-logger (English Language), which shall be linked by the Contractor to a colour monitor display in the Engineer's office. Each TBM shall have its own dedicated colour monitor. The data-logger shall display and record information in real time and shall have the facility to store all accumulated data from the tunnel drive and to read and display past data. As a minimum the data-logger shall record and report the following information:
 - i. Start and finish time of the excavation stroke.
 - ii. Stroke number, chainage and guidance system's prediction of the next ten strokes after each build.
 - iii. Numbers of thrust cylinders, location and pressures used during the stroke.
 - iv. Extensometer readings of thrust cylinders at the start and end of the stroke.
 - v. Articulation cylinder position at the start and the end of the excavation stroke - articulation angle.
 - vi. Amount of TBM roll at start and end of the excavation stroke.

- vii. Cutting direction, speed, pressure/torque of cutter-head.
 - viii. Shield position and attitude for each ring.
 - ix. Earth pressure readings throughout the excavation stroke at the plenum (excavation / mixing) chamber and screw-conveyor.
 - x. Volume and pressure of grout injected per stroke. Pressure shall be measured at the point of injection.
 - xi. Volume, type and location of ground conditioners added per ring and the cumulative amount per shift with the concentration value.
 - xii. Quantity of tail grease consumed per shift.
 - xiii. Speed and torque of screw conveyor
 - xiv. Rate of advance of TBM
 - xv. Use of copy cutter, amount and location
 - xvi. Gas detector sensors readings
- n) All data-loggers and ancillary equipment shall be fully operational at all times and shall be maintained by the Contractor. The frequency of data logging should be 5 sec and should also have live web feed.
- o) The main bearing Rating Life (L10 lifetime as per ITAtech report N°1- April 2013) shall be minimum double the expected project operation time according to the ITA guidelines for main drive calculation. The bearing shall be equipped with HBW labyrinth sealing.
- p) The TBM tail skin shall be fitted with three rows of tail wire brush and grease seal system that prevents the ingress of water, excavated material and/or grout into the TBM operational area. Facilities shall be provided for replacing the tail wire brush and grease seals from within the excavation / tunnel. The Contractor shall provide grout check “plates” located at the rear of the tail skin, to limit grout migration (from back grouting of the installed segments) along the shield towards the cutter head. An emergency tail seal shall be available in the event of a significant breach of the main seal
- q) A gas detection system shall be installed on the TBM for monitoring and recording the levels of toxic gases that may emanate from the ground and the tunnel construction equipment.
- r) The Contractor shall provide adequate forced ventilation, which complies with
- i) maintaining of humidity level below the maximum permitted level for workers during all weather conditions at work site.
 - ii) Maintaining minimum air-flow and oxygen requirements within the tunnel and at the tunnel face as per condition of Safety, Health and Environment, November 2020 .
- s) The contractor may obtain and use previous TBM data logs of TBM drives in the vicinity for better optimization of TBM drive and TBM design
- t) In case of TBMs with cutter discs at least one cutter disc repair plant per contract complying with the OEM's requirement with induction heating shall be provided by the contractor. The number of plant shall be increased in case of site requirement as per decision of Engineer
- u) CCTVs shall be installed in the offices of the Employer and the Engineer for live monitoring of the TBM Operations with live web feed.

14.9.4 Inspection and Testing

- a) The Employer/ Engineer shall be permitted to visit the TBM manufacturer's/ remanufacturer's premises for the purposes of inspection.
- b) The Contractor shall be responsible for the quality of all materials used or present within the TBM and must ensure that all such materials used or present are adequate for the task they are to perform.
- c) The Employer/Engineer shall be permitted at any stage during manufacture/ remanufacture of the TBM to inspect, examine and test on the manufacturers premises/ remanufacturer's site/ work site the materials, workmanship and performance of all plant and components to be supplied under the Contract. Such inspections, examination or testing shall not release the Contractor from any of his obligations under the Contract.
- d) Inspection of these TBM during the manufacturing/ remanufacturing process shall be done by the Engineer / Engineer's Authorized representative / third party approved by Engineer at various stages for ensuring that the guidelines for manufacturing/ remanufacturing and safety standards are being followed. On completion of fabrication or modification contractor has to demonstrate that all components operate correctly and in compliance to the Contract provisions by undertaking a Factory Acceptance Test (FAT) at the manufacturing/ re-manufacturing site before the Engineer or his authorized representative. An advance program for FAT and TBM operation manual to be submitted to Engineer 6 weeks before FAT test. Test running will also be required at the Site following assembly (Site Acceptance Test- SAT), prior to commencement of tunnel driving before the Engineer or his authorized representative.

14.9.5 Personnel and Training

- a) The Contractor shall ensure that all key personnel who are responsible for driving, maintenance and controlling the TBM have received the necessary training in the duties that they are required to perform and have appropriate experience. Each TBM operator should have an experience of satisfactorily driving TBM for a minimum 50% length of the block section for which the TBM is deployed. An experience certificate from the client department for satisfactory completion of the TBM drive length by the TBM operator is to be submitted beforehand for issuing notice of No Objection by the Engineer.
- b) The Contractor shall provide and maintain a complete list of the names of persons, and their duties, responsible for TBM operation, who have completed the appropriate training to an acceptable standard. The details and experience of all key personnel for driving and controlling the TBM shall be submitted to the Engineer for obtaining a Notice of No Objection.

14.9.6 Contractor's Submission for TBM Working

14.9.6.1 General

- a) The machine characteristics and specifications shall be submitted to the Engineer for obtaining his Notice of No Objection prior to procurement of TBM.
- b) The Contractor shall submit his programme for the provision, inspection, testing, transport, erection and commissioning of each and every TBM supplied for the Works, for obtaining Notice of No Objection from the Engineer.

14.9.6.2 TBM Method Statement

Not less than 60 days before the Contractor intends commencing TBM excavation, he shall submit to the Engineer for obtaining his Notice of No Objection, a detailed method statement, which shall include but not be limited to:

- a) Methods of transportation and erection of the TBM;
- b) Method of commencing the tunnel drives, including details of the temporary thrust arrangements;
- c) Methods of determining ground conditions ahead of the face and methods of treating such conditions;
- d) Methods for dealing with water wells/borewells that may be intersected or influenced by the excavations ;
- e) Methods of junctioning with the launch, retrieval and any other shafts, including dismantling of the TBM;
- f) Operational details, including excavation, segment handling, ring selection/orientation control, ring building procedures, annulus and proof drilling, grouting and control, alignment control, tunnel logistics, maintenance, slurry plant operation (STBM), effluent disposal, muck disposal, ground and spoil conditioning control (EPBM), interventions, changing cutters & picks and the like;
- g) Safety procedures, including compressed air working, cutter head entry, cutting tool changes, ventilation details, emergency evacuation procedures and the like ;
- h) Details of the proposed monitoring and reporting systems;
- i) Details of key personnel responsible for supervising, operating, maintaining and controlling the TBM.

14.9.6.3 TBM Daily Record

The Contractor shall produce operational data for each Earth Pressure Balance Machine (EPBM) or Slurry Tunnel Boring Machine (STBM) throughout the whole tunnelling process in both hard and soft (electronic) copy for each working shift. These shift reports shall be

submitted to the **Engineer** within 24 hours for Notice of No Objection and shall provide the following minimum information.

- a) Start and finish time of the excavation stroke including all stoppages, recording the reasons for the stoppages.
- b) Ring number, chainage and key position.
- c) Start and finish time of the ring build including all stoppages, recording the reasons for the stoppages.
- d) All delays and the reasons for those delays during the shift.
- e) Earth pressure readings at start, middle and end of excavation stroke for cutter chamber and screw-conveyor.
- f) Quantity of material excavated for each ring e.g. number of skips removed.
- g) Total advance for the shift and the accumulative advance.
- h) Number and location of any cutter bits/discs changed.
- i) Volume of grout injected per ring and the pressure, the accumulative volume of grout for the shift.
- j) Volume, type and location of ground/spoil conditioning added per ring and the accumulative amount per shift with the concentration value.
- k) General comments on description of the excavated material.
- l) Quantity of tail grease consumed per ring.
- m) Any segment damage on completed rings.
- n) The timing and nature of any machine maintenance carried out.
- o) 'Daily Mining Report' of TBM to be submitted to the Engineer's review and records.

14.9.6.4 TBM daily monitoring and reporting

Not less than 60 days before the commencement of TBM excavation, the Contractor shall submit details of his proposed monitoring and reporting scheme for the notice of **Engineer**. The content of this submission shall include, but not be limited to, the following:

- a) Chainage of face at the start and end of each shift;
- b) Line and level of the tunnel rings erected during each shift, including details of any corrections made to the plane of the rings;
- c) Survey control data;
- d) Serial numbers of the segments erected, referenced against ring numbers and tunnel chainage;
- e) Details of the geological conditions encountered during each shift, including details of any geological anomalies encountered;
- f) Operational data of the cutter-head drive, including torque and RPM;
- g) Thrust of propulsion rams;
- h) Operational data of slurry system(if applicable);
- i) Hours of operation of the TBM;

- j) Details of any operational delays, including the TBM, backup and slurry systems(if applicable), recorded in 5 minute intervals;
- k) Details of any probing undertaken;
- l) Detailed cycle times for each ring, identifying the boring and erection times;
- m) Details of any planned or unplanned maintenance carried out;
- n) List of cutting tools replaced, their position and serial numbers;
- o) List of spare parts used;
- p) Quantities and pressures used in the annulus grouting, with a reconciliation of the amount used;
- q) Number and classification of supervisors and workmen engaged during each shift;
- r) Any other information that the Engineer may reasonably request.

14.9.7 Elastomeric Gaskets

- The gasket shall be capable of providing a watertight seal under all combinations of specified tolerances associated with manufacturing and ring erection. Gaskets shall be dense, elastomeric synthetic rubber.
- Gaskets shall be manufactured to fit the groove preformed in the segment. Prototype gaskets shall be fit-tested to assess stretch characteristics.
- The material from which the gaskets are to be manufactured shall withstand any aggressive response from the ground or groundwater. In particular the gasket material shall withstand chemical attack and biological degradation such that the gasket functions properly for the design life of the facility.
- Elastomeric gaskets shall comply with the requirements of BS 774, BS EN 681 and BS EN 682. The material shall consist of a compound based on EPDM able to withstand the long term stresses and strains without detriment to the specified performance.
- The gasket cross section shall be dimensioned to suit the groove as detailed in the Drawings for the mating faces of the segmental tunnel linings. Manufacturing tolerances shall be ± 1 mm for width and ± 0.5 mm for thickness.
- Gaskets shall be manufactured from extruded solid sections with appropriate spaces within the section to enable the gasket to be fully compressible within the groove formed in the concrete segments. The gasket shall still be capable of further compression when its top surface is level with the groove.
- The extruded section shall be joined to form a rectangular gasket that is a stretch fit into the grooves of the segments. The corner joint shall be shot moulded and the corner pieces shall be of different section from the extruded lengths in order that the water-tightness characteristics described in the specification may be achieved and to avoid excessive load on the corners of the concrete segments.
- Gaskets shall be fitted into the groove cast in the segmental tunnel linings prior to erection. The adhesive used shall be as recommended by the gasket manufacturer with a 'notice of no objection' from the Engineer.

- The Contractor shall submit to the Engineer full details and samples of the gaskets which he proposes to use at least 60 days before the commencement of manufacturing. Further, the warranty should be given by supplier/manufacturer for satisfactory performance of the product including its application and supervision.
- The hydrophilic facing material shall be a vulcanised polychloroprene rubber formulated with hydrophilic polymers. The formulation of the hydrophilic material shall provide good water expansion properties with the minimum of leaching of the active materials.
- The Contractor shall provide the Engineer with a detailed statement regarding the durability of the proposed materials demonstrating their ability to meet the specified performance criteria for the design life of the structure. The statement shall provide any further information and test data relevant to the water absorption, long term swelling capacity, relaxation, chemical resistance and ageing of the materials. In particular the materials shall be resistant to attack from all substances in the ground and groundwater at the concentrations found in the site investigation, to the alkalinity of the tunnel lining concrete and tunnel grout and shall be resistant to microbiological attack. The statement shall include a list of substances known to be deleterious to the materials, together with an analysis of the risk of contact with such substances.
- The Contractor shall ensure that the grout is not permitted to penetrate to the gasket location as this would impair its function.
- The selected gasket shall have a proven reputation for satisfactory performance in tunnels with similar ground water pressure.
- The Contractor shall carefully detail the size and depth of the gasket groove to ensure that it is of sufficient volume that when the segment faces are fully closed, the volume of rubber in the gasket can be housed within the groove. Unless otherwise accepted by the Engineer the volume of the gasket groove shall be at least 5% larger than the volume of rubber in the gasket. Where compressible joint packings are systematically incorporated between the joint surfaces the compressed thickness of the packing may be considered in the calculation of the volume of the gasket groove.
- The gaskets shall form continuous loops (frames) around the segments and shall be bonded to the concrete surface with adhesives recommended by the gasket manufacturers and following the procedures recommended by the adhesive manufacturers.
- The design of the gaskets shall be such as to render them inherently resistant to damage during transport and erection of the linings.
- The Contractor shall provide drawings of the principal dimensions and proposed tolerances on the gaskets. The drawings shall include the dimensions and positions of the gasket grooves or mounting surfaces.
- The corners of the gaskets shall be moulded to the appropriate corner angles of the segments. Detailed drawings of all segments shall be supplied by the Contractor to the gasket manufacturer. The corners of the gaskets shall be designed to ensure that the volume of rubber remains constant and that they have the same load and closure forces as the main

body of the gasket. The corners of the gaskets shall be subject to full opening and closure tests to ensure the integrity of each joint.

- The gasket manufacturers shall be ISO 9001 (or equivalent national or international quality standard) certified and shall have in place detailed procedures to ensure the quality control of the gaskets at each stage of their testing and manufacture.
- Prior to commencing manufacture of the gaskets prototype samples for each segment type shall be subject to fitting trials in order to determine the optimum tension for the gaskets. Each gasket shall be lightly tensioned to ensure that it grips the segment and fits snugly into the gasket groove. Corners of the gasket shall be square and tight fitting. These trial fittings shall be conducted by representatives of the gasket manufacturer and witnessed by the Engineer.
- Installed gaskets shall be free from surface imperfections, voids, inclusions or flow marks and other defects which would impair satisfactory performance. The surfaces shall be smooth. Fabrication joints in the gasket material shall be made with such accuracy as not to impair satisfactory performance in the tunnel environment
- Prior to installation gaskets shall be stored under cover in a dry storage area in an undeformed relaxed condition at moderate temperatures and protected from direct sunlight. They shall be protected from circulating air and shall not be stored near equipment that can generate ozone (such as electric motors). The gaskets shall be kept clean, particularly avoiding contact with metals, solvents, oil and grease.
- Fitting of the gasket frame shall commence at the radial joint surfaces neatly pressing the gasket into the groove or on to the surface by hand. The circumferential joint surfaces shall then be fitted starting from the middle and working towards the two corners on each face. Care shall be taken to ensure that the frame is accurately located and that the corners are neither distorted nor loose. The frame may be lightly hammered into position using a rubber hammer and shall then be pressed onto the surface for a minimum period of five minutes until the adhesive has hardened.
- Unless otherwise accepted by the Engineer gasket frames shall not be installed onto the segment prior to seven days before their installation into the tunnel. Each completed segment shall be inspected for correct seating of the frame and uniform adhesion prior to storage. Completed segments shall be protected from precipitation and direct sunlight. Completed segments shall be stored under covered conditions or tarpaulins prior to installation in the tunnel.
- A series of tests shall be conducted for each gasket type. The tests shall be carried out using water with chemical content equivalent to the concentrations found in the ground water in the site investigation which will most impair their performance.
- Each test series shall comprise the testing of a straight joint, a 'T' joint such as occurs at the intersection of a radial joint and a circumferential joint in the tunnel lining and a cross joint. The configuration of the test rig shall be such that it can accurately simulate the combination of gaps, steps and lips defined herein.

- The gap between the faces of the test pieces, representing gaps in the joints of the tunnel lining, shall be 5mm greater than the theoretical value calculated from the shape of the joint surfaces and from the thickness of any packing which is to be used. The tests shall be performed with a lateral offset of 10mm at the groove in the following configurations.
- Straight joint : one side offset
- T' joint : one side of intersecting joint offset
- Cross joint : one side of intersecting joint offset
- The gasket test pressure shall be defined as twice the design hydrostatic head. Unless otherwise accepted by the Engineer, the design hydrostatic head shall be considered to be the maximum distance between the invert of the tunnel and the ground surface.
- The test pressure shall be applied in 1.0 bar increments by means of a variable pressure reflux valve or other stabilising device, capable of maintaining the applied pressure within 1% of the desired pressure at each pressure increment. The pressure shall be held for 15 minutes at each increment. The final pressure shall be held for 24 hours during which no visible sign of leakage shall be noticeable.
- If the Contractor envisages that gaps larger than those indicated above will occur in the tunnel, due for example to the use of thicker packings, then the Contractor shall carry out tests with an appropriately larger gap. Only those gaps shall be used in the Works that are covered by a representative test.
- The Contractor shall demonstrate that when the joints are closed to the fullest extent that will occur in the Works, no damage will be caused to the tunnel lining segments by the gaskets. "The fullest extent that will occur in the Works" shall be deemed to be:
 - In the circumferential joints - Closed to the maximum extent that will be allowed by the packings in the joints.
 - In the radial joints - Joint closed by the maximum extent that will be allowed by the gaskets.
- The Contractor shall provide evidence that with smaller joint gaps and offsets than those specified above, the water pressure that can be withstood by the gaskets will not be less than the specified test pressures. This evidence can be in the form of further testing or certified results of previous tests on identical gaskets.

Section – S.15

ROADWORK

15.1 CONTROL OF TRAFFIC

The contractor shall take all necessary precautions in co-ordination with and to the requirements of all the competent authorities concerned to protect the work from damage until such time as the seal coat or surface treatment has developed sufficient strength to carry normal traffic without any damage to it.

The new work shall be opened to traffic only after it is authorised by the Engineer.

The contractor shall submit a detailed traffic diversion/or control and regulation plan taking all safety measures during the course of work permitted by the concerned authorities to the Engineer for his consent before start of work.

The contractor shall take all precautions to avoid or minimise delays and inconvenience to road users during the course of the work. Where adequate detours or side tracks are available, traffic shall be temporarily diverted while the work is in progress depending on volume of traffic and subject to approval by Traffic Police. Adequate signs, signals, barriers and lamps for the warning and guidance of traffic shall be provided at all times during the course of the work till it is opened to traffic.

The Contractor shall take all reasonable precautions to protect traffic against accident, damage or disfigurement by construction equipment, tools, and materials, splashes and smirches of bitumen/ bituminous material or any other construction materials and shall be responsible for any claims arising from such damage or disfigurement.

Traffic signs erected shall be in accordance with the IRC Standards and/or as prescribed and approved by the Traffic Police Department.

15.2 GRANULAR SUB-BASE (NON-BITUMINOUS)

This work shall consist of laying and compacting well-graded material on prepared subgrade in accordance with the requirements of these specifications or as per MORTH standards, as acceptable to Highway authorities & road owing agency. The material shall be laid in one or more layers according to lines, grades and cross-sections shown on the drawings.

15.2.1 **Material**

The Material to be used for the work shall be natural sand, moorum, gravel, crushed stone, or combination thereof depending upon the grading specified in MORTH specifications for Roads and Bridges. The material shall be free from organic or other deleterious constituents.

15.2.2 **Physical requirements**

The material shall have a 10 percent fines value of 50 KN or more (for sample in soaked condition) when tested in compliance with BS:812 (Part III). The water absorption value of the coarse aggregate shall be determined by IS:2386 (Part 3); if this value is greater than 2 percent, the soundness test shall be carried out on the material delivered to site as per IS: 383. CBR Value shall be determined at the density and moisture content likely to be developed in equilibrium conditions which shall be taken as being the density relating to a uniform air voids content of 5 percent.

15.2.3 Strength of sub-base

It shall be ensured prior to actual execution that the material to be used in the sub-base satisfies the requirements of CBR and other physical requirements when compacted and finished.

15.2.4 Construction Operations**a) Preparation of sub-grade**

Immediately prior to the laying of sub-base, the sub-grade already finished or existing surface shall be prepared by removing all vegetation and other extraneous matter, lightly sprinkled with water if necessary and rolled with two passes of 80 – 100 KN smooth wheeled roller. Damage to the subgrade shall be made good before sub base is laid.

b) Spreading and compacting

The approved sub-base material shall be spread on the prepared sub-grade by a grader of suitable type and adequate capacity.

When the sub-base material consists of combination of materials, mixing shall be done mechanically by the mix-in-place method.

The equipment used for mix-in-place construction shall be approved equipment capable of mixing the material to the desired degree.

Moisture contents of the loose material at the time of compaction shall be checked in accordance with IS: 2720 (Part 7) and suitably adjusted.

Rolling procedure shall be as described under relevant Subsection except stated herein.

Rolling shall be continued till the density achieved is at least 98% of the maximum dry density for the material determined as per IS:2720 (Part 8).

15.2.5 Control of Traffic

Control of traffic shall be as described under Subsection 15.1.

15.3 WATER-BOUND MACADAM SUB-BASE/ BASE (NON-BITUMINOUS)**15.3.1 Description**

The work shall consist of furnishing, placing, watering and compacting sub-base material mechanically interlocked by rolling and bounded together with screening and/ or binding material to the required degree on a prepared sub-grade/ sub-base or the existing surface as the case may be in accordance with these Specifications, and to the lines, levels, grades, dimensions and cross sections as shown on Drawings and/ or required by the Engineer.

15.3.2 Materials**a) Coarse aggregate**

The coarse aggregates shall be hard and durable crushed stones, free from deleterious matter conforming to one of the gradings as set forth in Table 15.3.1, the physical requirements given in Table 15.3.2 subject to the Engineer's consent.

b) Screenings

Screenings to fill voids in the coarse aggregate shall generally consist of the same material as the coarse aggregate or of gravel (other than round material) or moorum as approved by

Engineer. However, where permitted non-plastic material such as moorum may be used for this purpose provided liquid limit and plasticity index of such material are below 20 and 6 respectively and fraction passing through 75 micron sieve does not exceed 10 percent.

c) Binding material

Binding material to be used for water-bound macadam as a filler material meant for preventing ravelling, shall be a suitable material and having a Plasticity Index (PI) value of less than 6 as determined in accordance with IS : 2720 (Part-5).

Table 15.3.1

Grading requirements of coarse aggregates

Grading	Size Range	IS Sieve Designation	Percent Passing by weight
1.	63 mm to 45 mm	75 mm	100
		63 mm	90-100
		53 mm	25-75
		45 mm	0-15
		22.4 mm	0-5
2.	53 mm to 22.4 mm	63 mm	100
		53 mm	95-100
		45 mm	65-90
		22.4 mm	0-10
		11.2 mm	0-5

Note: The compacted thickness of layer shall be 75 mm.

Table 15.3.2

Physical requirements of coarse aggregates or water-bound macadam sub-base and base courses

S.No.	Test	Test Method	Requirement (Maximum)
1.**	Los Angeles Abrasion value or Aggregate Impact value	IS:2386 (Part-4)	40 percent(max)
2.		IS:2386 (Part-4) or IS:5640*	30 percent(max)
3.	Combined Flakiness and Elongation Indices (Total)**	IS : 2386 (Part-1)	35 per cent

* Aggregate which get softened in presence of water shall be tested for Impact value under wet conditions in accordance with IS:5640.

15.3.3 Construction Method

a) Preparation of Sub-grade/ sub-base

- i. The surface of the sub-grade/ sub-base or existing surface shall be shaped and prepared to the lines, levels, grades, dimensions and cross sections as shown on the Drawings. Damage to or deterioration of sub-grade/ sub-base shall be made good before sub-base/ base is overlaid.
- ii. Inverted Choke
If water bound macadam is to be laid directly over the sub grade, without any intervening pavement or soling course, a 25 mm course of screenings (Grading B) or coarse sand shall be spread and compacted on the prepared subgrade before application of the coarse aggregate. In case of fine sand or silty or clayey sub grade, a 100 mm insulating layer of screenings or coarse sand shall be laid, the gradation of which will depend on drainage requirements. Alternatively, appropriate geosynthetics performing functions of separation and drainage layer may be used over the prepared sub-grade subject to the satisfaction of the Engineer.

b) Spreading coarse aggregates

- i. The coarse aggregates of specified size and grading shall be spread uniformly in layers with each compacted layer thickness not more than 75mm for Grading 1 and Grading 2 and in a manner that prevents segregation into fine and coarse materials.
- ii. Sub-base/ or base material shall contain moisture nearly equalising the optimum moisture content at the time of compaction.
- iii. Immediately after each layer has been spread and shaped satisfactorily, each layer shall be thoroughly compacted with suitable and adequate compaction equipment. Rolling operations shall begin from the outer edge of roadbed towards the centre, gradually in a longitudinal direction; except on super-elevated curves, where rolling shall begin at the lower edge and progress towards the upper edge.

The rolling shall be continued until the aggregates are thoroughly keyed, well-bounded and firmly set in its full depth.

c) Tolerance

The finished sub-base/ base at any point shall not vary more than 15mm below and 12mm above the planned grade or adjusted grade with 3m straight edge applied to the surface parallel to the centreline of the road. With the template laid transversely the maximum permissible variation from specified profile shall be 12mm and 8mm respectively.

The sub-base/ base course completed in each day's work shall have an average thickness not less than the required thickness.

Sub-base/ base course which does not conform to the above requirements shall be reworked.

15.4 BITUMINOUS MATERIALS

15.4.1 Materials

Materials shall meet the requirements of the relevant IS Codes. These shall be of the following types.

a) Cut back Bitumen

Cut back bitumen shall be Rapid Curing (RC), Medium Curing (MC) or Slow Curing (SC) conforming to IS : 217.

b) Cationic Emulsion

Bitumen emulsions of the cationic type for roads shall conform to IS: 8887. Emulsified bitumen shall be Rapid Setting (RS), Medium Setting (MS), or Slow Setting (SS).

The physical and chemical requirements of the three types emulsions shall comply with the requirements specified in Table 1 of IS: 8887.

c) Paving Bitumen

Paving bitumen shall be conforming to IS: 73 and of the following two types:

Type 1 Paving bitumen from non-waxy crude shall satisfy the requirements given in Table 1 of IS: 73.

Type 2 Paving bitumen from waxy crude shall satisfy the requirements given in Table 2 of IS: 73.

The temperature at application of bituminous materials shall be maintained as per manufacturer's instructions and/or as directed by the Engineer's Representative.

An anti-stripping and bonding agent should be used in all final restoration road works. It should conform to IS: 14982-2022 specifications. The percentage can be from 0.5% to 1.25% by weight of bitumen content. The optimum dose can be ascertained using latest MORTH / BIS guidelines.;

15.4.2 Methods of Storage and Handling

Asphaltic material shall be handled and stored with due regard for safety and in such a way that at the time of use in the work the material conforms to the Specifications. Following precautions shall be taken while using these materials:

- a) Work with these materials shall be carried out in good weather conditions and it shall be carried out in warm and dry weather, and not in wet or extremely cold weather.
- b) Emulsified asphalt shall be handled with care and not subjected to mechanical shocks or extremes of temperature likely to cause separation of the asphalt. Emulsified asphalt showing sign of separation shall not be used.
- c) During heating, no water or moisture shall be allowed to enter the boiler.
- d) Heating of bitumen shall be done to the correct temperature range, as prescribed by the manufacturer for the grade used. The temperature shall be controlled with the use of a suitable thermometer, and the material shall be drawn and used while still at such temperature as is prescribed by manufacturer or in accordance with latest MORTH specifications.

- e) It shall be ensured that mixing of ingredients is thorough and all particles of aggregates are coated uniformly and fully.

15.5 PRIME COAT

15.5.1 Description

This work shall consist of the cleaning and preparing of the surface to be primed to specified lines, grade, and cross-section, booming and clearing thoroughly and applying bituminous material in accordance with these Specifications.

15.5.2 Materials

The choice of the primer shall depend upon the porosity characteristics of the surface to be primed. The primer shall be Medium Curing Cutback (MC) and the particular grade to be used for the work shall have the consent of the Engineer. Slow setting Cationic emulsion conforming to IS : 8887 may also be used. Sampling and testing of bituminous primer shall be as per IS : 217, IS : 454 and IS : 8887.

15.5.3 Construction Methods

a) Weather Limitations

Prime coat shall not be applied at a time when the surface is wet or when the weather is foggy, rainy or windy.

b) Equipment

The equipment used for the work shall include a power broom and primer material distributor spraying it uniformly at specified rates and temperatures. It shall be equipped with self-heating arrangement, suitable pump, adequate capacity compressor and spraying bar with nozzles having constant volume or pressure system.

Spraying by manual methods may be allowed for inaccessible or small areas with the consent of the Engineer.

c) Cleaning Surface

Immediately prior to applying the prime coat the surface to be primed shall be swept clean from all loose dirt and other objectionable material and shall be shaped to the required lines, grades, cross section.

d) Application of bituminous primer

The primer material shall be applied by means of a distributor at rates usually from 0.8 to 1.4 litres per square metre and at a temperature within the allowable range corresponding to the material used and porosity condition of surface over which it is laid. The temperature of primer at time of application may vary from 40⁰ C to 60⁰ C for cutback bitumen and 40⁰ C to 60⁰ C for bitumen emulsion.

Prime coat shall be allowed to penetrate for at least 48 hours to allow penetration into the base course and aeration of volatile from the primer material, then covered with clean dry sand or stone screening.

Areas containing an excess or deficiency of priming material shall be corrected by the addition of sand or primer.

15.6 TACK COAT

15.6.1 Description

This work shall consist of furnishing and applying bituminous material to an existing road surface or to an existing bituminous prime coat surface which has dried out or preparatory to laying another bituminous layer over it.

15.6.2 Materials

The material for tack coat shall be a bituminous or cut back emulsion of suitable type and grade.

15.6.3 Construction Methods

a) Cleaning Surface

The whole surface on which the tack coat is to be applied shall be cleaned of dust and any extraneous material before the start of application of tack coat by using a power broom or any other equipment/ method.

b) Application of tack coat material

The tack coat material shall be applied uniformly by means of a distributor at controlled rates as per MORTH specifications and at the temperature within the allowable range corresponding to the material used. It shall be done with self propelled or towelled bitumen.

Surfaces of structures and trees adjacent to the areas being treated shall be protected in such a way as to prevent their being splattered or marred.

15.7 BITUMINOUS MACADAM

15.7.1 Description

The work shall consist of one or more applications of compacted crushed aggregates premixed with bituminous binder (suitable grade) to a primed non-bituminous surface or previously constructed bituminous surface and in conformity with the lines, grades, dimensions and cross-sections shown on the Drawings. This shall comprise of a single course of 50mm to 100mm thickness as specified in the approve or as Directed by Engineer.

15.7.2 Materials

a) Bitumen

The bitumen shall be paving bitumen of suitable grade approved by the Engineer and conforming to IS : 73.

b) Additives

Adhesion and Ant-stripping agent shall be added to the bitumen subject to Engineer's consent at the required percentage of additive. The additive shall be thoroughly mixed with the bituminous material in accordance with the manufacturer's instructions.

c) Aggregates

Aggregates shall consist of clean and hard crushed stone free from dust, clay, dirt and any other deleterious matter. The physical requirements shall be as given in Table 15.7.1. Aggregates shall conform to one of the two gradings given in Table 15.7.2 depending on the compacted thickness; the actual grading shall have the consent of the Engineer.

Table 15.7.1
Physical requirements of aggregates for bituminous macadam

Property	Test	Requirement	Test Method
Clearliness	Grain Size Analysis	Max. 5% passing 0.075 micron	IS: 2386 Part I
Particle shape	Combined Flakiness and Elongation Indices	Max 35%	IS: 2386 Part I
Strength	Los Angeles Abrasion value or Aggregate Impact value	Max 40% Max 30%	IS: 2386 Part IV IS: 2386 Part IV
Durability	Soundness(Sodium or Magnesium) Sodium sulphate Magnesium sulphate	5 Cycles Max 12% Max. 18%	 IS: 2386 Part V IS: 2386 Part V
Water Absorption	Water Absorption	Max. 2%	IS: 2386 Part III
Stripping	Coating and stripping of Bitumen Aggregate	Min. Retained Coating 95%	IS: 6241
Water Sensitivity	Retained Tensile Strength	Min 80%	AASTHO 283

* If the minimum retained tensile strength falls below 80%, use of anti stripping agent is recommended to meet the minimum requirements.

Table 15.7.2
Aggregate grading for bituminous macadam

Grading	1	2
Nominal Maximum aggregate size*	40mm	19mm
Layer Thickness	80-100mm	50-75mm
IS Sieve Size (mm)	Cumulative % Weight of Total aggregate passing	
45	100	
37.5	90-100	
26.5	75-100	100
19	-	90-100
13.2	35-61	56-88
4.75	13-22	16-36
2.36	4-19	4-19
0.3	2-10	2-10
0.075	0-8	0-8
Bitumen content** percent by mass of total mix	3.3**	3.4**

*Nominal maximum aggregate size is the largest specified sieve size upon which any of the aggregate material is retained.

Table 15.7.3**Mixing, Laying and Rolling Temperatures for Bituminous Mixes (Degree Celcius)**

Bitumen Viscosity Grade	Bitumen Temperature	Aggregate Temperature	Mixed Material Temperature	Laying Temperature	*Rolling Temperature
VG-40	160-170	160-175	160-170	150 Min	100 Min
VG-30	150-165	150-170	150-165	140 Min	90 Min
VG-20	145-165	145-170	145-165	135 Min	85 Min
VG-10	140-160	140-165	140-160	130 Min	80 Min

- **Rolling must be completed before the mat cools to these minimum temperatures.**

15.7.3 Construction Methods**a) Weather and Control of Work**

The work of laying shall not be undertaken during rainy or foggy weather or when the base course is damp or wet, or during dust storm or when the atmospheric temperature in shade is 15°C or less.

The Engineer may order work to cease temporarily on account of adverse weather, unsatisfactory condition of materials, equipment or any conditions which he considers may affect the work adversely.

b) Cleaning and Preparation of Surface

Prior to the application of binder, loose dirt and other objectionable material shall be removed from the surface to be treated by means of the power broom or blower or both. If this does not provide a uniformly clean surface, additional sweeping shall be done by hand, using stiff brushes or similar brooms. The areas inaccessible to the cleaning means shall be cleaned manually. The sweeping shall extend 200mm beyond each edge of the area to be treated.

Adherent patches of objectionable material shall be removed from the surface by steel scraper or other approved method and where the Engineer so directs the scraped area shall be washed down with water and hand brooms.

No application of bituminous material shall be undertaken until the surface has been cleaned to the satisfaction of the Engineer.

Before application of the bituminous material any necessary preliminary patching of the surface of the road (To fill in potholes.) shall be done to the complete satisfaction of the Engineer.

Tack coat shall be applied in accordance with these Specifications. Prime coat if required, shall conform to Subsection 15.5.

c) Plant and Equipment

All plant used by the Contractor for the preparation, hauling and placing of asphalt mixtures shall be subject to the consent of the Engineer and shall minimise smock, dust and noxious emission and odours. These shall generally meet the following requirements:

- i. The mixing plant shall be a batching plant and shall have adequate capacity sufficient to supply the finisher on the road continuously when spreading the asphaltic mix at normal speed and required thickness.
- ii. Scale for any weigh box shall be designed to be accurate to within 1% of the maximum load required and shall be fully automatically controlled.

The Contractor shall provide and have at hand not less than ten 25 kilograms weights for frequent testing of all scales.

- iii. Weigh box or hopper shall include a means for accurately weighing each bin size of aggregate in a weight box or hopper, suspended on scales, ample in size to hold a full batch without running over.
- iv. The asphaltic materials shall be stored in storage tanks designed to keep the temperature of the asphaltic material at maximum temperature of 110° C. The properties of the asphaltic material kept in that storage tanks shall be in good condition before mixing.

The plant shall be provided with a circulating system to ensure continuous circulation between the storage tank and the mixer.
- v. The plant shall be provided with a cold bin for feeding the aggregates. Bin shall have a calibration gate and a mechanical means to insure uniform feeding of the aggregates into the drier as required by the Engineer.
- vi. The rotary drier shall be capable of drying and heating the aggregates to the specified temperature.
- vii. The plant shall be provided with plant screens capable of screening all aggregates to the specified sizes.
- viii. The plant shall include at least 3 hot bins for storing the aggregates fed from the drier after passing through the screen. Each bin shall be provided with an overflow pipe to prevent any backing up of material into other bins.
- ix. The plant shall be provided with asphaltic control unit by weighing to obtain the proper amount of asphaltic material in the mix within the tolerance specified for the job-mix.
- x. The batch mixer shall be an approved twin pugmill type and capable of producing a continuous uniform mixture within the job-mix tolerances. The mixer capacity shall not be less than 1,000 kilogram batch.

- xi. An armoured thermometer reading from 50° C to 200° C shall be fixed in the asphaltic feed line at a suitable location near the discharge valve at the mixer unit.

The plant shall be further equipped with an electric pyrometer, or other approved thermometric instrument so placed at the discharge chute of the drier as to register automatically or indicate the temperature of the heated aggregate.

- xii. The plant shall be equipped with a dust collector.
- xiii. The plant shall be equipped with accurate positive means to govern the time of mixing and to maintain it constant. The time of mixing shall be divided into two steps, dry mixing and wet mixing. For dry mixing, the aggregate from hot bins shall be mixed for a period of 5-15 seconds. For wet mixing, the mixing time shall begin with the start of the asphalt spray after dry mixing. The wet mixing shall take about 30-45 seconds. The mixing time shall be extended if in the consideration of the Engineer the material obtained is not homogeneous.

d) Equipment for Hauling and placing

- i. Trucks for hauling asphaltic mixtures shall have tight, clean, and smooth metal beds that have been sprayed with soapy water, thinned fuel oil, or lime solution to prevent the mixing from adhering to the beds (The amount of sprayed fluid shall however be kept to the practical minimum. Each load shall be covered with a canvas or other suitable material of such size as to protect the mixture from the weather). Any truck causing excessive segregation of material by its spring suspension or other contributing factors, or that shows oil leaks in detrimental amounts, or that causes undue delays, shall upon direction of the Engineer be removed from the work until such conditions are corrected.
- ii. The equipment for spreading and finishing shall be mechanical, self powered pavers, capable of spreading and finishing the mixture true to the lines, grades, dimensions and cross sections.

The pavers shall be equipped with hoppers and distributing screws of the reversing type to place the mixture evenly.

The pavers shall maintain trueness of grade and confine the edges of the pavement to true lines without the use of stationary side forms. The equipment shall include blending or joint levelling devices for smoothing and adjusting longitudinal joints between lanes. The assembly shall be adjustable to give the cross-section shape prescribed and shall be so designed and operated as to place the thickness or weight per square metre of material required.

Pavers shall be equipped with activated screeds and devices for heating the screeds to the temperature required for the laying of the mixture without pulling or marring.

The term "screed" includes any cutting, crowing, or other practical action that is effective in producing a finished surface of the evenness and texture specified, without tearing, shoving, or gouging.

If, during construction, it is found that the spreading and finishing equipment in operation leaves in the pavement surface tracks or indented areas or other objectionable irregularities, the use of such equipment shall be discontinued and other satisfactory spreading and finishing shall be provided by the Contractor forthwith.

e) Preparation and transport of mix

Bituminous macadam mix shall be prepared in a hot-mix plant either owned by the Contractor or it may be taken from an approved hot mix plant before supply of mix for the work, consent for the use of the mix shall be taken from the Engineer. The hot-mix plant should be of adequate capacity of batch mix type with the features as described under Subsection 15.7.3(3) or otherwise approved by Engineer unless some work specific features are required and capable of yielding a mix of proper and uniform quality with thoroughly coated aggregates. The plant shall meet the overall requirements through stringent quality control practices.

The mineral aggregates shall be dried and heated to a temperature between 150° C and 163° C. The contractor shall submit for consent the exact temperature to the Engineer. Surfaces of aggregates shall be clean and free of carbon and unburnt fuel oil. The aggregates, immediately after heating, shall be screened into three or more fractions and conveyed into separate bins ready for combining and mixing with asphaltic material.

The dried mineral aggregates prepared as prescribed above, shall be combined in the plant in the amount of each fraction of aggregate required to meet the job-mix formula for the

particular mixture. The proper amount of asphaltic material shall be distributed over the mineral aggregate and the whole thoroughly mixed for a period of at least 30 seconds, or longer if necessary to produce a homogeneous mixture in which all particles of the mineral aggregates are coated uniformly. The total mixing time shall be regulated by a suitable locking means.

The mixture shall when emptied from the mixer be at a temperature between 150° C and 163° C even for tolerances.

The mixture shall be transported from the mixing plant to the point of use in vehicles conforming to the requirements of Subsection 15.7.3 (4)(a) unless otherwise approved by the Engineer.

f) Application of the Pre-mix

The application of the mix shall proceed immediately after application of tack coat. The mix shall be spread immediately by means of self-propelled mechanical paver with suitable screeds capable of spreading, tamping, and finishing the mix true to lines, levels, dimensions and cross-sections specified. Any bare or insufficiently filled areas shall be re-treated by the mechanical spreader or covered by hand as necessary to give uniform and complete coverage. Any aggregate spread in excess of the agreed rate shall be scattered and evenly distributed on the road or otherwise removed and stockpiled.

The temperature of the mix at the time of laying shall be in the range of 120 or 160° C.

g) Rolling

After the spreading of the mix, the rolling shall be done by road roller of suitable type and capacity. Rolling shall start as soon as possible after the material has been spread and it shall be completed within limited time frame, and to meet this, the Contractor shall deploy a set of rollers. Rolling shall be done with care to avoid unduly roughening of the pavement surface. It shall commence at the edges and progress towards the centre longitudinally except that on super-elevated and unidirectional cambered portions, it shall progress from the lower to the upper edge parallel to the centre line of the pavement.

The speed of the rollers shall not exceed 5 kilometre per hour for steel wheeled rollers and 7 kilometre per hour for pneumatic tired rollers and shall be at all times slow enough to avoid displacement of the hot mixture. Any displacements occurring as a result of reversing the direction of the roller or from any other cause shall at once be corrected with rakes and fresh mixture where required. Care shall be exercised in rolling not to displace the line and grade of the edges.

Rolling shall progress continuously as may be necessary to obtain uniform compaction while the mixture is in a workable condition and until all roller marks are eliminated.

Heavy equipment or rollers shall not be permitted to stand on the finished surface until it has thoroughly cooled or set.

Any petroleum products dropped or spilled from the vehicles or equipment employed by the Contractor upon any portion of the pavement under construction is cause for the removal and replacement of the contaminated pavement by the Contractor.

When the roller has passed over the whole area once, any high spots or depressions which become apparent shall be corrected by removing or adding premixed material. Rolling shall then be continued until the entire surface has been rolled to 95 % of the average laboratory density, and there is no crushing of aggregates. and all roller marks are eliminated. In each

pass of the roller, preceding track shall be overlapped uniformly by at least 1/3rd width. The roller wheels shall be kept damp to prevent premix from adhering to the wheels and being picked up. In no case shall fuel/ lubricating oil be used for this purpose.

Along kerbs, man-holes etc., and at any other locations where proper consolidation by rollers is not practicable, alternative means such as steel rammers shall simultaneously be used to secure adequate consolidation.

15.7.4 Surface Control

a) Surface Regularity

Maximum permissible undulation in longitudinal profile with 3m straight edge shall be as 12mm.

Maximum permissible variation from specified cross profile under camber template shall be as 8mm.

Surface evenness requirements in respect of both longitudinal and cross profiles should be simultaneously satisfied.

Tests for conformity with the specified crown and grade shall be made immediately after initial compaction, and variations shall be corrected by removing or adding materials as may be necessary. Rolling shall then be continued as specified. After final rolling, the smoothness of the course shall be checked again and any irregularity of the surface exceeding the permissible limits corrected as agreed by the Engineer's Representative, including removal and replacement.

b) Surface Finish

The bituminous macadam shall be covered with either the next pavement course or wearing course, as the case may be, without any delay. If there is to be any delay, the course shall be covered with the seal coat. The seal coat in such cases shall be considered incidental to the work and shall not be paid separately.

15.7.5 Control of Traffic

This shall be as described under Subsection 15.1 above.

15.8 OPEN-GRADED PRE-MIX CARPET

15.8.1 Description

This work shall consist of laying and compacting an open-graded carpet generally of 20mm thickness or as otherwise specified in a single course composed of suitable small sized aggregates premixed with a bituminous binder on a previously prepared base to serve as a wearing course.

15.8.2 Materials

a) Binder

Binder shall be bitumen of suitable grade meeting the requirements of the work and other environmental conditions. This shall be conforming to the requirements of IS : 73, IS : 217 and IS : 454 or other approved cut back bitumen as applicable.

b) Coarse aggregates

Coarse aggregates consist of crushed stones and shall be clean, strong, durable, and free

from organic or other deleterious materials. The aggregates shall be hydrophobic and of low porosity. If hydrophilic aggregates are to be used, bitumen shall preferably be treated with anti-stripping agents of approved quality in suitable doses.

The aggregates shall meet the requirements given in Table 15.7.1 except that the water absorption shall be limited to 1 per cent. The Stone Polishing Value as measured by BS : 812-(Part-114) shall not be less than 55.

c) Proportioning of Materials

They shall comprise of a mix of stone chipping 13.2mm size (passing 22.4 mm sieve and retained on 11.2 mm size) and 11.2 mm size (passing 13.2 mm sieve and retained on 5.6 mm sieve.)

The contractor shall propose material proportions to the Engineer for his consent.

15.8.3 Construction Methods

a) Weather and Control of Work

This shall be as carried out per Subsection 15.7.3(1).

b) Cleaning and Preparation of Surface

This shall be as carried out per Subsection 15.7.3(3).

c) Tack Coat

This shall be applied as per Subsection 15.6.

d) Preparation and transport of Premix

The binder shall be heated to a temperature appropriate to the grade of bitumen in boilers of suitable design avoiding local overheating and ensuring a continuous supply.

The aggregates shall be dry and suitably pre-heated to the required temperature before they are placed in a mixer. After about 15 seconds of dry mixing, the heated binder shall be distributed over the aggregates at the rate specified. Mixing shall be continuous and thorough to ensure a homogeneous mixture in which all particles are coated uniformly and the discharge temperature shall be within the specified range.

The mixing of binder with chippings shall be continued until the chippings are thoroughly coated with binder. The mix shall be discharged and immediately transported from mixer to the point of use in suitable vehicles or wheel barrows. The vehicles employed for transport shall be clean and the mix being transported should be covered in transit and protected from any kind of damage.

e) Spreading and Rolling

Immediately after the application of tack coat, premixed material shall be spread by means of mechanical paver finisher truly to lines, levels, dimensions and cross section as specified. The areas not covered by the mechanical means shall be treated with manual means for which the Engineer has given his consent.

f) Rolling

This shall be carried out as per Subsection 15.7.3(7)

15.8.4 Control of Traffic

Subsection 15.1 shall be followed.

15.9 **BITUMINOUS CONCRETE**

15.9.1 **Description**

This work shall consist of a surfacing of single-layer bituminous concrete of specified thickness on previously prepared bituminous surface to the lines, grades, dimensions and cross section as shown on Drawings. It shall be 25mm/40mm thick as required by Engineer.

Materials

a) Bitumen

The bitumen shall be paving bitumen of suitable penetration grade within the range S 35 to S 90 or A 90 to IS: 73. The actual grade of bitumen to be used shall be appropriate to the requirements of the work and environmental conditions.

b) Coarse aggregates

The aggregates shall satisfy the physical requirements given in Table 15.7.1. Flakiness index shall not exceed 30% and water absorbed not more than 1%

c) Fine aggregates

Fine aggregates shall be the fraction passing 2.36 mm sieve and retained on 75 micron sieve, consisting of crushed run screenings, natural sand or a mixture of both. These shall be clean, hard, durable, uncoated, dry and free from any injurious, soft or flaky pieces and organic or other deleterious substances.

d) Filler

Filter shall consist of finely divided mineral matter such as rock dust, hydrated lime or cement. The filter shall be graded within following limits:

IS Sieve	Per cent passing by weight
600 micron	100
300 micron	95 – 100
75 micron	85 – 100

The filter shall be free from organic impurities and have a Plasticity Index not greater than 4. The Plasticity Index requirement shall not apply if filter is cement or lime. When coarse aggregate is gravel, 2 per cent of mass of total aggregate of Portland cement or hydrated lime shall be added and percentage of fine aggregate reduced accordingly. Cement or lime is not required when the gravel is lime stone.

e) Aggregate gradation

Mineral aggregates, including filler shall be so graded or combined as to conform to gradings set forth in Table 15.9.1 below.

Table 15.9.1

Sieve Designation	Per cent by weight passing through sieve for		
	25mm thick Grade 1	25-40mm thick Grade 2	>40mm thick Grade 1
26.5mm	--	--	100

22.4mm	--	100	75-100
13.2mm	100	80-100	--
11.2mm	90-100	75-95	50-85
5.6mm	60-80	55-75	20-40
2.8mm	40-55	40-55	5-20
710micron	20-30	20-30	--
300micron	15-25	15-25	--
180micron	10-20	10-20	--
90micron	5-11	5-11	0-5

15.9.2 Mix Design

a) Requirement of Mix

Apart from conformity with grading and quality requirements of individual ingredients, the mix shall also meet the requirements set forth in Table 15.9.2.

Table 15.9.2

Requirements of Bituminous Concrete Mix

S.NO	Description	Requirements
1.	Marshall stability (ASTM Designation : D-1559) determined on Marshall specimens compacted by 75 compaction blows on each end	820 Kg (1800 pounds)
2.	Marshall flow (mm)	Minimum 2-4
3.	Per cent air voids in mix	3-5
4.	Per cent voids in mineral aggregate (VMA)	Minimum 11-13
5.	Percent voids in mineral aggregates filled by bitumen (VFB)	65-75
6.	Binder content, per cent by weight of mix	Minimum 4.5
7.	Water sensitivity (ASTM : D-1075) loss of Stability on immersion in water at 60 deg. C	Minimum 75% Retained strength
	Swell Test (Asphalt Instt. MS-2, No. 2)	Maximum 1.5%

b) Binder content

Binder content shall be so determined as to achieve the requirements of the mix set forth in Table 15.9.2. Marshall method for arriving at binder content shall be adopted.

c) Job Mix Formula

Before starting work the Contractor shall submit to the Engineer for his consent. The job mix formula for the mixture shall fix a single percentage of aggregate passing each required sieve size, a single percentage of asphalt to be added to the aggregate, and a single temperature at which the mixture is to be delivered on the road, all of which shall fall within the ranges of the composition and the temperature limits. The formula shall give the following details:

- I. Source and location of all materials
- II. Proportions of all materials as described under :

Binder	- as percentage by weight of total mix
Coarse aggregate/ Fine aggregate/ Mineral Filler	- as percentage by weight of total aggregate including Mineral Filler
- III. A single definite percentage passing each sieve for the mixed aggregate (Vide Table 15.9.1)
- IV. The results of test as per specifications obtained by the contractor
- V. Test results of physical characteristics of aggregates to be used
- VI. Mixing temperature and compacting temperature

d) Application of job-mix formula and Allowable Tolerances

The approved job mix formula shall remain effective unless and until modified. Each day as many samples of the materials and mixtures shall be taken and tested considers necessary for checking the required uniformity of the mixture.

All mixture furnished shall conform to the job-mix formula within the range of tolerances set in forth in Table 15.9.3.

Table 15.9.3**Permissible variations from the job-mix formula**

SL No	Description of Ingredients	Permissible Variation by Weight of Total mix in Percentage
1	Aggregate passing 13.2mm sieve and larger	± 8
2	Aggregate passing 9.5mm sieve and 4.75mm sieve	± 7
3	Aggregate passing 2.36mm sieve & 1.18mm sieve	± 6
4	Aggregate passing 600 micron sieve & 300 micron sieve	± 5
5	Aggregate passing 150 micron sieve	± 4
6	Aggregate passing 75 micron sieve	± 3

7	Binder	± 0.3
8	Mixing Temperature (Centigrade)	± 10

When unsatisfactory results or changed conditions make it necessary, a new job mix shall be submitted to the Engineer.

Should a change in a material be encountered or should a change in a source of material be made, a new job mix formula shall be submitted before the mixture containing the new material is delivered.

15.9.3 Construction Methods

a) Weather Limitation

The control over the weather conditions shall be as described under Subsection 15.7.3 (1) above.

b) Progress of Work

No work shall be performed when there is insufficient hauling, spreading or finishing equipment, or labour to ensure progress at a rate not less than 75% of the capacity of the mixing plant.

c) Preparation of Existing Surface

The surface on which the mix is to be laid shall be swept thoroughly and cleaned of all loose dirt and other objectionable material using mechanical broom immediately before start of work. In portions where mechanical means cannot reach, the surface shall be prepared, shaped and conditioned to specified levels, grade and cross-fall (camber).

d) Preparation of Mix

A Hot-mix plant of adequate capacity and capable of producing a proper and uniform quality mix shall be used for preparing the mix. The plant may be either a weigh batch type or volumetric proportioning continuous or drum mix type. The plant shall have co-ordinated set of essential units capable of producing uniform mix as per the job-mix formula.

The temperature of the binder at the time of mixing shall be in the range of 150 to 163 degree C and of aggregates in the range of 155 to 163 degree C, provided also that at no time shall the difference in temperature between the aggregates and binder exceed 14 degree C. The Contractor shall submit the exact temperatures and total mixing time for the consent of the Engineer.

Mixing shall be thorough to ensure that a homogeneous mixture is obtained in which all particle of mineral aggregates are coated uniformly.

e) Transportation and Delivery of Mix.

The mix shall be transported from the mixing plant to the point of use in suitable tipper vehicles. The vehicles employed for the transport shall be clean and be covered in transit.

f) Spreading and Finishing

The mix transported from the hot mix plant to the site and shall be spread by means of a self-propelled mechanical paver with suitable screeds capable of spreading, tamping and finishing the mix to specified grade, elevation, and cross-section. However, in restricted locations and

narrow widths, where available equipment cannot be operated, other suitable means shall be employed subject to the consent of the Engineer. The mixture shall be laid upon an approved surface and only when weather conditions are considered suitable. The temperature of the mix, at the time of laying, shall be in the range of 120 degree C to 160 degree C.

The prime coat and tack coat to be applied shall be as per Subsections 15.5 and 15.6 respectively.

Spreading, finishing and compacting of the mix shall be carried out during daylight hours only, unless satisfactory illumination is provided by the Contractor.

g) Compaction of Mixture

Immediately after spreading of mix by paver, it shall be thoroughly and uniformly compacted by rolling with a set of self-propelled rollers moving at a speed not more than 5 km per hour, immediately following close to the paver. Generally with each paver, two steel wheeled tandem rollers and one pneumatic tired roller will be required. The initial or breakdown rolling shall be with 8 to 10 ton static weight smooth three wheeled steel roller and finish rolling with 6 to 8 ton tandem roller. The breakdown rolling shall preferably be followed by an intermediate rolling with a smooth wheel pneumatic roller of 10 to 25 ton having a tire pressure of 7kg/sqcm moving with a speed not more than 7 km per hour and shall be at all times slow enough to avoid displacement of the hot mixture. Means shall be provided for checking and adjusting the tire pressure on the job at all times. All compaction operations, i.e., breakdown rolling can be accomplished by using vibratory roller of 8 to 10 ton static weight. During initial or breakdown rolling and finished rolling, the vibratory shall be switched off. The joints and edges shall be rolled with a 8 to 10 ton three wheeled static roller.

No delays in rolling the paved surface shall be tolerated, the breakdown roller must be right up to the paver at all times and the intermediate pneumatic roller right up to the breakdown roller. The compaction of the asphaltic concrete shall be controlled by temperature as follows:

<u>Roller</u>	<u>Temperature</u>
Breakdown	120°C - 135°C
Pneumatic	95°C - 115°C
Finishing	< 65°C

Rolling procedure shall be as specified under Subsection 15.7.3 (7).

Rolling shall be continued till the density achieved is at least 98% of that of laboratory Marshall specimen. Rolling operations shall be completed in all respects before the temperature of the mix falls below 100 degree C.

h) Joints

Both longitudinal and lateral joints in successive courses shall be staggered so as not to be one above the other. Longitudinal joints and edges shall be constructed true to delineating lines parallel to the centre line of the road. Longitudinal joints shall be offset by at least 150mm from those in the lower course.

Longitudinal and transverse joints shall be made in a careful manner so that well bonded and sealed joints are provided for the full depth of the course.

i) Surface regularity

Surface shall be tested for undulations in longitudinal and cross profiles with 3 m straight

edge and crown template respectively. Crown template shall conform to the typical cross section.

Maximum permissible undulation in longitudinal profile with 3m straight edge shall be as 8mm.

Maximum permissible variation from specified cross profile under camber template shall be as 4mm.

Surface evenness requirements in respect of both longitudinal and cross profiles should be simultaneously satisfied.

- j) Protection of the pavement from traffic

Subsection 15.1 shall apply except as stated below.

Section of the newly finished works shall be protected from traffic of any kind until the mixture has cooled to approximately ambient air temperature and well set.

15.10 SEAL COAT

15.10.1 Description

This work shall consist of application of a seal coat for sealing the voids in a bituminous surface laid to the specified levels, grade, and cross fall. Seal coat used shall be of premix type unless otherwise approved by the Engineer.

15.10.2 Materials

- a) Binder

The binder shall be bitumen of a suitable grade appropriate to the requirements of the work and other environmental conditions as directed by the Engineer and satisfying the requirements of IS : 73, 217, 454 or other cut back as applicable.

- b) Aggregates

The aggregates shall be sand or grit and shall consist of clean, hard, durable, dry particles and shall be free from dust, soft or flaky/ elongated material, organic matter or other deleterious substances. The aggregates shall pass 2.36mm sieve and be retained on 180 micron sieve. The quantity used for premixing shall be 0.06 cum per 10 sq m area.

15.10.3 Construction Methods

- a) Preparation of base

The seal coat shall be applied immediately after laying of bituminous course which is required to be sealed. Before application of seal coat materials, the surface shall be cleaned free of any dust or other objectionable matter.

- b) Preparation and Application of Mix

Mixtures of approved type shall be employed for mixing aggregates with suitable bituminous binder.

The binder shall be heated in boilers of suitable design, to a temperature appropriate to the grade of bitumen. The aggregates shall be clean, dry and suitably heated to a temperature before the same are placed in the mixture. Mixing of binder with aggregates to specified proportions shall be continued till the latter are thoroughly coated with the former.

The mix shall be immediately transported from the mixing plant to the point of use and spread uniformly on the bituminous surface to be sealed.

c) Rolling

As soon as sufficient length has been covered with pre-mixed material, the surface shall be rolled with 8-10 ton smooth wheeled steel, suitable vibratory or other equipment.

As regards procedure for rolling it shall be as specified under Subsection 15.7.3 (7).

d) Control of Traffic

Subsection 15.1 shall apply.

15.11 CEMENT CONCRETE PAVEMENTS

15.11.1 General

This work shall consist of constructing Plain/ or Reinforced Cement Concrete Pavements as required in accordance with these Specification and in conformity with the lines, levels, grades and dimension in accordance with the design.

15.11.2 Materials

a) General

The concrete materials viz. cement, aggregates, water, steel reinforcement, admixtures shall be in accordance with Section 3 (Concrete: Plain and Reinforced) except as specified herein.

b) Dowel and Tie bars

Dowel bars shall be plain round bars. They shall be free from burring or other deformation restricting slippage in the concrete. Before delivery to the Works, one half of the length of each dowel bar shall be painted with one coat of bituminous material.

Tie bars shall be deformed bars free from oil, dirt, loose rust and scale.

These shall conform to the requirements of IS : 432, IS : 1139 and IS : 1786 as relevant.

c) Sleeves

The sleeves for dowel bars of expansion joints shall be of plastic material. This shall be designed to cover the dowels specified by the Designer, with a closed end, and with a suitable stop to hold the end of the sleeve a distance equal to the thickness of joint filler or at least 30mm from the end of the dowel bar. These shall be of such design that they do not deflect or collapse during construction, and the arrangement of sleeves shall be in accordance with these Specifications.

d) Waterproof Membrane

Where Waterproof membrane is to be provided, it shall be an impermeable polythene plastic sheeting. Where an overlap of underlay material is necessary this shall be at least 300mm. Water shall not be allowed to pond on the membrane which shall be completely dry when the concrete is laid.

e) Jointing Materials

i. Joint Filler

The expansion joint fillers shall conform to the requirements of IS: 1838. They shall be punched to admit the dowels where called for as specified by the Designer. The filler for each joint shall be furnished in a single piece for the full depth and width required for the joint. When the use of more than one piece is authorized for a joint, the abutting ends shall

be fastened closely together securely and accurately to shape by stapling or other satisfactory positive fastening.

ii. Joint Primer

Joint primer shall be fully compatible with the joint sealant and shall be applied strictly in accordance with the manufacturer's instructions.

iii. Joint Sealing Compound

The Sealing Compound of hot poured, elastomeric type shall conform to AASHTO M282 and cold applied sealant shall be in accordance with BS 5212 (Part 2).

15.11.3 Equipment and Tools

a) General

The concrete paving shall be carried out by use of mechanised method. Equipment and tools necessary for handling materials and performing the work shall have the consent of the Engineer as to design, type, capacity and mechanical, condition shall be at the site of the work before work is started. In special cases like a very short length of road to be laid at a location, other methods may be approved by Engineer.

b) Batching and Mixing Plant

This shall be of suitable type, capacity and make meeting the requirements of work.

c) Paving Equipment

The concrete shall be placed with an approved fixed form or slip form paver with independent units designed to (i)spread, (ii)consolidate, screed and float finish, (iii)texture and cure the freshly placed concrete in one complete pass of the machine in such a manner that a minimum of hand finishing will be necessary and so as to provide a dense and homogeneous pavement in conformity with the plans and Specifications.

Vibrators for full width vibration of concrete paving slabs may be either the surface pan type or the internal type. They may be attached to the spread finisher. They shall not come in contact with the joint, sub base or side forms.

The frequency of the surface vibrators shall not be less than 3500 impulses per minute and for the internal type not less than 5000 impulses per minute. The variable vibration setting shall be provided in the machine.

At least two spare vibrators and one generating unit shall be on hand in case of any breakdown of the vibrating equipment being used.

d) Concrete Saw for joint cutting

The mechanical saw for cutting concrete shall be adequately powered to cut rapidly with a water-cooled diamond edge saw blade to the depth required. A water tank with flexible hoses and pump shall be made available in this activity on priority basis. The Contractor shall have at least one standby saw in good working condition.

e) Forms

Straight side forms shall be metal forms having a thickness of at least 5mm and have a depth equal to the prescribed edge thickness of the pavement slab.

Curved forms shall be of the radius called for as specified by the Designer and acceptable flexible forms shall be installed with that radius. Built-up forms with horizontal joints shall not

be used. Forms shall be free from kinks, bend or wraps. Forms shall not deflect more than 6 mm when tested as a simple beam with a span of three metres under a load equal to that which the finishers or other construction equipment will exert on them. The top of the form shall not vary from a three metre straight edge by more than 3mm at any point and the side by more than 6mm at any point.

The forms shall contain provision for locking together tightly the ends of abutting from sections and for secure setting.

f) Curing Compounds

The curing compounds shall have a water retention efficiency index of 90% in accordance with BS 7542.

15.11.4 Construction Methods

a) Preparation of Sub-base

The sub-base, which shall generally be of water-bound macadam (WBM) conforming to Subsection 3.3. The sub base shall be wetted adequately or provided with a water proof membrane so that it does not absorb any water from the concrete to be laid over it.

Concrete shall not be placed on any portion of the sub-base until the consent of the Engineer is given.

b) Setting Forms

The sub-base under the forms shall be compacted and cut to grade so that forms, when set to the position are within ± 3 mm of a straight line formed by the top of the forms. If the sub-base is found to be below the required grade at the form line, the grade line shall be lifted by placing lean concrete mix 1:4:8 beneath the form and setting the form when it is set. Imperfections and variations above grade shall be corrected by tamping or cutting to the degree required.

The alignment and grade elevations of the forms shall be checked and the necessary corrections made by the Contractor immediately before and after placing the concrete. When any form has been disturbed or any roadbed has become unstable, the form shall be reset and rechecked.

On final setting of the forms, these shall be checked for at least half the length of pavement to be concreted in a particular day before concreting commences on that day. While concreting long lengths, the setting up of forms to the exact grade and alignment shall be in advance of the concreting operation by at least 60 m.

Forms shall be cleaned and oiled prior to the placing of concrete. The forms shall be removed not earlier than 24 hours after the concrete has been laid.

c) Preparation of Concrete

i Trial Mix / Mix Design

Subsection 15.2.1 shall be followed Minimum grade of concrete to be used is M25.

ii. Batching, Mixing and Transporting Materials

Subsection 15.2.4 shall apply.

The Ready-Mixed Concrete (RMC) shall conform to Subsection 3.19.

d) Placing Concrete

Concrete shall be placed only on a prepared sub-base as specified in Subsection 15.11.4(1). No concrete shall be placed around structures until they have been brought to the required grade and alignment nor until expansion joint material has been placed around them.

The concrete shall be spread, compacted and finished by a mechanical paver and in accordance with Subsection 15.11.3 (3). The mixing and placing of concrete shall progress only at such a rate as to permit proper finishing, protecting and curing of the pavement.

The truck mixers, truck agitators and other approved hauling equipment shall be equipped with means for discharge of concrete into the hopper of the paver without segregation of the materials. In all cases, the temperature of the concrete shall be measured at the point of discharge from the delivery vehicle.

The acceptance criteria regarding level, thickness, surface regularity, texture, finish, strength of concrete and all other quality control measures for hand laid concrete shall be the same as in the case of machine laid work.

The concrete shall be thoroughly consolidated against and along the faces of all forms by means of vibrators inserted in the concrete. Vibrators shall not be permitted to come in contact with a joint assembly, the sub-base or a side form. In no case shall the vibrator be operated longer than 30 seconds in any location. The vibrator shall be inserted in the concrete and worked along the full length and both sides of a joint.

Concrete shall be deposited as near to expansion and contraction joints as possible without disturbing them, but shall not be dumped from the discharge bucket on to a joint assembly.

Except at construction joints, concrete shall be shovelled against both sides of the joint simultaneously, maintaining equal pressure on both sides. It shall be deposited to a height of approximately 5 cm more than the depth of the joint, and shall be vibrated so that all honeycombing and voids are prevented. The vibrator shall be inserted in the concrete and worked along the full length and both sides of the joints.

e) Initial strike-off and Placement of Reinforcement

Where the concrete is laid in two layers, the bottom layer of concrete shall be struck off for the full width between longitudinal construction joint true to crown at the required distance below the finished surface elevation, for placement of reinforcement or for placement of a top layer of the required thickness.

The striking-off shall be accomplished by use of the finishing machine, unless some other approved device is allowed. The reinforcement shall be placed as called for by the Designer and pouring of concrete over it shall only be allowed after placement of reinforcement is proper in all respects and approved by the Engineer.

f) Joints

i General

Joints shall comply with the design approved for the construction.

A strip of the preformed expansion joint filler shall be placed around each structure which extends into or through the pavement before concrete is placed.

ii. Transverse Expansion Joints

These shall be formed at the design spacings. The material for a transverse joint shall be assembled at the roadbed, and placed into position as a unit.

iii. Transverse Contraction Joints

Transverse Contraction joints shall consist of planes of weakness created by forming or cutting grooves in the surface of the pavement. Transverse contraction joints shall also include load transfer dowel-bars where these are specified by the Designer.

The contraction joints shall be cut as soon as the concrete has undergone initial hardening and is hard enough to take up the load of joint sawing machine without causing damage to the slab. Grooves shall be at right angles to the centreline of the pavement and shall be true to line, subject to a tolerance of 5 mm in the width of the slab.

Any procedure for sawing joints that results in premature and uncontrolled cracking shall be revised immediately by adjusting the sequence of cutting the joints or the time interval involved between the placing of the concrete and cutting of the joints.

Load transfer assemblies for transverse contraction joints shall consist of dowel bars without sleeves and an approved auxiliary spacing and supporting element.

The assembly shall be placed into position so that the dowels are parallel to the centreline and shall be staked into position in such a way as to hold the assembly securely in position throughout construction.

iv. Longitudinal Joints

Longitudinal joints shall be constructed in conformity with the design. Planes of weakness shall be created by forming or cutting grooves in the surface of the pavement in accordance with the applicable provisions of this Section.

When adjacent lanes of pavement are constructed separately, steel side forms shall be used which will form a keyway along the construction joint. The bars may be bent at angles against the form of the first lane constructed and straightened into final position before the concrete of the adjacent lane is poured.

v. Transverse Construction Joint

Transverse construction joints shall be placed whenever concreting is completed after a day's work or is suspended for more than duration permissible for continuous pouring of concrete.

Joints shall be formed by placing installing bars or suitable bulkhead material so that a vertical face with approved key is formed or shall be butt joints formed with suitable material so that a vertical face is formed with no key. No tie bars shall be necessary when key joints are formed but dowel bars of the same dimensions and at the same spacing as for contraction joints shall be necessary at all butt joints.

g) Finishing

i Machine Finishing

As soon as the concrete has been placed, it shall be struck off and screeded by an approved finishing machine or tools to the grades and cross sections specified by the

Designer and to a level slightly above grade so that when properly consolidated and finished the surface of the pavement will be at the exact level and grade. The machine or tool shall go over each area of pavement as many times and at such intervals as necessary to give the proper compaction and to leave a surface of uniform texture, true to grade and cross section.

Excessive operation over a given area shall be avoided. The tops of the forms shall be kept clean by an effective device attached to the machine and the travel of the machine on the forms shall be maintained true without lift, wobble or other variation tending to effect the precision finish.

After concrete has been placed on both sides of the joint and struck off, the installing bar or channel cap shall be slowly and carefully withdrawn, the concrete shall be carefully spaded and additional freshly mixed concrete worked into any depression left by the removal of the installing bar.

A diagonal finishing machine shall be used if available.

ii. Hand Finishing

A portable screed shall be provided for use. The screed shall be at least 60 cm longer than the width of the slab to be struck off and consolidated. It shall be of approved shape, sufficiently rigid to retain its shape and constructed either of metal or of other material shod with metal. (If necessary, a second screed shall be provided for striking off the bottom layer of concrete).

The screed shall then be placed on the forms and slip along them, without lifting, in a combined longitudinal and transverse shearing motion moving always in the direction in which the work is progressing. If necessary this shall be repeated until the surface is of uniform texture, true to grade and contour, and free from porous areas.

h) Edging at Forms and Joints

After the concrete's initial set, the edges of the pavement along each side of each slab, and on each side of transverse expansion joints, planes of weakness except when sawed transverse construction joints, and emergency construction joints shall be worked with an approved tool and rounded to a radius of 5 mm. A well defined and continuous radius shall be produced and a smooth, dense mortar finish obtained. The surface of the slab shall not be unduly disturbed by tilting of the tool during use.

All joints shall be tested with a straight edge before the concrete has set, and correction shall be made if one side of the joint is higher than the other or if they are higher or lower than the adjacent slabs.

i) Surface Texture

The surface of the carriage-way shall be textured by wire brushing in a direction at right angles to the longitudinal axis of the carriage-way. The pavement shall be given this broomed texturing as soon as surplus water has risen to the surface.

The wire brushes shall be either mechanically operated or manual methods may be allowed depending upon the type of paver being used on the Work. In either case the wire broom shall be not less than 450 mm wide with two rows of spring steel. At least two brooms in working order shall be on the site at all times.

The surface texturing shall be completed before the concrete is in such condition that the surface is torn or unduly roughened by the brooming. The broomed surface shall be free from rough areas, porous areas, irregularities, or depressions.

j) Surface Requirements

After the concrete has hardened sufficiently, the surface shall be given a further test for trueens, using an approved 3 m straight edge laid on the surface. Any portion of the surface, when tested in the longitudinal direction, which shows a variation or departure from the testing edge of more than 3.5mm but not exceeding 7mm shall be marked and immediately ground down with an approved grinding tool until the variation does not exceed 3.5mm.

Whenever the variation or departure from the testing edge is more than 7.0mm the pavement shall be removed and replaced. Such removal shall be of the full depth and width of the slab and at least 3m long.

k) Curing

Immediately after the surface texturing, the surface and sides of the slab shall be cured by approved curing method for not less than 7 days. During this period measures shall be taken to prevent the loss of moisture.

The concrete shall not be left exposed between stages of curing.

The surface shall be inspected regularly to ascertain the earliest time at which it is able to withstand the spreading of moisture retaining material. This shall be by ponding of water or spreading and wetting either two layers of burlap or two mats of cotton / jute or a layer of sand or other approved highly absorbent material. Whatever material is used it shall be kept continuously moist for not less than 7 days and to a degree which will ensure that 100% humidity is maintained adjacent to the concrete surface. A membrane curing compound meeting the requirements of BS 7542 may be used subject to the consent of the Engineer.

Concrete surfaces which are subjected to heavy rainfall within three hours after the curing compound has been applied shall be resprayed by the method and the coverage specified above.

Concrete surfaces to which membrane curing compounds have been applied shall be adequately protected for the duration of the entire curing period from the pedestrian and vehicular traffic, except as required for joint sawing operations and surfaces tests, and from any other cause which will disrupt the continuity of the membrane. The curing membrane so formed shall be maintained intact for a period of not less than 14 days. The entire surface shall be protected from the effects of solar radiation and in addition by the use of frames covered with material with heat and light reflecting properties.

Concrete liable to be affected by running water shall be adequately protected from the damage during the setting period.

l) Removing Forms

Forms shall be removed only after stipulated period and carefully so as to avoid damage to the pavement.

m) Protection of Pavement

The Contractor shall erect and maintain suitable barricades and shall employ watchmen to

exclude public traffic and that of his employees and agents from the newly constructed pavement until opened for use. These barriers shall be arranged as not to interfere with public traffic on any lane intended to be kept open and necessary signs and lights shall be maintained by the Contractor clearly indicating any lanes open to the public.

Where any stipulated public traffic lane is contiguous to the slab or lane being placed, the Contractor shall provide, erect, and subsequently remove a substantial temporary guard fence along the prescribed dividing line, which shall be maintained there and protected by signages until the slab is opened to traffic. The Contractor's plan of operation shall be such as to obviate any need for encroachment on the public traffic lane or lanes under use .

The same shall be approved by the local competent authority.

Any part of the pavement damaged by traffic or other cause prior to its final acceptance shall be repaired or replaced by the Contractor.

n) Sealing Joints

Before the pavement is opened to traffic, and as soon after the curing period as is feasible, all joints both longitudinal and transverse, shall be filled with the material approved for use as seal.

Both primer and sealing compound shall be treated and applied strictly in accordance with the manufacturer's specifications/ instruction and by use of approved equipment.

The sealing material shall be poured into each joint opening as directed by the Engineer. The pouring shall be done in such a manner that the material will not be spilled on the exposed surfaces of the concrete. Any excess material on the surface of the concrete pavement shall be removed immediately and the pavement surface cleaned.

Section – S.16 BUILDING WORKS

16.1 General Requirements

16.1.1 Preambles to Outline Construction Specification

General

- a) For convenience, this document contains references to a variety of International standards which are included as indicative information only

Wherever practical Indian Standards [IS], Codes of Practice, etc. shall be utilized and take precedence

- b) The document and the individual clauses contained within it have been included for general and outline purposes only; - and, in consequence: -
- The contents are to be accepted as indicative only; and are to be reviewed, amended and developed, as deemed appropriate, to suit the formulated designs and site specific requirements.
 - The contents, as included, are to be considered as limited in extent and overall scope; and shall be developed and expanded to specify the entirety and detail of the works.
 - Items included in this, Outline Document may or may not be finally incorporated into the Contractor's working specification.
- c) In general, the relevant items of building works shall be carried out in accordance with the specifications mentioned in the contract documents / CPWD specifications (latest edition) / relevant IS codes and as approved by the Engineer.

16.1.2 Technical

- a) The final Specification document shall be structured to clearly address both the Material and the Workmanship [including Protection] aspects of the works.
- b) Emphasis shall be placed on the Contractor and all Sub-contractors to abide by the requirement to take all appropriate site dimensions, as deemed necessary to undertake and complete the works.
- c) Equal emphasis is to be placed on the Contractor and all Sub-contractors, as considered appropriate, to abide by the requirement to prepare and submit shop drawings for approval by the Engineer, prior to commencement of any specialized works.
- d) It shall be made abundantly clear that the Contractor and all appropriate Sub-contractors / Suppliers shall be duty bound to furnish the Employer's Representative with a sufficient quantity of samples, mock-ups and process and the continuance of the works at no additional cost to the Employer.
- e) Wherever deemed appropriate by the Engineer, materials and workmanship shall be in strict accordance with manufacturer's recommendations.
- f) In all given circumstances, sufficient due care and attention shall be paid to prevent electrolytic corrosion between dissimilar materials and metals, in particular.
- g) Similarly all necessary precautions shall be taken to ensure adequate corrosion protection for all exposed and hidden elements.

16.1.3 General Requirements Materials

The Contractor will note the requirement to use materials available in India as far as possible. These materials must meet the requirements of the relevant Indian Standard (IS), or, where appropriate an equivalent International Standard.

16.1.4 Compliance with Specification

The Contractor shall comply fully with the requirements of the following specifications in regard to quality of materials, submission of samples for approval prior to commencement of installation work and methods and procedure of installation.

All proprietary materials or processes submitted by the Contractor and approved by the Engineer shall be used or carried out strictly in accordance with the manufacturer's instructions and recommendations and also to comply with this Specification.

Where one or more proprietary materials or processes are named in this specification for Architectural and Building Works as acceptable materials or workmanship the Contractor shall still be responsible to ensure that these materials or workmanship comply with the requirements described in this Specification. In particular all materials shall comply with appropriate requirements for fire resistance.

Where materials are proposed by the Contractor for any part of the Works that require certain tests and where no previous test certificates have been issued by any competent authorities or approved testing laboratory, the Contractor shall at his own cost, submit the material for the appropriate test at an approved laboratory.

16.2 Materials

Cement and water for mortar shall be as specified under Section 3 "Concrete: Plain & Reinforced".

Lime shall be approved hydrated lime or quick lime to BS 890 delivered to site in sealed bags bearing the manufacturer's name or brand. Lime shall be prepared to the appropriate requirements of BS 5628, and shall be soaked in water for not less than 16 hours before use.

Sand shall be clean and sharp, free from salts, loam and organic matter, complying with the requirements of BS 1199/1200, as appropriate and be well graded from 5mm down.

Plasticisers shall comply with BS 4887. Integral waterproofing agents for mortar may be either powder additive or equal approved mixed in accordance with the manufacturer's instructions.

- a) **FLY ASH BASED PRODUCTS:** Fly ash based products such as Mechanized Autoclaved Sand Lime Fly ash Bricks/ Fly Ash Lime Gypsum Bricks/Autoclaved Aerated Concrete (AAC) Blocks have to be used in all construction activities.

Bricks shall be fetching from an approved kiln, machine pressed, well burnt, hard, square, or uniform shape, colour and size with all sharp clean arises and free from all defects. Samples shall be submitted to the Engineer and approved before placing an order.

Concrete blocks shall be obtained from an approved manufacturer. Concrete blocks shall be hollow with a minimum average compressive strength of 7.0 N/Sqmm and solid concrete block with a minimum average compressive strength of 12.5 N/Sqmm.

Materials for precast concrete lintels shall be as specified under Section 3 "Concrete: Plain & Reinforced."

Horizontal wall reinforcement shall be galvanized steel mesh reinforcement, 22 gauge or as specified. Steel bar reinforcement shall be as specified under Section 3 "Concrete: Plain & Reinforced."

Movement joint filler shall be as proposed by the Designer; and approved by the Engineer, sealer shall be coloured silicone sealant to the approval of the Engineer.

b) Mortar

Mortar shall comprise one part cement and four parts sand or the mix proportion as specified by the (ready mix) manufacturer and got approved by the Engineer with minimum compressive strength of 7.5 N/Sqmm at 28 days thoroughly mixed with water to provide workability. The grade of mortar shall be as per IS 2250.

Plasticisers may only be used with the approval of the Engineer and shall be added strictly in accordance with the manufacturer's instructions.

Mixing of mortar shall be done by mechanical batch mixer or by hand on a clean, watertight platform of adequate size. All constituent materials shall be accurately gauged.

Mortar shall be used within one hour of mixing. Mortar that has started to set shall not be used. Detempering of hardened or partly hardened mortar will not be permitted.

c) Blockwork Generally

Blockwork shall, unless otherwise described, be built in stretcher bond of hollow cellular or solid blockwork with inserts/reinforcements as per GFC drawings or approved by the Engineer.

Blocks shall be well wetted before laying and kept wet until laid.

Hollow blocks shall be grouted solid with mortar where required by the Design.

Blocks shall be laid in true and regular courses on a full bed of mortar of 10mm average thickness, exclusive of any key in the jointing surfaces of the blocks. Sufficient mortar shall be used in bedding and jointing to ensure that all keys are solidly filled.

All horizontal joints shall be properly level. The vertical joints shall be properly lined and quoins, jambs and other angles plumbed as the work proceeds. All walls shall be plumbed vertical.

Standard size blocks shall be used wherever possible. Broken blocks shall not be used except where required for bonding purposes. Walls and partitions shall be bonded to one another at angles and junctions.

Joints on faces of block walls which are to be rendered or plastered shall be raked out for a depth of 10mm as the work proceeds.

Walls shall be carried up regularly without leaving any part more than one metre lower than another unless the permission of the Engineer is first obtained. Work which is left at different levels shall be racked back.

Before commencing any blockwork the Contractor shall confer with other trades to ensure that all pipes, ducts, conduits, sleeves, bolts, frame lugs, etc. or any other materials

necessary to be installed in the blockwork at the time it is built have been fixed or provided for.

Firepots around ducts, cable trays, waterpipes, drains and the like shall be of an approved intumescent material.

d) Blockwork Reinforcement

Blockwork shall be reinforced to BS 5628/CPWD latest specifications.

Mesh wall reinforcement is to be built in at every second course. Mesh shall be 100mm wide for 150mm blockwork and 150mm wide for 200mm blockwork.

Where shown on the Drawings, the block units are to be vertically reinforced through the core of the block units with high yield steel bars, securely tied to the starter bars left projecting from concrete structure. The core of block unit is to be grouted solid around bar with mortar or with a lean mix concrete with 10mm maximum aggregate.

e) Movement Joints

Movement joints shall be sealed by an approved sealer applied in strict accordance with the manufacturer's instructions. The surface of the concrete or blockwork to which the sealer is to adhere shall be straight and cleaned of all filler material, dirt, oil, grease and other matter. The sealer shall be applied by methods recommended by the manufacturer and approved by the Engineer so that the sealer is brought flush to the surface of structure and a smooth surface is achieved. Excess material and spillage shall be properly cleaned off and removed.

f) Precast Concrete Units

Precast concrete units shall be cast, reinforced, handled and erected all as specified under Section 3 "Concrete: Plain & Reinforced."

- g)** Acrylic intumescent sealant 2 hours fire rated in accordance with BS 476-Part20, IS 1530 Part 4 to seal gap & joint in fire rated walls and floors and around service penetration for 25 mm gap and 12 mm depth.